Industria y Comercio

SUPERINTENDENCIA

03-22965

Delegatura de propiedad Industrial

División de Nuevas Creaciones

PCT QF

SOLICITUD

PATENTE DE INVENCIÓN

21 **EXPEDIENTE No.** 03-22965

54. **TÍTULO** Compuestos heterociclicos fundidos de succinimida y sus analogos moduladores de la función nuclear receptora de hormonas

51 **CLASIFICACIÓN INTERNACIONAL** A61K 31/40 C07D 491/08

71 **SOLICITANTE** Bristol-Myers Squibb Company

DOMICILIO Princeton, New Jersey, Estados Unidos.

74 **APODERADO** Ramiro Castro Duque QF

22 **BOGOTÁ, D. C.,** SS

(FORMA P-10)

PETITORIO

Industria y Comercio
SUPERINTENDENCIA

13 022965 00

SUPERINDUSTRIA Y COMERCIO
Radicacion : 03022965 00000000 Folios: 436
Fecha (AMD): 2003-03-19 10:54:38
Tramite : 011 PCT-PATENT 378 FASE NACI 411 PRESENTAC
Dependencia: 2020 DIVISION DE NUEVAS CREACIONES

FORMULARIO ÚNICO DE SOLICITUD DE PATENTE

PCT

ENTRADA EN FASE NACIONAL

1 SOLICITUD DE:

☒ Patente de Invención. ☐ Patente de Modelo de Utilidad.

☒ Capítulo I. ☒ Capítulo II.

2 SOLICITANTE (71)	Nombre: BRISTOL – MYERS SQUIBB COMPANY Dirección: P.O. Box 4000, Princeton, NJ 08543-4000, Estados Unidos de América Nacionalidad o Domicilio: Estados Unidos Lugar de Constitución: Estados Unidos Teléfono: Fax: E-mail	**IDENTIFICACION** C.C. ☐ NIT ☐ C.E. ☐ Otro ☐ Cual____ Número ____
3 REPRESENTANTE O APODERADO	Nombre: RAMIRO CASTRO DUQUE Dirección: Cra. 7 No. 16-56 Piso 9 Teléfono: 380-2200 Fax: 380-2700 E-mail:	**IDENTIFICACION** C.C. ☒ NIT ☐ C.E. ☐ Otro ☐ Cual____ Número 170.322 TP 1003.
4 INVENTOR (ES) (72)	Nombre: James A. Balog, Aberra Fura, Soren Giese, Wenying Li, Dacia A. Pickering, Mark E. Salvati, Ramesh N. Patel, Ronald L. Hanson Dirección: 17 Terrell Road, Lambertville, New Jersey 08530, US; 15 Cresthill Road, Lawrenceville, New Jersy 08648, US; 523 Windmere Way, New Hope, Pennsylvania, 18938, US; 6221 Town Place, Middletown, Connecticut 06457, US; 507 Drexel Avenue, Lawrenceville, New Jersey 08648-3844, US; 9 Tracey Drive, Lawrenceville, New Jersey 08648, US; 572 Cabot Hill Road, Bridgewater, New Jersey 08807, US; 54 Whitewood Drive, Morris Plains, New Jersey 07950, Estados Unidos de América (Respectivamente) Nacionalidad o Domicilio: Estados Unidos de América	

5 PCT (86)

Solicitud Internacional No. PCT/US01/19655 Fecha 20-06-2001

Publicación Internacional No. WO 02/24702 A1 Fecha 28-03-2002

Título (54): COMPUESTOS HETEROCICLICOS FUNDIDOS DE SUCCINIMIDA Y SUS ANALOGOS, MODULADORES DE LA FUNCIÓN NUCLEAR RECEPTORA DE HORMONAS

7 Clasificación Internacional (51) A 61 K 31/40 ; C07D491/08

8 Prioridad SI ☒ NO ☐	(33) País de Origen	(32) Fecha	(31) Número de Solicitud
	US	19-09-2000	60/233.519
	US	18-04-2001	60/284.730
	US	18-04-2001	60/284.438

9 Comprobante de pago No. 0915756436104114124 Fecha 18-03-2003

10 ANEXOS

- [x] Comprobante de pago de la tasa de presentación de la solicitud. $400.000
- [x] Comprobante de pago por reivindicación de prioridad. $336.000
- [ ] Documento que acredita la existencia y representación legal cuando el solicitante sea persona jurídica.
- [x] Poderes, si fuere el caso. Protocolo No. 19358
- [ ] Documento de cesión del inventor al solicitante o a su causante.
- [ ] Declaraciones
- [x] Copia de la solicitud internacional. (Resumen, descripción, reivindicaciones, dibujos)
- [ ] Traducción de la solicitud internacional al castellano. (Resumen, descripción, reivindicaciones, dibujos)
- [ ] Copia del examen preliminar efectuado por la IPEA.
- [ ] Traducción del examen preliminar efectuado por la IPEA.
- [ ] De ser el caso, copia del contrato de acceso.
- [ ] De ser el caso, documento que acredite la licencia o autorización de uso de conocimientos tradicionales de las comunidades indígenas.
- [ ] De ser el caso, certificado de depósito del material biológico.
- [ ] Arte final 12x12.
- [ ] De ser el caso, información sobre otras solicitudes de patente o títulos obtenidos en el extranjero por el mismo titular o su causante, relacionadas parcial o totalmente con la invención de esta solicitud.
- [ ] Otros

11 FIGURA CARACTERÍSTICA:

Solicito la concesión de la patente

NOMBRE: FABIO CASTRO DUQUE

FIRMA

C.C. 17.022.2 de Bogotá T.P. 1003 del C.S.J.

Instrucciones para la presentación de los anexos, ver reverso de esta página.

3 A.

SUPERINDUSTRIA Y COMERCIO
Radicacion : 03022965 00000000 Folios: 436
Fecha (MM): 2003-03-19 10:54:38 D
Tramite : 011 PCT-PATENT 378 FASE NACI 411 PRESENTAC
Dependencia: 2020 DIVISION DE NUEVAS CREACIONES

NIT : 800176089-2

RECIBO OFICIAL DE CAJA : 03 - 15,275
FECHA : MARZO 3 DE 2003

***** C O N S I G N A C I O N *****

DEPOSITANTE	TIPO PAGO	BANCO	CUENTA	No. PAGO	FECHA PGO	Vr. PAGO
BRIGARD & CASTRO LTDA	CONSIGNACION	BANCO POPULAR	050-00110-6	2198734	03/03/2003	23,740,000.00

***** C O N C E P T O *****

CANT.	RENTISTICO	CONCEPTO	TOTAL CONCEPTO
1	50005-01-01 SOLICITUDES	1 TRAMITES DE SOL. DE PATENTE DE IN	400,000.00
		TOTAL : $	400,000.00

SON: CUATROCIENTOS MIL PESOS

RESPONSABLE : _____

RECIBO DE CAJA APLICADO AL EXPEDIENTE No._____

Carrera 13 No. 27-00 Pisos 5, 7 y 10
Conmutador 382 0840
Fax 350 5220
E-mail: info@sic.gov.co
www.sic.gov.co
Bogotá, D.C., Colombia

RC4

Industria y Comercio
SUPERINTENDENCIA Y COMERCIO
Radicacion : 03022965 00000000 Folios: 436
Fecha (AMD): 2003-03-19 10:54:38
Tramite : 011 PCT-PATENT 378 FASE NACI 411 PRESENTAC
Dependencia: 2020 DIVISION DE NUEVAS CREACIONES

NIT : 800176089-2

RECIBO OFICIAL DE CAJA : 03 - 13,410
FECHA : FEBRERO 21 DE 2003

***** C O N S I G N A C I O N *****

DEPOSITANTE	TIPO PAGO	BANCO	CUENTA	No. PAGO	FECHA PGO	Vr. PAGO
BRIGARD & CASTRO LTDA	CONSIGNACION	BANCO POPULAR	050-00110-6	7421737	21/02/2003	5,160,000.00

***** C O N C E P T O *****

CANT.	RENTISTICO	CONCEPTO	TOTAL CONCEPTO
1	50005-01-01 SOLICITUDES	82 INVOCACION DE UNA PRIORIDAD EN NU	112,000.00
		TOTAL : $	112,000.00

SON: CIENTO DOCE MIL PESOS

RESPONSABLE : _____

RECIBO DE CAJA APLICADO AL EXPEDIENTE No._____

Carrera 13 No. 27-00 Pisos 5, 7 y 10
Conmutador 382 0840
Fax 350 5220
E-mail: info@sic.gov.co
www.sic.gov.co
Bogotá, D.C., Colombia

5

SUPERINTENDENCIA Y COMERCIO

Radicacion : 03022965 00000000 Folios: 436

Fecha (AMD): 2003-03-19 10:54:38

Tramite : 011 PCT-PATENT 370 FASE NACI 411 PRESENTAC

Dependencia: 2020 DIVISION DE NUEVAS CREACIONES

NCIA

NIT : 800176089-2

RECIBO OFICIAL DE CAJA : 03 - 13,411
FECHA : FEBRERO 21 DE 2003

***** C O N S I G N A C I O N *****

DEPOSITANTE	TIPO PAGO	BANCO	CUENTA	No. PAGO	FECHA PGO	Vr. PAGO
BRIGARD & CASTRO LTDA	CONSIGNACION	BANCO POPULAR	050-00110-6	7421737	21/02/2003	5,160,000.00

***** C O N C E P T O *****

CANT.	RENTISTICO	CONCEPTO	TOTAL CONCEPTO
1	50005-01-01 SOLICITUDES	82 INVOCACION DE UNA PRIORIDAD EN NU	112,000.00
		TOTAL : $	112,000.00

SON: CIENTO DOCE MIL PESOS

RESPONSABLE : _____

RECIBO DE CAJA APLICADO AL EXPEDIENTE No._____

Carrera 13 No. 27-00 Pisos 5, 7 y 10
Conmutador 382 0840
Fax 350 5220
E-mail: info@sic.gov.co
www.sic.gov.co
Bogotá, D.C., Colombia

Industria y Comercio

SUPERINTENDENCIA

SUPERINDUSTRIA Y COMERCIO Folios: 436
Radicacion : 03022965 00000000
Fecha (MMD): 2003-03-19 10:54:38
Tramite : 011 PCT-PATENT 378 FASE NACI 411 PRESENTAC
Dependencia: 2020 DIVISION DE NUEVAS CREACIONES

NIT : 800176089-2

RECIBO OFICIAL DE CAJA : 03 - 13,412
FECHA : FEBRERO 21 DE 2003

***** C O N S I G N A C I O N *****

DEPOSITANTE	TIPO PAGO	BANCO	CUENTA	No. PAGO	FECHA PGO	Vr. PAGO
BRIGARD & CASTRO LTDA	CONSIGNACION	BANCO POPULAR	050-00110-6	7421737	21/02/2003	5,160,000.00

***** C O N C E P T O *****

CANT.	RENTISTICO	CONCEPTO		TOTAL CONCEPTO
1	50005-01-01 SOLICITUDES	82	INVOCACION DE UNA PRIORIDAD EN NU	112,000.00
			TOTAL : $	112,000.00

SON: CIENTO DOCE MIL PESOS

RESPONSABLE : _____

RECIBO DE CAJA APLICADO AL EXPEDIENTE No._____

Carrera 13 No. 27-00 Pisos 5, 7 y 10
Conmutador 382 0840
Fax 350 5220
E-mail: info@sic.gov.co
www.sic.gov.co
Bogotá, D.C., Colombia

92514

(12) INTERNATIONAL APPLICATION PUBLISHED UNDER THE PATENT COOPERATION TREATY (PCT)

(19) World Intellectual Property rganization
International Bureau

(43) International Publication Date
28 March 2002 (28.03.2002)

PCT

(10) International Publication Number
WO 02/24702 A1

(51) International Patent Classification[7]: C07D 491/08, 495/08, 471/08, A61K 31/40, 31/439, A61P 35/00

(21) International Application Number: PCT/US01/19655

(22) International Filing Date: 20 June 2001 (20.06.2001)

(25) Filing Language: English

(26) Publication Language: English

(30) Priority Data:

60/233,519	19 September 2000 (19.09.2000)	US
60/284,730	18 April 2001 (18.04.2001)	US
60/284,438	18 April 2001 (18.04.2001)	US

(71) Applicant *(for all designated States except US)*: BRISTOL-MYERS SQUIBB COMPANY [US/US]; P.O. Box 4000, Lawrenceville-Princeton Road, Princeton, NJ 08543-4000 (US).

(72) Inventors; and

(75) Inventors/Applicants *(for US only)*: SALVATI, Mark, E. [US/US]; 9 Tracey Drive, Lawrenceville, NJ 08648 (US). BALOG, James, Aaron [US/US]; 2 Sassafras Court, Scotch Plains, NJ 07076 (US). PICKERING, Darla, A. [—/US]; 507 Drexel Avenue, Lawrenceville, NJ 08648-3844 (US). GIESE, Sören [DE/US]; 1113 Polo Run Drive, Yardley, PA 19067 (US). FURA, Aberra [ET/US]; 15 Cresthill Road, Lawrenceville, NJ 08648 (US). LI, Wenying [CN/US]; 6221 Town Place, Middletown, CT 06457 (US). PATEL, Ramesh, N. [US/US]; 572 Cabot Hill Road, Bridgewater, NJ 08807 (US). HANSON, Ronald, L. [US/US]; 54 Whitewood Drive, Morris Plains, NJ 07950 (US).

(74) Agents: ALGIERI, Aldo, A. et al.; Bristol-Myers Squibb, P.O. Box 4000, Lawrenceville-Princeton Road, Princeton, NJ 08543-4000 (US).

(81) Designated States *(national)*: AE, AG, AL, AM, AT, AU, AZ, BA, BB, BG, BR, BY, BZ, CA, CH, CN, CO, CR, CU, CZ, DE, DK, DM, DZ, EC, EE, ES, FI, GB, GD, GE, GH, GM, HR, HU, ID, IL, IN, IS, JP, KE, KG, KP, KR, KZ, LC, LK, LR, LS, LT, LU, LV, MA, MD, MG, MK, MN, MW, MX, MZ, NO, NZ, PL, PT, RO, RU, SD, SE, SG, SI, SK, SL, TJ, TM, TR, TT, TZ, UA, UG, US, UZ, VN, YU, ZA, ZW.

(84) Designated States *(regional)*: ARIPO patent (GH, GM, KE, LS, MW, MZ, SD, SL, SZ, TZ, UG, ZW), Eurasian patent (AM, AZ, BY, KG, KZ, MD, RU, TJ, TM), European patent (AT, BE, CH, CY, DE, DK, ES, FI, FR, GB, GR, IE, IT, LU, MC, NL, PT, SE, TR), OAPI patent (BF, BJ, CF, CG, CI, CM, GA, GN, GW, ML, MR, NE, SN, TD, TG).

Published:

— *with international search report*

— *before the expiration of the time limit for amending the claims and to be republished in the event of receipt of amendments*

For two-letter codes and other abbreviations, refer to the "Guidance Notes on Codes and Abbreviations" appearing at the beginning of each regular issue of the PCT Gazette.

WO 02/24702 A1

(54) Title: FUSED HETEROCYCLIC SUCCINIMIDE COMPOUNDS AND ANALOGS THEREOF, MODULATORS OF NUCLEAR HORMONE RECEPTOR FUNCTION

(57) Abstract: Fused cyclic compounds, methods of using such compounds in the treatment of nuclear hormone receptor-associated conditions such as cancer and immune disorders, and pharmaceutical compositions containing such compounds.

Fused Heterocyclic Succinimide Compounds and Analogs Thereof, Modulators of Nuclear Hormone Receptor Function

This application claims priority from U.S. Application Serial No. 60/233,519, filed September 19, 2000, from U.S. Application Serial No. 60/284,730, filed April 18, 2001, and from U.S. Application Serial No. 60/284,438, filed April 18, 2001, which provisional applications are incorporated herein by reference in their entirety.

Field of the Invention

The present invention relates to fused cyclic compounds, to methods of using such compounds in the treatment of nuclear hormone receptor-associated conditions such as cancer, and to pharmaceutical compositions containing such compounds.

Background of the Invention

Nuclear hormone receptors (NHR's) constitute a large super-family of ligand-dependent and sequence-specific transcription factors. Members of this family influence transcription either directly, through specific binding to the promoter target genes (Evans, in *Science* 240: 889-895 (1988)), or indirectly, via protein-protein interactions with other transcription factors (Jonat et al., *Cell* 62: 1189-1204 (1990), Schuele et al., *Cell* 62: 1217-1226 (1990), and Yang-Yen et al., *Cell* 62: 1205-1215 (1990)). The nuclear hormone receptor super-family (also known in the art as the "steroid/thyroid hormone receptor super-family") includes receptors for a variety of hydrophobic ligands, including cortisol, aldosterone, estrogen, progesterone, testosterone, vitamine D3, thyroid hormone and retinoic acid (Evans, 1988, supra). In addition to these conventional nuclear hormone receptors, the super-family contains a number of proteins that have no known ligands, termed orphan nuclear hormone receptors (Mangelsdorf et al., *Cell* 83: 835-839 (1995), O'Malley et al., *Mol. Endocrinol:* 10: 1293 (1996), Enmark et al., *Mol. Endocrinol.* 10, 1293-1307 (1996) and Giguere, *Endocrin. Rev.* 20, 689-725 (1999)). The conventional nuclear hormone receptors are generally transactivators in the presence of ligand, and can either be active repressors or transcriptionally inert in the absence of ligand. Some of the

orphan receptors behave as if they are transcriptionally inert in the absence of ligand. Others, however, behave as either constitutive activators or repressors. These orphan nuclear hormone receptors are either under the control of ubiquitous ligands that have not been identified, or do not need to bind ligand to exert these activities.

In common with other transcription factors, the nuclear hormone receptors have a modular structure, being comprised of three distinct domains: an N-terminal domain of variable size containing a transcriptional activation function AF-1, a highly conserved DNA binding domain and a moderately conserved ligand-binding domain. The ligand-binding domain is not only responsible for binding the specific ligand but also contains a transcriptional activation function called AF-2 and a dimerisation domain (Wurtz et al., *Nature Struc. Biol.* 3, 87-94 (1996), Parker et al., *Nature Struc. Biol.* 3, 113-115 (1996) and Kumar et al., *Steroids* 64, 310-319 (1999)). Although the overall protein sequence of these receptors can vary significantly, all share both a common structural arrangement indicative of divergence from an ancestral archetype, and substantial homology (especially, sequence identity) at the ligand-binding domain.

The steroid binding nuclear hormone receptors (SB-NHR's) comprise a sub-family of nuclear hormone receptors. These receptors are related in that they share a stronger sequence homology to one another, particularly in the ligand binding domain (LBD), than to the other members of the NHR super-family (Evans, 1988, **supra**) and they all utilize steroid based ligands. Some examples of this sub-family of NHR's are the androgen receptor (AR), the estrogen receptor (ER), the progesterone receptor (PR), the glucocorticoid receptor (GR), the mineralocorticoid receptor (MR), the aldosterone receptor (ALDR) and the steroid and xenobiotic receptor (SXR) (Evans *et al.*, WO 99/35246). Based on the strong sequence homology in the LBD, several orphan receptors may also be members of the SB-NHR sub-family.

Consistent with the high sequence homology found in the LBD for each of the SB-NHR's, the natural ligands for each is derived from a common steroid core. Examples of some of the steroid based ligands utilized by members of the SB-NHR's include cortisol, aldosterone, estrogen, progesterone, testosterone and

dihydrotestosterone. Specificity of a particular steroid based ligand for one SB-NHR versus another is obtained by differential substitution about the steroid core. High affinity binding to a particular SB-NHR, coupled with high level specificity for that particular SB-NHR, can be achieved with only minor structural changes about the steroid core (e.g., Waller et al., *Toxicol. Appl. Pharmacol.* 137, 219-227 (1996) and Mekenyan et al., *Environ. Sci. Technol.* 31, 3702-3711 (1997), binding affinity for progesterone towards the androgen receptor as compared to testosterone).

Numerous synthetically derived steroidal and non-steroidal agonists and antagonists have been described for the members of the SB-NHR family. Many of these agonist and antagonist ligands are used clinically in man to treat a variety of medical conditions. RU486 is an example of a synthetic agonist of the PR, which is utilized as a birth control agent (Vegeto et al., *Cell* 69: 703-713 (1992)), and Flutamide is an example of an antagonist of the AR, which is utilized for the treatment of prostate cancer (Neri et al, *Endo.* 91, 427-437 (1972)). Tamoxifen is an example of a tissues specific modulator of the ER function, that is used in the treatment of breast cancer (Smigel, *J. Natl. Cancer Inst.* 90, 647-648 (1998)). Tamoxifen can function as an antagonist of the ER in breast tissue while acting as an agonist of the ER in bone (Grese et al., *Proc. Natl. Acad. Sci. USA* 94, 14105-14110 (1997)). Because of the tissue selective effects seen for Tamoxifen, this agent and agents like it are referred to as "partial-agonist" or partial-antagonist". In addition to synthetically derived non-endogenous ligands, non-endogenous ligands for NHR's can be obtained from food sources (Regal et al., *Proc. Soc. Exp. Biol. Med.* 223, 372-378 (2000) and Hempstock et al., *J. Med. Food* 2, 267-269 (1999)). The flavanoid phytoestrogens are an example of an unnatural ligand for SB-NHR's that are readily obtained from a food source such as soy (Quella et al., *J. Clin. Oncol.* 18, 1068-1074 (2000) and Banz et al., *J. Med. Food* 2, 271-273 (1999)). The ability to modulate the transcriptional activity of individual NHR by the addition of a small molecule ligand, makes them ideal targets for the development of pharmaceutical agents for a variety of disease states.


As mentioned above, non-natural ligands can be synthetically engineered to serve as modulators of the function of NHR's. In the case of SB-NHR's, engineering

of an unnatural ligand can include the identification of a core structure which mimics the natural steroid core system. This can be achieved by random screening against several SB-NHR's or through directed approaches using the available crystal structures of a variety of NHR ligand binding domains (Bourguet et al., *Nature* 375, 377-382 (1995), Brzozowski, et al., *Nature* 389, 753-758 (1997), Shiau et al., *Cell* 95, 927-937 (1998) and Tanenbaum et al., *Proc. Natl. Acad. Sci. USA* 95, 5998-6003 (1998)). Differential substitution about such a steroid mimic core can provide agents with selectivity for one receptor versus another. In addition, such modifications can be employed to obtain agents with agonist or antagonist activity for a particular SB-NHR. Differential substitution about the steroid mimic core can result in the formation of a series of high affinity agonists and antagonists with specificity for, for example, ER versus PR versus AR versus GR versus MR. Such an approach of differential substitution has been reported, for example, for quinoline based modulators of steroid NHR in *J. Med. Chem.*, 41, 623 (1999); WO 9749709; US 5696133; US 5696130; US 5696127; US 5693647; US 5693646; US 5688810; US 5688808 and WO 9619458, all incorporated herein by reference.

The compounds of the present invention comprise a core which serves as a steroid mimic, and are useful as modulators of the function of steroid binding nuclear hormone receptors, as well as other NHR as described following.

Summary of the Invention

The present invention provides fused cyclic compounds of the following formula I and salts thereof, which compounds are especially useful as modulators of nuclear hormone receptor function:



(I)

12
19

As used in formula I, and throughout the specification, the symbols have the following meanings unless otherwise indicated, and are, for each occurrence, independently selected:

G is an aryl or heterocyclo (e.g., heteroaryl) group, where said group is mono- or polycyclic, and which is optionally substituted at one or more positions, preferably with hydrogen, alkyl or substituted alkyl, alkenyl or substituted alkenyl, alkynyl or substituted alkynyl, halo, cycloalkyl or substituted cycloalkyl, cycloalkenyl or substituted cycloalkenyl, aryl or substituted aryl, heterocyclo or substituted heterocyclo, arylalkyl or substituted arylalkyl, heterocycloalkyl or substituted heterocycloalkyl, CN, $R^1OC=O$, $R^1C=O$, $R^1C=S$, $R^1HNC=O$, $R^1R^2NC=O$, $HOCR^3R^{3'}$, nitro, R^1OCH_2, R^1O, NH_2, NR^4R^5, SR^1, $S=OR^1$, SO_2R^1, SO_2OR^1, $SO_2NR^1R^{1'}$, $(R^1O)(R^{1'}O)P=O$, oxo, $(R^1)(R^{1'})P=O$, or $(R^{1'})(NHR^1)P=O$;

Z_1 is O, S, NH, or NR^6;

Z_2 is O, S, NH, or NR^6;

A_1 is CR^7 or N;

A_2 is CR^7 or N;

Y is J-J'-J" where J is $(CR^7R^{7'})n$ and n = 0-3, J' is a bond or O, S, S=O, SO_2, NH, NR^7, C=O, OC=O, $NR^1C=O$, $CR^7R^{7'}$, $C=CR^8R^{8'}$, $R^2P=O$, $R^2P=S$, $R^2OP=O$, $R^2NHP=O$, $OP=OOR^2$, $OP=ONHR^2$, $OP=OR^2$, OSO_2, $C=NR^7$, NHNH, $NHNR^6$, NR^6NH, N=N, cycloalkyl or substituted cycloalkyl, cycloalkenyl or substituted cycloalkenyl, heterocyclo or substituted heterocyclo or aryl or substituted aryl, and J" is $(CR^7R^{7'})n$ and n = 0-3, where Y is not a bond;

W is $CR^7R^{7'}—CR^7R^{7'}$, $CR^8=CR^{8'}$, $CR^7R^{7'}—C=O$, $NR^9—CR^7R^{7'}$, $N=CR^8$, N=N, $NR^9—NR^{9'}$, $S—CR^7R^{7'}$, $SO—CR^7R^{7'}$, $SO_2—CR^7R^{7'}$, cycloalkyl or substituted cycloalkyl, cycloalkenyl or substituted cycloalkenyl, heterocyclo or substituted heterocyclo, or aryl or substituted aryl, wherein when W is not $NR^9—CR^7R^{7'}$, $N=CR^8$, N=N, $NR^9—NR^{9'}$, $S—CR^7R^{7'}$, $SO—CR^7R^{7'}$, $SO_2—CR^7R^{7'}$, or heterocyclo or substituted heterocyclo, then J' must be O, S, S=O,

13

SO_2, NH, NR^7, OC=O, NR^1C=O, OP=OOR^2, OP=ONHR^2, OSO_2, NHNH, $NHNR^6$, NR^6NH, or N=N;

Q_1 is H, alkyl or substituted alkyl, alkenyl or substituted alkenyl, cycloalkyl or substituted cycloalkyl, cycloalkenyl or substituted cycloalkenyl, heterocycloalkyl or substituted heterocycloalkyl, arylalkyl or substituted arylalkyl, alkynyl or substituted alkynyl, aryl or substituted aryl, heterocyclo (e.g., heteroaryl) or substituted heterocyclo (e.g., substituted heteroaryl), halo, CN, R^1OC=O, R^4C=O, R^5R^6NC=O, $HOCR^7R^{7'}$, nitro, R^1OCH_2, R^1O, NH_2, C=OSR^1, SO_2R^1 or NR^4R^5;

Q_2 is H, alkyl or substituted alkyl, alkenyl or substituted alkenyl, cycloalkyl or substituted cycloalkyl, cycloalkenyl or substituted cycloalkenyl, heterocycloalkyl or substituted heterocycloalkyl, arylalkyl or substituted arylalkyl, alkynyl or substituted alkynyl, aryl or substituted aryl, heterocyclo (e.g., heteroaryl) or substituted heterocyclo (e.g., substituted heteroaryl), halo, CN, R^1OC=O, R^4C=O, R^5R^6NC=O, $HOCR^7R^{7'}$, nitro, R^1OCH_2, R^1O, NH_2, C=OSR^1, SO_2R^1 or NR^4R^5;

L is a bond, $(CR^7R^{7'})n$, NH, NR^5, NH $(CR^7R^{7'})n$, or $NR^5(CR^7R^{7'})n$, where n = 0-3;

R^1 and $R^{1'}$ are each independently H, alkyl or substituted alkyl, cycloalkyl or substituted cycloalkyl, cycloalkenyl or substituted cycloalkenyl, heterocyclo or substituted heterocyclo, cycloalkylalkyl or substituted cycloalkyalkyl, cycloalkenylalkyl or substituted cycloalkenylalkyl, heterocycloalkyl or substituted heterocycloalkyl, aryl or substituted aryl, arylalkyl or substituted arylalkyl;

R^2 is alkyl or substituted alkyl, cycloalkyl or substituted cycloalkyl, cycloalkenyl or substituted cycloalkenyl, heterocyclo or substituted heterocyclo, cycloalkylalkyl or substituted cycloalkylalkyl, cycloalkenylalkyl or substituted cycloalkenylalkyl, heterocycloalkyl or substituted heterocycloalkyl, aryl or substituted aryl, arylalkyl or substituted arylalkyl;

R^3 and $R^{3'}$ are each independently H, alkyl or substituted alkyl, cycloalkyl or substituted cycloalkyl, cycloalkenyl or substituted cycloalkenyl, heterocyclo or substituted heterocyclo, cycloalkylalkyl or substituted cycloalkylalkyl,

14

cycloalkenylalkyl or substituted cycloalkenylalkyl, heterocycloalkyl or substituted heterocycloalkyl, aryl or substituted aryl, arylalkyl or substituted arylalkyl, halo, CN, hydroxylamine, hydroxamide, alkoxy or substituted alkoxy, amino, NR^1R^2, thiol, alkylthio or substituted alkylthio;

R^4 is H, alkyl or substituted alkyl, cycloalkyl or substituted cycloalkyl, cycloalkenyl or substituted cycloalkenyl, heterocyclo or substituted heterocyclo, cycloalkylalkyl or substituted cycloalkylalkyl, cycloalkenylalkyl or substituted cycloalkenylalkyl, heterocycloalkyl or substituted heterocycloalkyl, aryl or substituted aryl, arylalkyl or substituted arylalkyl, $R^1C{=}O$, $R^1NHC{=}O$, SO_2OR^1, or $SO_2NR^1R^{1'}$;

R^5 is alkyl or substituted alkyl, cycloalkyl or substituted cycloalkyl, cycloalkenyl or substituted cycloalkenyl, heterocyclo or substituted heterocyclo, cycloalkylalkyl or substituted cycloalkylalkyl, cycloalkenylalkyl or substituted cycloalkenylalkyl, heterocycloalkyl or substituted heterocycloalkyl, aryl or substituted aryl, arylalkyl or substituted arylalkyl, $R^1C{=}O$, $R^1NHC{=}O$, SO_2R^1, SO_2OR^1, or $SO_2NR^1R^{1'}$;

R^6 is alkyl or substituted alkyl, cycloalkyl or substituted cycloalkyl, cycloalkenyl or substituted cycloalkenyl, heterocyclo or substituted heterocyclo, cycloalkylalkyl or substituted cycloalkylalkyl, cycloalkenylalkyl or substituted cycloalkenylalkyl, heterocycloalkyl or substituted heterocycloalkyl, aryl or substituted aryl, arylalkyl or substituted arylalkyl, CN, OH, OR^1, $R^1C{=}O$, $R^1NHC{=}O$, SO_2R^1, SO_2OR^1, or $SO_2NR^1R^{1'}$;


R^7 and $R^{7'}$ are each independently H, alkyl or substituted alkyl, alkenyl or substituted alkenyl, cycloalkyl or substituted cycloalkyl, cycloalkenyl or substituted cycloalkenyl, heterocyclo or substituted heterocyclo, cycloalkylalkyl or substituted cycloalkylalkyl, cycloalkenylalkyl or substituted cycloalkenylalkyl, heterocycloalkyl or substituted heterocycloalkyl, aryl or substituted aryl, arylalkyl or substituted arylalkyl, halo, CN, OR^1, nitro, hydroxylamine, hydroxylamide, amino, NHR^4, NR^2R^5, NOR^1, thiol, alkylthio or substituted alkylthio, $R^1C{=}O$, $R^1OC{=}O$, $R^1NHC{=}O$, SO_2R^1, SOR^1, $PO_3R^1R^{1'}$, $R^1R^{1'}NC{=}O$, $C{=}OSR^1$, SO_2R^1, SO_2OR^1, or $SO_2NR^1R^{1'}$, or, wherein

A_1 or A_2 contains a group R^7 and W contains a group R^7, said R^7 groups of A_1 or A_2 and W together form a heterocyclic ring;

R^8 and $R^{8'}$ are each independently H, alkyl or substituted alkyl, alkenyl or substituted alkenyl, cycloalkyl or substituted cycloalkyl, cycloalkenyl or substituted cycloalkenyl, heterocyclo or substituted heterocyclo, cycloalkylalkyl or substituted cycloalkyalkyl, cycloalkenylalkyl or substituted cycloalkenylalkyl, heterocycloalkyl or substituted heterocycloalkyl, aryl or substituted aryl, arylalkyl or substituted arylalkyl, nitro, halo, CN, OR^1, amino, NHR^4, NR^2R^5, NOR^1, alkylthio or substituted alkylthio, $C{=}OSR^1$, $R^1OC{=}O$, $R^1C{=}O$, $R^1NHC{=}O$, $R^1R^{1'}NC{=}O$, SO_2OR^1, $S{=}OR^1$, SO_2R^1, $PO_3R^1R^{1'}$, or $SO_2NR^1R^{1'}$; and

R^9 and $R^{9'}$ are each independently H, alkyl or substituted alkyl, alkenyl or substituted alkenyl, cycloalkyl or substituted cycloalkyl, cycloalkenyl or substituted cycloalkenyl, heterocyclo or substituted heterocyclo, cycloalkylalkyl or substituted cycloalkylalkyl, cycloalkenylalkyl or substituted cycloalkenylalkyl, heterocycloalkyl or substituted heterocycloalkyl, aryl or substituted aryl, arylalkyl or substituted arylalkyl, CN, OH, OR^1, $R^1C{=}O$, $R^1OC{=}O$, $R^1NHC{=}O$, SO_2R^1, SO_2OR^1, or $SO_2NR^1R^{1'}$.

Compounds within formula I are novel, a preferred subgenus of which is the following formula Ia:



(Ia)

where G, L, Z_1, Z_2, A_1, A_2, Q_1 and Q_2 are as defined above;

Y' is J-J'-J" where J is $(CR^7R^{7'})n$ and n = 0-3, J' is a bond or O, S, S=O, SO_2, NH, NR^7, $CR^7R^{7'}$, $R^2P{=}O$, $R^2P{=}S$, $R^2OP{=}O$, $R^2NHP{=}O$, $OP{=}OOR^2$, $OP{=}ONHR^2$,

16

OSO_2, NHNH, $NHNR^6$, NR^6NH, N=N, cycloalkyl or substituted cycloalkyl, cycloalkenyl or substituted cycloalkenyl, or heterocyclo or substituted heterocyclo, and J" is $(CR^7R^{7'})n$ and n = 0-3, where Y is not a bond; and

W' is $CR^7R^{7'}$—$CR^7R^{7'}$, $CR^7R^{7'}$—C=O, NR^9—$CR^7R^{7'}$, N=CR^8, N=N, NR^9—$NR^{9'}$, cycloalkyl or substituted cycloalkyl, cycloalkenyl or substituted cycloalkenyl, heterocyclo or substituted heterocyclo, or aryl or substituted aryl, wherein, when W' is not NR^9—$CR^7R^{7'}$, N=CR^8, N=N, NR^9—$NR^{9'}$, or heterocyclo or substituted heterocyclo, then J' must be O, S, S=O, SO_2, NH, NR^7, OP=OOR^2, OP=ONHR^2, OSO_2, NHNH, $NHNR^6$, NR^6NH, or N=N; or alternatively,

Y' is NR^7—CR^7R^7 and W' is CR^8=$CR^{8'}$; or, alternatively,

Y' is $CR^7R^{7'}$—C=O and W' is NR^9—$CR^7R^{7'}$;

where R^2, R^6, R^7, $R^{7'}$, R^8, R^9 and $R^{9'}$ are as defined above and with the provisos that (1) when Y' is -O-, Q_1 and Q_2 are hydrogen, Z_1 and Z_2 are O, W' is $-CH_2-CH_2-$, and A_1 and A_2 are CH, then G-L is not phenyl, monosubstituted phenyl or phenyl which is substituted with two or more of the following groups: methoxy, halo, NO_2, methyl, CH_3-S-, OH, CO_2H, trifluoromethyl, -C(O)-C_6H_5, NH_2, 4-7-epoxy, hexahydro-1H-isoindole-1,3(2H)dione, or -C(O)-CH_3;

(2) when Y' is -O-, Q_1 and Q_2 are hydrogen, Z_1 and Z_2 are O, W' is CH_2-CH_2, and one of A_1 and A_2 is CH and the other is CR^7, then G-L is not unsubstituted phenyl;

(3) when Y' is -O-, Q_1 and Q_2 are hydrogen, Z_1 and Z_2 are O, W' is CH_2-CH_2, and one of A_1 and A_2 is CH and the other is C-CH_3, then G-L is not phenyl substituted with chloro and/or methyl;

(4) when Y' is -O- or -S-, Q_1 and Q_2 are hydrogen, Z_1 and Z_2 are O, W' is CH_2-CH_2, and one of A_1 and A_2 is CH and the other is CH or C-alkyl, then G-L is not N-substituted piperazine-alkyl- or N-substituted imidazolidine-alkyl-;

(5) when Y' is -O-; Q_1 and Q_2 are hydrogen, Z_1 and Z_2 are O, W' is CH_2-CH_2, and A_1 and A_2 are CH, then G-L is not oxazole or triazole;

(6) when Y' is -O-; Q_1 and Q_2 are hydrogen or methyl, Z_1 and Z_2 are O, W' is CH_2-CH_2, and A_1 and A_2 are CH or C-CH_3, then G-L is not thiazole or substituted thiazole (in addition such compounds where G-L is optionally

17

substituted thiadiazole or partially saturated thiazole are optionally removed by proviso where A_1 and A_2 are both CH);

(7) when Y' contains a group J' selected from S, S=O, SO_2, NH, NR^7, R^2P=O, R^2P=S, R^2OP=O, R^2NHP=O, OP=OOR^2, OP=$ONHR^2$, OSO_2, NHNH, NHR^6, NR^6NH or N=N, W' is CR^7R^7- CR^7R^7, and Z_1 and Z_2 are O, then G-L is not unsubstituted phenyl;

(8) when Y' is NR^7, W' is unsubstituted or substituted phenyl, and Q_1 and Q_2 are hydrogen, then Z_1 and Z_2 are not O;

(9) when Y' is -O-, Q_1 and Q_2 are hydrogen, Z_1 and Z_2 are O, W' is dihydroisoxazole bearing an optionally substituted phenyl group, and A_1 and A_2 are CH, then G-L is not unsubstituted phenyl or dichlorophenyl;

(10) when Y' is O, Q_1 and Q_2 are hydrogen, Z_1 and Z_2 are O, W' is ethylene oxide, and A_1 and A_2 are CH, then G-L is not methylphenyl or chlorophenyl;

(11) when Y' is NR^7—CR^7R^7, W' is CR^E=CR^E, Q_1 and Q_2 are hydrogen, A_1 and A_2 are CH, C-CH_3, C-CH_2-C_6H_5 or C-CH_2-CH_3, and Z_1 and Z_2 are O, then G-L is not unsubstituted phenyl, monosubstituted phenyl or methylpyridinyl;

(12) when Y' is CR^7R^7—C=O, W' is NR^9—CR^7R^7, Q_1 and Q_2 are hydrogen, A_1 and A_2 are CH, and Z_1 and Z_2 are O, then G-L is not unsubstituted phenyl;

(13) when Y' is CHR^7—NR^7 where R^7 is unsubstituted phenyl, methoxy or ethoxy and R^7 is unsubstituted phenyl, methyl or -C(O)-C_6H_5, W' is dimethoxyphenylene or unsubstituted phenylene, Z_1 and Z_2 are O, Q_1 and Q_2 are hydrogen, and A_1 and A_2 are CH, C-CN, C-C(O)-C_6H_5, or -C(O)-dimethoxyphenyl, then G-L is not unsubstituted phenyl;

(14) the compound of formula Ia is not 6,10-epithio-4H-thieno-[3',4':5,6]cyclooct[1,2-*f*]isoindole-7,9(5H,8H)-dione, 8-(3,5-dichlorophenyl)-6,6a,9a,10,11,12,-hexahydro-1,3,6,10-tetramethyl-2,2,13-trioxide, (6R,6aR,9aS,10S);

(15) when Y' is O, W' is –CH_2-CH_2-, Q_1 and Q_2 are methyl, Z_1 and Z_2 are O, and A_1 and A_2 are CH, then G-L is not unsubstituted phenyl, phenyl substituted with methoxy, phenyl-alkyl-, or morpholine-alkyl, nor is the


compound bridged to itself through a group L which is alkylene to form a bis compound;

(16) when Y' is –O-, Q_1 and Q_2 are hydrogen, Z_1 and Z_2 are O, W' is CR^7R^7-CR^7R^7, and A_1 and A_2 are CH, then G-L is not an unsubstituted phenyl group; and

(17) when Y' is –O-, Q_1 and Q_2 are hydrogen, Z_1 and Z_2 are O, W' is cyclopentyl, cyclohexyl, 3-phenyl-2-isoxazoline or CR^7R^7-CR^7R^7 where R^7 and $R^{7'}$ are each independently defined as Cl, Br, H and 4-butyrolactone and R^7 and $R^{7'}$ are not all simultaneously H, and A_1 and A_2 are CH, then G-L is not an unsubstituted naphthyl ring or a monosubstituted phenyl ring, where said substituent is methoxy, Br, Cl, NO_2, methyl, ethyl, CH_2-phenyl, S-phenyl, or O-phenyl.

Preferably, compounds of formula I are monomeric, and are not comprised within other oligomers or polymers.

Another preferred novel subgenus is that of the following formula Ib:



Ib

where G, Z_1, Z_2, Q_1 and Q_2 are as defined above;

Y' is J-J'-J" where J is $(CR^7R^{7'})n$ and n = 0-3, J' is a bond or O, S, S=O, SO_2, NH, NR^7, $CR^7R^{7'}$, R^2P=O, R^2P=S, R^2OP=O, R^2NHP=O, OP=OOR^2, OP=$ONHR^2$, OSO_2, NHNH, $NHNR^6$, NR^6NH, N=N, cycloalkyl or substituted cycloalkyl, cycloalkenyl or substituted cycloalkenyl, or heterocyclo or substituted heterocyclo, and J" is $(CR^7R^{7'})n$ and n = 0-3, where Y is not a bond; and

W' is $CR^7R^{7'}$—$CR^7R^{7'}$, $CR^7R^{7'}$—C=O, NR^9—$CR^7R^{7'}$, N=CR^8, N=N, NR^9—$NR^{9'}$, cycloalkyl or substituted cycloalkyl, cycloalkenyl or substituted cycloalkenyl, heterocyclo or substituted heterocyclo, or aryl or substituted aryl, wherein, when W' is not NR^9—$CR^7R^{7'}$, N=CR^8, N=N, NR^9—$NR^{9'}$, or heterocyclo or substituted heterocyclo, then J' must be O, S, S=O, SO_2, NH, NR^7, OP=OOR^2, OP=ONHR^2, OSO_2, NHNH, $NHNR^6$, NR^6NH, or N=N; or alternatively, Y' is $CR^7R^{7'}$-C=O and W' is NR^9- $CR^7R^{7'}$;

L is a bond; and

A_1 and A_2 are as defined above, especially where A_1 and/or A_2 are alkyl or optionally substituted alkyl (preferred such optional substituents being one or more groups V^1 defined below), with the proviso that, when Y' = O and W' = -CH_2-CH_2-, then at least one of A_1 or A_2 is not CH;

with the further provisos (2), (3), (6), (7) and (8) above.

The compounds of formula I and salts thereof comprise a core which can serve as a steroid mimic (and do not require the presence of a steroid-type (e.g., cyclopentanoperhydrophenanthrene analog) structure).

Further Description of the Invention

The following are definitions of terms used in the present specification. The initial definition provided for a group or term herein applies to that group or term throughout the present specification individually or as part of another group, unless otherwise indicated.

The terms "alkyl" and "alk" refers to a straight or branched chain alkane (hydrocarbon) radical containing from 1 to 12 carbon atoms, preferably 1 to 6 carbon atoms. Exemplary such groups include, but are not limited to, methyl, ethyl, propyl, isopropyl, n-butyl, t-butyl, isobutyl, pentyl, hexyl, isohexyl, heptyl, 4,4-dimethylpentyl, octyl, 2,2,4-trimethylpentyl, nonyl, decyl, undecyl, dodecyl, and the like. "Substituted alkyl" refers to an alkyl group substituted with one or more substituents, preferably 1 to 4 substituents, at any available point of attachment. Exemplary substituents include but are not limited to one or more of the following groups: halo (e.g., a single halo substituent or multiple halo substitutents forming, in

the latter case, groups such as a perfluoroalkyl group or an alkyl group bearing Cl_3 or CF_3), alkoxy, alkylthio, hydroxy, carboxy (i.e., -COOH), alkoxycarbonyl, alkylcarbonyloxy, amino (i.e., $-NH_2$), carbamoyl or substituted carbomoyl, carbamate or substituted carbamate, urea or substituted urea, amidinyl or substituted amidinyl, thiol (i.e., -SH), aryl, heterocycle, cycloalkyl, heterocycloalkyl, -S-aryl, -S-heterocycle, -S=O-aryl, -S=O-heterocycle, arylalkyl-O-, $-S(O)_2$-aryl, $-S(O)_2$-heterocycle, $-NHS(O)_2$-aryl, $-NHS(O)_2$-heterocycle, $-NHS(O)_2NH$-aryl, $-NHS(O)_2NH$-heterocycle, $-P(O)_2$-aryl, $-P(O)_2$-heterocycle, $-NHP(O)_2$-aryl, $-NHP(O)_2$-heterocycle, $-NHP(O)_2NH$-aryl, $-NHP(O)_2NH$-heterocycle, -O-aryl, -O-heterocycle, -NH-aryl, -NH-heterocycle, -NHC=O-aryl, -NHC=O-alkyl, -NHC=O-heterocycle, -OC=O-aryl, -OC=O-heterocycle, -NHC=ONH-aryl, -NHC=ONH-heterocycle, -OC=OO-aryl, -OC=OO-heterocycle, -OC=ONH-aryl, -OC=ONH-heterocycle, -NHC=OO-aryl, -NHC=OO-heterocycle, -NHC=OO-alkyl, -C=ONH-aryl, -C=ONH-heterocycle, -C=OO-aryl, -C=OO-heterocycle, $-N(alkyl)S(O)_2$-aryl, $-N(alkyl)S(O)_2$-heterocycle, $-N(alkyl)S(O)_2NH$-aryl, $-N(alkyl)S(O)_2NH$-heterocycle, $-N(alkyl)P(O)_2$-aryl, $-N(alkyl)P(O)_2$-heterocycle, $-N(alkyl)P(O)_2NH$-aryl, $-N(alkyl)P(O)_2NH$-heterocycle, -N(alkyl)-aryl, -N(alkyl)-heterocycle, -N(alkyl)C=O-aryl, -N(alkyl)C=O-heterocycle, -N(alkyl)C=ONH-aryl, -N(alkyl)C=ONH-heterocycle, -OC=ON(alkyl)-aryl, -OC=ON(alkyl)-heterocycle, -N(alkyl)C=OO-aryl, -N(alkyl)C=OO-heterocycle, -C=ON(alkyl)-aryl, -C=ON(alkyl)-heterocycle, $-NHS(O)_2N(alkyl)$-aryl, $-NHS(O)_2N(alkyl)$-heterocycle, $-NHP(O)_2N(alkyl)$-aryl, $NHP(O)_2N(alkyl)$-heterocycle, -NHC=ON(alkyl)-aryl, -NHC=ON(alkyl)-heterocycle, $-N(alkyl)S(O)_2N(alkyl)$-aryl, $-N(alkyl)S(O)_2N(alkyl)$-heterocycle, $-N(alkyl)P(O)_2N(alkyl)$-aryl, $-N(alkyl)P(O)_2N(alkyl)$-heterocycle, -N(alkyl)C=ON(alkyl)-aryl, and -N(alkyl)C=ON(alkyl)-heterocycle. In the aforementioned exemplary substitutents, in each instance, groups such as "alkyl", "aryl" and "heterocycle" can themselves be optionally substituted; for example, "alkyl" in the group "NCH=OO-alkyl" recited above can be optionally substituted so that both "NHC=OO-alkyl" and "NHC=OO-substituted alkyl" are exemplary substitutents. Exemplary alkyl substituents also

include groups such as "T" and "T-R^{12n}" (which are defined below), especially for substituted alkyl groups within A_1 or A_2.

The term "alkenyl" refers to a straight or branched chain hydrocarbon radical containing from 2 to 12 carbon atoms and at least one carbon-carbon double bond. Exemplary such groups include ethenyl or allyl. "Substituted alkenyl" refers to an alkenyl group substituted with one or more substituents, preferably 1 to 4 substituents, at any available point of attachment. Exemplary substituents include, but are not limited to, alkyl or substituted alkyl, as well as those groups recited above as exemplary alkyl substituents.

The term "alkynyl" refers to a straight or branched chain hydrocarbon radical containing from 2 to 12 carbon atoms and at least one carbon to carbon triple bond. Exemplary such groups include ethynyl. "Substituted alkynyl" refers to an alkynyl group substituted with one or more substituents, preferably 1 to 4 substituents, at any available point of attachment. Exemplary substituents include, but are not limited to, alkyl or substituted alkyl, as well as those groups recited above as exemplary alkyl substituents.

The term "cycloalkyl" refers to a fully saturated cyclic hydrocarbon group containing from 1 to 4 rings and 3 to 8 carbons per ring. Exemplary such groups include cyclopropyl, cyclobutyl, cyclopentyl, cyclohexyl, etc. "Substituted cycloalkyl" refers to a cycloalkyl group substituted with one or more substituents, preferably 1 to 4 substituents, at any available point of attachment. Exemplary substituents include, but are not limited to, nitro, cyano, alkyl or substituted alkyl, as well as those groups recited above as exemplary alkyl substituents, and as previously mentioned as preferred aryl substituents in the definition for G. Exemplary substituents also include spiro-attached or fused cyclic substituents, especially cycloalkenyl or substituted cycloalkenyl.

The term "cycloalkenyl" refers to a partially unsaturated cyclic hydrocarbon group containing 1 to 4 rings and 3 to 8 carbons per ring. Exemplary such groups include cyclobutenyl, cyclopentenyl, cyclohexenyl, etc. "Substituted cycloalkenyl" refers to a cycloalkenyl group substituted with one more substituents, preferably 1 to 4 substituents, at any available point of attachment. Exemplary substituents include

but are not limited to nitro, cyano, alkyl or substituted alkyl, as well as those groups recited above as exemplary alkyl substituents, and as previously mentioned as preferred aryl substituents in the definition for G. Exemplary substituents also include spiro-attached or fused cyclic substituents, especially cycloalkyl or substituted cycloalkyl.

The terms "alkoxy" or "alkylthio" refer to an alkyl group as described above bonded through an oxygen linkage (-O-) or a sulfur linkage (-S-), respectively. The terms "substituted alkoxy" or "substituted alkylthio" refer to a substituted alkyl group as described above bonded through an oxygen or sulfur linkage, respectively.

The term "alkoxycarbonyl" refers to an alkoxy group bonded through a carbonyl group.

The term "alkylcarbonyl" refers to an alkyl group bonded through a carbonyl group. The term "alkylcarbonyloxy" refers to an alkylcarbonyl group bonded through an oxygen linkage.

The terms "arylalkyl", "substituted arylalkyl," "cycloalkylalkyl," "substituted cycloalkylalkyl," "cycloalkenylalkyl", "substituted cycloalkenylalkyl", "heterocycloalkyl" and "substituted heterocycloalkyl" refer to aryl, cycloalkyl, cycloalkenyl and heterocyclo groups bonded through an alkyl group, substituted on the aryl, cycloalkyl, cycloalkenyl or heterocyclo and/or the alkyl group where indicated as "substituted."

The term "aryl" refers to cyclic, aromatic hydrocarbon groups which have 1 to 5 aromatic rings, especially monocyclic or bicyclic groups such as phenyl, biphenyl or naphthyl. Where containing two or more aromatic rings (bicyclic, etc.), the aromatic rings of the aryl group may be joined at a single point (e.g., biphenyl), or fused (e.g., naphthyl, phenanthrenyl and the like). "Substituted aryl" refers to an aryl group substituted by one or more substituents, preferably 1,2,3,4 or 5 substituents, at any point of attachment. Exemplary substituents include, but are not limited to, nitro, cycloalkyl or substituted cycloalkyl, cycloalkenyl or substituted cycloalkenyl, cyano, alkyl-$S(O)_m$- (m=0, 1 or 2), alkyl or substituted alkyl, as well as those groups recited above as exemplary alkyl substituents and as previously mentioned as preferred aryl substituents in the definition for G. Exemplary substituents also include fused cyclic

substituents, such as heterocyclo or cycloalkenyl, or substituted heterocyclo or cycloalkenyl, groups (e.g., thereby forming a fluoroenyl, tetrahydronapthalenyl, or dihydroindenyl group).

"Carbamoyl" refers to the group –CONH- which is bonded on one end to the remainder of the molecule and on the other to hydrogen or an organic moiety (such as alkyl, substituted alkyl, aryl, substituted aryl, heterocycle, alkylcarbonyl, hydroxyl and substituted nitrogen). "Carbamate" refers to the group –O-CO-NH- which is bonded on one end to the remainder of the molecule and on the other to hydrogen or an organic moiety (such as those listed above). "Urea" refers to the group -NH-CO-NH- which is bonded on one end to the remainder of the molecule and on the other to hydrogen or an organic moiety (such as those listed above). "Amidinyl" refers to the group –C(=NH)(NH_2). "Substituted carbamoyl," "substituted carbamate," "substituted urea" and "substituted amidinyl" refer to carbamoyl, carbamate, urea or amidinyl groups as described above in which one more of the hydrogen groups are replaced by an organic moiety (such as those listed above).

The terms "heterocycle", heterocyclic" and "heterocyclo" refer to fully saturated, or partially or fully unsaturated, including aromatic (i.e., "heteroaryl") cyclic groups (for example, 3 to 7 membered monocyclic, 7 to 11 membered bicyclic, or 10 to 16 membered tricyclic ring systems) which have at least one heteroatom in at least one carbon atom-containing ring. Each ring of the heterocyclic group containing a heteroatom may have 1, 2, 3, or 4 heteroatoms selected from nitrogen atoms, oxygen atoms and/or sulfur atoms, where the nitrogen and sulfur heteroatoms may optionally be oxidized and the nitrogen heteroatoms may optionally be quaternized. (The term "heteroarylium" refers to a heteroaryl group bearing a quaternary nitrogen atom and thus a positive charge.) The heterocyclic group may be attached to the remainder of the molecule at any heteroatom or carbon atom of the ring or ring system. Exemplary monocyclic heterocyclic groups include ethylene oxide, azetidinyl, pyrrolidinyl, pyrrolyl, pyrazolyl, oxetanyl, pyrazolinyl, imidazolyl, imidazolinyl, imidazolidinyl, oxazolyl, oxazolidinyl, isoxazolinyl, isoxazolyl, thiazolyl, thiadiazolyl, thiazolidinyl, isothiazolyl, isothiazolidinyl, furyl, tetrahydrofuryl, thienyl, oxadiazolyl, piperidinyl, piperazinyl, 2-oxopiperazinyl, 2-oxopiperidinyl, 2-oxopyrrolodinyl, 2-oxoazepinyl,

azepinyl, hexahydrodiazepinyl, 4-piperidonyl, pyridyl, pyrazinyl, pyrimidinyl, pyridazinyl, triazinyl, triazolyl, tetrazolyl, tetrahydropyranyl, morpholinyl, thiamorpholinyl, thiamorpholinyl sulfoxide, thiamorpholinyl sulfone, 1,3-dioxolane and tetrahydro-1,1-dioxothienyl, and the like. Exemplary bicyclic heterocyclic groups include indolyl, isoindolyl, benzothiazolyl, benzodioxolyl, benzoxazolyl, benzoxadiazolyl, benzothienyl, quinuclidinyl, quinolinyl, tetrahydroisoquinolinyl, isoquinolinyl, benzimidazolyl, benzopyranyl, indolizinyl, benzofuryl, benzofurazanyl, chromonyl, coumarinyl, benzopyranyl, cinnolinyl, quinoxalinyl, indazolyl, pyrrolopyridyl, furopyridinyl (such as furo[2,3-c]pyridinyl, furo[3,2-b]pyridinyl] or furo[2,3-b]pyridinyl), dihydrobenzodioxinyl, dihydrodioxidobenzothiophenyl, dihydroisoindolyl, dihydroindolyl, dihydroquinolinyl, dihydroquinazolinyl (such as 3,4-dihydro-4-oxo-quinazolinyl), triazinylazepinyl, tetrahydroquinolinyl and the like. Exemplary tricyclic heterocyclic groups include carbazolyl, benzidolyl, phenanthrolinyl, dibenzofuranyl, acridinyl, phenanthridinyl, xanthenyl and the like.

"Substituted heterocycle," "substituted heterocyclic," and "substituted heterocyclo" (such as "substituted heteroaryl") refer to heterocycle, heterocyclic or heterocyclo groups substituted with one or more substituents, preferably 1 to 4 substituents, at any available point of attachment. Exemplary substituents include, but are not limited to, cycloalkyl or substituted cycloalkyl, cycloalkenyl or substituted cycloalkenyl, nitro, oxo (i.e., = O), cyano, alkyl-$S(O)_m$- (m = 0, 1 or 2), alkyl or substituted alkyl, as well as those groups recited above as exemplary alkyl substituents, and as previously mentioned as preferred heterocyclo substituents in the definition for G.

The term "quaternary nitrogen" refers to a tetravalent positively charged nitrogen atom including, for example, the positively charged nitrogen in a tetraalkylammonium group (e.g., tetramethylammonium, N-methylpyridinium), the positively charged nitrogen in protonated ammonium species (e.g., trimethyl-hydroammonium, N-hydropyridinium), the positively charged nitrogen in amine N-oxides (e.g., N-methyl-morpholine-N-oxide, pyridine-N-oxide), and the positively charged nitrogen in an N-amino-ammonium group (e.g., N-aminopyridinium).

The terms "halogen" or "halo" refer to chlorine, bromine, fluorine or iodine.

25

The terms "hydroxylamine" and "hydroxylamide" refer to the groups OH-NH- and OH-NH-CO-, respectively.

When a functional group is termed "protected", this means that the group is in modified form to mitigate, especially preclude, undesired side reactions at the protected site. Suitable protecting groups for the methods and compounds described herein include, without limitation, those described in standard textbooks, such as Greene, T. W. et al., *Protective Groups in Organic Synthesis*, Wiley, N.Y. (1991).

When a term such as "(CRR)n" is used, it denotes an optionally substituted alkyl chain existing between the two fragments to which it is bonded, the length of which chain is defined by the range described for the term n. An example of this is n=0-3, implying from zero to three (CRR) units existing between the two fragments, which are attached to the primary and terminal (CRR) units. In the situation where the term n is set to zero (n = 0) then a bond exists between the two fragments attached to (CRR).

Unless otherwise indicated, any heteroatom with unsatisfied valences is assumed to have hydrogen atoms sufficient to satisfy the valences.

Divalent groups, such as those in the definition of W (e.g., NR^9-$CR^7R^{7'}$), may be bonded in either direction to the remainder of the molecule (e.g, $-\underset{|}{A_1}-NR^9-CR^7R^{7'}-\underset{|}{A_2}-$ or, $-\underset{|}{A_1}-CR^7R^{7'}-NR^9-\underset{|}{A_2}-$ for the aforementioned group within the definition of W).

Carboxylate anion refers to a negatively charged group $-COO^-$.

The compounds of formula I form salts which are also within the scope of this invention. Reference to a compound of the formula I herein is understood to include reference to salts thereof, unless otherwise indicated. The term "salt(s)", as employed herein, denotes acidic and/or basic salts formed with inorganic and/or organic acids and bases. In addition, when a compound of formula I contains both a basic moiety, such as but not limited to a pyridine or imidazole, and an acidic moiety such as but not limited to a carboxylic acid, zwitterions ("inner salts") may be formed and are included within the term "salt(s)" as used herein. Pharmaceutically acceptable (i.e., non-toxic, physiologically acceptable) salts are preferred, although other salts are also

useful, e.g., in isolation or purification steps which may be employed during preparation. Salts of the compounds of the formula I may be formed, for example, by reacting a compound I with an amount of acid or base, such as an equivalent amount, in a medium such as one in which the salt precipitates or in an aqueous medium followed by lyophilization.

The compounds of formula I which contain a basic moiety, such as but not limited to an amine or a pyridine or imidazole ring, may form salts with a variety of organic and inorganic acids. Exemplary acid addition salts include acetates (such as those formed with acetic acid or trihaloacetic acid, for example, trifluoroacetic acid), adipates, alginates, ascorbates, aspartates, benzoates, benzenesulfonates, bisulfates, borates, butyrates, citrates, camphorates, camphorsulfonates, cyclopentanepropionates, digluconates, dodecylsulfates, ethanesulfonates, fumarates, glucoheptanoates, glycerophosphates, hemisulfates, heptanoates, hexanoates, hydrochlorides, hydrobromides, hydroiodides, hydroxyethanesulfonates (e.g., 2-hydroxyethanesulfonates), lactates, maleates, methanesulfonates, naphthalenesulfonates (e.g., 2-naphthalenesulfonates), nicotinates, nitrates, oxalates, pectinates, persulfates, phenylpropionates (e.g., 3-phenylpropionates), phosphates, picrates, pivalates, propionates, salicylates, succinates, sulfates (such as those formed with sulfuric acid), sulfonates (such as those mentioned herein), tartrates, thiocyanates, toluenesulfonates such as tosylates, undecanoates, and the like.

The compounds of formula I which contain an acidic moiety, such but not limited to a carboxylic acid, may form salts with a variety of organic and inorganic bases. Exemplary basic salts include ammonium salts, alkali metal salts such as sodium, lithium and potassium salts, alkaline earth metal salts such as calcium and magnesium salts, salts with organic bases (for example, organic amines) such as benzathines, dicyclohexylamines, hydrabamines (formed with N,N-bis(dehydroabietyl)ethylenediamine), N-methyl-D-glucamines, N-methyl-D-glycamides, t-butyl amines, and salts with amino acids such as arginine, lysine and the like. Basic nitrogen-containing groups may be quaternized with agents such as lower alkyl halides (e.g. methyl, ethyl, propyl, and butyl chlorides, bromides and iodides), dialkyl sulfates (e.g. dimethyl, diethyl, dibutyl, and diamyl sulfates), long

chain halides (e.g. decyl, lauryl, myristyl and stearyl chlorides, bromides and iodides), aralkyl halides (e.g. benzyl and phenethyl bromides), and others.

Prodrugs and solvates of the compounds of the invention are also contemplated herein. The term "prodrug" as employed herein denotes a compound which, upon administration to a subject, undergoes chemical conversion by metabolic or chemical processes to yield a compound of the formula I, or a salt and/or solvate thereof. Solvates of the compounds of formula I include, for example, hydrates.

Compounds of the formula I, and salts thereof, may exist in their tautomeric form (for example, as an amide or imino ether). All such tautomeric forms are contemplated herein as part of the present invention.

All stereoisomers of the present compounds (for example, those which may exist due to asymmetric carbons on various substituents), including enantiomeric forms and diastereomeric forms, are contemplated within the scope of this invention. Individual stereoisomers of the compounds of the invention may, for example, be substantially free of other isomers (e.g., as a pure or substantially pure optical isomer having a specified activity), or may be admixed, for example, as racemates or with all other, or other selected, stereoisomers. The chiral centers of the present invention may have the S or R configuration as defined by the IUPAC 1974 Recommendations. The racemic forms can be resolved by physical methods, such as, for example, fractional crystallization, separation or crystallization of diastereomeric derivatives or separation by chiral column chromatography. The individual optical isomers can be obtained from the racemates by any suitable method, including without limitation, conventional methods, such as, for example, salt formation with an optically active acid followed by crystallization.

All configurational isomers of the compounds of the present invention are contemplated, either in admixture or in pure or substantially pure form. The definition of compounds of the present invention embraces both cis (*Z*) and trans (*E*) alkene isomers, as well as cis and trans isomers of cyclic hydrocarbon or heterocyclo rings. In certain cases, for example, the exo or endo conformation can be preferred for the fused ring system bonded to G-L in formula I. For example, for androgen receptor antagonists (or selective androgen receptor modulators), where Y is O or

NR^7, the exo configuration can be preferred, while for most other definitions of Y, the endo configuration can be preferred. As can be appreciated, the preferred configuration can be a function of the particular compound and its preferred activity. Separation of configurational isomers can be achieved by any suitable method, such as column chromatography.

Throughout the specifications, groups and substituents thereof may be chosen to provide stable moieties and compounds.

Embodiments indicated herein as exemplary or preferred are intended to be illustrative and not limiting.

29

Methods of Preparation

The compounds of the present invention may be prepared by methods such as those illustrated in the following Schemes I to XI. Solvents, temperatures, pressures, and other reaction conditions may readily be selected by one of ordinary skill in the art. Starting materials are commercially available or readily prepared by one of ordinary skill in the art. Combinatorial techniques may be employed in the preparation of compounds, for example, where the intermediates possess groups suitable for these techniques. See the following which describe other methods which may be employed in the preparation of compounds of the present invention: Li, *et al.*, *Eur. J. Org. Chem.* **9**, 1841-1850 (1998); Li, Y-Q, *Synlett.* **5**, 461-464 (1996); Thiemann, *et al.*, *Bull. Chem. Soc. Jpn.* **67**, 1886-1893 (1994); Tsuge *et al.*, *Heterocycles* **14**, 423-428 (1980); Ward *et al.*, *Can J. Chem.* **75**, 681-693 (1997); Ward *et al.*, *Can J. Chem.* **69**, 1487-1497 (1991); Ward *et al.*, *Tetrahedron Lett.* **31**, 845-848 (1990); Fleming *et al.*, *J. Org. Chem.* **44**, 2280-2282 (1979); Jankowski *et al.*, *J. Organomet. Chem.* **595**, 109-113 (2000); Keglevich *et al.*, *J. Organomet. Chem.* **579**, 182-189 (1999); Keglevich *et al.*, *J. Organomet. Chem.* **570**, 49-539 (1998); Jankowski *et al.*, *Hetroat. Chem.* **7**, 369-374 (1996); Jankowski *et al.*, *J. Am. Chem. Soc.* **113**, 7011-7017 (1991); Quin *et al.*, *Tetrahedron Lett.* **31**, 6473-6476 (1990); Quin *et al.*, *J. Org. Chem.* **59**, 120-129 (1994); Quin *et al.*, *J. Org. Chem.* **58**, 6212-6216 (1993); Quin *et al.*, *Phosphorous, Sulfur Silicon Relat. Elem.* **63**, 349-362 (1991); Quin *et al.*, *Hetroat. Chem.* **2**, 359-367 (1991); Hussong *et al.*, *Phosphorus Sulfur.* **25**, 201-212 (1985); Quin *et al.*, *J. Org. Chem.* **51**, 3341-3347 (1986); Myers *et al.*, *J. Am. Chem. Soc.* **114**, 5684-5692 (1992); Myers *et al.*, *J. Am. Chem. Soc.* **113**, 6682-6683 (1991); Shen *et al.*,US Patent No. 5817679; Cordone *et al.*, *J. Am. Chem. Soc.* **111**, 5969-5970 (1989); Jung *et al.*, *J. Chem. Soc. Commun.* 630-632 (1984); Lay *et al.*, *J. Am. Chem. Soc.* **104**, 7658-7659 (1982); Gonzalez *et al.*, *J. Am. Chem. Soc.* **117**, 3405-3421 (1995); Kreher *et al.*, *Chem Ber.* **125**, 183-189 (1992); Simig *et al.*, *Synlett.* **7**, 425-426 (1990); Sha *et al.*, *J. Org. Chem.* **55**, 2446-2450 (1990); Drew *et al.*, *J. Chem. Soc., Perkin Trans. 1* **7**, 1277-1284 (1985); Kreher *et al.*, *Anorg. Chem., Org Chem.* **31B**, 599-604 (1976); Avalos *et al.*, *Tetrahedron Lett.* **39**, 9301-9304 (1998); Gousse *et al.*, *Macromolecules* **31**, 314-321 (1998); Mikhailyuchenko


30

et al., Khim. Geterotsikl. Soedin. 6, 751-758 (1993); Lubowitz *et al.*, US Patent No. 4476184; Padwa *et al., J. Org. Chem.* 61, 3706-3714 (1996); Schlessinger *et al., J. Org. Chem.* 59, 3246-3247 (1994); Buchmeiser *et al.*, WO Publication No. 9827423; Tanabe *et al.*, Japanese Patent Document JP 07144477; Mochizucki *et al.*, Japanese Patent Document JP 63170383; Hosoda *et al.*, Japanese Patent Document JP 62053963; Onaka *et al.*, Japanese Patent Document JP 62053964; Kato *et al.*, Japanese Patent Document JP 53086035; Kato *et al.*, Japanese Patent Document JP 51088631; Tottori *et al.*, Japanese Patent Document JP 49124225; Augustin *et al.*, German Patent Document DD101271; Title *et al.*, French Patent Document FR 2031538; Gousse *et al., Polym. Int.* 48, 723-731 (1999); Padwa *et al., J. Org. Chem.* 62, 4088-4096 (1997); Theurillat-Moritz *et al., Tetrahedron: Asymmetry* 7, 3163-3168 (1996); Mathews *et al., J. Carbohydr. Chem.* 14, 287-97 (1995); Srivastava *et al., Natl. Acad. Sci. Lett. (India)* 15, 41-44 (1992); Mayorga *et al., Rev. Cubana Quim.* 4, 1-6 (1988); Kondoli *et al., J. Chem. Res., Synop.* 3, 76 (1987); Primelles *et al., Cent. Azucar* 7-14 (1985); Solov'eva *et al., Khim. Geterotsikl. Soedin.* 5, 613-15 (1984); Liu *et al., Yaoxue Xuebao* 18, 752-759 (1983); Joshi *et al., Indian J. Chem, Sect. B.* 22B, 131-135 (1983); Amos *et al.*, WO Publication No. 9829495; Odagiri *et al.*, US Patent No. 4670536; Gallucci *et al.*, European Patent Document EP 355435; Redmore, D. US Patent No. 3821232; Nakano *et al., Heterocycles* 35, 37-40 (1993); Tomisawa *et al., Chem. Pharm. Bull.* 36, 1692-1697 (1988); Krow *et al., J. Heterocycl. Chem.* 22, 131-135 (1985); Krow *et al., J. Org. Chem.* 47, 1989-1993 (1982); Liu *et al., Yaoxue Xuebao* 18, 752-759 (1983); Nishikawa *et al., Yaoxue Xuebao* JP 01061457; and/or Rice *et al., J. Med. Chem.* 11, 183-185 (1968).

All documents cited in the present specification, such as those cited in this "Methods of Preparation" as well as other sections herein, are incorporated herein by reference in their entirety. Reference to any document herein is not to be construed as an admission that such document is prior art.

31

Scheme 1




II III IV

As illustrated in Scheme I, a diene of formula II can be reacted with a dienophile of formula III, under conditions readily selected by one skilled in the art (such as by the addition of heat ("Δ")), to obtain a compound of formula IV, which is a compound of formula I. An intermediate diene of formula II can be obtained from commercial sources or readily made by one skilled in the art, for example, in accordance with the following literature documents and the references found therein: Hofman *et al., J. Agric. Food Chem.* 45, 898-906 (1997); Baciocchi *et al., J. Chem. Soc., Perkin Trans. 2* 8, 821-824 (1975); Wu *et al., J. Heterocycles* 38, 1507-1518 (1994); Yin *et al., Tetrahedron Lett.* 38, 5953-5954 (1997); Mic'ovic' *et al.,Tetrahedron* 20, 2279-2287 (1964); Gorbunova *et al., J. Org. Chem.*. 35, 1557-1566 (1999); Rassu *et al., Chem. Soc. Rev.* 29, 109-118 (2000); Kaberdin *et al., Russ. Chem . Rev.*. 68, 765-779 (1999); Barluenga *et al., Aldrichimica Acta* 32, 4-15 (1999); Bogdanowicz-Szwed *et al., Pol. Wiad. Chem.* 52, 821-842 (1998); Casiraghi *et al., Adv. Asymmetric Synth.* 3, 113-189 (1998); and/or Baeckvall *et al., Chem. Rev.* 98, 2291-2312 (1998). An intermediate dieneophile of formula III can be obtained from commercial sources or readily made by one skilled in the art, for example, in accordance with the following literature references and the references found therein: Deshpande *et al., Heterocycles* 51, 2159-2162 (1999); Seijas *et al., J. Chem. Res., Synop.* 7, 420-421 (1999); Langer *et al., Eur. J. Org. Chem.* 7, 1467-1470 (1998); Kita *et al.,* Japanese Patent Document JP 09194458; Lopez-Alvarado *et al., J. Org. Chem.* 61, 5865-5870 (1996); Condon *et al.,* US Patent No. 5523277; Sasakihara *et al.,* Japanese Patent Document JP 04290868; Igarashi *et al.,* Japanese Patent Document JP 04149173; Aoyama *et al.,* Japanese Patent Document JP 04134063; Aoyama *et al.,* Japanese Patent Document JP 04134062; Pastor *et al., J. Org. Chem.* 53, 5776-5779 (1988); and/or Takahashi *et al., Chem. Lett.* 6, 1229-1232 (1987).

32

Scheme II




V VI IV

As illustrated in Scheme II, compounds of formula I can be obtained by reaction of a primary amine of formula V with a substituted anhydride-like intermediate of formula VI, for example, in a solvent such as acetic acid with or without heating, to yield a compound of formula IV, which is a compound of formula I. Primary amines of formula V can be obtained from commercial sources or readily synthesized by one skilled in the art. Anhydride-like agents of formula VI can be obtained from commercial sources or readily synthesized by one skilled in the art. The documents listed following describe exemplary approaches for the synthesis of intermediates of formula VI as well as synthetic approaches which can be applied to the synthesis of compounds of formula IV (all incorporated herein by reference in their entirety): Kohler, E. P.; Tishler, M.; Potter, H.; Thompson, H. T. *J. Am. Chem. Soc.* 1939, 1057-1061; Yur'ev, Y. K.; Zefirov, N. S. *J. Gen. Chem. U.S.S.R. (Engl. Transl.)* 1961, 31, 772-5; Norman G. Gaylord US Patent No. 3,995,099; Schueler, P. E.; Rhodes, Y. E. *J. Org. Chem.* 1974, 39, 2063-9; Ishitobi, H.; Tanida, H; Tsuji, T. *Bull. Chem. Soc. Japan* 1971, 44, 2993-3000; Stájer, G.; Virág, M.; Szabó, A. E.; Bernáth, G.; Sohár, P.; Sillanpää, R. *Acta. Chem. Scand.* 1996, 50, 922-30; Hart, H.; Ghosh, T. *Tetrahedron Lett.* 1988,29,881-884; Kato, M.; Yamamoto, S.; Yoshihara, T.; Furuichi, K; Miwa, T. *Chem. Lett.* 1987, 1823-1826; Kottwitz, J.; Vorbrüggen, H. *Synthesis* 1995, 636-637; Creary, X. *J. Org. Chem.* 1975, 40, 3326-3331; Alder, K.; Ache, H.-J.; Flock, F. H. *Chem. Ber.* 1960, 93, 1888-1895; Toder, B. H.; Branca, S. J.; Dieter, R. K.; Smith, A. B. III *Synth. Commun.* 1975, 5, 435-439; Sprague, P. W.; Heikes, J. E.; Gougoutas, J. Z.; Malley, M. F.; Harris, D. N.; and/or Greenberg, R. *J. Med. Chem.* 1985, 28, 1580-1590.

The aforementioned approach(es) can be applied in a combinatorial fashion, for example, by utilizing a multi-well reaction block such as is described in Waldemar Ruediger, Wen-Jeng Li, John W., Allen Jr., and Harold N. Weller III, US Patent No. 5,961,925, Apparatus for Synthesis of Multiple Organic Compounds With Pinch Valve Block (incorporated herein by reference in its entirety). By utilizing the above-mentioned multi-well reaction block, one can, for example, perform multiples of 96 reactions at a time. Solvent can then be removed from the reaction tubes without removal from the reaction block and the crude products can be precipitated using a base such as sodium bicarbonate. The precipitates can be collected by filtration of the reaction block and then the desired products can be transferred directly to 96 well plates for screening. In this fashion, a large array of compounds of formula I can be synthesized, and tests conducted as desired by an automated approach.

34


Scheme III



Scheme III describes a method for preparing an intermediate compound of formula VI which can be used to synthesize a compound of formula I, as described in Scheme II. As described in Scheme III, a diene of formula II can be reacted with a dieneophile of formula VII to yield the intermediate of formula VI. The methods applied to obtain such a transformation are analogous to those described in Scheme I.

35

Scheme IV




II VIII IX VI

Scheme IV describes a method for preparing an intermediate compound of formula VI which can be used to synthesize a compound of formula I, as described in Scheme II. As shown in Scheme IV, a diene of formula II can be reacted with a dieneophile of formula VIII to yield the intermediate of formula IX. The intermediate of formula IX can be dehydrated to an anhydride-like intermediate of formula VI. Dehydration of the bis-acid intermediate of formula IX to can be achieved by a variety of methods, such as those known to one skilled in the art and described in the following documents and the references embodied therein: Sprague *et al., J. Med. Chem.* **28**, 1580-1590 (1985); and/or Retemi *et al., J. Org. Chem.* **61**, 6296-6301 (1996).

Schemes I to IV describe general methods for the synthesis of compounds of formula I, and intermediates thereof, in which substitution about the ring system is incorporated directly, for example, at the level of the intermediate diene, dienophile, anhydride-like intermediate and amine groups. In addition to these approaches, additional substitution can be incorporated onto an already-prepared compound of formula I by a variety of approaches to prepare other compounds of the formula I. Exemplary methods for further substitution are described in Schemes V to XI.

37


Scheme V



Scheme V describes one such approach to incorporating additional substitution into a structure of formula I. As illustrated in Scheme V, a compound of formula X, which is a compound of formula I where A_1 and A_2 are CR^7, W is NH—CHR^7 and Y is CHR^7—CHR^7, can be functionalized at the free amine of the group W by reaction with any of a variety of electrophilic agents such as acid halides or alkyl halides in the presence of base, for example, by methods known by one skilled in the art. In Scheme V, X is a leaving group, and a compound of formula XI is a compound of formula I where A_1 and A_2 are CR^7, W is NR^7—CHR^7 and Y is CHR^7—CHR^7.

38


Scheme VI



Scheme VI describes an additional approach for further incorporating substitution onto a compound of formula I. As illustrated in Scheme VI, a compound of formula XII, which is a compound of formula I where A_1 and A_2 are CR^7, W is S—CHR^7 and Y is CHR^7—CHR^7, can be partially oxidized with an oxidizing agent such as mCPBA or other agents such as those known to one skilled in the art, to give the sulfoxide analog of formula XIII, which is a compound of formula I where A_1 and A_2 are CR^7, W is SO—CHR^7 and Y is CHR^7—CHR^7. Further treatment of a compound of formula XIII with an oxidizing agent such as mCPBA or other agents such as those known to one skilled in the art, can yield the sulphone analog of formula XIV, which is a compound of formula I where A_1 and A_2 are CR^7, W is SO_2—CHR^7 and Y is CHR^7—CHR^7. Alternatively, a compound of formula XII can be converted directly to a compound of formula XIV by prolonged treatment with an oxidizing agent, such as mCPBA, or with other agents such as those known to one skilled in the art.

39

Scheme VII




Scheme VII describes another approach to incorporating additional substitution onto a compound of formula I. As illustrated in Scheme VII, a diene of formula IIa can be reacted with a dienophile of formula III, as described in Scheme I, to yield a compound of formula IVa, which is a compound of formula I where Y is O, A_2 is CR^7 and A_1 is C—$(CH_2)_q$—T. The compound of formula IVa can be reacted with a reagent of formula R^{12}—T' to obtain a compound of formula IVb or IVc which are compounds of formula I where Y is O, A_2 is CR^7 and A_1 is C—$(CH_2)_q$—T'—R^{12} or C—$(CH_2)_q$—T—R^{12}, respectively. The reagent R^{12}—T' can be obtained from commercial sources.or can readily be prepared by one skilled in the art.

In the above Scheme, R^{12} has the same definition as R^7 defined earlier, q is zero or an integer from 0-8, and T is defined either as (1) a nucleophilic center such as, but not limited, to a nitrogen, oxygen or sulfur-containing group, capable of undergoing a nucleophilic substitution reaction with the leaving group T' or (2) a leaving group capable undergoing a nucleophilic substitution reaction with a nucleophilic group T' (such as, but not limited, to a nitrogen, oxygen or sulfur-containing nucleophilic group). T' has the same definition as T. In the present case, for example, a nucleophilic substitution reaction occurs when the attacking reagent (the nucleophile) brings an electron pair to the substrate, using this pair to form the new bond, and the leaving group (the nucleofuge) comes away with the electron pair, leaving as an anionic intermediate. For a detailed discussion of the mechanism of

aliphatic nucleophilic substitutions and a review of specific aliphatic nucleophilic substitution reactions see *Advanced Organic Chemistry, Reactions, Mechanisms, and Structure, 4th Addition.* Jerry March (Ed.), John Wiley & Sons, New York (1992) 293-500 and the references therein. Compounds of the formulae **IVa, IVb,** or **IVc** may, of course, be employed in the methods described herein (especially, in the treatment of nuclear hormone receptor-associated conditions) without undergoing further reaction of T or T'.

41


Scheme VIII



An alternate approach to compounds of formula IVa, IVb and IVc is illustrated in Scheme VIII. For this approach, techniques such as those described in Schemes II, III and IV can be applied to the preparation of an intermediate of formula VIa, where T and q are as defined in Scheme VII. The intermediate of formula VIa can be reacted with a substitited amine of formula V, as described in Scheme II, to yield the compound of formula IVa, which is a compound of formula I where Y is O, A_2 is CR^7 and A_1 is C—$(CH_2)_q$—T. The compound of formula IVa can be treated in the manner described in Scheme VII to obtain compounds of formula IVb or IVc which are compounds of formula I where Y is O, A_2 is CR^7 and A_1 is C—$(CH_2)_q$—T'—R^{12} or C—$(CH_2)_q$—T—R^{12}, respectively.


42

Scheme IX




Scheme IX describes another approach to incorporating further substitution onto a compound of formula I. As illustrated in Scheme IX (where X is a leaving group), a diene of formula IIb can be reacted with a dienophile of formula III, as described in Scheme I, to yield a compound of formula IVe, which is a compound of formula I where Y is NH, and A_1 and A_2 are CR^7. The compound of formula IVe can be functionalized at the free amine by reacting with a variety of electrophilic agents such as acid halides or alkyl halides in the presence of base, for example by methods known by one skilled in the art and described in Scheme V, to yield a compound of formula IVf, which is a compound of formula I where Y is NR^7 and A_1 and A_2 are CR^7.

Scheme X



An alternate approach to compounds of formula IVe and IVf is illustrated in Scheme X. For this approach, techniques as described in Schemes II, III and IV can be applied to the preparation of an intermediate of formula VIb. The intermediate of formula VIb can be reacted with a substituted amine of formula V, as described in Scheme II, to yield a compound of formula IVe, which is a compound of formula I where Y is NH, and A_1 and A_2 are CR^7. The latter intermediate can be treated in the manner described in Scheme V to obtain a compound of formula IVf, which is a compound of formula I where Y is NR^7, and A_1 and A_2 are CR^7.


Scheme XI



Scheme XI describes another approach to incorporating additional substitution onto a compound of formula I. As illustrated in Scheme XI, a diene of formula IIc can be reacted with a dienophile of formula III, as described in Scheme I, to yield a compound of formula IVg, which is a compound of formula I where Y is SO and A_1 and A_2 are CR^7. A compound of formula IVg can be treated with an oxidizing agent such as mCPBA, as described in Scheme VI, to yield a compound of formula IVh, which is a compound of formula I where Y is SO_2 and A_1 and A_2 are CR^7.

45

Scheme XII




XV XVI

Scheme XII describes another approach to incorporating additional substitution onto a compound of formula I. As illustrated in Scheme XII, a compound of formula XV, which can be prepared in accordance with the above Schemes, can be incubated in the presence of a suitable enzyme or microorganism resulting in the formation of a hydroxylated analog of formula XVI. Such a process can be employed to yield regiospecific as well as enantiospecific incorporation of a hydroxyl group into a molecule of formula XV by a specific microorganism or by a series of different microorganisms. Such microorganisms can, for example, be bacterial, yeast or fungal in nature and can be obtained from distributors such as ATCC or identified for use in this method such as by methods known to one skilled in the art. Compound XVI is a compound of formula I where Y is as described above and A_1 and A_2 are preferably CR^7.

46

Scheme XIII




XVII XVIII

Scheme XIII describes another approach to incorporating additional substitution onto a compound of formula I. As illustrated in Scheme XIII, a compound of formula XVII, which can be prepared in accordance with the above Schemes, can be incubated in the presence of a suitable enzyme or microorganism resulting in the formation of a diol analog of formula XVIII. Such a process can be employed to yield regiospecific as well as enantiospecific transformation of a compound of formula XVII to a 1-2 diol of formula XVIII by a specific microorganism or by a series of different microorganisms. Such microorganisms can, for example, be bacterial, yeast or fungal in nature and can be obtained from distributors such as ATCC or identified for use in this method such as by methods known to one skilled in the art. Compound XVIII is a compound of formula I where Y is as described above and A_1 and A_2 are preferably CR^7.

The present invention also provides the methods of Schemes XII and XIII.


Thus, in one embodiment, the present invention provides a method for preparation of a compound of the following formula XVI, or salt thereof:



XVI

where the symbols are as defined herein,


comprising the steps of contacting a compound of the following formula XV, or salt thereof:



XV


where the symbols are as defined above;
with an enzyme or microorganism capable of catalyzing the hydroxylation of said compound XV to form said compound XVI, and effecting said hydroxylation.

In another preferred embodiment, the present invention provides a method for preparation of a compound of the following formula XVIII, or salt thereof:



XVIII

where the symbols are as defined herein,
comprising the steps of contacting a compound of the following formula XVII, or salt thereof:



XVII

where the symbols are as defined above;
with an enzyme or microorganism capable of catalyzing the opening of the epoxide ring of compound XVII to form the diol of said compound XVIII, and effecting said ring opening and diol formation.

All stereoconfigurations of the unspecified chiral centers of the compounds of the formulae XV, XVI, XVII and XVIII are contemplated in the methods of the present invention, either alone (that is, substantially free of other stereoisomers) or in admixture with other stereoisomeric forms. Conversion of one isomer selectively

(e.g., hydroxylation of the exo isomer preferentially to hydroxylation of the endo isomer) when contacting an isomeric mixture is a preferred embodiment of the invention. Conversion to one isomer selectively (e.g., hydroxylation on the exo face "exo isomer" preferentially to the endo face "endo isomer" or regioselective opening of an epoxide to form only one of two possible regioisomers of a trans diol) is a preferred embodiment of the invention. Hydroxylation of an achiral intermediate to form a single optical isomer of the hydroxylated product is also a preferred embodiment of the invention. Resolution of a recemic mixture of an intermediate by selective hydroxylation, or epoxide ring opening and diol formation, to generate one of the two possible optical isomers is also a preferred embodiment of the invention. The term "resolution" as used herein denotes partial, as well as, preferably, complete resolution.

The terms "enzymatic process" or "enzymatic method", as used herein, denote a process or method of the present invention employing an enzyme or microorganism. The term "hydroxylation", as used herein, denotes the addition of a hydroxyl group to a methylene group as described above. Hydroxylation can be achieved, for example, by contact with molecular oxygen according to the methods of the present invention. Diol formation can be achieved, for example, by contact with water according to the methods of the present invention. Use of "an enzyme or microorganism" in the present methods includes use of two or more, as well as a single, enzyme or microorganism.

The enzyme or microorganism employed in the present invention can be any enzyme or microorganism capable of catalyzing the enzymatic conversions described herein. The enyzmatic or microbial materials, regardless of origin or purity, can be employed in the free state or immobilized on a support such as by physical adsorption or entrapment. Microorganisms or enzymes suitable for use in the present invention can be selected by screening for the desired activity, for example, by contacting a candidate microorganism or enzyme with a starting compound XV or XVII or salt thereof, and noting conversion to the corresponding compound XVI or XVIII or salt thereof. The enzyme may, for example, be in the form of animal or plant enzymes or mixtures thereof, cells of microorganisms, crushed cells, extracts of cells, or of synthetic origin.

Exemplary microorganisms include those within the genera: *Streptomyces* or *Amycolatopsis*. Particularly preferred microorganisms are those within the species *Streptomyces griseus*, especially *Streptomyces griseus* ATCC 10137, and *Amycolatopsis orientalis* such as ATCC 14930, ATCC 21425, ATCC 35165, ATCC 39444, ATCC 43333, ATCC 43490, ATCC 53550, ATCC 53630, and especially

ATCC 43491. The term "ATCC" as used herein refers to the accession number of the American Type Culture Collection, 10801 University Blvd., Manassas Virginia 20110-2209, the depository for the organism referred to. It should be understood that mutants of these organisms are also contemplated by the present invention, for use in the methods described herein, such as those modified by the use of chemical, physical (for example, X-rays) or biological means (for example, by molecular biology techniques).

Preferred enzymes include those derived from microorganisms, particularly those microorganisms described above. Enzymes may be isolated, for example, by extraction and purification methods such as by methods known to those of ordinary skill in the art. An enzyme may, for example, be used in its free state or in immobilized form. One embodiment of the invention is that where an enzyme is adsorbed onto a suitable carrier, e.g., diatomaceous earth (porous Celite Hyflo Supercel), microporous polypropylene (Enka Accurel® polypropylene powder), or a nonionic polymeric adsorbent such as Amberlite® XAD-2 (polystyrene) or XAD-7 (polyacrylate) from Rohm and Haas Co. When employed to immobilize an enzyme, a carrier may control the enzyme particle size and prevent aggregation of the enzyme particles when used in an organic solvent. Immobilization can be accomplished, for example, by precipitating an aqueous solution of the enzyme with cold acetone in the presence of the Celite Hyflo Supercel followed by vacuum drying, or in the case of a nonionic polymeric adsorbent, incubating enzyme solutions with adsorbent on a shaker, removing excess solution and drying enzyme-adsorbent resins under vacuum. While it is desirable to use the least amount of enzyme possible, the amount of enzyme required will vary depending upon the specific activity of the enzyme used.

Hydroxylation as described above can occur *in vivo*. For example, liver enzyme can selectively, relative to the endo isomer, hydroxylate the exo isomer of a compound of the present invention. In conducting the methods of the present invention outside the body, liver microsomal hydroxylase can be employed as the enzyme for catalysis.

These processes may also be carried out using microbial cells containing an enzyme having the ability to catalyze the conversions. When using a microorganism to perform the conversion, these procedures are conveniently carried out by adding the cells and the starting material to the desired reaction medium.

Where microorganisms are employed, the cells may be used in the form of intact wet cells or dried cells such as lyophilized, spray-dried or heat-dried cells, or in the form of treated cell material such as ruptured cells or cell extracts. Cell extracts immobilized on Celite® or Accurel® polypropylene as described earlier may also be

employed. The use of genetically engineered organisms is also contemplated. The host cell may be any cell, e.g. *Escherichia coli*, modified to contain a gene or genes for expressing one or more enzymes capable of catalysis as described herein.

Where one or more microorganisms are employed, the enzymatic methods of the present invention may be carried out subsequent to the fermentation of the microorganism (two-stage fermentation and conversion), or concurrently therewith, that is, in the latter case, by *in situ* fermentation and conversion (single-stage fermentation and conversion).

Growth of the microorganisms can be achieved by one of ordinary skill in the art by the use of an appropriate medium. Appropriate media for growing microorganisms include those which provide nutrients necessary for the growth of the microbial cells. A typical medium for growth includes necessary carbon sources, nitrogen sources, and elements (e.g. in trace amounts). Inducers may also be added. The term "inducer", as used herein, includes any compound enhancing formation of the desired enzymatic activity within the microbial cell.

Carbon sources can include sugars such as maltose, lactose, glucose, fructose, glycerol, sorbitol, sucrose, starch, mannitol, propylene glycol, and the like; organic acids such as sodium acetate, sodium citrate, and the like; and alcohols such as ethanol, propanol and the like.

Nitrogen sources can include N-Z amine A, corn steep liquor, soy bean meal, beef extracts, yeast extracts, molasses, baker's yeast, tryptone, nutrisoy, peptone, yeastamin, amino acids such as sodium glutamate and the like, sodium nitrate, ammonium sulfate and the like.

Trace elements can include magnesium, manganese, calcium, cobalt, nickel, iron, sodium and potassium salts. Phosphates may also be added in trace or, preferably, greater than trace amounts.

The medium employed can include more than one carbon or nitrogen source or other nutrient.

Preferred media for growth include aqueous media.

The agitation and aeration of the reaction mixture affects the amount of oxygen available during the conversion process when conducted, for example, in shake-flask cultures or fermentor tanks during growth of microorganisms.

Incubation of the reaction medium is preferably at a temperature between about 4 and about 60°C. The reaction time can be appropriately varied depending upon the amount of enzyme used and its specific activity. Reaction times may be reduced by increasing the reaction temperature and/or increasing the amount of enzyme added to the reaction solution.

It is also preferred to employ an aqueous liquid as the reaction medium, although an organic liquid, or a miscible or immiscible (biphasic) organic/aqueous liquid mixture, may also be employed. The amount of enzyme or microorganism employed relative to the starting material is selected to allow catalysis of the enzymatic conversions of the present invention.

Solvents for the organic phase of a biphasic solvent system may be any organic solvent immiscible in water, such as toluene, cyclohexane, xylene, trichlorotrifluoroethane and the like. The aqueous phase is conveniently of water, preferably deionized water, or a suitable aqueous buffer solution, especially a phosphate buffer solution. The biphasic solvent system preferably comprises between about 10 to 90 percent by volume of organic phase and between about 90 to 10 percent by volume of aqueous phase, and most preferably contains at or about 20 percent by volume of organic phase and at or about 80 percent by volume of the aqueous phase.

An exemplary embodiment of such processes starts with preparation of an aqueous solution of the enzyme(s) or microbes to be used. For example, the preferred enzyme(s) or microbes can be added to a suitable amount of an aqueous solvent, such as phosphate buffer or the like. This mixture is preferably adjusted to and maintained at a desired pH.

The compounds XVI and XVIII produced by the processes of the present invention can be isolated and purified, for example, by methods such as extraction, distillation, crystallization, and column chromatography.

Preferred Compounds

A preferred subgenus of the compounds of the present invention includes compounds of the formula I or salts thereof wherein one or more, preferably all, of the following substituents are as defined below:

G is an aryl or heterocyclo (e.g., heteroaryl) group, where said group is mono- or polycyclic, and which is optionally substituted at one or more positions, preferably with hydrogen, alkyl or substituted alkyl, alkenyl or substituted alkenyl, alkynyl or substituted alkynyl, halo, cycloalkyl or substituted cycloalkyl, cycloalkenyl or substituted cycloalkenyl, aryl or substituted aryl, heterocyclo or substituted heterocyclo, arylalkyl or substituted arylalkyl, heterocycloalkyl or substituted heterocycloalkyl, CN, $R^1OC=O$, $R^1C=O$,

52

$R^1HNC=O$, $R^1R^2NC=O$, $HOCR^3R^{3'}$, nitro, R^1OCH_2, R^1O, NH_2, NR^4R^5, $S=OR^1$, SO_2R^1, $SO_2NR^1R^{1'}$, $(R^1)(R^{1'})P=O$, or $(R^{1'})(NHR^1)P=O$;

Z_1 is O, S, NH, or NR^6;

Z_2 is O, S, NH, or NR^6;

A_1 is CR^7 or N;

A_2 is CR^7 or N;

Y is J-J'-J" where J is $(CR^7R^{7'})n$ and n = 0-3, J' is a bond or O, S, S=O, SO_2, NH, OC=O, C=O, NR^7, $CR^7R^{7'}$, $R^2P=O$, $R^2P=S$, $R^2OP=O$, $R^2NHP=O$, $OP=OOR^2$, $OP=ONHR^2$, $OP=OR^2$, OSO_2, NHNH, $NHNR^6$, NR^6NH, N=N, cycloalkyl or substituted cycloalkyl, cycloalkenyl or substituted cycloalkenyl, or heterocyclo or substituted heterocyclo, and J" is $(CR^7R^{7'})n$ and n = 0-3, where Y is not a bond;

W is $CR^7R^{7'}$—$CR^7R^{7'}$, $CR^7R^{7'}$—C=O, NR^9—$CR^7R^{7'}$, $N=CR^8$, N=N, NR^9—$NR^{9'}$, cycloalkyl or substituted cycloalkyl, cycloalkenyl or substituted cycloalkenyl, heterocyclo or substituted heterocyclo, or aryl or substituted aryl, wherein, when W is not NR^9—$CR^7R^{7'}$, $N=CR^8$, N=N, NR^9—$NR^{9'}$, or heterocyclo or substituted heterocyclo, then J' must be O, S, S=O, SO_2, NH, NR^7, $OP=OOR^2$, $OP=ONHR^2$, OSO_2, NHNH, $NHNR^6$, NR^6NH, or N=N;

Q_1 is H, alkyl or substituted alkyl, alkenyl or substituted alkenyl, cycloalkyl or substituted cycloalkyl, cycloalkenyl or substituted cycloalkenyl, heterocycloalkyl or substituted heterocycloalkyl, arylalkyl or substituted arylalkyl, alkynyl or substituted alkynyl, aryl or substituted aryl, heterocyclo (e.g., heteroaryl) or substituted heterocyclo (e.g., substituted heteroaryl), halo, CN, $R^1OC=O$, $R^4C=O$, $R^5R^6NC=O$, $HOCR^7R^{7'}$, nitro, R^1OCH_2, R^1O, NH_2, or NR^4R^5;

Q_2 is H, alkyl or substituted alkyl, alkenyl or substituted alkenyl, cycloalkyl or substituted cycloalkyl, cycloalkenyl or substituted cycloalkenyl, heterocycloalkyl or substituted heterocycloalkyl, arylalkyl or substituted arylalkyl, alkynyl or substituted alkynyl, aryl or substituted aryl, heterocyclo (e.g., heteroaryl) or substituted heterocyclo (e.g., substituted heteroaryl), halo,

53

CN, $R^1OC=O$, $R^4C=O$, $R^5R^6NC=O$, $HOCR^7R^{7'}$, nitro, R^1OCH_2, R^1O, NH_2, or NR^4R^5;

L is a bond, $(CR^7R^{7'})n$, NH, NR^5 or $NR^5(CR^7R^{7'})n$, where n = 0-3;

R^1 and $R^{1'}$ are each independently H, alkyl or substituted alkyl, cycloalkyl or substituted cycloalkyl, cycloalkenyl or substituted cycloalkenyl, heterocyclo or substituted heterocyclo, cycloalkylalkyl or substituted cycloalkyalkyl, cycloalkenylalkyl or substituted cycloalkenylalkyl, heterocycloalkyl or substituted heterocycloalkyl, aryl or substituted aryl, arylalkyl or substituted arylalkyl;

R^2 is alkyl or substituted alkyl, cycloalkyl or substituted cycloalkyl, cycloalkenyl or substituted cycloalkenyl, heterocyclo or substituted heterocyclo, cycloalkylalkyl or substituted cycloalkylalkyl, cycloalkenylalkyl or substituted cycloalkenylalkyl, heterocycloalkyl or substituted heterocycloalkyl, aryl or substituted aryl, arylalkyl or substituted arylalkyl;

R^3 and $R^{3'}$ are each independently H, alkyl or substituted alkyl, cycloalkyl or substituted cycloalkyl, cycloalkenyl or substituted cycloalkenyl, heterocyclo or substituted heterocyclo, cycloalkylalkyl or substituted cycloalkylalkyl, cycloalkenylalkyl or substituted cycloalkenylalkyl, heterocycloalkyl or substituted heterocycloalkyl, aryl or substituted aryl, arylalkyl or substituted arylalkyl, halo, CN, hydroxylamine, hydroxamide, alkoxy or substituted alkoxy, amino, NR^1R^2, thiol, alkylthio or substituted alkylthio;

R^4 is H, alkyl or substituted alkyl, cycloalkyl or substituted cycloalkyl, cycloalkenyl or substituted cycloalkenyl, heterocyclo or substituted heterocyclo, cycloalkylalkyl or substituted cycloalkylalkyl, cycloalkenylalkyl or substituted cycloalkenylalkyl, heterocycloalkyl or substituted heterocycloalkyl, aryl or substituted aryl, arylalkyl or substituted arylalkyl, $R^1C=O$, $R^1NHC=O$, or $SO_2NR^1R^{1'}$;

R^5 is alkyl or substituted alkyl, cycloalkyl or substituted cycloalkyl, cycloalkenyl or substituted cycloalkenyl, heterocyclo or substituted heterocyclo, cycloalkylalkyl or substituted cycloalkylalkyl, cycloalkenylalkyl or substituted cycloalkenylalkyl, heterocycloalkyl or substituted heterocycloalkyl, aryl or

substituted aryl, arylalkyl or substituted arylalkyl, $R^1C=O$, $R^1NHC=O$, SO_2R^1, or $SO_2NR^1R^{1'}$;

R^6 is alkyl or substituted alkyl, cycloalkyl or substituted cycloalkyl, cycloalkenyl or substituted cycloalkenyl, heterocyclo or substituted heterocyclo, cycloalkylalkyl or substituted cycloalkylalkyl, cycloalkenylalkyl or substituted cycloalkenylalkyl, heterocycloalkyl or substituted heterocycloalkyl, aryl or substituted aryl, arylalkyl or substituted arylalkyl, CN, OH, OR^1, $R^1C=O$, $R^1NHC=O$, SO_2R^1, or $SO_2NR^1R^{1'}$;

R^7 and $R^{7'}$ are each independently H, alkyl or substituted alkyl, alkenyl or substituted alkenyl, cycloalkyl or substituted cycloalkyl, cycloalkenyl or substituted cycloalkenyl, heterocyclo or substituted heterocyclo, cycloalkylalkyl or substituted cycloalkylalkyl, cycloalkenylalkyl or substituted cycloalkenylalkyl, heterocycloalkyl or substituted heterocycloalkyl, aryl or substituted aryl, arylalkyl or substituted arylalkyl, halo, CN, OR^1, nitro, hydroxylamine, hydroxylamide, amino, NHR^4, NR^2R^5, NOR^1, thiol, alkylthio or substituted alkylthio, $R^1C=O$, $R^1OC=O$, $R^1NHC=O$, SOR^1, $PO_3R^1R^{1'}$, $R^1R^{1'}NC=O$, $C=OSR^1$, SO_2R^1, or $SO_2NR^1R^{1'}$;

R^8 and $R^{8'}$ are each independently H, alkyl or substituted alkyl, alkenyl or substituted alkenyl, cycloalkyl or substituted cycloalkyl, cycloalkenyl or substituted cycloalkenyl, heterocyclo or substituted heterocyclo, cycloalkylalkyl or substituted cycloalkyalkyl, cycloalkenylalkyl or substituted cycloalkenylalkyl, heterocycloalkyl or substituted heterocycloalkyl, aryl or substituted aryl, arylalkyl or substituted arylalkyl, nitro, halo, CN, OR^1, amino, NHR^4, NR^2R^5, NOR^1, alkylthio or substituted alkylthio, $C=OSR^1$, $R^1OC=O$, $R^1C=O$, $R^1NHC=O$, $R^1R^{1'}NC=O$, $S=OR^1$, SO_2R^1, $PO_3R^1R^{1'}$, or $SO_2NR^1R^{1'}$;

R^9 and $R^{9'}$ are each independently H, alkyl or substituted alkyl, cycloalkyl or substituted cycloalkyl, cycloalkenyl or substituted cycloalkenyl, heterocyclo or substituted heterocyclo, cycloalkylalkyl or substituted cycloalkylalkyl, cycloalkenylalkyl or substituted cycloalkenylalkyl, heterocycloalkyl or

55

substituted heterocycloalkyl, aryl or substituted aryl, arylalkyl or substituted arylalkyl, CN, OH, OR^1, $R^1C{=}O$, $R^1OC{=}O$, $R^1NHC{=}O$, or $SO_2NR^1R^{1'}$;

especially where the groups W and Y of this preferred subgenus are also within the definitions of W' and Y' of formula Ia, with the provisos (1) to (14) of said formula Ia where appropriate to this subgenus, and most preferably where (i) when Y' is -O- and W' is $CR^7R^{7'}$—CR^7R^7, A_1 and A_2 are not simultaneously CH; and (ii) when L is a bond, G is not an unsubstituted phenyl group.

Another, more preferred subgenus of the compounds of the invention includes compounds of the formula I or salts thereof wherein one or more, preferably all, of the following substituents are as defined below:

G is an aryl or heterocyclo (e.g., heteroaryl) group, where said group is mono- or polycyclic, and which is optionally substituted at one or more positions, preferably with hydrogen, alkyl or substituted alkyl, alkenyl or substituted alkenyl, alkynyl or substituted alkynyl, halo, cycloalkyl or substituted cycloalkyl, cycloalkenyl or substituted cycloalkenyl, aryl or substituted aryl, heterocyclo or substituted heterocyclo, arylalkyl or substituted arylalkyl, heterocycloalkyl or substituted heterocycloalkyl, CN, $R^1C{=}O$, $R^1HNC{=}O$, $R^1R^2NC{=}O$, $HOCR^1R^{1'}$, nitro, R^1OCH_2, R^1O, NH_2, NR^4R^5, SO_2R^1, or $SO_2NR^1R^{1'}$;

Z_1 is O;

Z_2 is O;

A_1 is CR^7;

A_2 is CR^7;

Y is J-J'-J" where J is $(CR^7R^{7'})n$ and n = 0-3, J' is a bond or O, S, S=O, SO_2, NH, NR^7, $CR^7R^{7'}$, $R^2P{=}O$, $R^2P{=}S$, $R^2OP{=}O$, $R^2NHP{=}O$, $OP{=}OOR^2$, $OP{=}ONHR^2$, $OP{=}OR^2$, OSO_2, NHNH, $NHNR^6$, NR^6NH, N=N, cycloalkyl or substituted cycloalkyl, cycloalkenyl or substituted cycloalkenyl, or heterocyclo or substituted heterocyclo, and J" is $(CR^7R^{7'})n$ and n = 0-3, where Y is not a bond;

W is $CR^7R^{7'}$—$CR^7R^{7'}$, $CR^7R^{7'}$—C=O, NR^9—$CR^7R^{7'}$, N=CR^8, N=N, NR^9—$NR^{9'}$, cycloalkyl or substituted cycloalkyl, cycloalkenyl or substituted cycloalkenyl, heterocyclo or substituted heterocyclo, or aryl or substituted aryl, wherein, when W is not NR^9—$CR^7R^{7'}$, N=CR^8, N=N, NR^9—$NR^{9'}$, or heterocyclo or substituted heterocyclo, then J' must be O, S, S=O, SO_2, NH, NR^7, OP=OOR^2, OP=ONHR^2, OSO_2, NHNH, NHNR^6, NR^6NH, or N=N;

Q_1 is H, alkyl or substituted alkyl, alkenyl or substituted alkenyl, cycloalkyl or substituted cycloalkyl, cycloalkenyl or substituted cycloalkenyl, heterocycloalkyl or substituted heterocycloalkyl, arylalkyl or substituted arylalkyl, alkynyl or substituted alkynyl, aryl or substituted aryl, heterocyclo (e.g., heteroaryl) or substituted heterocyclo (e.g., substituted heteroaryl), halo, CN, R^4C=O, R^5R^6NC=O, HO$CR^7R^{7'}$, nitro, R^1OCH_2, R^1O, NH_2, or NR^4R^5;

Q_2 is H, alkyl or substituted alkyl, alkenyl or substituted alkenyl, cycloalkyl or substituted cycloalkyl, cycloalkenyl or substituted cycloalkenyl, heterocycloalkyl or substituted heterocycloalkyl, arylalkyl or substituted arylalkyl, alkynyl or substituted alkynyl, aryl or substituted aryl, heterocyclo (e.g., heteroaryl) or substituted heterocyclo (e.g., substituted heteroaryl), halo, CN, R^4C=O, R^5R^6NC=O, HO$CR^7R^{7'}$, nitro, R^1OCH_2, R^1O, NH_2, or NR^4R^5;

L is a bond;

R^1 and $R^{1'}$ are each independently H, alkyl or substituted alkyl, cycloalkyl or substituted cycloalkyl, cycloalkenyl or substituted cycloalkenyl, heterocyclo or substituted heterocyclo, cycloalkylalkyl or substituted cycloalkyalkyl, cycloalkenylalkyl or substituted cycloalkenylalkyl, heterocycloalkyl or substituted heterocycloalkyl, aryl or substituted aryl, arylalkyl or substituted arylalkyl;

R^2 is alkyl or substituted alkyl, cycloalkyl or substituted cycloalkyl, cycloalkenyl or substituted cycloalkenyl, heterocyclo or substituted heterocyclo, cycloalkylalkyl or substituted cycloalkylalkyl, cycloalkenylalkyl or substituted cycloalkenylalkyl, heterocycloalkyl or substituted heterocycloalkyl, aryl or substituted aryl, arylalkyl or substituted arylalkyl;

R^3 and $R^{3'}$ are each independently H, alkyl or substituted alkyl, cycloalkyl or substituted cycloalkyl, cycloalkenyl or substituted cycloalkenyl, heterocyclo or substituted heterocyclo, cycloalkylalkyl or substituted cycloalkylalkyl, cycloalkenylalkyl or substituted cycloalkenylalkyl, heterocycloalkyl or substituted heterocycloalkyl, aryl or substituted aryl, arylalkyl or substituted arylalkyl, halo, CN, alkoxy or substituted alkoxy, amino, NR^1R^2, alkylthio or substituted alkylthio;

R^4 is H, alkyl or substituted alkyl, cycloalkyl or substituted cycloalkyl, cycloalkenyl or substituted cycloalkenyl, heterocyclo or substituted heterocyclo, cycloalkylalkyl or substituted cycloalkylalkyl, cycloalkenylalkyl or substituted cycloalkenylalkyl, heterocycloalkyl or substituted heterocycloalkyl, aryl or substituted aryl, arylalkyl or substituted arylalkyl, $R^1C{=}O$, $R^1NHC{=}O$, or $SO_2NR^1R^{1'}$;

R^5 is alkyl or substituted alkyl, cycloalkyl or substituted cycloalkyl, cycloalkenyl or substituted cycloalkenyl, heterocyclo or substituted heterocyclo, cycloalkylalkyl or substituted cycloalkylalkyl, cycloalkenylalkyl or substituted cycloalkenylalkyl, heterocycloalkyl or substituted heterocycloalkyl, aryl or substituted aryl, arylalkyl or substituted arylalkyl, $R^1C{=}O$, $R^1NHC{=}O$, SO_2R^1, or $SO_2NR^1R^{1'}$;

R^6 is alkyl or substituted alkyl, cycloalkyl or substituted cycloalkyl, cycloalkenyl or substituted cycloalkenyl, heterocyclo or substituted heterocyclo, cycloalkylalkyl or substituted cycloalkylalkyl, cycloalkenylalkyl or substituted cycloalkenylalkyl, heterocycloalkyl or substituted heterocycloalkyl, aryl or substituted aryl, arylalkyl or substituted arylalkyl, CN, OH, OR^1, $R^1C{=}O$, $R^1NHC{=}O$, SO_2R^1, or $SO_2NR^1R^{1'}$;

R^7 and $R^{7'}$ are each independently H, alkyl or substituted alkyl, alkenyl or substituted alkenyl, cycloalkyl or substituted cycloalkyl, cycloalkenyl or substituted cycloalkenyl, heterocyclo or substituted heterocyclo, cycloalkylalkyl or substituted cycloalkylalkyl, cycloalkenylalkyl or substituted cycloalkenylalkyl, heterocycloalkyl or substituted heterocycloalkyl, aryl or substituted aryl, arylalkyl or substituted arylalkyl, halo, CN, OR^1, nitro,

amino, NHR^4, NR^2R^5, alkylthio or substituted alkylthio, $R^1C{=}O$, $R^1NHC{=}O$, SO_2R^1, $R^1R^{1'}NC{=}O$, or $SO_2NR^1R^{1'}$;

R^8 and $R^{8'}$ are each independently H, alkyl or substituted alkyl, alkenyl or substituted alkenyl, cycloalkyl or substituted cycloalkyl, cycloalkenyl or substituted cycloalkenyl, heterocyclo or substituted heterocyclo, cycloalkylalkyl or substituted cycloalkyalkyl, cycloalkenylalkyl or substituted cycloalkenylalkyl, heterocycloalkyl or substituted heterocycloalkyl, aryl or substituted aryl, arylalkyl or substituted arylalkyl, nitro, halo, CN, OR^1, amino, NHR^4, NR^2R^5, alkylthio or substituted alkylthio, $R^1C{=}O$, $R^1NHC{=}O$, $R^1R^{1'}NC{=}O$, SO_2R^1, or $SO_2NR^1R^{1'}$; and

R^9 and $R^{9'}$ are each independently H, alkyl or substituted alkyl, cycloalkyl or substituted cycloalkyl, cycloalkenyl or substituted cycloalkenyl, heterocyclo or substituted heterocyclo, cycloalkylalkyl or substituted cycloalkylalkyl, cycloalkenylalkyl or substituted cycloalkenylalkyl, heterocycloalkyl or substituted heterocycloalkyl, aryl or substituted aryl, arylalkyl or substituted arylalkyl, CN, OH, OR^1, $R^1C{=}O$, $R^1NHC{=}O$, or $SO_2NR^1R^{1'}$;

especially where the groups W and Y of this preferred subgenus are also within the definitions of W' and Y' of formula Ia, with the provisos (1) to (14) of said formula Ia where appropriate to this subgenus, and most preferably where (i) when Y' is -O- and W' is $CR^7R^{7'}$—$CR^7R^{7'}$; A_1 and A_2 are not simultaneously CH; and (ii) when L is a bond, G is not an unsubstituted phenyl group.

A particularly preferred subgenus of the compounds of the invention includes compounds of the formula I or salts thereof wherein one or more, preferably all, of the substituents are as defined below:

G is an aryl (especially, phenyl or naphthyl) or heterocyclo (especially those heterocyclo groups G of the compounds of the Examples herein) group, where said group is mono- or polycyclic, and which is optionally substituted at one or more positions, preferably with substituents as exemplified in any of the compounds of the Examples herein;

59

L is a bond, $(CR^7R^{7'})n$ (where n is 1 and R^7 and $R^{7'}$ are each independently H, alkyl or substituted alkyl), or -CH2-NH-;

A_1 and A_2 are each independently CR^7 where R^7 (i) is hydrogen, alkyl or substituted alkyl, arylalkyl or substituted arylalkyl, alkenyl or substituted alkenyl (for example, alkenyl substituted with aryl (especially, phenyl or naphthyl) or substituted aryl, or alkenyl substituted with heterocyclo or substituted heterocyclo), aryl or substituted aryl, heterocyclo or substituted heterocyclo, heterocycloalkyl or substituted heterocycloalkyl, where, for each, preferred substituents are one or more groups selected from V^1 (especially A_1 and A_2 groups of the formula CR^7 where R^7 for each of A_1 and/or A_2 is independently selected from C_{1-4} alkyl which alkyl is substituted by one or more groups V^1), or (ii) forms, together with R^7 of a group W (especially where W is $CR^7R^{7'}$-$CR^7R^{7'}$), a heterocyclic ring;

V^1 is OH, CN, halo, -O-aryl, -O-substituted aryl, -O-heterocyclo, -O-substituted heterocyclo, -O-CO-alkyl, -O-CO-substituted alkyl, -O-(alkylsilyl), -O-arylalkyl, -O-substituted arylalkyl, -O-CO-alkyl, -O-CO-substituted alkyl, -O-CO-arylalkyl, -O-CO-substituted arylalkyl, -O-CO-aryl, -O-CO-substituted aryl, -O-CO-heterocyclo, -O-CO-substituted heterocyclo, -S-(optionally substituted aryl)-NH-CO-(optionally substituted alkyl), -SO-(optionally substituted aryl)-NH-CO-(optionally substituted alkyl), -SO2-(optionally substituted aryl)-NH-CO-(optionally substituted alkyl), -NH-SO2-aryl, -NH-SO2-substituted aryl, -NH-CO-O-(optionally substituted arylalkyl), -NH-CO-O-alkyl, -NH-CO-O-substituted alkyl, -NH-CO-alkyl, -NH-CO-substituted alkyl, -NH-CO-aryl, -NH-CO-substituted aryl, -NH-CO-(optionally substituted arylalkyl), -NH-CO-(optionally substituted alkyl)-O-(optionally substituted aryl), -N(optionally substituted alkyl)(optionally substituted aryl), -N(optionally substituted alkyl)(optionally substituted arylalkyl), -COH, -COOH, -CO-O-alkyl, -CO-O-substituted alkyl, -CO-O-optionally substituted arylalkyl, -CO-aryl, -CO-substituted aryl, -O-CO-NH-aryl, -O-CO-NH-substituted

60

aryl, -CO-NH-aryl, -CO-NH-substituted aryl, -CO-NH-arylalkyl, -CO-NH-substituted arylalkyl, -O-(optionally substituted aryl)-NH-CO-(optionally substituted alkyl);

Y is –O-, -SO-, -N(V^2)-, -CH_2-N(V^2)-, -CO-N(alkyl)-, -CH_2-S-, -CH_2-SO_2-;

V^2 is hydrogen, alkyl, arylalkyl, -CO-alkyl, -CO-O-aryl, -CO-O-arylalkyl;


W is $CR^7R^{7'}$—$CR^7R^{7'}$ (where R^7 and $R^{7'}$ are each independently selected from H, OH, alkyl or substituted alkyl (such as hydroxyalkyl), or where R^7 forms a heterocyclic ring together with R^7 of A_1 or A_2), CR^8=$CR^{8'}$ (where R^8 and $R^{8'}$ are each independently selected from H, alkyl or substituted alkyl (such as hydroxyalkyl)), $CR^7R^{7'}$—C=O (where R^7 and $R^{7'}$ are each hydrogen, or where R^7 forms a heterocyclic ring together with R^7 of A_1 or A_2), N=CR^8 (where R^8 is alkyl), cycloalkyl or substituted cyclalkyl, or heterocyclo or substituted heterocyclo;


Z_1 and Z_2 are O; and


Q_1 and Q_2 are H.


Preferred G-L groups are optionally substituted naphthyl and optionally substituted fused bicyclic heterocyclic groups such as optionally substituted benzo-fused heterocyclic groups (e.g., bonded to the remainder of the molecule through the benzene portion), especially such groups wherein the heterocyclic ring bonded to benzene has 5 members exemplified by benzoxazole, benzothiazole, benzothiadiazole, benzoxadiazole or benzothiophene, for example:

61













62







(e.g., )






or



where

X = halo (esp F), OH, CN, NO_2 or 

(e.g.,  .  or );

U is O or S (where S can optionally be oxygenated, e.g., to SO);

U^1 is CH_3 or CF_3;

63

each U^2 is independently N, CH or CF;


U^3 is N, O or S;

U^4 and U^5, together with the atoms to which they are bonded, form an optionally substituted 5-membered heterocyclic ring which can be partially unsaturated or aromatic and which contains 1 to 3 ring heteroatoms;

each U^6 is independently CH or N; and

(p) denotes optional double bond(s) within the ring formed by U^3, U^4 and U^5.

An especially preferred subgenus includes compounds of the formula I having the following structure, or salts thereof:



where G is an optionally substituted naphthyl or benzo-fused bicyclic heterocyclic group, R^7 is CH_3 or C_{1-4}alkyl substituted by V' and R^7 is H or hydroxyl.

Compounds where R^7 is hydroxyl can provide enhanced water solubility and metabolic stability, relative to the corresponding compounds where R^7 is H, in addition to having good permeability and high systemic blood levels. These hydroxyl-bearing compounds can be obtained *in vivo* by metabolism of the corresponding compound where R^7 is H, as well as by synthetic preparative methods such as those described herein.

Use and Utility

The compounds of the present invention modulate the function of nuclear hormone receptors (NHR), and include compounds which are, for example, agonists,

64

partial agonists, antagonists or partial antagonists of the androgen receptor (AR), the estrogen receptor (ER), the progesterone receptor (PR), the glucocorticoid receptor (GR), the mineralocorticoid receptor (MR), the steroid and xenobiotic receptor (SXR), other steroid binding NHR's, the Orphan receptors or other NHR's. Selective modulation of one such NHR relative to others within the NHR family is preferred. "Modulation" includes, for example, activation (e.g., agonist activity such as selective androgen receptor agonist activity) or inhibition (e.g., antagonist activity).

The present compounds are thus useful in the treatment of NHR-associated conditions. A "NHR-associated condition", as used herein, denotes a condition or disorder which can be treated by modulating the function of a NHR in a subject, wherein treatment comprises prevention (e.g., prophylactic treatment), partial alleviation or cure of the condition or disorder. Modulation may occur locally, for example, within certain tissues of the subject, or more extensively throughout a subject being treated for such a condition disorder.

The compounds of the present invention are useful for the treatment of a variety of conditions and disorders including, but not limited to, those described following:

Compounds of formula I can be applied as agonists, partial agonists, antagonists, or partial antagonists of the estrogen receptor, preferably selectively to that receptor, in an array of medical conditions which involve modulation of the estrogen receptor pathway. Applications of said compounds include but are not limited to: osteoporosis, hot flushes, vaginal dryness, prostate cancer, breast cancer, endometrial cancer, cancers expressing the estrogen receptor such as the aforementioned cancers and others, contraception, pregnancy termination, menopause, amennoreahea, and dysmennoreahea.

Compounds of formula I can be applied as agonists, partial agonists, antagonists or partial antagonists of the progesterone receptor, preferably selectively to that receptor, in an array of medical conditions which involve modulation of the progesterone receptor pathway. Applications of said compounds include but are not limited to: breast cancer, other cancers containing the progesterone receptor; endometriosis, cachexia, contraception, menopause, cyclesynchrony, meniginoma,

dysmennoreahea, fibroids, pregnancy termination, labor induction and osteoporosis.

Compounds of formula I can be applied as agonists, partial agonists, antagonists or partial antagonists of the glucocorticoid receptor, preferably selectively to that receptor, in an array of medical conditions which involve modulation of the glucocorticoid receptor pathway. Applications of said compounds include but are not limited to: inflammatory diseases, autoimmune diseases, prostate cancer, breast cancer, Alzheimer's disease, psychotic disorders, drug dependence, non-insulin dependent Diabetes Mellitus, and as dopamine receptor blocking agents or otherwise as agents for the treatment of dopamine receptor mediated disorders.

Compounds of formula I can be applied as agonists, partial agonists, antagonists or partial antagonists of the mineralocorticoid receptor, preferably selectively to that receptor, in an array of medical conditions which involve modulation of the mineralocorticoid receptor pathway. Applications of said compounds include but are not limited to: drug withdrawal syndrome and inflammatory diseases.

Compounds of formula I can be applied as agonists, partial agonists, antagonists or partial antagonists of the aldosterone receptor, preferably selectively to that receptor, in an array of medical conditions which involve modulation of the aldosterone receptor pathway. One application of said compounds includes but is not limited to: congestive heart failure.

Compounds of formula I can be applied as agonists, partial agonists, antagonists or partial antagonists of the androgen receptor, preferably selectively to that receptor, in an array of medical conditions which involve modulation of the androgen receptor pathway. Applications of said compounds include but are not limited to: hirsutism, acne, seborrhea, Alzheimer's disease, androgenic alopecia, hypogonadism, hyperpilosity, benign prostate hypertrophia, adenomas and neoplasies of the prostate (such as advanced metastatic prostate cancer), treatment of benign or malignant tumor cells containing the androgen receptor such as is the case for breast, brain, skin, ovarian, bladder, lymphatic, liver and kidney cancers, pancreatic cancers modulation of VCAM expression and applications therein for the treatment of heart disease, inflammation and immune modulations, modulation of VEGF expression and

the applications therein for use as antiangiogenic agents, osteoporosis, suppressing spermatogenesis, libido, cachexia, endometriosis, polycystic ovary syndrome, anorexia, androgen supplement for age related decreased testosterone levels in men, male menopause, male hormone replacement, male and female sexual dysfunction, and inhibition of muscular atrophy in ambulatory patients. For example, pan AR modulation is contemplated, with prostate selective AR modulation ("SARM") being particularly preferred, such as for the treatment of early stage prostate cancers. .

Compounds of formula I can be applied as (preferably, selective) antagonists of the mutated androgen receptor, for example, found in many tumor lines. Examples of such mutants are those found in representative prostate tumor cell lines such as LNCap, (T877A mutation, Biophys. Acta, 187, 1052 (1990)), PCa2b, (L701H & T877A mutations, J. Urol., 162, 2192 (1999)) and CWR22, (H874Y mutation, Mol. Endo., 11, 450 (1997)). Applications of said compounds include but are not limited to: adenomas and neoplasies of the prostate, breast cancer and endometrial cancer.

Compounds of formula I can be applied as agonists, partial agonists, antagonists or partial antagonists of the steroid and xenobiotic receptor, preferably selectively to that receptor, in an array of medical conditions which involve modulation of the steroid and xenobiotic receptor pathway. Applications of said compounds include but are not limited to: treatment of disregulation of cholesterol homeostasis, attenuation of metabolism of pharmaceutical agents by co-administration of an agent (compound of the present invention) which modulates the P450 regulator effects of SXR.

Along with the aforementioned NHR, there also exist a number of NHR for which the activating or deactivating ligands may not be characterized. These proteins are classified as NHR due to strong sequence homology to other NHR, and are known as the Orphan receptors. Because the Orphan receptors demonstrate strong sequence homology to other NHR, compounds of formula I include those which serve as modulators of the function of the Orphan NHR. Orphan receptors which are modulated by NHR modulators such as compounds within the scope of formula I are exemplified, but not limited to, those listed in Table 1. Exemplary therapeutic

applications of modulators of said Orphan receptors are also listed in Table 1, but are not limited to the examples therein.

Table 1. Exemplary Orphan nuclear hormone receptors, form (M = monomeric, D = heterodimeric, H = homodimeric), tissue expression and target therapeutic applications. (CNS=central nervous system)

Receptor	Form	Tissue Expression	Target Therapeutic Application
NURR1	M/D	Dopaminergic Neurons	Parkinson's Disease
RZRβ	M	Brain (Pituitary), Muscle	Sleep Disorders
RORα	M	Cerebellum, Purkinje Cells	Arthritis, Cerebellar Ataxia
NOR-1	M	Brain, Muscle , Heart, Adrenal, Thymus	CNS Disorders, Cancer
NGFI-Bβ	M/D	Brain	CNS Disorders
COUP-Tfα	H	Brain	CNS Disorders
COUP-TFβ	H	Brain	CNS Disorders
COUP-TFγχ	H	Brain	CNS Disorders
Nur77	H	Brain, Thymus, Adrenals	CNS Disorders
Rev-ErbAα	H	Muscle, Brain (Ubiquitous)	Obesity
HNF4α	H	Liver, Kidney, Intestine	Diabetes
SF-1	M	Gonads, Pituitary	Metabolic Disorders
LXRα,β	D	Kidney (Ubiquitous)	Metabolic Disorders
GCNF	M/H	Testes, Ovary	Infertility
ERRα,β	M	Placenta, Bone	Infertility, Osteoporosis
FXR	D	Liver, Kidney	Metabolic Disorders
CARα	H	Liver, Kidney	Metabolic Disorders
PXR	H	Liver, Intestine	Metabolic Disorders

The present invention thus provides methods for the treatment of NHR-associated conditions, comprising the step of administering to a subject in need thereof at least one compound of formula I in an amount effective therefor. Other

therapeutic agents such as those described below may be employed with the inventive compounds in the present methods (for example, separately, or formulated together as a fixed dose). In the methods of the present invention, such other therapeutic agent(s) can be administered prior to, simultaneously with or following the administration of the compound(s) of the present invention.

The present invention also provides pharmaceutical compositions comprising at least one of the compounds of the formula I capable of treating a NHR-associated condition in an amount effective therefor, and a pharmaceutically acceptable carrier (vehicle or diluent). The compositions of the present invention can contain other therapeutic agents as described below, and can be formulated, for example, by employing conventional solid or liquid vehicles or diluents, as well as pharmaceutical additives of a type appropriate to the mode of desired administration (for example, excipients, binders, preservatives, stabilizers, flavors, etc.) according to techniques such as those well known in the art of pharmaceutical formulation.

It should be noted that the compounds of the present invention are, without limitation as to their mechanism of action, useful in treating any of the conditions or disorders listed or described herein such as inflammatory diseases or cancers, or other proliferate diseases, and in compositions for treating such conditions or disorders. Such conditions and disorders include, without limitation, any of those described previously, as well as those described following such as: maintenance of muscle strength and function (e.g., in the elderly); reversal or prevention of frailty or age-related functional decline ("ARFD") in the elderly (e.g., sarcopenia); treatment of catabolic side effects of glucocorticoids; prevention and/or treatment of reduced bone mass, density or growth (e.g., osteoporosis and osteopenia); treatment of chronic fatigue syndrome (CFS); chronic malagia; treatment of acute fatigue syndrome and muscle loss following elective surgery (e.g., post-surgical rehabilitation); acceleration of wound healing; accelerating bone fracture repair (such as accelerating the recovery of hip fracture patients); accelerating healing of complicated fractures, e.g. distraction osteogenesis; in

joint replacement; prevention of post-surgical adhesion formation; acceleration of tooth repair or growth; maintenance of sensory function (e.g., hearing, sight, olefaction and taste); treatment of periodontal disease; treatment of wasting secondary to fractures and wasting in connection with chronic obstructive pulmonary disease (COPD), chronic liver disease, AIDS, weightlessness, cancer cachexia, burn and trauma recovery, chronic catabolic state (e.g., coma), eating disorders (e.g., anorexia) and chemotherapy; treatment of cardiomyopathy; treatment of thrombocytopenia; treatment of growth retardation in connection with Crohn's disease; treatment of short bowel syndrome; treatment of irritable bowel syndrome; treatment of inflammatory bowel disease; treatment of Crohn's disease and ulcerative colits; treatment of complications associated with transplantation; treatment of physiological short stature including growth hormone deficient children and short stature associated with chronic illness; treatment of obesity and growth retardation associated with obesity; treatment of anorexia (e.g., associated with cachexia or aging); treatment of hypercortisolism and Cushing's syndrome; Paget's disease; treatment of osteoarthritis; induction of pulsatile growth hormone release; treatment of osteochondrodysplasias; treatment of depression, nervousness, irritability and stress; treatment of reduced mental energy and low self-esteem (e.g., motivation/assertiveness); improvement of cognitive function (e.g., the treatment of dementia, including Alzheimer's disease and short term memory loss); treatment of catabolism in connection with pulmonary dysfunction and ventilator dependency; treatment of cardiac dysfunction (e.g., associated with valvular disease, myocardial infarction, cardiac hypertrophy or congestive heart failure); lowering blood pressure; protection against ventricular dysfunction or prevention of reperfusion events; treatment of adults in chronic dialysis; reversal or slowing of the catabolic state of aging; attenuation or reversal of protein catabolic responses following trauma (e.g., reversal of the catabolic

state associated with surgery, congestive heart failure, cardiac myopathy, burns, cancer, COPD etc.); reducing cachexia and protein loss due to chronic illness such as cancer or AIDS; treatment of hyperinsulinemia including nesidioblastosis; treatment of immunosuppressed patients; treatment of wasting in connection with multiple sclerosis or other neurodegenerative disorders; promotion of myelin repair; maintenance of skin thickness; treatment of metabolic homeostasis and renal homeostasis (e.g., in the frail elderly); stimulation of osteoblasts, bone remodeling and cartilage growth; regulation of food intake; treatment of insulin resistance, including NIDDM, in mammals (e.g., humans); treatment of insulin resistance in the heart; improvement of sleep quality and correction of the relative hyposomatotropism of senescence due to high increase in REM sleep and a decrease in REM latency; treatment of hypothermia; treatment of congestive heart failure; treatment of lipodystrophy (e.g., in patients taking HIV or AIDS therapies such as protease inhibitors); treatment of muscular atrophy (e.g., due to physical inactivity, bed rest or reduced weight-bearing conditions); treatment of musculoskeletal impairment (e.g., in the elderly); improvement of the overall pulmonary function; treatment of sleep disorders; and the treatment of the catabolic state of prolonged critical illness; treatment of hirsutism, acne, seborrhea, androgenic alopecia, anemia, hyperpilosity, benign prostate hypertrophy, adenomas and neoplasies of the prostate (e.g., advanced metastatic prostate cancer) and malignant tumor cells containing the androgen receptor, such as is the case for breast, brain, skin, ovarian, bladder, lymphatic, liver and kidney cancers; cancers of the skin, pancreas, endometrium, lung and colon; osteosarcoma; hypercalcemia of malignancy; metastatic bone disease; treatment of spermatogenesis, endometriosis and polycystic ovary syndrome; conteracting preeclampsia, eclampsia of pregnancy and preterm labor; treatment of premenstrual syndrome; treatment of vaginal dryness; age related decreased testosterone

levels in men, male menopause, hypogonadism, male hormone replacement, male and female sexual dysfunction (e.g., erectile dysfunction, decreased sex drive, sexual well-being, decreased libido), male and female contraception, hair loss, Reaven's Syndrome and the enhancement of bone and muscle performance/strength; and the conditions, diseases, and maladies collectively referenced to as "Syndrome X" or Metabolic Syndrome as detailed in Johannsson *J. Clin. Endocrinol. Metab.*, 82, 727-34 (1997).

The present compounds have therapeutic utility in the modulation of immune cell activation/proliferation, e.g., as competitive inhibitors of intercellular ligand/receptor binding reactions involving CAMs (Cellular Adhesion Molecules) and Leukointegrins. For example, the present compounds modulate LFA-ICAM 1, and are particularly useful as LFA-ICAM 1 antagonists, and in the treatment of all conditions associated with LFA-ICAM 1 such as immunological disorders. Preferred utilities for the present compounds include, but are not limited to: inflammatory conditions such as those resulting from a response of the non-specific immune system in a mammal (e.g., adult respiratory distress syndrome, shock, oxygen toxicity, multiple organ injury syndrome secondary to septicemia, multiple organ injury syndrome secondary to trauma, reperfusion injury of tissue due to cardiopulmonary bypass, myocardial infarction or use with thrombolysis agents, acute glomerulonephritis, vasculitis, reactive arthritis, dermatosis with acute inflammatory components, stroke, thermal injury, hemodialysis, leukapheresis, ulcerative colitis, necrotizing enterocolitis and granulocyte transfusion associated syndrome) and conditions resulting from a response of the specific immune system in a mammal (e.g., psoriasis, organ/tissue transplant rejection, graft vs. host reactions and autoimmune diseases including Raynaud's syndrome, autoimmune thyroiditis, dermatitis, multiple sclerosis, rheumatoid arthritis, insulin-dependent diabetes mellitus, uveitis, inflammatory bowel disease including Crohn's disease and ulcerative colitis, and systemic lupus erythematosus). The present compounds can be used in treating asthma or as an adjunct to minimize toxicity with cytokine therapy in the

treatment of cancers. The present compounds can be employed in the treatment of all diseases currently treatable through steroid therapy. The present compounds may be employed for the treatment of these and other disorders alone or with other immunosuppressive or antiinflammatory agents. In accordance with the invention, a compound of the formula I can be administered prior to the onset of inflammation (so as to suppress an anticipated inflammation) or after the initiation of inflammation. When provided prophylactically, the immunosupressive compound(s) are preferably provided in advance of any inflammatory response or symptom (for example, prior to, at, or shortly after the time of an organ or tissue transplant but in advance of any symptoms or organ rejection). The prophylactic administration of a compound of the formula I prevents or attenuates any subsequent inflammatory response (such as, for example, rejection of a transplanted organ or tissue, etc.) Administration of a compound of the formula I attenuates any actual inflammation (such as, for example, the rejection of a transplanted organ or tissue).

The compounds of the formula I can be administered for any of the uses described herein by any suitable means, for example, orally, such as in the form of tablets, capsules, granules or powders; sublingually; bucally; parenterally, such as by subcutaneous, intravenous, intramuscular, or intrasternal injection or infusion techniques (e.g., as sterile injectable aqueous or non-aqueous solutions or suspensions); nasally, including administration to the nasal membranes, such as by inhalation spray; topically, such as in the form of a cream or ointment; or rectally such as in the form of suppositories; in dosage unit formulations containing non-toxic, pharmaceutically acceptable vehicles or diluents. The present compounds can, for example, be administered in a form suitable for immediate release or extended release. Immediate release or extended release can be achieved by the use of suitable pharmaceutical compositions comprising the present compounds, or, particularly in the case of extended release, by the use of devices such as subcutaneous implants or osmotic pumps. The present compounds can also be administered liposomally.

Exemplary compositions for oral administration include suspensions which can contain, for example, microcrystalline cellulose for imparting bulk, alginic acid or sodium alginate as a suspending agent, methylcellulose as a viscosity enhancer, and

sweeteners or flavoring agents such as those known in the art; and immediate release tablets which can contain, for example, microcrystalline cellulose, dicalcium phosphate, starch, magnesium stearate and/or lactose and/or other excipients, binders, extenders, disintegrants, diluents and lubricants such as those known in the art. The compounds of formula I can also be delivered through the oral cavity by sublingual and/or buccal administration. Molded tablets, compressed tablets or freeze-dried tablets are exemplary forms which may be used. Exemplary compositions include those formulating the present compound(s) with fast dissolving diluents such as mannitol, lactose, sucrose and/or cyclodextrins. Also included in such formulations may be high molecular weight excipients such as celluloses (avicel) or polyethylene glycols (PEG). Such formulations can also include an excipient to aid mucosal adhesion such as hydroxy propyl cellulose (HPC), hydroxy propyl methyl cellulose (HPMC), sodium carboxy methyl cellulose (SCMC), maleic anhydride copolymer (e.g., Gantrez), and agents to control release such as polyacrylic copolymer (e.g. Carbopol 934). Lubricants, glidants, flavors, coloring agents and stabilizers may also be added for ease of fabrication and use.

Exemplary compositions for nasal aerosol or inhalation administration include solutions in saline which can contain, for example, benzyl alcohol or other suitable preservatives, absorption promoters to enhance bioavailability, and/or other solubilizing or dispersing agents such as those known in the art.

Exemplary compositions for parenteral administration include injectable solutions or suspensions which can contain, for example, suitable non-toxic, parenterally acceptable diluents or solvents, such as mannitol, 1,3-butanediol, water, Ringer's solution, an isotonic sodium chloride solution, or other suitable dispersing or wetting and suspending agents, including synthetic mono- or diglycerides, and fatty acids, including oleic acid, or Cremaphor.

Exemplary compositions for rectal administration include suppositories which can contain, for example, a suitable non-irritating excipient, such as cocoa butter, synthetic glyceride esters or polyethylene glycols, which are solid at ordinary temperatures, but liquify and/or dissolve in the rectal cavity to release the drug.

Exemplary compositions for topical administration include a topical carrier such as Plastibase (mineral oil gelled with polyethylene).

The effective amount of a compound of the present invention can be determined by one of ordinary skill in the art, and includes exemplary dosage amounts for a adult human of from about 1 to 100 (for example, 15) mg/kg of body weight of active compound per day, which can be administered in a single dose or in the form of individual divided doses, such as from 1 to 4 times per day. It will be understood that the specific dose level and frequency of dosage for any particular subject can be varied and will depend upon a variety of factors including the activity of the specific compound employed, the metabolic stability and length of action of that compound, the species, age, body weight, general health, sex and diet of the subject, the mode and time of administration, rate of excretion, drug combination, and severity of the particular condition. Preferred subjects for treatment include animals, most preferably mammalian species such as humans, and domestic animals such as dogs, cats and the like, subject to NHR-associated conditions.

As mentioned above, the compounds of the present invention can be employed alone or in combination with each other and/or other suitable therapeutic agents useful in the treatment of NHR-associated conditions, e.g., an antibiotic or other pharmaceutically active material.

For example, the compounds of the present invention can be combined with growth promoting agents, such as, but not limited to, TRH, diethylstilbesterol, theophylline, enkephalins, E series prostaglandins, compounds disclosed in U.S. Patent No. 3,239,345, e.g., zeranol, and compounds disclosed in U.S. Patent No. 4,036,979, e.g., sulbenox or peptides disclosed in U.S. Patent No. 4,411,890.

The compounds of the invention can also be used in combination with growth hormone secretagogues such as GHRP-6, GHRP-1 (as described in U.S. Patent No. 4,411,890 and publications WO 89/07110 and WO 89/07111), GHRP-2 (as described in WO 93/04081), NN703 (Novo Nordisk), LY444711 (Lilly), MK-677 (Merck), CP424391 (Pfizer) and B-HT920, or with growth hormone releasing factor and its analogs or growth hormone and its analogs or somatomedins including IGF-1

and IGF-2, or with alpha-adrenergic agonists, such as clonidine or serotinin 5-HT_D agonists, such as sumatriptan, or agents which inhibit somatostatin or its release, such as physostigmine and pyridostigmine. A still further use of the disclosed compounds of the invention is in combination with parathyroid hormone, PTH(1-34) or bisphosphonates, such as MK-217 (alendronate).

A still further use of the compounds of the invention is in combination with estrogen, testosterone, a selective estrogen receptor modulator, such as tamoxifen or raloxifene, or other androgen receptor modulators, such as those disclosed in Edwards, J. P. et al., *Bio. Med. Chem. Let.*, 9, 1003-1008 (1999) and Hamann, L. G. et al., *J. Med. Chem.*, 42, 210-212 (1999).

A further use of the compounds of this invention is in combination with progesterone receptor agonists ("PRA"), such as levonorgestrel, medroxyprogesterone acetate (MPA).

The compounds of the present invention can be employed alone or in combination with each other and/or other modulators of nuclear hormone receptors or other suitable therapeutic agents useful in the treatment of the aforementioned disorders including: anti-diabetic agents; anti-osteoporosis agents; anti-obesity agents; anti-inflammatory agents; anti-anxiety agents; anti-depressants; anti-hypertensive agents; anti-platelet agents; anti-thrombotic and thrombolytic agents; cardiac glycosides; cholesterol/lipid lowering agents; mineralocorticoid receptor antagonists; phospodiesterase inhibitors; protein tyrosine kinase inhibitors; thyroid mimetics (including thyroid receptor agonists); anabolic agents; HIV or AIDS therapies; therapies useful in the treatment of Alzheimer's disease and other cognitive disorders; therapies useful in the treatment of sleeping disorders; anti-proliferative agents; and anti-tumor agents.

Examples of suitable anti-diabetic agents for use in combination with the compounds of the present invention include biguanides (e.g., metformin), glucosidase inhibitors (e.g,. acarbose), insulins (including insulin secretagogues or insulin

sensitizers), meglitinides (e.g., repaglinide), sulfonylureas (e.g., glimepiride, glyburide and glipizide), biguanide/glyburide combinations (e.g., Glucovance®), thiazolidinediones (e.g., troglitazone, rosiglitazone and pioglitazone), PPAR-alpha agonists, PPAR-gamma agonists, PPAR alpha/gamma dual agonists, SGLT2 inhibitors, glycogen phosphorylase inhibitors, inhibitors of fatty acid binding protein (aP2) such as those disclosed in U.S. Serial No. 09/519,079 filed March 6, 2000, glucagon-like peptide-1 (GLP-1), and dipeptidyl peptidase IV (DP4) inhibitors.

Examples of suitable anti-osteoporosis agents for use in combination with the compounds of the present invention include alendronate, risedronate, PTH, PTH fragment, raloxifene, calcitonin, steroidal or non-steroidal progesterone receptor agonists, RANK ligand antagonists, calcium sensing receptor antagonists, TRAP inhibitors, selective estrogen receptor modulators (SERM), estrogen and AP-1 inhibitors.

Examples of suitable anti-obesity agents for use in combination with the compounds of the present invention include aP2 inhibitors, such as those disclosed in U.S. Serial No. 09/519,079 filed March 6, 2000, PPAR gamma antagonists, PPAR delta agonists, beta 3 adrenergic agonists, such as AJ9677 (Takeda/Dainippon), L750355 (Merck), or CP331648 (Pfizer) or other known beta 3 agonists as disclosed in U.S. Patent Nos. 5,541,204, 5,770,615, 5,491,134, 5,776,983 and 5,488,064, a lipase inhibitor, such as orlistat or ATL-962 (Alizyme), a serotonin (and dopamine) reuptake inhibitor, such as sibutramine, topiramate (Johnson & Johnson) or axokine (Regeneron), a thyroid receptor beta drug, such as a thyroid receptor ligand as disclosed in WO 97/21993 (U. Cal SF), WO 99/00353 (KaroBio) and GB98/284425 (KaroBio), and/or an anorectic agent, such as dexamphetamine, phentermine, phenylpropanolamine or mazindol.

Examples of suitable anti-inflammatory agents for use in combination with the compounds of the present invention include prednisone, dexamethasone, Enbrel®, cyclooxygenase inhibitors (i.e., COX-1 and/or COX-2 inhibitors such as NSAIDs,

aspirin, indomethacin, ibuprofen, piroxicam, Naproxen , Celebrex , Vioxx), CTLA4-Ig agonists/antagonists, CD40 ligand antagonists, IMPDH inhibitors, such as mycophenolate (CellCept®) integrin antagonists, alpha-4 beta-7 integrin antagonists, cell adhesion inhibitors, interferon gamma antagonists, ICAM-1, tumor necrosis factor (TNF) antagonists (e.g., infliximab, OR1384), prostaglandin synthesis inhibitors, budesonide, clofazimine, CNI-1493, CD4 antagonists (e.g., priliximab), p38 mitogen-activated protein kinase inhibitors, protein tyrosine kinase (PTK) inhibitors, IKK inhibitors, and therapies for the treatment of irritable bowel syndrome (e.g., Zelmac® and Maxi-K® openers such as those disclosed in U.S. Patent No. 6,184,231 B1).

Example of suitable anti-anxiety agents for use in combination with the compounds of the present invention include diazepam, lorazepam, buspirone, oxazepam, and hydroxyzine pamoate.

Examples of suitable anti-depressants for use in combination with the compounds of the present invention include citalopram, fluoxetine, nefazodone, sertraline, and paroxetine.

Examples of suitable anti-hypertensive agents for use in combination with the compounds of the present invention include beta adrenergic blockers, calcium channel blockers (L-type and T-type; e.g. diltiazem, verapamil, nifedipine, amlodipine and mybefradil), diuretics (e.g., chlorothiazide, hydrochlorothiazide, flumethiazide, hydroflumethiazide, bendroflumethiazide, methylchlorothiazide, trichloromethiazide, polythiazide, benzthiazide, ethacrynic acid tricrynafen, chlorthalidone, furosemide, musolimine, bumetanide, triamtrenene, amiloride, spironolactone), renin inhibitors, ACE inhibitors (e.g., captopril, zofenopril, fosinopril, enalapril, ceranopril, cilazopril, delapril, pentopril, quinapril, ramipril, lisinopril), AT-1 receptor antagonists (e.g., losartan, irbesartan, valsartan), ET receptor antagonists (e.g., sitaxsentan, atrsentan and compounds disclosed in U.S. Patent Nos. 5,612,359 and 6,043,265), Dual ET/AII antagonist (e.g., compounds disclosed in WO 00/01389), neutral endopeptidase (NEP)

inhibitors, vasopepsidase inhibitors (dual NEP-ACE inhibitors) (e.g., omapatrilat and gemopatrilat), and nitrates.

Examples of suitable anti-platelet agents for use in combination with the compounds of the present invention include GPIIb/IIIa blockers (e.g., abciximab, eptifibatide, tirofiban), P2Y12 antagonists (e.g., clopidogrel, ticlopidine, CS-747), thromboxane receptor antagonists (e.g., ifetroban), aspirin, and PDE-III inhibitors (e.g., dipyridamole) with or without aspirin.

Examples of suitable cardiac glycosides for use in combination with the compounds of the present invention include digitalis and ouabain.

Examples of suitable cholesterol/lipid lowering agents for use in combination with the compounds of the present invention include HMG-CoA reductase inhibitors (e.g., pravastatin, lovastatin, atorvastatin, simvastatin, NK-104 (a.k.a. itavastatin, or nisvastatin or nisbastatin) and ZD-4522 (a.k.a. rosuvastatin, or atavastatin or visastatin)), squalene synthetase inhibitors, fibrates, bile acid sequestrants, ACAT inhibitors, MTP inhibitors, lipooxygenase inhibitors, cholesterol absorption inhibitors, and cholesterol ester transfer protein inhibitors (e.g., CP-529414).

Examples of suitable mineralocorticoid receptor antagonists for use in combination with the compounds of the present invention include spironolactone and eplerinone.

Examples of suitable phospodiesterase inhibitors for use in combination with the compounds of the present invention include PDEIII inhibitors such as cilostazol, and PDE V inhibitors such as sildenafil.

Examples of suitable thyroid mimetics for use in combination with the compounds of the present invention include thyrotropin, polythyroid, KB-130015, and dronedarone.

Examples of suitable anabolic agents for use in combination with the compounds of the present invention include testosterone, TRH diethylstilbesterol, estrogens, β-agonists, theophylline, anabolic steroids, dehydroepiandrosterone,

enkephalins, E-series prostagladins, retinoic acid and compounds as disclosed in U.S. Pat. No. 3,239,345, e.g., Zeranol®; U.S. Patent No. 4,036,979, e.g., Sulbenox® or peptides as disclosed in U.S. Pat. No. 4,411,890.

Examples of suitable HIV or AIDS therapies for use in combination with the compounds of the present invention include indinavir sulfate, saquinavir, saquinavir mesylate, ritonavir, lamivudine, zidovudine, lamivudine/zidovudine combinations, zalcitabine, didanosine, stavudine, and megestrol acetate.

Examples of suitable therapies for treatment of Alzheimer's disease and cognitive disorders for use in combination with the compounds of the present invention include donepezil, tacrine, revastigmine, 5HT6, gamma secretase inhibitors, beta secretase inhibitors, SK channel blockers, Maxi-K blockers, and KCNQs blockers.

Examples of suitable therapies for treatment of sleeping disorders for use in combination with the compounds of the present invention include melatonin analogs, melatonin receptor antagonists, ML1B agonists, and GABA/NMDA receptor antagonists.

Examples of suitable anti-proliferative agents for use in combination with the compounds of the present invention include cyclosporin A, paclitaxel, FK 506, and adriamycin.

Examples of suitable anti-tumor agents for use in combination with the compounds of the present invention include paclitaxel, adriamycin, epothilones, cisplatin and carboplatin.

Compounds of the present invention can further be used in combination with nutritional supplements such as those described in U.S. 5,179,080, especially in combination with whey protein or casin, amino acids (such as leucine, branched amino acids and hydroxymethylbutyrate), triglycerides, vitamins (e.g., A, B6, B12, folate, C, D and E), minerals (e.g., selenium, magnesium, zinc, chromium, calcium and potassium), carnitine, lipoic acid, creatine, and coenzyme Q-10.

In addition, compounds of the present invention can be used in combination with therapeutic agents used in the treatment of sexual dysfunction, including but not limited to PDE5 inhibitors, such as sildenafil or IC-351; with an antiresorptive agent, hormone replacement therapies, vitamin D analogues, calcitonins, elemental calcium and calcium supplements, cathepsin K inhibitors, MMP inhibitors, vitronectin receptor antagonists, Src SH_2 antagonists, vacular $-H^+$- ATPase inhibitors, progesterone receptor agonists, ipriflavone, fluoride, RANK antagonists, PTH and its analogues and fragments, Tibolone, HMG-CoA reductase inhibitors, SERM's, p38 inhibitors, prostanoids, 17-beta hydroxysteroid dehydrogenase inhibitors and Src kinase inhibitors.

Compounds of the present invention can be used in combination with male contraceptives, such as nonoxynol 9 or therapeutic agents for the treatment of hair loss, such as minoxidil and finasteride or chemotherapeutic agents, such as with LHRH agonists.

For their preferred anticancer or antiangiogenic use, the compounds of the present invention can be administered either alone or in combination with other anti-cancer and cytotoxic agents and treatments useful in the treatment of cancer or other proliferative diseases, for example, where the second drug has the same or different mechanism of action than the present compounds of formula I. Examples of classes of anti-cancer and cytotoxic agents useful in combination with the present compounds include but are not limited to: alkylating agents such as nitrogen mustards, alkyl sulfonates, nitrosoureas, ethylenimines, and triazenes; antimetabolites such as folate antagonists, purine analogues, and pyrimidine analogues; antibiotics such as anthracyclines, bleomycins, mitomycin, dactinomycin, and plicamycin; enzymes such as L-asparaginase; farnesyl-protein transferase inhibitors; 5α reductase inhibitors; inhibitors of 17β-hydroxy steroid dehydrogenase type 3; hormonal agents such as glucocorticoids, estrogens/ antiestrogens, androgens/ antiandrogens, progestins, and luteinizing hormone-releasing hormone antagonists, octreotide acetate; microtubule-disruptor agents, such as ecteinascidins or their analogs and derivatives; microtubule-stabilizing agents such as taxanes, for example, paclitaxel (Taxol®), docetaxel

81

(Taxotere®), and their analogs, and epothilones, such as epothilones A-F and their analogs; plant-derived products, such as vinca alkaloids, epipodophyllotoxins, taxanes; and topiosomerase inhibitors; prenyl-protein transferase inhibitors; and miscellaneous agents such as hydroxyurea, procarbazine, mitotane, hexamethylmelamine, platinum coordination complexes such as cisplatin and carboplatin; and other agents used as anti-cancer and cytotoxic agents such as biological response modifiers, growth factors; immune modulators and monoclonal antibodies. The compounds of the invention may also be used in conjunction with radiation therapy.

Representative examples of these classes of anti-cancer and cytotoxic agents include but are not limited to mechlorethamine hydrochloride, cyclophosphamide, chlorambucil, melphalan, ifosfamide, busulfan, carmustin, lomustine, semustine, streptozocin, thiotepa, dacarbazine, methotrexate, thioguanine, mercaptopurine, fludarabine, pentastatin, cladribin, cytarabine, fluorouracil, doxorubicin hydrochloride, daunorubicin, idarubicin, bleomycin sulfate, mitomycin C, actinomycin D, safracins, saframycins, quinocarcins, discodermolides, vincristine, vinblastine, vinorelbine tartrate, etoposide, etoposide phosphate, teniposide, paclitaxel, tamoxifen, estramustine, estramustine phosphate sodium, flutamide, buserelin, leuprolide, pteridines, diyneses, levamisole, aflacon, interferon, interleukins, aldesleukin, filgrastim, sargramostim, rituximab, BCG, tretinoin, irinotecan hydrochloride, betamethosone, gemcitabine hydrochloride, altretamine, and topoteca and any analogs or derivatives thereof.

Preferred member of these classes include, but are not limited to, paclitaxel, cisplatin, carboplatin, doxorubicin, carminomycin, daunorubicin, aminopterin, methotrexate, methopterin, mitomycin C, ecteinascidin 743, or porfiromycin, 5-fluorouracil, 6-mercaptopurine, gemcitabine, cytosine arabinoside, podophyllotoxin or podophyllotoxin derivatives such as etoposide, etoposide phosphate or teniposide, melphalan, vinblastine, vincristine, leurosidine, vindesine and leurosine.

Examples of anticancer and other cytotoxic agents include the following: epothilone derivatives as found in German Patent No. 4138042.8; WO 97/19086, WO 98/22461, WO 98/25929, WO 98/38192, WO 99/01124, WO 99/02224, WO

82

99/02514, WO 99/03848, WO 99/07692, WO 99/27890, WO 99/28324, WO 99/43653, WO 99/54330, WO 99/54318, WO 99/54319, WO 99/65913, WO 99/67252, WO 99/67253 and WO 00/00485; cyclin dependent kinase inhibitors as found in WO 99/24416 (see also U.S. Patent No. 6,040,321); and prenyl-protein transferase inhibitors as found in WO 97/30992 and WO 98/54966; and agents such as those described generically and specifically in U.S. Patent No. 6,011,029 (the compounds of which U.S. Patent can be employed together with any NHR modulators (including, but not limited to, those of present invention) such as AR modulators, ER modulators, with LHRH modulators, or with surgical castration, especially in the treatment of cancer).

The combinations of the present invention can also be formulated or co-administered with other therapeutic agents that are selected for their particular usefulness in administering therapies associated with the aforementioned conditions. For example, the compounds of the invention may be formulated with agents to prevent nausea, hypersensitivity and gastric irritation, such as antiemetics, and H_1 and H_2 antihistaminics.

As it pertains to the treatment of cancer, the compounds of this invention are most preferably used alone or in combination with anti-cancer treatments such as radiation therapy and/or with cytostatic and/or cytotoxic agents, such as, but not limited to, DNA interactive agents, such as cisplatin or doxorubicin; inhibitors of farnesyl protein transferase, such as those described in U.S. Patent No. 6,011,029; topoisomerase II inhibitors, such as etoposide; topoisomerase I inhibitors, such as CPT-11 or topotecan; tubulin stabilizing agents, such as paclitaxel, docetaxel, other taxanes, or epothilones; hormonal agents, such as tamoxifen; thymidilate synthase inhibitors, such as 5-fluorouracil; antimetabolites, such as methoxtrexate; antiangiogenic agents, such as angiostatin, ZD6474, ZD6126 and comberstatin A2; kinase inhibitors, such as her2 specific antibodies, Iressa and CDK inhibitors; histone deacetylase inhibitors, such as CI-994 and MS-27-275. Such compounds may also be combined with agents which suppress the production of circulating testosterone such as LHRH agonists or antagonists or with surgical castration.

For example, known therapies for advanced metastatic prostate cancer include "complete androgen ablation therapy" wherein tumor growth is inhibited by controlling the supply of androgen to the prostate tissues via chemical castration (castration serves to inhibit the production of circulating testosterone (T) and dihydrotestosterone (DHT)) followed by the administration of androgen receptor (AR) antagonists (which inhibit the function T/DHT derived from the conversion of circulating androgen precursors to T/DHT by the prostate tissue). The compounds of the present invention can be employed as AR antagonists in complete ablation therapy, alone or in combination with other AR antagonists such as Flutamide, Casodex, Nilutamide, or Cyproterone acetate.

The compounds of the present invention may be employed adjuvant to surgery.

Another application of the present compounds is in combination with antibody therapy such as but not limited to antibody therapy against PSCA. An additional application is in concert with vaccine / immune modulating agents for the treatment of cancer.

Compounds of the present invention can be employed in accordance with the methods described in U.S. Provisional Patent Application Serial No. 60/284,438, entitled "Selective Androgen Receptor Modulators and Methods for Their Identification, Design and Use" filed April 18, 2001 by Mark E. Salvati *et al.* (Attorney Docket No. LD0250(PSP)), which Provisional Patent Application is incorporated herein by reference in its entirety (including, but not limited to, reference to all specific compounds within formula I of the present invention), and U.S. Patent Application Serial No. _____ (unassigned), entitled "Selective Androgen Receptor Modulators and Methods for Their Identification, Design and Use" filed June 20, 2001 by Mark E. Salvati *et al.* (Attorney Docket No. LD0250(NP)), which Patent Application is incorporated herein by reference in its entirety (including, but not limited to, reference to all specific compounds within formula I of the present invention).

For racemates of compounds of the present invention, one enantiomer can, for example be a full AR antagonist while the other can be an AR antagonist in tumor

84

tissue while having no activity or agonist activity in nontumor tissue containing the androgen receptor.

The above other therapeutic agents, when employed in combination with the compounds of the present invention, can be used, for example, in those amounts indicated in the Physicians' Desk Reference (PDR) or as otherwise determined by one of ordinary skill in the art.

The following assays can be employed in ascertaining the activity of a compound as a NHR modulator. Preferred are those compounds with an activity greater than 20μm for binding or transactivation in any of these assays. Various compounds of the present invention were determined to have AR modulator activity utilizing the transactivation assay, and standard AR binding assays as described following.

Transactivation Assays:

AR Specific Assay:

Compounds of the present invention were tested in transactivation assays of a transfected reporter construct and using the endogenous androgen receptor of the host cells. The transactivation assay provides a method for identifying functional agonists and partial agonists that mimic, or antagonists that inhibit, the effect of native hormones, in this case, dihydrotestosterone (DHT). This assay can be used to predict *in vivo* activity as there is a good correlation in both series of data. See, e.g. T. Berger et al., *J. Steroid Biochem. Molec. Biol.* 773 (1992), the disclosure of which is herein incorporated by reference.

For the transactivation assay a reporter plasmid is introduced by transfection (a procedure to induce cells to take foreign genes) into the respective cells. This reporter plasmid, comprising the cDNA for a reporter protein, such as secreted alkaline phosphatase (SEAP), controlled by prostate specific antigen (PSA) upstream sequences containing androgen response elements (AREs). This reporter plasmid functions as a reporter for the transcription-modulating activity of the AR. Thus, the reporter acts as a surrogate for the products (mRNA then protein) normally expressed by a gene under control of the AR and its native hormone. In order to detect antagonists, the transactivation assay is carried out in the presence of constant concentration of the natural AR hormone (DHT) known to induce a defined reporter signal. Increasing concentrations of a suspected antagonist will decrease the reporter signal (e.g., SEAP production). On the other hand, exposing the transfected cells to increasing concentrations of a suspected agonist will increase the production of the reporter signal.

For this assay, LNCaP and MDA 453 cells were obtained from the American Type Culture Collection (Rockville, MD), and maintained in RPMI 1640 or DMEM medium supplemented with 10% fetal bovine serum (FBS; Gibco) respectively. The respective cells were transiently transfected by electroporation according to the optimized procedure described by Heiser, 130 Methods Mol. Biol., 117 (2000), with the pSEAP2/PSA540/Enhancer reporter plasmid. The reportet

plasmid, was constructed as follows: commercial human placental genomic DNA was used to generate by Polymerase Cycle Reaction (PCR) a fragment containing the BglII site (position 5284) and the Hind III site at position 5831 of the human prostate specific antigen promoter (Accession # U37672), Schuur, et al., *J. Biol. Chem.*, 271 (12): 7043-51 (1996). This fragment was subcloned into the pSEAP2/basic (Clontech) previously digested with BglII and HindIII to generate the pSEAP2/PSA540 construct. Then a fragment bearing the fragment of human PSA upstream sequence between positions –5322 and –3873 was amplified by PCR from human placental genomic DNA. A XhoI and a BglII sites were introduced with the primers. The resulting fragment was subcloned into pSEAP2/PSA540 digested with XhoI and BglII respectively, to generate the pSEAP2/PSA540/Enhancer construct. LNCaP and MDA 453 cells were collected in media containing 10% charcoal stripped FBS. Each cell suspension was distributed into two Gene Pulser Cuvetts (Bio-Rad) which then received 8 μg of the reporter construct, and electoporated using a Bio-Rad Gene Pulser at 210 volts and 960 μFaraday. Following the transfections the cells were washed and incubated with media containing charcoal stripped fetal bovine serum in the absence (blank) or presence (control) of 1 nM dihydrotestosterone (DHT; Sigma Chemical) and in the presence or absence of the standard anti-androgen bicalutamide or compounds of the present invention in concentrations ranging from 10-10 to 10-5 M (sample). Duplicates were used for each sample. The compound dilutions were performed on a Biomek 2000 laboratory workstation.

After 48 hours, a fraction of the supernatant was assayed for SEAP activity using the Phospha-Light Chemiluminescent Reporter Gene Assay System (Tropix, Inc).

Viability of the remaining cells was determined using the CellTiter 96 Aqueous Non-Radioactive Cell Proliferation Assay (MTS Assay, Promega). Briefly, a mix of a tetrazolium compound (3-(4,5-dimethylthiazol-2-yl)-5-(3-carboxymethoxyphenyl)- 2-(4-sulfophenyl)-2H-tetrazolium, inner salt; MTS) and an electron coupling reagent (phenazine methosulfate; PMS) are added to the cells. MTS (Owen's reagent) is bioreduced by cells into a formazan that is soluble in tissue culture medium, and therefore its absorbance at 490nm can be measured directly from 96 well assay plates

without additional processing. The quantity of formazan product as measured by the amount of 490nm absorbance is directly proportional to the number of living cells in culture. For each replicate the SEAP reading was normalized by the Abs490 value derived from the MTS assay. For the antagonist mode, the % Inhibition was calculated as:

% Inhibition = 100 x (1 – [average control – average blank / average sample – average blank])

Data was plotted and the concentration of compound that inhibited 50% of the normalized SEAP was quantified (IC_{50}).

For the agonist mode % Control was referred as the effect of the tested compound compared to the maximal effect observed with the natural hormone, in this case DHT, and was calculated as:

% Control = 100 x average sample – average blank/ average control – average blank

Data was plotted and the concentration of compound that activates to levels 50% of the normalized SEAP for the control was quantified (EC_{50}).

GR Specificity Assay:

The reporter plasmid utilized was comprised of the cDNA for the reporter SEAP protein, as described for the AR specific transactivation assay. Expression of the reporter SEAP protein was controlled by the mouse mammary tumor virus long terminal repeat (MMTV LTR) sequences that contains three hormone response elements (HREs) that can be regulated by both GR and PR see, e.g. G. Chalepakis et al., Cell, 53(3), 371 (1988). This plasmid was transfected into A549 cells, which expresses endogenous GR, to obtain a GR specific transactivation assay. A549 cells were obtained from the American Type Culture Collection (Rockville, MD), and maintained in RPMI 1640 supplemented with 10% fetal bovine serum (FBS; Gibco).

Determination of the GR specific antagonist activity of the compounds of the present invention was identical to that described for the AR specific transactivation assay, except that the DHT was replaced with 5 nM dexamethasone (Sigma Chemicals), a specific agonist for GR. Determination of the GR specific agonist activity of the compounds of the present invention was performed as described for the AR transactivation assay, wherein one measures the activation of the GR specific reporter system by the addition of a test compound, in the absence of a known GR specific agonists ligand.

PR Specific Assay:

The reporter plasmid utilized was comprised of the cDNA for the reporter SEAP protein, as described for the AR specific transactivation assay. Expression of the reporter SEAP protein was controlled by the mouse mammary tumor virus long terminal repeat (MMTV LTR) sequences that contains three hormone response elements (HREs) that can be regulated by both GR and PR. This plasmid was transfected into T47D, which expresses endogenous PR, to obtain a PR specific transactivation assay. T47D cells were obtained from the American Type Culture Collection (Rockville, MD), and maintained in DMEM medium supplemented with 10% fetal bovine serum (FBS; Gibco). Determination of the PR specific antagonist activity of the compounds of the present invention was identical to that described for the AR specific transactivation assay, except that the DHT was replaced with 1 nM Promegastone (NEN), a specific agonist for PR. Determination of the PR specific agonist activity of the compounds of the present invention was performed as described for the AR transactivation assay, wherein one measures the activation of the PR specific reporter system by the addition of a test compound, in the absence of a known PR specific agonists ligand.

AR Binding Assay:

For the whole cell binding assay, human LNCaP cells (T877A mutant AR) or MDA 453 (wild type AR) in 96-well microtiter plates containing RPMI 1640 or DMEM supplemented with 10% charcoal stripped CA-FBS (Cocaleco Biologicals)

89

respectively, were incubated at 37°C to remove any endogenous ligand that might be complexed with the receptor in the cells. After 48 hours, either a saturation analysis to determine the K_d for tritiated dihydrotestosterone, [^{3}H]-DHT, or a competitive binding assay to evaluate the ability of test compounds to compete with [^{3}H]-DHT were performed. For the saturation analysis, media (RPMI 1640 or DMEM – 0.2% CA-FBS) containing [^{3}H]-DHT (in concentrations ranging from 0.1 nM to 16 nM) in the absence (total binding) or presence (non-specific binding) of a 500-fold molar excess of unlabeled DHT were added to the cells. After 4 hours at 37°C, an aliquot of the total binding media at each concentration of [^{3}H]-DHT was removed to estimate the amount of free [^{3}H]-DHT. The remaining media was removed, cells were washed three times with PBS and harvested onto UniFilter GF/B plates (Packard), Microscint (Packard) was added and plates counted in a Top-Counter (Packard) to evaluate the amount of bound [^{3}H]-DHT.

For the saturation analysis, the difference between the total binding and the non-specific binding, was defined as specific binding. The specific binding was evaluated by Scatchard analysis to determine the K_d for [^{3}H]-DHT. See e.g. D. Rodbard, Mathematics and statistics of ligand assays: an illustrated guide: In: J. Langon and J. J. Clapp, eds., Ligand Assay, Masson Publishing U.S.A., Inc., New York, pp. 45-99, (1981), the disclosure of which is herein incorporated by reference.

For the competition studies, media containing 1 nM [^{3}H]-DHT and compounds of the invention ("test compounds") in concentrations ranging from 10^{-10} to 10^{-5} M were added to the cells. Two replicates were used for each sample. After 4 hours at 37°C, cells were washed, harvested and counted as described above. The data was plotted as the amount of [^{3}H]-DHT (% of control in the absence of test compound) remaining over the range of the dose response curve for a given compound. The concentration of test compound that inhibited 50% of the amount of [^{3}H]-DHT bound in the absence of competing ligand was quantified (IC_{50}) after log-logit transformation. The K_i values were determined by application of the Cheng-Prusoff equation to the IC_{50} values, where:

$$K_i = \frac{IC_{50}}{(1 + (^3\text{H-DHT}) / K_d \text{ for } ^3\text{H-DHT})}$$

After correcting for non-specific binding, IC_{50} values were determined. The IC_{50} is defined as the concentration of competing ligand needed to reduce specific binding by 50%. The K_ds for [^{3}H]-DHT for MDA 453 and LNCaP were 0.7 and 0.2 nM respectively.

Human Prostate Cell Proliferation Assay:

Compounds of the present invention were tested ("test compounds") on the proliferation of human prostate cancer cell lines. For that, MDA PCa2b cells, a cell line derived from the metastasis of a patient that failed castration, Navone et al., *Clin. Cancer Res.*, 3, 2493-500 (1997), were incubated with or without the test compounds for 72 hours and the amount of [^{3}H]-thymidine incorporated into DNA was quantified as a way to assess number of cells and therefore proliferation. The MDA PCa2b cell line was maintained in BRFF-HPC1 media (Biological Research Faculty & Facility Inc., MD) supplemented with 10% FBS. For the assay, cells were plated in Biocoated 96-well microplates and incubated at 37°C in 10% FBS (charcoal-stripped)/BRFF-BMZERO (without androgens). After 24 hours, the cells were treated in the absence (blank) or presence of 1 nM DHT (control) or with test compounds (sample) of the present invention in concentrations ranging from 10^{-10} to 10^{-5} M. Duplicates were used for each sample. The compound dilutions were performed on a Biomek 2000 laboratory work station. Seventy two hours later 0.44 uCi. of [^{3}H]-Thymidine (Amersham) was added per well and incubated for another 24 h followed by tripsinization, harvesting of the cells onto GF/B filters. Micro-scint PS were added to the filters before counting them on a Beckman TopCount.

The % Inhibition was calculated as:

$$\% \text{ Inhibition} = 100 \times (1 - [\text{average}_{control} - \text{average}_{blank} / \text{average}_{sample} - \text{average}_{blank}])$$

Data was plotted and the concentration of compound that inhibited 50% of the [^{3}H]-Thymidine incorporation was quantified (IC_{50}).

C2C12 Mouse Myoblast Transactivation Assay:

Two functional transactivation assays were developed to assess the efficacy of androgen agonists in a muscle cell background using a luciferase reporter. The first

91

assay (ARTA Stable 1) uses a cell line, Stable 1 (clone #72), which stably expresses the full length rat androgen receptor but requires the transient transfection of an enhancer/reporter. This cell line was derived from C2C12 mouse moyoblast cells. The second assay (ARTA Stable 2) uses a cell line, Stable 2 (clone #133), derived from Stable 1 which stably expresses both rAR and the enhancer/luciferase reporter.

The enhancer/reporter construct used in this system is pGL3/2XDR-1/luciferase. 2XDR-1 was reported to be an AR specific response element in CV-1 cells, Brown et. al. *The Journal of Biological Chemisty* **272**, 8227-8235, (1997). It was developed by random mutagenesis of an AR/GR consensus enhancer sequence.

ARTA Stable 1:

1. Stable 1 cells are plated in 96 well format at 6,000 cells/well in high glucose DMEM without phenol red (Gibco BRL, Cat. No.: 21063-029) containing 10% charcoal and dextran treated FBS (HyClone Cat. No.: SH30068.02), 50 mM HEPES Buffer (Gibco BRL, Cat. No.: 15630-080), 1X MEM Na Pyruvate (Gibco BRL, Cat. No.: 11360-070), 0.5X Antibiotic-Antimycotic, and 800 µg/ml Geneticin (Gibco BRL, Cat. No.: 10131-035).
2. 48 hours later, cells are transfected with pGL3/2XDR-1/luciferase using LipofectAMINE Plus™ Reagent (Gibco BRL, Cat. No.: 10964-013). Specifically, 5 ng/well pGL3/2XDR-1/luciferase DNA and 50 ng/well Salmon Sperm DNA (as carrier) are diluted with 5 µl/well Opti-MEMem media (Gibco BRL, Cat. No.: 31985-070). To this, 0.5 µl/well Plus reagent is added. This mixture is incubated for 15 minutes at room temperature. In a separate vessel, 0.385 µl/well LipofectAMINE reagent is diluted with 5 µl/well Opti-MEM. The DNA mixture is then combined with the LipofectAMINE mixture and incubated for an additional 15 minutes at room temperature. During this time, the media from the cells is removed and replaced with 60 µl/well of Opti-MEM. To this is added 10 µl/well of the DNA/LipofectAMINE transfection mixture. The cells are incubated for 4 hours.
3. The transfection mixture is removed from the cells and replaced with 90 µl of media as in #1 above.

92

4. 10 µl/well of appropriate drug dilution is placed in each well.
5. 24 hours later, the Steady-Glo™ Luciferase Assay System is used to detect activity according to the manufacturer's instructions (Promega, Cat. No.: E2520).

ARTA stable 2

1. Stable 2 cells are plated in 96 well format at 6,000 cells/well in high glucose DMEM without phenol red (Gibco BRL, Cat. No.: 21063-029) containing 10% charcoal and dextran treated FBS (HyClone Cat. No.: SH30068.02), 50 mM HEPES Buffer (Gibco BRL, Cat. No.: 15630-080), 1X MEM Na Pyruvate (Gibco BRL, Cat. No.: 11360-070), 0.5X Antibiotic-Antimycotic, 800 µg/ml Geneticin (Gibco BRL, Cat. No.: 10131-035) and 800 µg/ml Hygromycin β (Gibco BRL, Cat. No.: 10687-010).
2. 48 hours later, the media on the cells is removed and replaced with 90 µl fresh. 10 µl/well of appropriate drug dilution is placed in each well.
3. 24 hours later, the Steady-GloTM Luciferase Assay System is used to detect activity according to the manufacturer's instructions (Promega, Cat. No.: E2520).

See U.S. Patent Application Serial No. ____ (unassigned), entitled "Cell Lines and Cell-BasedAssays for Identification of Androgen Receptor Modulators" filed June 20, 2001 by Jacek Ostrowski *et al.* (Attorney Docket No. D0177), which Patent Application is incorporated herein by reference in its entirety.

Proliferation Assays

Murine Breast Cell Proliferation Assay:

The ability of compounds of the present invention ("test compounds") to modulate the function of the AR was determined by testing said compounds in a proliferation assay using the androgen responsive murine breast cell line derived from the Shionogi tumor, Hiraoka *et al., Cancer Res.*, 47, 6560-6564 (1987). Stable AR dependent clones of the parental Shionogi line were established by passing tumor fragments under the general procedures originally described in Tetuo, *et. al., Cancer Research* 25, 1168-1175 (1965). From the above procedure, one stable line, SC114,

was isolated, characterized and utilized for the testing of example compounds. SC114 cells were incubated with or without the test compounds for 72 hours and the amount of [3H]-thymidine incorporated into DNA was quantified as a surrogate endpoint to assess the number of cells and therefore the proliferation rate as described in Suzuki *et. al., J. Steroid Biochem. Mol. Biol.* 37, 559-567 (1990). The SC114 cell line was maintained in MEM containing 10^{-8} M testosterone and 2% DCC-treated FCS. For the assay, cells were plated in 96-well microplates in the maintenance media and incubated at 37°C. On the following day, the medium was changed to serum free medium [Ham's F-12:MEM (1;1, v/v) containing 0.1% BSA] with (antagonist mode) or without (agonist mode) 10^{-8} M testosterone and the test compounds of the present invention in concentrations ranging from 10^{-10} to 10^{-5} M. Duplicates were used for each sample. The compound dilutions were performed on a Biomek 2000 laboratory work station. Seventy two hours later 0.44uCi of [3H]-Thymidine (Amersham) was added per well and incubated for another 2 hr followed by tripsinization, and harvesting of the cells onto GF/B filters. Micro-scint PS were added to the filters before counting them on a Beckman TopCount.

For the antagonist mode, the % Inhibition was calculated as:

$$\% \text{ Inhibition} = 100 \times (1 - [\text{average}_{\text{sample}} - \text{average}_{\text{blank}} / \text{average}_{\text{control}} - \text{average}_{\text{blank}}])$$

Data was plotted and the concentration of compound that inhibited 50% of the [^{3}H]-Thymidine incorporation was quantified (IC_{50}).

For the agonist mode % Control was referred as the effect of the tested compound compared to the maximal effect observed with the natural hormone, in this case DHT, and was calculated as:

$$\% \text{ Control} = 100 \times (\text{average}_{\text{sample}} - \text{average}_{\text{blank}}) / (\text{average}_{\text{control}} - \text{average}_{\text{blank}})$$

Data was plotted and the concentration of compound that inhibited 50% of the [^{3}H]-Thymidine incorporation was quantified (EC_{50}).

94

***In Vitro* Assay to Measure GR Induced AP-1 Transrepression:**

The AP-1 assay is a cell based luciferase reporter assay. A549 cells, which contain endogenous glucocorticoid receptor, were stably transfected with an AP-1 DNA binding site attached to the luciferase gene. Cells are then grown in RPMI + 10% fetal calf serum (charcoal-treated) + Penicillin/Streptomycin with 0.5mg/ml geneticin. Cells are plated the day before the assay at approximately 40000 cells/well. On assay day, the media is removed by aspiration and 20 µl assay buffer (RPMI without phenol red + 10% FCS (charcoal-treated) + Pen/Strep) is added to each well. At this point either 20 µl assay buffer (control experiments), the compounds of the present invention ("test compounds") (dissolved in DMSO and added at varying concentrations) or dexamethasome (100 nM in DMSO, positive control) are added to each well. The plates are then pre-incubated for 15 minutes at 37°C, followed by stimulation of the cells with 10 ng/ml PMA. The plates are then incubated for 7 hrs at 37°C after which 40 µl luciferase substrate reagent is added to each well. Activity is measured by analysis in a luminometer as compared to control experiments treated with buffer or dexamethasome. Activity is designated as % inhibition of the reporter system as compared to the buffer control with 10 ng/ml PMA alone. The control, dexamethasone, at a concentration of ≤10 µM typically suppresses activity by 65%. Test compounds which demonstrate an inhibition of PMA induction of 50% or greater at a concentration of test compound of ≤10 µM are deemed active.

Wet Prostate Weight Assay AR Antagonist Assay:

The activity of compounds of the present invention as AR antagonists was investigated in an immature male rat model, a standard, recognized test of antiandrogen activity of a given compound, as described in L. G. Hershberger et al., *Proc. Soc. Expt. Biol. Med.*, **83**, 175 (1953); P. C. Walsh and R. F. Gittes, "Inhibition of extratesticular stimuli to prostate growth in the castrated rat by antiandrogens", *Endocrinology*, **86**, 624 (1970); and B. J. Furr et al., "ICI 176,334: A novel non-

steroid, peripherally selective antiandrogen", *J. Endocrinol.*, 113, R7-9 (1987), the disclosures of which are herein incorporated by reference.

The basis of this assay is the fact that male sexual accessory organs, such as the prostate and seminal vesicles, play an important role in reproductive function. These glands are stimulated to grow and are maintained in size and secretory function by the continued presence of serum testosterone (T), which is the major serum androgen (>95%) produced by the Leydig cells in the testis under the control of the pituitary luteinizing hormone (LH) and follicle stimulating hormone (FSH). Testosterone is converted to the more active form, dihydrotestosterone, (DHT), within the prostate by 5α-reductase. Adrenal androgens also contribute about 20% of total DHT in the rat prostate, compared to 40% of that in 65-year-old men. F. Labrie et al. Clin. Invest. Med., 16, 475-492 (1993). However, this is not a major pathway, since in both animals and humans, castration leads to almost complete involution of the prostate and seminal vesicles without concomitant adrenalectomy. Therefore, under normal conditions, the adrenals do not support significant growth of prostate tissues. M. C. Luke and D. S. Coffey, "*The Physiology of Reproduction*" ed. By E. Knobil and J. D. Neill, 1, 1435-1487 (1994). Since the male sex organs are the tissues most responsive to modulation of the androgen activity, this model is used to determine the androgen dependent growth of the sex accessory organs in immature castrated rats.

Male immature rats (19-20 days old Sprague-Dawley, Harlan Sprague-Dawely) were castrated under metofane ansestesia. Five days after surgery these castrated rats (60-70g, 23-25 day-old) were dosed for 3 days. Animals were dosed sub-cutaneously (s.c.) 1mg/kg with Testosterone Proprionate (TP) in arachis oil vehicle and anti-androgen test compounds (compounds of the present invention) were dosed orally by gavage (p.o.) in dissolved/suspensions of 80% PEG 400 and 20% Tween 80 (PEGTW). Animals were dosed (v/w) at 0.5 ml of vehicle /100g body weight. Experimental groups were as follows:

1. Control vehicle
2. Testosterone Propionate (TP) (3 mg/rat/day, subcutaneous)
3. TP plus Casodex (administered p.o. in PEGTW, QD) , a recognized antiandrogen, as a reference compound.

4. To demonstrate antagonist activity, a compound of the present invention ("test compound") was administered (p.o. in PEGTW, QD) with TP (s.c. as administered in group 2) in a range of doses.
5. To demonstrate agonist activity a compound of the present invention ("test compound") was administered alone (p.o.. in PEGTW, QD) in a range of doses.

At the end of the 3-day treatment, the animals were sacrificed, and the ventral prostate weighed. To compare data from different experiments, the sexual organs weights were first standardized as mg per 100 g of body weight, and the increase in organ weight induced by TP was considered as the maximum increase (100%). ANOVA followed by one-tailed Student or Fischer's exact test was used for statistical analysis.

The gain and loss of sexual organ weight reflect the changes of the cell number (DNA content) and cell mass (protein content), depending upon the serum androgen concentration. See Y. Okuda et al., *J. Urol.*, 145, 188-191 (1991), the disclosure of which is herein incorporated by reference. Therefore, measurement of organ wet weight is sufficient to indicate the bioactivity of androgens and androgen antagonist. In immature castrated rats, replacement of exogenous androgens increases seminal vesicles (SV) and the ventral prostate (VP) in a dose dependent manner.

The maximum increase in organ weight was 4 to 5-fold when dosing 3 mg/rat/day of testosterone (T) or 1 mg/rat/day of testosterone propionate (TP) for 3 days. The EC_{50} of T and TP were about 1 mg and 0.03 mg, respectively. The increase in the weight of the VP and SV also correlated with the increase in the serum T and DHT concentration. Although administration of T showed 5-times higher serum concentrations of T and DHT at 2 hours after subcutaneous injection than that of TP, thereafter, these high levels declined very rapidly. In contrast, the serum concentrations of T and DHT in TP-treated animals were fairly consistent during the 24 hours, and therefore, TP showed about 10-30-fold higher potency than free T.

In this immature castrated rat model, a known AR antagonist (Casodex) was also administered simultaneously with 0.1 mg of TP (ED_{90}), inhibiting the testosterone-mediated increase in the weights of the VP and SV in a dose dependent

97

manner. The antagonist effects were similar when dosing orally or subcutaneously. Compounds of the invention also exhibited AR antagonist activity by suppressing the testosterone-mediated increase in the weights of VP and SV.

Levator Ani & Wet Prostate Weight Assay AR Agonist Assay:

The activity of compounds of the present invention as AR agonists was investigated in an immature male rat model, a recognized test of anabolic effects in muscle and sustaining effects in sex organs for a given compound, as described in L. G. Hershberger et al., *Proc. Soc. Expt. Biol. Med.*, 83, 175 (1953); B. L. Beyler et al, "Methods for evaluating anabolic and catabolic agents in laboratory animals", *J. Amer. Med. Women's Ass.*, 23, 708 (1968); H. Fukuda et al., "Investigations of the levator ani muscle as an anabolic steroid assay", *Nago Dai. Yak. Ken. Nem.* 14, 84 (1966) the disclosures of which are herein incorporated by reference.

The basis of this assay lies in the well-defined action of androgenic agents on the maintenance and growth of muscle tissues and sexual accessory organs in animals and man. Androgenic steroids, such as testosterone (T), have been well characterized for their ability to maintain muscle mass. Treatment of animals or humans after castrations with an exogenous source of T results in a reversal of muscular atrophy. The effects of T on muscular atrophy in the rat levator ani muscle have been well characterized. M. Masuoka et al., "Constant cell population in normal, testosterone deprived and testosterone stimulated levator ani muscles" *Am. J. Anat.* 119, 263 (1966); Z. Gori et al., "Testosterone hypertrophy of levator ani muscle of castrated rats. I. Quantitative data" *Boll. –Soc. Ital. Biol. Sper.* 42, 1596 (1966); Z. Gori et al., "Testosterone hypertrophy of levator ani muscle of castrated rats. II. Electron-microscopic observations" *Boll. –Soc. Ital. Biol. Sper.* 42, 1600 (1966); A. Boris et al., *Steroids* 15, 61 (1970). As described above, the effects of androgens on maintenance of male sexual accessory organs, such as the prostate and seminal vesicles, is well described. Castration results in rapid involution and atrophy of the prostate and seminal vesicles. This effect can be reversed by exogenous addition of androgens. Since both the levator ani muscle and the male sex organs are the tissues most responsive to the effects of androgenic agents, this model is used to determine

98

the androgen dependent reversal of atrophy in the levator ani muscle and the sex accessory organs in immature castrated rats. Sexually mature rats (200-250 g, 6-8 weeks-old, Sprague-Dawley, Harlan) were acquired castrated from the vendor (Taconic). The rats were divided into groups and treated daily for 7 to 14 days with one of the following:

1. Control vehicle
2. Testosterone Propionate (TP) (3 mg/rat/day, subcutaneous)
3. TP plus Casodex (administered p.o. in PEGTW, QD) , a recognized antiandrogen, as a reference compound.
4. To demonstrate antagonist activity, a compound of the present invention ("test compound") was administered (p.o. in PEGTW, QD) with TP (s.c. as administered in group 2) in a range of doses.
5. To demonstrate agonist activity a compound of the present invention ("test compound") was administered alone (p.o. in PEGTW, QD) in a range of doses.

At the end of the 7-14-day treatment, the animals were sacrificed by carbon dioxide, and the levator ani, seminal vesicle and ventral prostate weighed. To compare data from different experiments, the levator ani muscle and sexual organ weights were first standardized as mg per 100 g of body weight, and the increase in organ weight induced by TP was considered as the maximum increase (100%). Super-anova (one factor) was used for statistical analysis.

The gain and loss of sexual organ weight reflect the changes of the cell number (DNA content) and cell mass (protein content), depending upon the serum androgen concentration. See Y. Okuda et al., *J. Urol.*, 145, 188-191 (1991), the disclosure of which is herein incorporated by reference. Therefore, measurement of organ wet weight is sufficient to indicate the bioactivity of androgens and androgen antagonist. In immature castrated rats, replacement of exogenous androgens increases levator ani, seminal vesicles (SV) and prostate in a dose dependent manner.

The maximum increase in organ weight was 4 to 5-fold when dosing 3 mg/rat/day of testosterone (T) or 1 mg/rat/day of testosterone propionate (TP) for 3 days. The EC_{50} of T and TP were about 1 mg and 0.03 mg, respectively. The

increase in the weight of the VP and SV also correlated with the increase in the serum T and DHT concentration. Although administration of T showed 5-times higher serum concentrations of T and DHT at 2 hours after subcutaneous injection than that of TP, thereafter, these high levels declined very rapidly. In contrast, the serum concentrations of T and DHT in TP-treated animals were fairly consistent during the 24 hours, and therefore, TP showed about 10-30-fold higher potency than free T.

MDA PCa2b Human Prostate Zenograft Assay:

In Vivo Antitumor Testing: MDA-PCa-2b human prostate tumors were maintained in Balb/c nu/nu nude mice. Tumors were propagated as subcutaneous transplants in adult male nude mice (4-6 weeks old) using tumor fragments obtained from donor mice. Tumor passage occurred every 5-6 weeks.

For antitumor efficacy trial, the required number of animals needed to detect a meaningful response were pooled at the start of the experiment and each was given a subcutaneous implant of a tumor fragment (~50 mg) with a 13-gauge trocar. Tumors were allowed to grow to approx. 100-200 mg (tumors outside the range were excluded) and animals were evenly distributed to various treatment and control groups. Treatment of each animal was based on individual body weight. Treated animals were checked daily for treatment related toxicity/mortality. Each group of animals was weighed before the initiation of treatment (Wt1) and then again following the last treatment dose (Wt2). The difference in body weight (Wt2-Wt1) provides a measure of treatment-related toxicity.

Tumor response was determined by measurement of tumors with a caliper twice a week, until the tumors reach a predetermined "target" size of 0.5 gm. Tumor weights (mg) were estimated from the formula: Tumor weight = (length x width2) ÷ 2

Tumor response end-point was expressed in terms of tumor growth inhibition (%T/C), defined as the ratio of median tumor weights of the treated tumors (T) to that of the control group (C).

To estimate tumor cell kill, the tumor volume doubling time was first calculated with the formula:

TVDT = Median time (days) for control tumors to reach target size –

Median time (days) for control tumors to reach half the target size s

And, Log cell kill = (T-C) ÷ (3.32 x TVDT)

Statistical evaluations of data were performed using Gehan's generalized Wilcoxon test.

Dunning Prostate Tumor:

Dunning R3327H prostate tumor is a spontaneously derived, well differentiated androgen responsive adenocarcinoma of the prostate (Smolev JK, Heston WD, Scott WW, and Coffey DS, *Cancer Treat Rep.* **61**, 273-287 (1977)). The growth of the R3327H subline has been selected for its highly androgen-dependent and reproducible growth in intact male rats. Therefore, this model and other sublines of this tumor have been widely used to evaluate *in vivo* antitumor activities of antiandrogens such as flutamide and bacilutamide/Casodex (Maucher A., and von Angerer, *J. Cancer Res. Clin. Oncol.*, **119**, 669-674 (1993), Furr B.J.A. *Euro. URL.* **18** (suppl. 3), 2-9 (1990), Shain S.A. and Huot RI. *J. Steriod Biochem.* **31**, 711-718 (1988)).

At the beginning of the study, the Dunning tumor pieces (about 4 x 4 mm) are transplanted subcutaneously to the flank of mature male Copenhagen rats (6-7 weeks old, Harlan-Sprague Dawley, Indianapolis, MD). About 6 weeks after the implantation, the animals with tumors of measurable size (about 80 - 120 mm^2) are randomized into treatment groups (8-10 rats/group) and the treatments are initiated. One group of the rats are castrated to serve as the negative control of tumor growth. Animals are treated daily with compounds of the current invention, standard antiandrogens such as bacilutamide or vehicle (control) for an average of 10 to 14 weeks. Test compounds are dissolved in a vehicle of (2.5 ml/kg of body weight) 10% polyethylene glycol and 0.05% Tween-80 in 1% carboxymethyl cellulose, PEG/CMC, (Sigma, St Louis, MO). Typical therapeutic experiments would include three groups of three escalating doses for each standard or test compound (in a range of 300-3 mg/kg).

Tumors in the vehicle (control) group reach a size of 1500 to 2500 mm^3, whereas the castrated animal group typically shows tumor stasis over the 14 weeks of

observation. Animals treated orally with 20 mg/kg of bicalutamide or flutamide would be expected to show a 40% reduction in tumor volumes compared to control after 14 weeks of treatment. The size of tumors are measured weekly by vernier caliper (Froboz, Switzerland), taking perpendicular measurements of length and width. Tumor volumes are measured in mm^3 using the formula: Length x Width x Height = Volume. Statistical differences between treatment groups and control are evaluated using multiple ANOVA analysis followed by one tail non-parametric Student t test.

Mature Rat Prostate Weight Assay:

The activity of compounds of the present invention were investigated in a mature male rat model, which is a variation of the Levator ani & wet prostate weight assay described above. The above *in vivo* assays are recognized assays for determining the anabolic effects in muscle and sustaining effects in sex organs for a given compound, as described in L. G. Hershberger *et al.*, *83 Proc. Soc. Expt. Biol. Med.*, 175 (1953); B. L. Beyler *et al*, "Methods for evaluating anabolic and catabolic agents in laboratory animals", *23 J. Amer. Med. Women's Ass.*, 708 (1968); H. Fukuda *et al.*, "Investigations of the levator ani muscle as an anabolic steroid assay", *14 Nago Dai. Yak. Ken. Nem.* 84 (1966) the disclosures of which are herein incorporated by reference. The basis of this assay lies in the well-defined action of androgenic agents on the maintenance and growth of muscle tissues and sexual accessory organs in animals and man.

The male sexual accessory organs, such as the prostate and seminal vesicles, play an important role in reproductive function. These glands are stimulated to grow and are maintained in size and secretory function by the continued presence of serum testosterone (T), which is the major serum androgen (>95%) produced by the Leydig cells in the testis under the control of the pituitary luteinizing hormone (LH) and follicle stimulating hormone (FSH). Testosterone is converted to the more active form, dihydrotestosterone, (DHT), within the prostate by 5α-reductase. Adrenal androgens also contribute about 20% of total DHT in the rat prostate, compared to 40% of that in 65-year-old men. F. Labrie *et. al. 16 Clin. Invest. Med.*,

102

475-492 (1993). However, this is not a major pathway, since in both animals and humans, castration leads to almost complete involution of the prostate and seminal vesicles without concomitant adrenalectomy. Therefore, under normal conditions, the adrenals do not support significant growth of prostate tissues, M. C. Luke and D. S. Coffey, "The Physiology of Reproduction" ed. By E. Knobil and J. D. Neill, 1, 1435-1487 (1994). Since the male sex organs and the levator ani are the tissues most responsive to modulation of the androgen activity, this model is used to determine the activity of compounds that modulate the androgen receptor pathway in mature rats.

Along with its mitogenic activity on tissues such as prostate, seminal vesicle and muscle, testosterone also serves as a negative regulator for its own biosynthesis. Testosterone production in the Leydig cells of the testis is controlled by the level of circulating LH released from the pituitary gland. LH levels are themselves controlled by the level of LHRH produced in the hypothalmic region. Testosterone levels in the blood serve to inhibit the secretion of LHRH and subsequently reduce levels of LH and ultimately the levels of circulating testosterone levels. By measuring blood levels of LH as they are effected by compounds of the present invention ("test compounds"), it is possible to determine the level of agonist or antagonist activity of said compounds at the hypothalamic axis of this endocrine cycle.

Matched sets of Harlan Sprague-Dawely rats (40-42 days old, 180-220 g), were dosed orally by gavage (p.o.) with the test compounds in dissolved/suspensions of 80% PEG 400 and 20% Tween 20 (PEGTW) for 14 days. Two control groups, one intact and one castrated were dose orally only with the PEGTW vehicle. Animals were dosed (v/w) at 0.5 ml of vehicle /100g body weight. Experimental groups were as follows:

1. Intact vehicle (p.o., PEGTW, QD)
2. Control vehicle (p.o., PEGTW, QD)
3. Bicalutamide (Casodex, a recognized antiandrogen, as a reference compound) or a compound of the present invention, p.o. in PEGTW QD. (in a range of doses).

At the end of the 14-day treatment, the animals were sacrificed, and the ventral prostate, the seminal vesicles, and the levator ani were removed surgically and

weighed. To compare data from different experiments, the organs weights were first standardized as mg per 100 g of body weight, and expressed as a percentage of the value of the respective organ in the intact group.

Rat luteinizing hormone (rLH) is quantitatively determined with the Biotrak [125 I] kit (Amersham Pharmacia Biotek), following the manufacturer directions. The assay is based on the competition by the LH present in the serum of the binding of [^{125}I] rLH to an Amerlex-M bead/antibody suspension. The radioactivity that remains after incubation with the serum and subsequent washes is extrapolated into a standard curve to obtain a reading in ng/ml.

The gain and loss of sexual organ and levator ani weight reflect the changes of the cell number (DNA content) and cell mass (protein content), depending upon the serum androgen concentration, see Y. Okuda *et al., J. Urol.*, 145, 188-191 (1991), the disclosure of which in herein incorporated by reference. Therefore, measurement of organ wet weight is sufficient to indicate the bioactivity of androgens and androgen antagonist. In the mature rats assay, active agonist agents will have no effect or will increase the weight of one or more of the androgen responsive organs (levator ani, prostate, seminal vessicle) and will have no effect or a suppressive effect on LH secretion. Compounds with antagonist activity will decrease the weight of one or more of the androgen responsive organs (levator ani, prostate, seminal vesicle) and will have no effect or a reduced suppressive effect on LH secretion.

CWR22 Human Prostate Zenograft Assay:

In Vivo Antitumor Testing: CWR22 human prostate tumors were maintained in Balb/c nu/nu nude mice. Tumors were propagated as subcutaneous transplants in adult male nude mice (4-6 weeks old) using tumor fragments obtained from donor mice. Tumor passage occurred every 5-6 weeks.

For antitumor efficacy trial, the required number of animals needed to detect a meaningful response were pooled at the start of the experiment and each was given a subcutaneous implant of a tumor fragment (~50 mg) with a 13-gauge trocar. Tumors were allowed to grow to approx. 100-200 mg (tumors outside the range were excluded) and animals were evenly

distributed to various treatment and control groups. Treatment of each animal was based on individual body weight. Treated animals were checked daily for treatment related toxicity/mortality. Each group of animals was weighed before the initiation of treatment (Wt1) and then again following the last treatment dose (Wt2). The difference in body weight (Wt2-Wt1) provides a measure of treatment-related toxicity.

Tumor response was determined by measurement of tumors with a caliper twice a week, until the tumors reach a predetermined "target" size of 0.5 gm. Tumor weights (mg) were estimated from the formula: Tumor weight = (length x width2) + 2.

Tumor response end-point was expressed in terms of tumor growth inhibition (%T/C), defined as the ratio of median tumor weights of the treated tumors (T) to that of the control group (C).

To estimate tumor cell kill, the tumor volume doubling time was first calculated with the formula:

TVDT = Median time (days) for control tumors to reach target size – Median time (days) for control tumors to reach half the target size

And, Log cell kill = (T-C) + (3.32 x TVDT)

Statistical evaluations of data were performed using Gehan's generalized Wilcoxon test.

The following Examples illustrate embodiments of the present invention, and are not intended to limit the scope of the claims.

Abbreviations

The following abbreviations are used herein:

DBU = 1,8-diazabicyclo[5.4.0]undec-7-ene

4-DMAP = 4-dimethylaminopyridine

ee = enantiomeric excess

DMF = dimethylformamide

EtOAc = ethyl acetate

LDA = lithium diisopropylamide

Hünig's Base = N,N-diisopropylethylamine

Me = methyl

RT = retention time

TFA = trifluoroacetic acid

THF = tetrahydrofuran

TLC = thin layer chromatography

TMS = trimethylsilyl

pTSA = para-toluenesulfonic acid

Δ = heat

t-Bu = *tert*-butyl

$PhCH_3$ = toluene

Pd/C = palladium on activated charcoal

TsCl = tosyl chloride

TBSOTf = *tert*-butyldimethylsilyl trifluoromethane sulfonate

TBS = *tert*-butyldimethylsilane

MeI = methyl iodide

$(BOC)_2O$ = di-*tert*-butyl dicarbonate

TEA = triethylamine

n-BuLi = *n*-butyllithium

rt = room temperature

LC = liquid chromatography

Ts = tosyl

Ph = phenyl

EtOH = ethanol

DCE = dichloroethane

DMSO = dimethylsulfoxide

Ra-Ni = Raney Nickel

MS = molecular sieves

MS(ES) = Electro-Spray Mass Spectrometry

mCPBA = m-chloroperoxybenzoic acid

106

sat = saturated

AcOH = acetic acid

MeOH = methanol

Et_2O = diethyl ether

Ac = acetyl

DEAD = diethyl azodicarboxylate

h = hours

Et = ethyl

WSDCC = water soluble dicarbonyl diimide, 1-(3-dimethylaminopropyl)-3-ethylcarbodiimide hydrochloride

TBAF = tetrabutylammonium fluoride

DBAD = di-terbutylazodicarboxylate

DCC = Dicyclohexylcarbodiimide

Wilkinson's catalyst = $RhCl(PPh_3)_3$

ADDP = 1,1-[azodicarbonyl]dipiperidine

DMA = dimethylacetamide


DME = 1,2-dimethoxyethane

BOP = benzotriazol-1-yloxytris(dimethylamino)-phosphonium hexafluorophosphate


107

Example 1

(3aα,4α,7α,7aα)-2-(4-Bromo-3-methylphenyl)tetrahydro-4,7-ethanothiopyrano[3,4-c]pyrrole-1,3,8(2H,4H)-trione (1C)




A. 4-(tert-Butyldimethylsiloxy)-2H-thiopyran (1A)



2,3-Dihydro-4H-thiopyran-4-one (1.50 g, 13.14 mol, synthesized as described in Richards *et al., J. Org. Chem.* 46, 4836-4842 (1981)) was dissolved in CH_2Cl_2 (130 mL) and triethylamine (5.47 mL, 39.41 mmol) was added. *tert*-Butyldimethylsilyl trifluoromethanesulfonate (3.62 mL, 15.77 mmol) was then added. After 10 minutes, the volatiles were removed by rotary evaporator at 25°C. The resulting yellow oil was passed through a short column of SiO_2 eluting with 3% TEA in hexanes to yield 1.82 g of compound 1A as an orange oil.

B. 1-[4-bromo-3-methylphenyl]-1H-pyrrole-2,5-dione (1B)



4-Bromo-3-methylaniline (1.55 g, 8.33 mmol) and maleic anhydride (0.898 g, 9.16 mmol) were dissolved in acetic acid (10 mL) and heated at 115 °C for 12 h. The reaction was then cooled to 25°C and the acetic acid was removed in vacuo. The resulting residue was suspended in 5% K_2CO_3 (100 mL), stirred for 25 minutes and followed by filtering and rinsing with water. The material was then dried in vacuo to give compound 1B as a light brown solid (1.65 g). HPLC: 100% at 2.96 min


(retention time) (YMC S5 ODS column 4.6 x 50 mm eluting with 10-90% aqueous methanol over 4 minutes containing 0.1% TFA, 4 mL/min, monitoring at 220 nm).

C. (3aα,4α,7α,7aα)-2-(4-Bromo-3-methylphenyl)tetrahydro-4,7-ethanothiopyrano[3,4-c]pyrrole-1,3,8(2H,4H)-trione (1C)

Compound **1A** (0.313 g, 1.41 mmol) and compound **1B** (0.250 g, 0.94 mmol) were dissolved in toluene and heated to reflux for 5 h. The toluene was then removed by passing a stream of argon through the reaction flask. The residue was then purified by flash chromatography on SiO_2 eluting with 20% hexane in chloroform. This gave 0.168 g of the enol ether intermediate as a yellow solid. The enol ether intermediate was dissolved in dichloroethane (2.0 mL) and TFA (0.25 mL) was added. After 0.5 h, the reaction was quenched with saturated aqueous $NaHCO_3$ and extracted with CH_2Cl_2 (2 x 30 mL). The organics were dried over anhydrous sodium sulfate and evaporated to give 0.079 g of compound **1C** as a white solid. HPLC: 99% at 3.010 min (retention time) (YMC S5 ODS column 4.6 x 50 mm eluting with 10-90% aqueous methanol over 4 minutes containing 0.1% TFA, 4 mL/min, monitoring at 220 nm), MS (ES): m/z 396.9 $[M+NH_4]^+$.

Example 2

(3aα,4α,7α,7aα)-2-(4-Bromo-3-methylphenyl)tetrahydro-4,7-ethanothiopyrano[3,4-c]pyrrole-1,3,8(2H,4H)-trione 5,5-dioxide (2)




Compound **1C** (0.040 g, 0.105 mmol) was dissolved in CH_2Cl_2 (4.0 mL) and cooled to 0°C. *m*-CPBA (60% purity, 0.061 g, 0.210 mmol) was added and the reaction was then warmed to 25°C. After 1 h, a 1:1 mixture of saturated $NaHCO_3$ and saturated sodium sulfite (20 mL) was added with vigorous stirring. After 15 minutes,

the mixture was extracted with CH_2Cl_2 (2 x 30 mL) and the organics were dried over anhydrous sodium sulfate to yield 0.031 g of compound 2 as a white solid. No purification was necessary. HPLC: 78% at 2.290 min (retention time) (YMC S5 ODS column 4.6 x 50 mm eluting with 10-90% aqueous methanol over 4 minutes containing 0.1% TFA, 4 mL/min, monitoring at 220 nm), MS (ES): m/z 429.8 $[M+NH_4]^+$.

Example 3

(3aα,4β,7β,7aα)-2-(3-Chlorophenyl)hexahydro-4-methyl-4, 7-epoxy-1H-isoindole-1,3(2H)-dione (3)





3-Chloroaniline (0.100 g, 0.787 mmol) and 3,6-endoxo-3-methylhexahydrophthalic anhydride (0.172 g, 0.945 mmol) were dissolved in AcOH (2.0 mL) and heated to 110°C for 11 h. The reaction was then cooled to 25°C and poured into cold saturated aq K_2CO_3 and stirred vigorously for 10 min. The solution was then filtered and rinsed with water. The resulting filtrate was dried in vacuo to give 0.118 g of compound 3 as a white solid. No further purification was needed. HPLC: 99% at 2.510 min (retention time) (YMC S5 ODS column 4.6 x 50 mm eluting with 10-90% aqueous methanol over 4 minutes containing 0.1% TFA, 4 mL/min, monitoring at 220 nm), MS (ES): m/z 292.32 $[M+H]^+$.

110

Example 4

(3aα,4α,7α,7aα)- and (3aα,4β,7β,7aα)-4-[(Acetyloxy)methyl]-3a,4,7,7a-tetrahydro-2-[3-(trifluoromethyl)phenyl]-4,7-epoxy-1H-isoindole-1,3(2H)-dione (4i and 4ii, respectively)







2-Acetoxymethylfuran (0.599 mL, 4.78 mmol) and 1-[3-(trifluoromethyl)-phenyl]-1H-pyrrole-2,5-dione (0.500 g, 2.39 mmol) were dissolved in methylene chloride (3.0 mL) at 25°C. After 22 h, the volatiles were removed in vacuo and the resulting residue was purified by flash chromatography on SiO_2 eluting with 0-15% acetone in methylene chloride to give 0.438 g of a yellow oil, as a 2:1 mixture of compound 4i and compound 4ii, which was not separated. HPLC: 100% at 3.093 min (retention time) (YMC S5 ODS column 4.6 x 50 mm eluting with 10-90% aqueous methanol over 4 minutes containing 0.1% TFA, 4 mL/min, monitoring at 220 nm), MS (ES): m/z 398.9 $[M+ NH_4]^+$.

Example 5

(3aα,4α,7α,7aα)- and (3aα,4β,7β,7aα)-4-[(Acetyloxy)methyl]-Hexahydro-2-[3-(trifluoromethyl)phenyl]-4,7-epoxy-1H-isoindole-1,3(2H)-dione (5i and 5ii, respectively)







The 2:1 mixture of compounds **4i** and **4ii** (0.361 g, from Example 4) was dissolved in ethyl acetate (25 mL) and Pd/C (10% Pd, 0.2 g) was added. Hydrogen was introduced via a balloon and the reaction was stirred at 25°C for 4 h; followed by filtration through celite and rinsed with ethyl acetate. Concentration in vacuo gave a yellow oil that was determined to be a 2:1 mixture of compound **5i** and compound **5ii** (0.348 g), which was not separated. HPLC: 100% at 2.900 min (retention time) (YMC S5 ODS column 4.6 x 50 mm eluting with 10-90% aqueous methanol over 4 minutes containing 0.1% TFA, 4 mL/min, monitoring at 220 nm), MS (ES): m/z 401.0 $[M+ NH_4]^+$.

Example 6

(3aα,4α,7α,7aα)- and (3aα,4β,7β,7aα)-3a,4,7,7a-Tetrahydro-5-(hydroxymethyl)-2-[3-(trifluoromethyl)phenyl]-4,7-epoxy-1H-isoindole-1,3(2H)-dione (6i and 6ii, respectively)






1-[3-(Trifluoromethyl)phenyl]-1H-pyrrole-2,5-dione (0.500 g, 2.39 mmol) and 3-furanmethanol (0.412 mL, 4.78 mmol) were dissolved in methylene chloride (3.0 mL) and stirred at 25°C for 20 h. The volatiles were then removed in vacuo and the resulting material purified by flash chromatography on SiO_2 eluting with chloroform/acetone to give 0.379 g of compound **6i** and 0.220 g of compound **6ii**, both as white solids. Compound **6i**: HPLC: 100% at 2.197 min (retention time) (YMC S5 ODS column 4.6 x 50 mm eluting with 10-90% aqueous methanol over 4 minutes containing 0.1% TFA, 4 mL/min, monitoring at 220 nm), MS (ES): m/z 338.0 $[M-H]^-$. Compound **6ii**: HPLC: 100% at 2.477 min (retention time) (YMC S5 ODS column 4.6 x 50 mm eluting with 10-90% aqueous methanol over 4 minutes

containing 0.1% TFA, 4 mL/min, monitoring at 220 nm), MS (ES): m/z 338.0 [M-H]⁻

Example 7


(3aα,4α,7α,7aα)-3a,4,7,7a-Tetrahydro-5-(hydroxymethyl)-4-methyl-2-[3-(trifluoromethyl)phenyl]-4,7-epoxy-1H-isoindole-1,3(2H)-dione (7)



2-Methyl-3-furanmethanol (0.537 g, 4.78 mmol) and 1-[3-(trifluoromethyl)-phenyl]-1H-pyrrole-2,5-dione (0.500 g, 2.39 mmol) were dissolved in dichloroethane (2.0 mL) and stirred at 25°C for 20 h. The reaction was then concentrated in vacuo and purified by flash chromatography in SiO_2 eluting with ethyl acetate/methylene chloride to give 0.317 g of compound 7 as a white solid. No other possible isomer was isolated after chromatography. HPLC: 100% at 2.197 min (retention time) (YMC S5 ODS column 4.6 x 50 mm eluting with 10-90% aqueous methanol over 4 minutes containing 0.1% TFA, 4 mL/min, monitoring at 220 nm), MS (ES): m/z 351.9 [M-H]⁻.

Example 8

(3aα,4β,7β,7aα)-2-[3,5-Bis(trifluoromethyl)phenyl]hexahydro-4,7-epoxy-1H-isoindole-1,3(2H)-dione (8)




3,5-Bis-(trifluoromethyl)-aniline (0.017 g, 0.0075 mmol) was dissolved in acetic acid (0.300 mL) and transferred to a 1.5 mL conical vial with a septa cap.

Stock solutions of an additional 95 amines were prepared as described above. To each of the above vials was added 0.4 mL (0.12 mmol) of a stock solution of exo-7-oxabicyclo[2.2.1]heptane-2,3-dicarboxylic anhydride in acetic acid. The vials were then sealed and heated at 110°C for 11 h. Upon cooling to 25°C, the caps were removed from the vials and the acetic acid was removed in vacuo. To each vial was added 1 mL of 2:1 acetone/methylene chloride and the vials were heated at 40°C for 1 h. Once all products were in solution, they were transferred via robot to filter tubes with coarse frits pre-wetted with 0.2 mL of water. Nitrogen was blown through each tube until the volatile organics were removed. 1.5 mL of 10% aq K_2CO_3 was then added to each tube followed by vigorous shaking at 25°C for 15 min. The tubes were then drained, resealed and 1.0 mL of water was added to each tube followed by shaking. The tubes were drained again and washed with water a second time. The resulting residues in each tube was then dried in vacuo for 48 h. After drying, 1.0 mL of 20% TFA in methylene chloride was added to each tube and the racks were shaken for 30 min. The tubes were then drained into a 96-well plate with pre-tared custom micro-tubes present. Each tube was assayed for product purity (analytical LC) and identity (LC-MS). The tubes were then concentrated in vacuo and weighed for yields. The tube containing the reaction of 3,5-bistrifluoromethylaniline and exo-7-oxabicyclo[2.2.1]heptane-2,3-dicarboxylic anhydride, yielded 0.022 g of compound 8 as a white solid. HPLC: 94% at 4.03 min (retention time) (YMC S5 ODS column 4.6 x 50 mm eluting with 10-90% aqueous methanol over 4 minutes containing 0.1% TFA, 4 mL/min, monitoring at 220 nm), MS (ES): m/z 434.2 $[M+Na+MeOH]^+$. Of the remaining 95 additional reactions run, a total of 80 final compounds were obtained in >70% purity and >5 mg yield. Several samples needed further purification which was performed by short SiO_2 column eluting with methylene chloride/acetone. See Table 2 below.

114

Example 9


(3aα,4α,7α,7aα)-2-(4-Bromophenyl)octahydro-1,3-dioxo-4,7-etheno-5H-pyrrolo[3,4-c]pyridine-5-carboxylic acid phenyl ester (9)



1-[4-Bromophenyl]-1H-pyrrole-2,5-dione (0.250 g, 0.992 mmol, synthesized as described in Example 1B) and 1(2H)-pyridinecarboxylic acid phenylmethyl ester (0.299 g, 1.49 mmol, synthesized as described in Richard *et. al., J. Org. Chem.* 46, 4836-4842 (1981)) were dissolved in toluene and heated to 85°C for 1 h. Upon cooling to 25°C, the toluene was removed in vacuo. The resulting residue was dissolved in a minimum amount of chloroform and the product was precipitated by addition of hexanes. After 1 h at 25°C, the product was filtered and rinsed with cold 20% hexanes in chloroform giving compound 9 as a white solid (0.243 g) as a single isomer. HPLC: 100% at 3.393 min (retention time) (YMC S5 ODS column 4.6 x 50 mm eluting with 10-90% aqueous methanol over 4 minutes containing 0.1% TFA, 4 mL/min, monitoring at 220 nm), MS (ES): m/z 454.98 $[M+H]^+$.

Example 10

(3aα,4α,7α,7aα)-2-(4-Bromophenyl)octahydro-1,3-dioxo-4,7-etheno-5H-pyrrolo[3,4-c]pyridine-5-carboxylic acid phenylmethyl ester (10)




1-[3-(Trifluoromethyl)phenyl]-1H-pyrrole-2,5-dione (3.78 g, 15.7 mmol) and 1(2H)-pyridinecarboxylic acid phenylmethyl ester (4.0 g, 18.8 mmol, synthesized as

described in Richard *et. al., J. Org. Chem.* **46**, 4836-4842 (1981)) were dissolved in toluene and heated at 80°C for 3 h. After cooling to 25°C, the toluene was removed in vacuo and the resulting residue was purified by flash chromatography on SiO_2 eluting with methanol/methylene chloride to give 3.2 g of compound **10** as a yellow oil. HPLC: 95% at 3.510 min (retention time) (YMC S5 ODS column 4.6 x 50 mm eluting with 10-90% aqueous methanol over 4 minutes containing 0.1% TFA, 4 mL/min, monitoring at 220 nm), MS (ES): m/z 457.2 $[M+H]^+$.

Example 11

(3aα,4α,7α,7aα)-Hexahydro-2-[3-(trifluoromethyl)phenyl]-4,7-ethano-1H-pyrrolo[3,4-c]pyridine-1,3(2H)-dione trifluoroacetate (11)




Compound **10** (3.2 g) was dissolved in 100 ml of MeOH and 10% Pd/C DeGussa catalyst (2 g) was added. Hydrogen was then introduced via a balloon. After 1 h, the reaction was filtered through celite and rinsed with MeOH. The volatiles were removed in vacuo and the resulting crude material was purified by reverse phase preparative HPLC to yield 2.5 g of compound **11** as the TFA salt (white solid). HPLC: 99% at 1.843 min (retention time) (YMC S5 ODS column 4.6 x 50 mm eluting with 10-90% aqueous methanol over 4 minutes containing 0.1% TFA, 4 mL/min, monitoring at 220 nm), MS (ES): m/z 325.12 $[M+H]^+$.

116

Example 12


(3aα,4α,7α,7aα)-5-Acetylhexahydro-2-[3-(trifluoromethyl)phenyl]-4,7-ethano-1H-pyrrolo[3,4-c]pyridine-1,3(2H)-dione (12)



Compound 11 (0.100 g, 0.23 mmol) was suspended in THF (5.0 mL) and TEA (0.097 mL, 0.46 mmol) was added resulting in a homogeneous solution. Acetyl chloride (0.033 mL, 0.46 mmol) was then added. After 2 h, the reaction was quenched with saturated aqueous $NaHCO_3$ and extracted with methylene chloride (3 x 15 mL). The crude material was purified by preparative-TLC eluting with chloroform/acetone to give 0.099 g of compound 12 as a colorless oil. HPLC: 99% at 2.66 min (retention time) (YMC S5 ODS column 4.6 x 50 mm eluting with 10-90% aqueous methanol over 4 minutes containing 0.1% TFA, 4 mL/min, monitoring at 220 nm), MS (ES): m/z 367.0 $[M+H]^+$.

Example 13

(3aα,4α,7α,7aα)-5-Benzoylhexahydro-2-[3-(trifluoromethyl)phenyl]-4,7-ethano-1H-pyrrolo[3,4-c]pyridine-1,3(2H)-dione (13)




Compound 11 (0.100 g, 0.23 mmol) was suspended in THF (5.0 mL) and TEA (0.097 mL, 0.46 mmol) was added resulting in a homogeneous solution. Benzoyl chloride (0.05433 mL, 0.46 mmol) was then added. After 2 h, the reaction was

quenched with saturated aqueous $NaHCO_3$ and extracted with methylene chloride (3 x 15 mL). The crude material was purified by reverse phase preparative-HPLC to give 0.020 g of compound 13 as a white foam. HPLC: 99% at 3.183 min (retention time) (YMC S5 ODS column 4.6 x 50 mm eluting with 10-90% aqueous methanol over 4 minutes containing 0.1% TFA, 4 mL/min, monitoring at 220 nm), MS (ES): m/z 429.1 $[M+H]^+$.

Example 14

(3aα,4α,7α,7aα)-Hexahydro-5-methyl-2-[3-(trifluoromethyl)phenyl]-4,7-ethano-1H-pyrrolo[3,4-c]pyridine-1,3(2H)-dione (14)




Compound 11 (0.100 g, 0.23 mmol) was suspended in THF (5.0 mL) and TEA (0.097 mL, 0.46 mmol) was added resulting in a homogeneous solution. Dimethyl sulfate (0.043 mL, 0.46 mmol) was added and the reaction stirred at 25°C. After 14 h, the reaction was concentrated in vacuo and the crude material was purified by preparative-TLC eluting with 10% MeOH in methylene chloride to give 0.030 g of compound 14 as a white solid. HPLC: 100% at 1.797 min (retention time) (YMC S5 ODS column 4.6 x 50 mm eluting with 10-90% aqueous methanol over 4 minutes containing 0.1% TFA, 4 mL/min, monitoring at 220 nm), MS (ES): m/z 339.21 $[M+H]^+$.

118

Example 15


(3aα,4α,7α,7aα)-Hexahydro-5-(phenylmethyl)-2-[3-(trifluoromethyl)phenyl]-4,7-ethano-1H-pyrrolo[3,4-c]pyridine-1,3(2H)-dione trifluoroacetate (15)



Compound 11 (0.100 g, 0.23 mmol) was dissolved in DMF (5.0 mL) and K_2CO_3 (0.063 g, 0.46 mmol) was added. Benzyl bromide (0.041 mL, 0.35 mmol) was then added. The reaction was stirred at 25°C for 1 h, and then filtered and concentrated. The crude material was purified by reverse phase preparative-HPLC to give 0.055 g of compound 15 as a white solid. HPLC: 100% at 2.31 min (retention time) (YMC S5 ODS column 4.6 x 50 mm eluting with 10-90% aqueous methanol over 4 minutes containing 0.1% TFA, 4 mL/min, monitoring at 220 nm), MS (ES): m/z 415.36 $[M+H]^+$.

Example 16

(3aα,4α,7α,7aα)-Hexahydro-5-propyl-2-[3-(trifluoromethyl)phenyl]-4,7-ethano-1H-pyrrolo[3,4-c]pyridine-1,3(2H)-dione trifluoroacetate (16)




Compound 11 (0.100 g, 0.23 mmol) was dissolved in DMF (5.0 mL) and K_2CO_3 (0.079 g, 0.57 mmol) was added, followed by 1-bromopropane (0.031 mL, 0.34 mmol). The reaction was stirred at 25°C for 6 h, and then filtered and concentrated. The crude material was purified by reverse phase preparative-HPLC to

give 0.070 g of compound 16 as a white solid. HPLC: 100% at 1.907 min (retention time) (YMC S5 ODS column 4.6 x 50 mm eluting with 10-90% aqueous methanol over 4 minutes containing 0.1% TFA, 4 mL/min, monitoring at 220 nm), MS (ES): m/z 340.22 $[M+H]^+$.

Example 17

(3aα,4α,4aβ,5aβ,6α,6aα)-2-[4-Cyano-3-(trifluoromethyl)phenyl]decahydro-1,3-dioxo-4,6-(iminomethano)cycloprop[f]isoindole-7-carboxylic acid phenylmethyl ester (17)




1-Methyl-3-nitro-1-nitrosoguanidine (2.5 g, 17 mmol) was added portion-wise to a solution of 40% KOH/H_2O (15 mL) and Et_2O (25 mL) at 0°C. The ether layer turned yellow once addition was complete. After 30 min at 0°C, the ether layer was poured into a solution of (3aα,4α,7α,7aα)-2-[4-cyano-3-(trifluoromethyl)phenyl]-octahydro-1,3-dioxo-4,7-etheno-5H-pyrrolo[3,4-c]pyridine-5-carboxylic acid phenylmethyl ester (0.50 g, 1.09 mmol, prepared as described in Example 10) and $Pd(OAc)_2$ (0.010 g) in THF (10 mL) at 0°C. The reaction was then warmed slowly to 25°C and stirred for 24 h and then filtered through celite, rinsing with THF. The crude material was then purified by flash chromatography on SiO_2 eluting with $MeOH/CH_2Cl_2$ to give 0.34 g of compound 17 as a white solid and a single isomer. HPLC: 100% at 3.61 min (retention time) (YMC S5 ODS column 4.6 x 50 mm eluting with 10-90% aqueous methanol over 4 minutes containing 0.1% TFA, 4 mL/min, monitoring at 220 nm), MS (ES): m/z 496.25 $[M+H]^+$.

120

194

Example 18


(3aα,4α,4aβ,5aβ,6α,6aα)-4-[Decahydro-1,3-dioxo-4,6-(iminomethano)cycloprop[f]isoindol-2-yl]-2-(trifluoromethyl)benzonitrile (18)



Compound 17 (0.200 g, 0.404 mmol) was dissolved in MeOH (20 mL) and 5% Pd/C (0.200 g) was added. Hydrogen was then introduced via balloon. After 3 h, the reaction was filtered through celite, rinsed with MeOH and the volatiles were removed in vacuo to yield compound 18 (0.130 g) as a white solid. HPLC: 100% at 1.80 min (retention time) (YMC S5 ODS column 4.6 x 50 mm eluting with 10-90% aqueous methanol over 4 minutes containing 0.1% TFA, 4 mL/min, monitoring at 220 nm), MS (ES): m/z 362.09 $[M+H]^+$.

Example 19

(3aα,4α,4aβ,5aβ,6α,6aα)-4-[Decahydro-7-methyl-1,3-dioxo-4,6-(iminomethano)cycloprop[f]isoindol-2-yl]-2-(trifluoromethyl)benzonitrile (19)




Compound 17 (0.100 g, 0.277 mmol) was dissolved in CH_3CN (2.0 mL). TEA (0.19 mL, 1.39 mmol) and MeI (0.052 mL, 0.83 mmol) were then added and the reaction was stirred at 25°C for 14 h. The reaction was concentrated and the crude


material was dissolved in CH_2Cl_2/water and extracted with CH_2Cl_2 (3 x 15 mL). The combined organics were dried over anhydrous Na_2SO_4. The crude material was purified by flash chromatography eluting with 3% MeOH/CH_2Cl_2 to give 0.030 g of compound 19 as a light yellow solid. HPLC: 100% at 1.720 min (retention time) (YMC S5 ODS column 4.6 x 50 mm eluting with 10-90% aqueous methanol over 4 minutes containing 0.1% TFA, 4 mL/min, monitoring at 220 nm), MS (ES): m/z 376.11 $[M+H]^+$.

Example 20

(3aα,4β,7β,7aα)-4-(Octahydro-4,7-dimethyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl)-2-(trifluoromethyl)benzonitrile (20B)



A. (3aα,4β,7β,7aα)-Hexahydro-4,7-epoxyisobenzofuran-1,3-dione (20A)




Freshly distilled dimethyl furan (1.60 mL, 15.3 mmol) was dissolved in CH_2Cl_2 (2.0 mL) and maleic anhydride (1.0 g, 10.2 mmol) was added. The reaction was stirred at 25°C for 16 h and was then concentrated in vacuo to give a yellow solid. This solid was dissolved in ethyl acetate (30 mL) and Pd/C (10% Pd, 0.200 g) was added. Hydrogen was then introduced by a balloon and the reaction stirred for 24 h. The Pd was removed by filtration through celite rinsing with EtOAc followed by concentration in vacuo to give the compound 20A (1.69 g) as a white solid. 2-Dimensional NOE experiments confirmed the structural assignment to be that of compound 20A.

B. (3aα,4β,7β,7aα)-4-(Octahydro-4,7-dimethyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl)-2-(trifluoromethyl)benzonitrile (20B)


A solution of compound **20A** (603 mg, 3.21 mmol, 1 eq), 5-amino-2-cyanobenzotrifluoride (640 mg, 3.44 mmol, 1.07 eq) and TsOH (10 mg, cat amount) in toluene (5 mL) was heated in a sealed tube for 2 days. The reaction mixture was cooled to room temperature and then concentrated under reduced pressure. Purification by flash chromatography on silica gel eluting with 50% EtOAc/hexanes gave 400 mg (1.10 mmol, 34 %) of compound **20B** as a white solid. HPLC: 99% at 3.04 min (retention time) (YMC S5 ODS column 4.6 x 50 mm, 10-90% aqueous methanol over 4 minutes containing 0.2% phosphoric acid, 4 mL/min, monitoring at 220 nm), MS (ESI): m/z 382.2 $[M+NH_4]^+$.

Example 21

(3aα,4β,7β,7aα)-N-[4-[[2-[2-[4-Cyano-3-(trifluoromethyl)phenyl]octahydro-7-methyl-1,3-dioxo-4,7-epoxy-4H-isoindol-4-yl]ethyl]thio]phenyl]acetamide (21E)




A. 5-Methyl-2-furanethanol (21A)



A solution of n-BuLi (83 mL, 133.0 mmol, 1.2 eq, 1.6 M in hexanes) was added to a stirred solution of 2-methylfuran (10 mL, 110.8 mmol, 1 eq) in THF (85 mL) at 0°C under inert atmosphere. The reaction mixture was stirred for 4 h at room temperature then cooled to 0°C. Ethylene oxide (8.3 mL, 166.3 mmol, 1.5 eq) was added dropwise and the reaction mixture was allowed to warm to room temperature overnight. After quenching with saturated aqueous NH_4Cl, the resulting layers were separated and the aqueous layer was extracted with Et_2O (2 X). The combined


organic layers were dried over Na_2SO_4 and concentrated under reduced pressure. Distillation at atmospheric pressure (170-185 °C) gave 10.13 g (80.3 mmol, 72%) of compound **21A** as a light yellow oil.

B. 2-(2-Bromoethyl)-5-methylfuran (21B)




Ph_3Br_2 (3.68 g, 8.72 mmol, 1.1 eq) was added to a solution of compound **21A** (1 g, 7.93 mmol, 1 eq) in DMF (8 mL) and the reaction mixture was stirred at room temperature for 1 h. The reaction mixture was added to H_2O and extracted with EtOAc (3 X). The combined organic layers were washed with H_2O (2 X), dried over Na_2SO_4 and concentrated under reduced pressure. Purification by flash chromatography on silica gel eluting with 10% EtOAc/hexanes gave 0.507 g (2.68 mmol, 34%) of compound **21B**.

C. N-[4-[[2-(5-Methyl-2-furanyl)ethyl]thio]phenyl]acetamide (21C)



To a solution of 4-acetamidothiophenol (442 mg, 2.64 mmol, 1 eq) in THF (1 mL) at 0°C under inert atmosphere was added a solution of n-BuLi (2 mL, 3.17 mmol, 1.2 eq, 1.6 M in hexanes) in THF (1 mL). The reaction solution was stirred at room temperature for 10 mins and a solution of compound **21B** (0.5 g, 2.64 mmol, 1 eq) in THF (3 mL) was added. After all the starting material was consumed as determined by TLC, the reaction was quenched with H_2O and the mixture was extracted with EtOAc (2X), dried over Na_2SO_4 and concentrated under reduced pressure. Purification by flash chromatography on silica gel eluting with 50% EtOAc/hexanes gave 0.644 g (2.34 mmol, 88%) of compound **21C**. MS (ESI): m/z 276.09 $[M+H]^+$.

D. **(3aα,4β,7β,7aα)-N-[4-[[2-[2-[4-Cyano-3-(trifluoromethyl)phenyl]-1,2,3,3a,7,7a-hexahydro-7-methyl-1,3-dioxo-4,7-epoxy-4H-isoindol-4-yl]ethyl]thio]phenyl]acetamide (21D)**




A solution of compound 21C (195 mg, 0.708 mmol, 1 eq) and 4-(2,5-dihydro-2,5-dioxo-1H-pyrrol-1-yl)-2-trifluoromethylbenzonitrile (377 mg, 1.416 mmol, 2 eq, prepared as described for Example 1B) in CH_2Cl_2 (1.5 mL) was stirred at room temperature for two days. The reaction mixture was concentrated under reduced pressure to yield compound 21D as determined by NMR analysis. Compound 21D was used directly in the next step without purification.

E. **(3aα,4β,7β,7aα)-N-[4-[[2-[2-[4-Cyano-3-(trifluoromethyl)phenyl]-octahydro-7-methyl-1,3-dioxo-4,7-epoxy-4H-isoindol-4-yl]ethyl]thio]-phenyl]acetamide (21E)**

A solution of crude compound 21D (0.708 mmol) and 10% Pd/C (200 mg) in MeOH (20 mL) was stirred under a hydrogen atmosphere over night. Purification by preparative chromatography [HPLC at 34.4 min (retention time) (YMC S5 ODS column 20 x 250 mm, 0-100% aqueous methanol over 30 minutes containing 0.1% TFA, 10 mL/min, monitoring at 220 nm)] followed by flash chromatography on silica gel eluting with 1% MeOH/CH_2Cl_2 gave 29 mg (0.053 mmol, 7.5%) of compound 21E as a yellow powder. HPLC: 99% at 3.44 min (retention time) (YMC S5 ODS column 4.6 x 50 mm, 10-90% aqueous methanol over 4 minutes containing 0.2% phosphoric acid, 4 mL/min, monitoring at 220 nm), MS (ESI): m/z 544.01 $[M+H]^+$.

Example 22

(3aα,4β,7β,7aα)-N-[4-[[2-[2-[4-Cyano-3-(trifluoromethyl)phenyl]octahydro-7-methyl-1,3-dioxo-4,7-epoxy-4H-isoindol-4-yl]ethyl]sulfinyl]phenyl]acetamide (22)




*m*CPBA (12 mg, 0.05 mmol) was added portion-wise to a solution of crude compound **21E** (65 mg, 0.12 mmol, 1 eq) in CH_2Cl_2 (6 mL) until the starting material was consumed. Purification by preparative chromatography [HPLC at 30.5 min (retention time) (YMC S5 ODS column 30 x 250 mm, 0-100% aqueous methanol over 30 minutes containing 0.1% TFA, 25 mL/min, monitoring at 220 nm)] gave 27.5 mg (0.049 mmol, 41%) of compound **22** as a tan solid (~1:1 mixture of diastereomers). HPLC: 96% at 2.88 min (retention time) (YMC S5 ODS column 4.6 x 50 mm eluting with 10-90% aqueous methanol over 4 minutes containing 0.1% TFA, 4 mL/min, monitoring at 220 nm), MS (ESI): m/z 559.97 $[M+H]^+$.

Example 23

(3aα,4β,7β,7aα)-N-[4-[[2-[2-[4-Cyano-3-(trifluoromethyl)phenyl]octahydro-7-methyl-1,3-dioxo-4,7-epoxy-4H-isoindol-4-yl]ethyl]sulfonyl]phenyl]acetamide

(23)




*m*CPBA (26 mg, 0.105 mmol, 3 eq) was added to a solution of compound **21E** (19 mg, 0.035 mmol, 1 eq) in CH_2Cl_2 (6 mL) and the reaction was stirred at rt until starting material and the intermediate sulfoxide (compound **22**) were consumed as was apparent by TLC. Purification by preparative chromatography [HPLC at 53.3 min (retention time) (YMC S5 ODS column 30 x 250 mm, 0-70% aqueous methanol over 45 minutes containing 0.1% TFA, 25 mL/min, monitoring at 220 nm)] gave 27.5 mg (0.049 mmol, 40%) of compound **23** as a white solid. HPLC: 99% at 2.94 min (retention time) (YMC S5 ODS column 4.6 x 50 mm, 10-90% aqueous methanol over 4 minutes containing 0.2% phosphoric acid, 4 mL/min, monitoring at 220 nm), MS (ESI): m/z 575.95 $[M+H]^+$.


127

Example 24

(3aα,4β,7β,7aα)- and (3aα,4α,7α,7aα)-N-[2-[2-[4-Cyano-3-(trifluoromethyl)phenyl]octahydro-7-methyl-1,3-dioxo-4,7-epoxy-4H-isoindol-4-yl]ethyl]benzenesulfonamide (24Ci and 24Cii, respectively)




A. 5-Methyl-2-furanethanol 4-methylbenzenesulfonate (24A)



4-Methylbenzenesulfonyl chloride (907 mg, 4.76 mmol) was added to a solution of compound **21A** (500 mg, 3.96 mmol) in 6 ml of dry pyridine. The reaction was stirred at room temperature for 4 h, then quenched with ice. The reaction mixture was extracted with CH_2Cl_2 and the combined organic layers were washed with saturated aqueous sodium bicarbonate and water, dried and concentrated under reduced pressure to give 900 mg (81%) of compound **24A** as a yellow oil.

B. N-[2-(5-Methyl-2-furanyl)ethyl]benzenesulfonamide (24B)



Benzenesulfonamide (157 mg, 1 mmol) was added to a 10% aqueous solution of sodium hydroxide (0.4 ml, 1 mmol). A solution of compound **24A** (280 mg, 1 mmol) in acetone (1 mL) was then added. The reaction mixture was heated at 90 °C

for 8 h then cooled to room temperature. Ice was added and the mixture was extracted with CH_2Cl_2. The combined organic layers were washed with water, dried and concentrated under reduced pressure. Purification by flash chromatography on silica gel, eluting with CH_2Cl_2 gave 60 mg (23%) of compound **24B** as yellow oil.


C. (3aα,4β,7β,7aα)- and (3aα,4α,7α,7aα)-N-[2-[2-[4-Cyano-3-(trifluoromethyl)phenyl]octahydro-7-methyl-1,3-dioxo-4,7-epoxy-4H-isoindol-4-yl]ethyl]benzenesulfonamide (24Ci and 24Cii, respectively)

4-(2,5-Dihydro-2,5-dioxo-1H-pyrrol-1-yl)-2-trifluoromethylbenzonitrile (129 mg, 0.45 mmol, prepared as described in Example 1B) was added to a solution of compound **24B** (60 mg, 0.23 mmol) in CH_2Cl_2 (2 mL). The reaction mixture was stirred at room temperature for 2 days, concentrated under reduced pressure and purified by flash chromatography on silica gel, eluting with 70% EtOAc/hexanes, to give 20 mg (16%) of the unsaturated Diels-Alder product. The unsaturated product (20 mg) was immediately dissolved in 2 ml of ethanol and 10 mg of 10% Pd/C was added. The solution was stirred at room temperature overnight under a hydrogen atmosphere. The mixture was filtered and the filtrate was concentrated under reduced pressure. Purification by preparative reverse phase HPLC gave 7 mg of compound **24Ci** and 2 mg of compound **24Cii**. Compound **24Ci**: HPLC: 96% at 3.17 min (retention time) (YMC ODSA S5 C18 4.6X50 mm, 10%-90% aqueous methanol over 4 min gradient with 0.1% TFA, detected at 220 nm), MS (ES): m/z: 533.99 $[M+H]^+$. Compound **24Cii**: HPLC: 99% at 38.95 min (retention time) (YMC ODS S5 20X250 mm, 10%-90% aqueous methanol over 40 min gradient with 0.1% TFA, detected at 220 nm), MS (ES): m/z 533.99 $[M+H]^+$.


129

Example 25

(3aα,4β,7β,7aα)-4-[Octahydro-4-(2-hydroxyethyl)-7-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-2-(trifluoromethyl)benzonitrile (25B)



A. (3aα,4β,7β,7aα)- and (3aα,4α,7α,7aα)-4-[1,3,3a,4,7,7a-Hexahydro-4-(2-hydroxyethyl)-7-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-2-(trifluoromethyl)benzonitrile (25Ai and 25Aii, respectively)



A solution of compound **21A** (252 mg, 2 mmol, 1 eq) and 4-(2,5-dihydro-2,5-dioxo-1H-pyrrol-1-yl)-2-trifluoromethylbenzonitrile (798 mg, 3 mmol, 1.5 eq) in CH_2Cl_2 (10 mL) was stirred at room temperature for 2 days. The reaction mixture was concentrated under reduced pressure. Purification by flash chromatography on silica gel eluting with 65% EtOAc/hexanes gave 217 mg of pure compound **25Ai**, 73 mg of pure compound **25Aii** and 310 mg of a mixture of both compound **25Ai** and **25Aii**. All three fractions were isolated as white solids with a total isolated yield of 600 mg (1.53 mmol, 76.5%). Compound **25Ai**: HPLC 90% at 2.56 min (retention time) (YMC S5 ODS column 4.6 x 50 mm, 10-90% aqueous methanol over 4 minutes containing 0.2% phosphoric acid, 4 mL/min, monitoring at 220 nm). Compound

130


25Aii: HPLC 90% at 2.56 min (retention time) (YMC S5 ODS column 4.6 x 50 mm, 10-90% aqueous methanol over 4 minutes containing 0.2% phosphoric acid, 4 mL/min, monitoring at 220 nm).


B. (3aα,4β,7β,7aα)-4-[Octahydro-4-(2-hydroxyethyl)-7-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-2-(trifluoromethyl)benzonitrile (25B)

A solution of compound **25Ai** (0.2 g, 0.51 mmol, 1 eq) and 10% Pd/C (43 mg, cat.) in EtOH (12 mL) was stirred under a hydrogen atmosphere at room temperature for 2 h. The reaction mixture was filtered through celite and concentrated under reduced pressure to give 0.2 g (0.51 mmol, 100%) of compound **25B** as a white solid. HPLC: 95% at 2.59 min (retention time) (YMC S5 ODS column 4.6 x 50 mm eluting with 10-90% aqueous methanol over 4 minutes containing 0.1% TFA, 4 mL/min, monitoring at 220 nm), MS (ESI): m/z 394.97 $[M+H]^+$.


Example 26

(3aα,4α,7α,7aα)- and (3aα,4β,7β,7aα)-N-[4-[2-[2-[4-Cyano-3-(trifluoromethyl)phenyl]octahydro-7-methyl-1,3-dioxo-4,7-epoxy-4H-isoindol-4-yl]ethoxy]phenyl]acetamide (26Ci and 26Cii, respectively)






A. 2-[4-[2-(5-Methyl-2-furanyl)ethoxy]phenyl]acetamide (26A)



Triphenylphosphine (681 mg, 2.6 mmol, 1.3 eq) was added to a solution of compound **21A** (252 mg, 2 mmol, 1 eq) and 4-acetamidophenol (302 mg, 2 mmol, 1 eq) in CH_2Cl_2 (4 mL). THF (5 mL) was added to make the reaction mixture homogeneous and the mixture was then cooled to 0°C. DEAD (0.41 mL, 2.6 mmol, 1.3 eq) was added dropwise and the reaction mixture was stirred at room temperature overnight, then concentrated under reduced pressure. Purification by flash chromatography on silica gel eluting with 60% EtOAc/hexanes followed by preparative reverse phase HPLC gave 270 mg (52%, 1.04 mmol) of compound **26A** as a light brown solid. MS (ESI): m/z 260.09 $[M+H]^+$.

B. (3aα,4α,7α,7aα)- and (3aα,4β,7β,7aα)-N-[4-[2-[2-[4-Cyano-3-(trifluoromethyl)phenyl]-1,2,3,3a,7,7a-hexahydro-7-methyl-1,3-dioxo-4,7-epoxy-4H-isoindol-4-yl]ethoxy]phenyl]acetamide (26Bi and 26Bii, respectively)




A solution of compound **26A** (40 mg, 0.154 mmol, 1 eq) and 4-(2,5-dihydro-2,5-dioxo-1H-pyrrol-1-yl)-2-trifluoromethylbenzonitrile (88 mg, 0.31 mmol, 2 eq) in CH_2Cl_2 (2 mL) was stirred at room temperature for 2 days. The reaction mixture was concentrated under reduced pressure. Purification by flash chromatography on silica gel eluting with 75% EtOAc/hexanes gave 55 mg (0.105 mmol, 68 %) of a 5 to 1 mixture of compounds **26Bi** and **26Bii** as a white solid, which was used directly in the next step. HPLC 90% at 3.28 min (retention time) (YMC S5 ODS column 4.6 x 50 mm, 10-90% aqueous methanol over 4 minutes containing 0.2% phosphoric acid, 4 mL/min, monitoring at 220 nm).

C. (3aα,4α,7α,7aα)- and (3aα,4β,7β,7aα)-N-[4-[2-[2-[4-Cyano-3-(trifluoromethyl)phenyl]octahydro-7-methyl-1,3-dioxo-4,7-epoxy-4H-isoindol-4-yl]ethoxy]phenyl]acetamide (26Ci and 26Cii, respectively)


A solution of a mixture of compounds **26Bi** and **26Bii** (55 mg, 0.105 mmol, 1 eq) and 10% Pd/C (12 mg, cat.) in EtOH (3 mL) was stirred under a hydrogen atmosphere at room temperature overnight. The reaction mixture was filtered through celite and concentrated under reduced pressure to give 50 mg of crude product. Purification by flash chromatography on silica gel eluting with 70% EtOAc/hexanes gave 18 mg (0.034 mmol, 32 %) of compound **26Ci** [HPLC: 96% at 3.33 min (retention time) (YMC S5 ODS column 4.6 x 50 mm, 10-90% aqueous methanol over 4 minutes containing 0.2% phosphoric acid, 4 mL/min, monitoring at 220 nm). MS (ES): m/z 528.01 $[M+H]^+$]; and 2.3 mg (0.004 mmols, 4%, 85:15-endo:exo) of an 85:15 mixture of compound (by ^1H NMR) **26Cii** and compound **26Ci** respectively [HPLC: 90% at 3.35 min (retention time) (YMC S5 ODS column 4.6 x 50 mm, 10-90% aqueous methanol over 4 minutes containing 0.2% phosphoric acid, 4 mL/min, monitoring at 220 nm), MS (ESI): m/z 528.12 $[M+H]^+$].

Example 27

(3aα,4α,7α,7aα)-Hexahydro-2-(2-naphthalenyl)-4,7-epoxy-1H-isoindole-1,3(2H)-dione (27D)




A. (endo, endo)-7-Oxabicyclo[2.2.1]hept-5-ene-2,3-dicarboxylic acid (27A)




Compounds 27A, 27B and 27C were synthesized in accordance with the approaches described in Sprague *et al., J. Med. Chem.* 28, 1580-1590 (1985). A mixture of furan (100 mL, 1.38 mol, 1 eq) and maleic acid (159.6 g, 1.38 mol, 1 eq) in H_2O (340 mL) was stirred at room temperature for 5 days. The mixture was placed in a separatory funnel and the aqueous layer was separated from the layer containing the unreacted furan. The aqueous layer was treated with charcoal, filtered through celite and placed in the refrigerator. The desired product crystallized from solution upon seeding, was filtered, washed with cold water and dried over P_2O_5 to give 70 g (0.38 mol, 28%) of compound 27A as a white solid.

B. (endo, endo)-7-Oxabicyclo[2.2.1]heptane-2,3-dicarboxylic acid (27B)



To a solution of compound 27A (69 g, 0.375 mol, 1 eq) in EtOH (700 mL) was added 10% Pd/C (4.5 g, cat.) and the mixture was shaken under a hydrogen atmosphere at 55 psi until gas uptake ceased. The mixture was filtered through celite and concentrated in vacuo to give 66 g (0.355 mol, 95%) of compound 27B as a white solid.

C. (3aα,4α,7α,7aα)-Hexahydro-4,7-epoxyisobenzofuran-1,3-dione (27C)



A solution of compound 27B (66 g, 355 mol) in acetyl chloride (300 mL) was refluxed for 1 h. The reaction solution was concentrated in vacuo and the resulting residue was recrystallized from benzene to give 49.2 g (0.292 mol, 82%) of compound 27C as a white solid (>99% endo by ^1H NMR).


134

D. (3aα,4α,7α,7aα)-Hexahydro-2-(2-naphthalenyl)-4,7-epoxy-1H-isoindole-1,3(2H)-dione (27D)


Compound **27C** (45 mg, 0.30 mmol, 1 eq) was combined with 2-naphthalenamine (47 mg, 0.33 mmol, 1.1 eq) in acetic acid (1 mL) and heated at 115°C overnight. After the reaction was cooled to rt, a drop of water was added, and the resulting precipitate was filtered. The material was washed with methanol and dried to provide 65.7 mg (74.5%) of compound **27D** as a white crystalline solid. HPLC: 99% at 2.68 min (retention time) (YMC S5 ODS column 4.6 x 50 mm, 10-90% aqueous methanol over 4 minutes containing 0.2% phosphoric acid, 4 mL/min, monitoring at 220 nm), MS (ESI): m/z 294.0 $[M+H]^+$.

Example 28

(1aα,2β,2aα,5aα,6β,6aα)-Hexahydro-4-(2-naphthalenyl)-2,6-epoxy-3H-oxireno[f]isoindole-3,5(4H)-dione (28B)



A. (1aα,2β,2aα,5aα,6β,6aα)-Tetrahydro-2,6-epoxyoxireno[f]isobenzofuran-3,5(2aH,5aH)-dione (28A)



As described in Yur'ev, *et al.*, *J. Gen. Chem. U.S.S.R. (Engl. Transl.)* 31, 772-775 (1961), a solution of exo-7-oxabicyclo[2.2.1]heptane-2,3-dicarboxylic anhydride (5 g, 30.09 mmol), formic acid (10 mL) and hydrogen peroxide (6 mL) was stirred at room temperature. After 30 min, the reaction was placed in an ice bath (it became exothermic along with gas evolution) and was allowed to warm to room temperature


slowly. After stirring overnight, the resulting precipitate was collected by filtration and washed with glacial acetic acid and dried to yield 3.02 g of a white powder. The crude solid was boiled in acetyl chloride (100 mL) for 10 hours and the mixture was concentrated to ~20 mL under reduced pressure. The resulting precipitate was filtered, washed with dioxanes and dried to give 2.37 g of compound **28A** as a white powder.

B. (1aα,2β,2aα,5aα,6β,6aα)-Hexahydro-4-(2-naphthalenyl)-2,6-epoxy-3H-oxireno[f]isoindole-3,5(4H)-dione (28B)

Compound **28A** (100 mg, 0.520 mmol, 1.2 eq) was combined with 2-naphthalenamine (0.434 mmol, 1 eq) in acetic acid (2 mL) and heated at 115°C overnight. After the reaction was allowed to cool to rt, water was added, and the resulting precipitate was filtered. The material was washed sequentially with aqueous K_2CO_3 and water and then dried in a vacuum oven to provide 113.7 mg (85.3%) of compound **28B** as an off-white crystalline solid. HPLC: 99% at 1.76 min (retention time) (YMC S5 ODS column 4.6 x 50 mm, 10-90% aqueous methanol over 4 minutes containing 0.2% phosphoric acid, 4 mL/min, monitoring at 220 nm), MS (ESI): m/z 308.0 $[M+H]^+$.

Example 29

(3aα,4α,7α,7aα)-2-[4-Bromo-3-(trifluoromethyl)phenyl]-3a,4,7,7a-tetrahydro-4,7-dimethyl-4,7-epithio-1H-isoindole-1,3(2H)-dione 8-oxide (29)




136

2,5-Dimethylthiophene (0.048 mL, 0.42 mmol) and 4-(2,5-dihydro-2,5-dioxo-1H-pyrrol-1-yl)-2-trifluoromethylbenzonitrile (0.290 g, 0.625 mmol) were dissolved in CH_2Cl_2 (8.0 mL) and cooled to –20 °C. $BF_3 \cdot Et_2O$ (0.412 mL, 3.36 mmol) was added slowly followed by addition of *m*CPBA (~50%, 0.290 g, 0.84 mmol). After 2 h at –20 °C, the reaction was poured into saturated aq $NaHCO_3$ and extracted with CH_2Cl_2 (3 x 20 mL) and the organics dried over anhydrous Na_2SO_4. The crude product was purified by flash chromatography on SiO_2 eluting with 5%-10%-20% EtOAc in CH_2Cl_2 to give 0.119 g of compound **29** as a white solid. HPLC: 91% at 3.303 min (retention time) (YMC S5 ODS column 4.6 x 50 mm, 10-90% aqueous methanol over 4 minutes containing 0.2% phosphoric acid, 4 mL/min, monitoring at 220 nm). MS (ESI): m/z 480.2 $[M+H]^+$.

Example 30

(3aα,4α,7α,7aα)-2-[4-Bromo-3-(trifluoromethyl)phenyl]-3a,4,7,7a-tetrahydro-4,7-epithio-1H-isoindole-1,3(2H)-dione 8-oxide (30)




Thiophene (0.375 mL, 4.69 mmol) and 4-(2,5-dihydro-2,5-dioxo-1H-pyrrol-1-yl)-2-trifluoromethylbenzonitrile (0.100 g, 0.313 mmol) were dissolved in CH_2Cl_2 (50 mL) and *m*CPBA (~50%, 1.62 g, 4.69 mmol) was added and the stirred at 25°C for 3 h. Triphenylphosphine (2.0 g) was then added. After 15 min, the volatiles were removed in vacuo and the resulting residue was dissolved in CH_2Cl_2 (200 mL) and washed with saturated aq $NaHCO_3$ (3 x 50 mL) and dried over Na_2SO_4. The crude material was then purified by flash chromatography on SiO_2 eluting with 1% - 3% - 5% methanol in CH_2Cl_2 to give compound **30** as a white powder (0.059 g). NMR spectroscopy and LC analysis showed a single diastereomer. HPLC: 100% at 3.437


min (retention time) (YMC S5 ODS column 4.6 x 50 mm, 10-90% aqueous methanol over 4 minutes containing 0.2% phosphoric acid, 4 mL/min, monitoring at 220 nm), MS (ESI): m/z 443.2 $[M+H]^+$.

Example 31

(3aα,4α,7α,7aα)-Hexahydro-2-[3-(trifluoromethyl)phenyl]-4,7-imino-1H-isoindole-1,3(2H)-dione (31D)




A. 7-Azabicyclo[2.2.1]hepta-2,5-diene-2,3,7-tricarboxylic acid 2,3-dimethyl 7-(1,1-dimethylethyl) ester (31A)




The freshly distilled acetylenedicarboxylic acid dimethyl ester (6.7 mL, 54.0 mmol) and N-(tert-butyloxycarbonyl)-1H-pyrrole (9.0 mL, 54.0 mmol) were combined and heated at 120°C for 3 h. Purification by flash chromatography on SiO_2 eluting with EtOAc/CH_2Cl_2 gave 8.3 g of compound 31A as a yellow solid.

B. (exo,endo)-7-Azabicyclo[2.2.1]hept-2,5-diene-2,3,7-tricarboxylic acid 7-(1,1-dimethylethyl) ester (31B)



Compound **31A** (1.0 g, 3.5 mmol) was dissolved in MeOH (2.0 mL) and aq KOH (1 g in 5 mL H2O) was added. The reaction was heated to 50°C for 1 h. The reaction was then cooled to 25°C and Pd/C (0.5 g, 10% Pd) was added and the mixture was placed in a Parr apparatus for 14 h at 25°C. The reaction was then filtered through celite rinsing with water. The aqueous solution was acidified to pH = 2 by addition of 1 N HCl and then extracted with EtOAc (2 x 100 mL). Concentration of the organics gave the compound **31B** as a pale yellow solid.

C. (3aα,4α,7α,7aα)-Hexahydro-1,3-dioxo-4,7-iminoisobenzofuran-8-carboxylic acid 1,1-dimethylethyl ester (31C)



The crude compound **31B** was heated to 120°C in vacuo in a sublimation chamber, resulting in sublimation of compound **31C** as a white solid (0.051 g), which was collected directly and used in the next step without further purification.


D. (3aα,4α,7α,7aα)-Hexahydro-2-[3-(trifluoromethyl)phenyl]-4,7-imino-1H-isoindole-1,3(2H)-dione (31D)

Compound **31C** (0.050 g, 0.187 mmol) and the 1-amino-3-(trifluoromethyl)benzene (0.030 g, 0.187 mmol) were dissolved in AcOH (2.5 mL) and heated to 115°C for 4.5 h. The reaction was quenched by addition of saturated aqueous $NaHCO_3$ and the extracted with methylene chloride (3 x 15 mL). The crude

material was purified by preparative reverse phase HPLC to give 0.030 g of compound **31D** as a white solid. HPLC: 99% at 2.33 min (retention time) (YMC S5 ODS column 4.6 x 50 mm, 10-90% aqueous methanol over 4 minutes containing 0.2% phosphoric acid, 4 mL/min, monitoring at 220 nm), MS (ESI): m/z 311.15 $[M+H]^+$.

Example 32

(3aα,4β,7β,7aα)- and (3aα,4α,7α,7aα)-3a,4,7,7a-Tetrahydro-4,7-dimethyl-2-[3-(trifluoromethyl)phenyl]-4,7-epoxy-1H-isoindole-1,3(2H)-dione (32i and 32ii, respectively)




Freshly distilled 2,5-dimethylfuran (0.32 mL, 2.6 mmol) was dissolved in CH_2Cl_2 (2.0 mL) and 1-[3-(trifluoromethyl)phenyl]-1H-pyrrole-2,5-dione (0.5 g, 2.5 mmol) was added. The reaction was stirred at 25°C for 16 h and was then concentrated under reduced pressure. Purification by flash chromatography on silica gel eluting with 0.5% MeOH/CH_2Cl_2 gave 50 mg of compound **32i** and 250 mg of compound **32ii**, as white solids. Compound **32i**: HPLC: 92% at 3.047 min (retention time) (YMC S5 ODS column 4.6 x 50 mm, 10-90% aqueous methanol over 4 minutes containing 0.2% phosphoric acid, 4 mL/min, monitoring at 220 nm), MS (ES): m/z: 338.15 $[M+H]^+$; Compound **32ii**: HPLC: 98% at 3.08 min (retention time) (YMC S5 ODS column 4.6 x 50 mm, 10-90% aqueous methanol over 4 minutes containing 0.2% phosphoric acid, 4 mL/min, monitoring at 220 nm), MS (ES): m/z 338.30 $[M+H]^+$.

140

Example 33


(3aα,4α,7α,7a α)-Hexahydro-4,7-dimethyl-2-[3-(trifluoromethyl)phenyl]-4,7-epoxy-1H-isoindole-1,3(2H)-dione (33)



Compound **32ii** (0.080 g, 0.237 mmol) was dissolved in EtOAc (2 mL) and EtOH (1 ml) and Pd/C (10% Pd, 0.050 g) was added. Hydrogen was then introduced by a balloon and the reaction was stirred for 24 h. The mixture was filtered through celite, rinsed with EtOAc and concentrated in vacuo to give compound **33** (0.075g) as a white solid. No further purification was needed. HPLC: 90% at 3.233 min (retention time) (YMC S5 ODS column 4.6 x 50 mm, 10-90% aqueous methanol over 4 minutes containing 0.2% phosphoric acid, 4 mL/min, monitoring at 220 nm), MS (ES): m/z 340.40 $[M+H]^+$.


Example 34

(3aα,4α,7α,7aα)-Tetrahydro-5-methyl-2-(4-nitro-1-naphthalenyl)-4,7-etheno-1H-pyrrolo[3,4-c]pyridine-1,3,6(2H,5H)-trione (34B)



A. 4,5,7,7a-Tetrahydro-5-methyl-4,7-ethenofuro[3,4-c]pyridine-1,3,6(3aH)-trione (34A)

141



Compound **34A** was synthesized by a modification of the methods described in Tomisawa *et al.*, *Heterocycles* **6**, 1765-1766 (1977) and *Tetrahedron Lett.* **29**, 2465-2468 (1969). Maleic anhydride and 1-methyl-2-pyridone were suspended in 30 ml of anhydrous tolulene. The reaction vessel was fitted with a Dean Stark trap and refluxed for 48 hours. The dark colored solution was allowed to cool to rt and then the volatiles were removed in vacuo. The resulting brown paste was dissolved in 10 ml of boiling toluene and the hot solution was filtered under a nitrogen flow to remove particulates. On standing at 25°C the desired product precipitated from solution. The solid was isolated by filtration and washed with cold toluene to give compound **34A**, which was used without further purification.


B. (3aα,4α,7α,7aα)-Tetrahydro-5-methyl-2-(4-nitro-1-naphthalenyl)-4,7-etheno-1H-pyrrolo[3,4-c]pyridine-1,3,6(2H,5H)-trione (34B)

1-Amino-4-nitronaphthalene (0.094 g, 0.5 mmol) and compound **34A** (0.130 g, 0.63 mmol) were dissolved in AcOH (2.0 mL) and heated to 110°C for 11 h. The reaction was then cooled to 25°C and poured into cold saturated aqueous K_2CO_3 and stirred vigorously for 10 min. The solution was filtered and rinsed with water. The resulting filtrate was dried in vacuo and purified by silica gel chromatography using a solvent system of 4:6 EtOAc/Hexane, to give 0.172 g of compound **34B** as a white solid. HPLC: 92% at 2.472 min (retention time) (YMC S5 ODS column 4.6 x 50 mm eluting with 10-90% aqueous methanol over 4 minutes containing 0.1% TFA, 4 mL/min, monitoring at 220 nm), MS (ES): m/z 378.29 $[M+H]^+$.

142

Example 35


(3aα,4β,7β,7aα)-4-[4-[2-(4-Fluorophenoxy)ethyl]octahydro-7-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-2-(trifluoromethyl)benzonitrile (35)



DEAD (0.06 mL, 0.380 mmol, 1.5 eq) was added to a solution of triphenylphosphine (100 mg, 0.380 mmol, 1.5 eq) in THF (1.3 mL) at room temperature under an inert atmosphere. After stirring for 10 mins, 4-fluorophenol (43 mg, 0.380 mmol, 1.5 eq) was added in one portion. The reaction mixture was stirred for 5 mins, compound **25B** (100 mg, 0.254 mmol, 1 eq) was added and stirring was continued for 3.5 h. Purification by flash chromatography on silica gel eluting with 50% EtOAc/Hexanes followed by preparative chromatography [HPLC: 11.93 min (retention time) (YMC S5 ODS column 20 x 100 mm, 0-100% aqueous methanol over 10 minutes containing 0.1% TFA, 20 mL/min, monitoring at 220 nm)] gave 72 mg (58%) of compound **35** as a solid. HPLC: 99% at 3.74 min (retention time) (YMC S5 ODS column 4.6 x 50 mm, 10-90% aqueous methanol over 4 minutes containing 0.2% phosphoric acid, 4 mL/min, monitoring at 220 nm), MS (ESI): m/z 487.1 $[M-H]^-$.

Example 36

(3aα,4β,7β,7aα)-4-[4-(2-Bromoethyl)octahydro-7-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-2-(trifluoromethyl)benzonitrile (36)




A solution of **25B** (495 mg, 1.26 mmol, 1 eq) and pyridine (0.1 ml, 1.26 mmol, 1 eq) in CH_2Cl_2 (2 ml) was added to a solution of Ph_3PBr_2 (636 mg, 1.51

143

mmol, 1.2 eq) in CH_2Cl_2 (2ml) at 0°C. The reaction mixture was stirred at room temperature for 3 hr, then the solvent was removed under reduced pressure. The resulting residue was washed 2X with 10 ml portions of EtOAc-hexane (6:4) and the combined washings were purified by flash chromatography on silica gel eluting with 60% EtOAc/hexane to give 390 mg (0.85 mmol, 67.7%) of compound 36 as a white solid. HPLC: 99% at 3.51 min (retention time) (YMC S5 ODS column 4.6 x 50 mm, 10-90% aqueous methanol over 4 minutes containing 0.2% phosphoric acid, 4 mL/min, monitoring at 220 nm). MS (ESI): m/z 456.7 $[M-H]^-$.

Example 37


(3aα,4β,7β,7aα)-Hexahydro-4,7-dimethyl-2-(3-methyl-4-nitrophenyl)-4,7-epoxy-1H-isoindole-1,3(2H)-dione (37)



A combination of 4-nitro-3-methylaniline (0.050 g, 0.33 mmol), compound 20A (0.083 g, 0.43 mmol), TEA (0.2 mL), $MgSO_4$ (0.075 g) and toluene (0.8 mL) were combined in a sealed tube and the mixture was heated to 120°C for 14 h. After cooling to 25°C, the reaction was filtered, rinsed with CH_2Cl_2 and concentrated. The crude product was purified by preparative-TLC on SiO_2 eluting with CH_2Cl_2 to give 0.075 g of compound 37 as a pale yellow solid. HPLC: 100% at 2.733 min (retention time) (YMC S5 ODS column, 4.6 X 50 mm; 10-90% MeOH/H_2O gradient,+ 0.1% TFA; 4 mL/min, 220 nM detection), MS (ES): m/z 348.2 $[M+NH_4]^+$.




Examples 38 to 121

Additional compounds of the present invention were prepared by procedures analogous to those described above. The compounds of Examples 38 to 121 have the following structure (L is a bond):











where G, the compound name, retention time, molecular mass, and the procedure employed, are set forth in **Table 2**. The chromatography techniques used to determine the compound retention times of **Table 2** are as follows: **LCMS** = YMC S5 ODS column, 4.6 X 50 mm eluting with 10-90% MeOH/H_2O over 4 minutes containing 0.1% TFA; 4 mL/min, monitoring at 220 nm. The molecular mass of the compounds listed in **Table 2**, where provided, were determined by MS (ES) by the formula m/z.









Table 2

Ex. No.	G	Compound Name	Retention Time (Min.)/ Molecular Mass	Pro. of Ex.
38		(3aα,4β,7β,7aα)-2-(2-Fluorenyl)hexahydro-4,7-epoxy-1H-isoindole-1,3(2H)-dione	3.72 LCMS/ 332.20 $[M+H]^+$	8
39		(3aα,4β,7β,7aα)-2-[3-Chloro-4-(4-morpholinyl)phenyl]hexahydro-4,7-epoxy-1H-isoindole-1,3(2H)-dione	3.20 LCMS/ 363.20 $[M+H]^+$	8
40		(3aα,4β,7β,7aα)-2-(2,3-Dihydro-1H-inden-5-yl)hexahydro-4,7-epoxy-1H-isoindole-1,3(2H)-dione	3.26 LCMS/ 284.22 $[M+H]^+$	8









145









Ex. No.	G	Compound Name	Retention Time (Min.)/ Molecular Mass	Pro. of Ex.
41		(3aα,4β,7β,7aα)-2-(4-Bromo-1-naphthalenyl)hexahydro-4,7-epoxy-1H-isoindole-1,3(2H)-dione	3.73 LCMS/ 404.11 $[M+CH_3OH+H]^+$	8
42		(3aα,4β,7β,7aα)-2-(4-Chloro-1-naphthalenyl)hexahydro-4,7-epoxy-1H-isoindole-1,3(2H)-dione	3.63 LCMS/ 328.14 $[M+H]^+$	8
43		(3aα,4β,7β,7aα)-2-(5-Amino-1-naphthalenyl)hexahydro-4,7-epoxy-1H-isoindole-1,3(2H)-dione	1.64 LCMS/	8
44		(3aα,4β,7β,7aα)-Hexahydro-2-(7-hydroxy-1-naphthalenyl)-4,7-epoxy-1H-isoindole-1,3(2H)-dione	2.54 LCMS/ 308.23 $[M-H]^-$	8
45		(3aα,4β,7β,7aα)-Hexahydro-2-(4-nitro-1-naphthalenyl)-4,7-epoxy-1H-isoindole-1,3(2H)-dione	3.117 LCMS/ 404.11 $[M+CH_3OH+H]^+$	8
46		(3aα,4β,7β,7aα)-Hexahydro-2-(1H-indol-5-yl)-4,7-epoxy-1H-isoindole-1,3(2H)-dione	2.39 LCMS/ 283.23 $[M+H]^+$	8
47		(3aα,4β,7β,7aα)-Hexahydro-2-(1H-indazol-6-yl)-4,7-epoxy-1H-isoindole-1,3(2H)-dione	2.35 LCMS/ 282.23 $[M-H]^-$	8
48		(3aα,4β,7β,7aα)-2-(1,3-Benzodioxol-5-yl)hexahydro-4,7-epoxy-1H-isoindole-1,3(2H)-dione	2.47 LCMS/ 288.20 $[M+H]^+$	8

146









Ex. No.	G	Compound Name	Retention Time (Min.)/ Molecular Mass	Pro. of Ex.
49		(3aα,4β,7β,7aα)-2-[4-Amino-3-(trifluoromethyl)phenyl]hexahydro-4,7-epoxy-1H-isoindole-1,3(2H)-dione	2.71 LCMS/ 327.20 $[M+H]^+$	8
50		(3aα,4β,7β,7aα)-2-(3-Chloro-4-iodophenyl)hexahydro-4,7-epoxy-1H-isoindole-1,3(2H)-dione	3.70 LCMS/ 435.2 $[M+CH_3OH]^{+\cdot}$	8
51		(3aα,4β,7β,7aα)-Hexahydro-2-(8-quinolinyl)-4,7-epoxy-1H-isoindole-1,3(2H)-dione	2.28 LCMS/ 295.22 $[M+H]^+$	8
52		(3aα,4β,7β,7aα)-2-(2,3-Dihydro-1,4-benzodioxin-6-yl)hexahydro-4,7-epoxy-1H-isoindole-1,3(2H)-dione	2.55 LCMS/ 302.23 $[M+H]^+$	8
53		(3aα,4β,7β,7aα)-Hexahydro-2-[2-oxo-4-(trifluoromethyl)-2H-1-benzopyran-7-yl]-4,7-epoxy-1H-isoindole-1,3(2H)-dione	3.38 LCMS/ 412.17 $[M+CH_3OH+H]^+$	8
54		(3aα,4β,7β,7aα)-Hexahydro-2-(4-methyl-2-oxo-2H-1-benzopyran-7-yl)-4,7-epoxy-1H-isoindole-1,3(2H)-dione	2.74 LCMS/ 326.20 $[M+H]^+$	8
55		(3aα,4β,7β,7aα)-2-(2,5-Dimethoxy-4-nitrophenyl)hexahydro-4,7-epoxy-1H-isoindole-1,3(2H)-dione	2.70 LCMS/ 349.23 $[M+H]^+$	8
56		(3aα,4β,7β,7aα)-2,3,5,6-Tetrafluoro-4-(octahydro-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl)benzonitrile	2.97 LCMS	8

147









Ex. No.	G	Compound Name	Retention Time (Min.)/ Molecular Mass	Pro. of Ex.
57		(3aα,4β,7β,7aα)-Hexahydro-2-(2,4,5-trifluorophenyl)-4,7-epoxy-1H-isoindole-1,3(2H)-dione	2.90 LCMS	8
58		(3aα,4β,7β,7aα)-Hexahydro-2-(2,4,5-trichlorophenyl)-4,7-epoxy-1H-isoindole-1,3(2H)-dione	3.64 LCMS/ 346.39 $[M]^{+\cdot}$	8
59		(3aα,4β,7β,7aα)-2-(2-Amino-4,5-dichlorophenyl)hexahydro-4,7-epoxy-1H-isoindole-1,3(2H)-dione	3.23 LCMS	8
60		(3aα,4β,7β,7aα)-2-(3,4-Difluorophenyl)hexahydro-4,7-epoxy-1H-isoindole-1,3(2H)-dione	2.91 LCMS/ 280.23 $[M+H]^+$	8
61		(3aα,4β,7β,7aα)-1-Acetyl-2,3-dihydro-6-(octahydro-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl)-1H-indole	2.43 LCMS/ 359.26 $[M+CH_3OH+H]^+$	8
62		(3aα,4β,7β,7aα)-2-(3-Chloro-4-fluorophenyl)hexahydro-4,7-epoxy-1H-isoindole-1,3(2H)-dione	3.21 LCMS/ 328.14 $[M+CH_3OH+H]^+$	8
63		(3aα,4β,7β,7aα)-2-(3,4-Dichlorophenyl)hexahydro-4,7-epoxy-1H-isoindole-1,3(2H)-dione	3.54 LCMS/ 311.79 $[M-H]^-$	8
64		(3aα,4β,7β,7aα)-Hexahydro-2-(3,4,5-trichlorophenyl)-4,7-epoxy-1H-isoindole-1,3(2H)-dione	4.05 LCMS/ 378.10 $[M+CH_3OH+H]^+$	8

Ex. No.	G	Compound Name	Retention Time (Min.)/ Molecular Mass	Pro. of Ex.
65		(3aα,4β,7β,7aα)-2-(3-Chloro-4-methoxyphenyl)hexahydro-4,7-epoxy-1H-isoindole-1,3(2H)-dione	2.99 LCMS/ 308.11 $[M+H]^+$	8
66		(3aα,4β,7β,7aα)-2-(3-Chloro-4-methylphenyl)hexahydro-4,7-epoxy-1H-isoindole-1,3(2H)-dione	3.39 LCMS/ 292.20 $[M+H]^+$	8
67		(3aα,4β,7β,7aα)-Hexahydro-2-(2-methyl-1-naphthalenyl)-4,7-epoxy-1H-isoindole-1,3(2H)-dione	3.28 LCMS/ 308.23 $[M+H]^+$	8
68		(3aα,4β,7β,7aα)-2-(4-Chloro-3-methylphenyl)hexahydro-4,7-epoxy-1H-isoindole-1,3(2H)-dione	3.40 LCMS/ 292.20 $[M+H]^+$	8
69		(3aα,4β,7β,7aα)-2-(3,4-Dimethylphenyl)hexahydro-4,7-epoxy-1H-isoindole-1,3(2H)-dione	3.11 LCMS/ 272.23 $[M+H]^+$	8
70		(3aα,4β,7β,7aα)-2-[4-Bromo-3-(trifluoromethyl)phenyl]hexahydro-4,7-epoxy-1H-isoindole-1,3(2H)-dione	3.76 LCMS/ 421.98 $[M+CH_3OH+H]^+$	8
71		(3aα,4β,7β,7aα)-2-(4-Bromo-3-methylphenyl)hexahydro-4,7-epoxy-1H-isoindole-1,3(2H)-dione	3.50 LCMS/ 336.05 $[M+H]^+$	8
72		(3aα,4β,7β,7aα)-2-(4-Fluoro-3-nitrophenyl)hexahydro-4,7-epoxy-1H-isoindole-1,3(2H)-dione	2.80 LCMS/ 305.25 $[M-H]^-$	8









149 18









Ex. No.	G	Compound Name	Retention Time (Min.)/ Molecular Mass	Pro. of Ex.
73		(3aα,4β,7β,7aα)-2-[4-Fluoro-3-(trifluoromethyl)phenyl]hexahydro-4,7-epoxy-1H-isoindole-1,3(2H)-dione	3.45 LCMS/ 362.26 $[M+CH_3OH+H]^+$	8
74		(3aα,4β,7β,7aα)-2-(4-Chloro-3-nitrophenyl)hexahydro-4,7-epoxy-1H-isoindole-1,3(2H)-dione	3.19 LCMS/ 322.86 $[M]^{+\cdot}$	8
75		(3aα,4β,7β,7aα)-2-[4-Chloro-3-(trifluoromethyl)phenyl]hexahydro-4,7-epoxy-1H-isoindole-1,3(2H)-dione	3.68 LCMS/ 345.83 $[M]^{+\cdot}$	8
76		(3aα,4β,7β,7aα)-2-(4-Chloro-2-methoxy-5-methylphenyl)hexahydro-4,7-epoxy-1H-isoindole-1,3(2H)-dione	3.31 LCMS/ 322.20 $[M+H]^+$	8
77		(3aα,4β,7β,7aα)-2-(4-Amino-3-nitrophenyl)hexahydro-4,7-epoxy-1H-isoindole-1,3(2H)-dione	2.34 LCMS/ 302.27 $[M-H]^-$	8
78		(3aα,4β,7β,7aα)-Hexahydro-2-(4-methyl-3-nitrophenyl)-4,7-epoxy-1H-isoindole-1,3(2H)-dione	3.02 LCMS/ 335.20 $[M+CH_3OH+H]^+$	8
79		(3aα,4β,7β,7aα)-2-(3,4-Dimethoxyphenyl)hexahydro-4,7-epoxy-1H-isoindole-1,3(2H)-dione	2.35 LCMS/ 304.25 $[M+H]^+$	8
80		(3aα,4β,7β,7aα)-Hexahydro-2-(3-hydroxy-4-methoxyphenyl)-4,7-epoxy-1H-isoindole-1,3(2H)-dione	0.98 LCMS/ 321.19 $[M+CH_3OH]^{+\cdot}$	8

150









Ex. No.	G	Compound Name	Retention Time (Min.)/ Molecular Mass	Pro. of Ex.
81		(3aα,4β,7β,7aα)-Hexahydro-2-(4-methyl-5-nitro-2-pyridinyl)-4,7-epoxy-1H-isoindole-1,3(2H)-dione	0.54 LCMS/ 304.20 $[M+H]^+$	8
82		(3aα,4β,7β,7aα)-2-Chloro-4-(octahydro-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl)-α-phenylbenzeneacetonitrile	3.67 LCMS/ 423.8 $[M+CH_3OH]^{+\cdot}$	8
83		(3aα,4β,7β,7aα)-Hexahydro-2-(2-methoxy-3-dibenzofuranyl)-4,7-epoxy-1H-isoindole-1,3(2H)-dione	3.66 LCMS/ 364.25 $[M+H]^+$	8
84		(3aα,4β,7β,7aα)-Hexahydro-2-(2,3,4-trifluorophenyl)-4,7-epoxy-1H-isoindole-1,3(2H)-dione	3.06 LCMS/ 298.14 $[M+H]^+$	8
85		(3aα,4β,7β,7aα)-2-(2,3-Dihydro-2-methyl-1,3-dioxo-1H-isoindol-5-yl)hexahydro-4,7-epoxy-1H-isoindole-1,3(2H)-dione	2.70 LCMS/ 359.22 $[M+CH_3OH+H]^+$	8
86		(3aα,4β,7β,7aα)-2-(4-Bromo-2,3,5,6-tetrafluorophenyl)hexahydro-4,7-epoxy-1H-isoindole-1,3(2H)-dione	3.72 LCMS/ 426.07 $[M+CH_3OH+H]^+$	8
87		(3aα,4β,7β,7aα)-Hexahydro-2-(2-hydroxy-1-naphthalenyl)-4,7-epoxy-1H-isoindole-1,3(2H)-dione	2.52 LCMS/ 308.26 $[M-H]^-$	8
88		(3aα,4β,7β,7aα)-2-[2,5-Dichloro-4-(1H-pyrrol-1-yl)phenyl]hexahydro-4,7-epoxy-1H-isoindole-1,3(2H)-dione	3.70 LCMS/ 376.64 $[M-H]^-$	8

151









Ex. No.	G	Compound Name	Retention Time (Min.)/ Molecular Mass	Pro. of Ex.
89		(3aα,4β,7β,7aα)-Hexahydro-2-[4-(methoxymethyl)-2-oxo-2H-1-benzopyran-7-yl]-4,7-epoxy-1H-isoindole-1,3(2H)-dione	2.79 LCMS/ 356.26 $[M+H]^+$	8
90		(3aα,4β,7β,7aα)-2-(6-Benzothiazolyl)hexahydro-4,7-epoxy-1H-isoindole-1,3(2H)-dione	2.46 LCMS/ 301.19 $[M+H]^+$	8
91		(3aα,4β,7β,7aα)-2-Methoxy-4-(octahydro-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl)benzoic acid methyl ester	2.75 LCMS/ 332.25 $[M+H]^+$	8
92		(3aα,4β,7β,7aα)-2-Methyl-5-(octahydro-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl)benzonitrile	2.80 LCMS/ 315.26 $[M+CH_3OH+H]^+$	8
93		(3aα,4β,7β,7aα)-Hexahydro-2-(2-oxo-2H-1-benzopyran-6-yl)-4,7-epoxy-1H-isoindole-1,3(2H)-dione	2.45 LCMS/ 312.20 $[M+H]^+$	8
94		(3aα,4β,7β,7aα)-Hexahydro-2-(2,3,5,6-tetramethyl-4-nitrophenyl)-4,7-epoxy-1H-isoindole-1,3(2H)-dione	3.59 LCMS/ 377.25 $[M+CH_3OH+H]^+$	8
95		(3aα,4β,7β,7aα)-Hexahydro-2-(2,4,5-trimethylphenyl)-4,7-epoxy-1H-isoindole-1,3(2H)-dione	3.33 LCMS/ 286.30 $[M+H]^+$	8
96		(3aα,4β,7β,7aα)-2-(4-Fluoro-3-methylphenyl)hexahydro-4,7-epoxy-1H-isoindole-1,3(2H)-dione	3.00 LCMS/ 276.23 $[M+H]^+$	8

Ex. No.	G	Compound Name	Retention Time (Min.)/ Molecular Mass	Pro. of Ex.
97		(3aα,4β,7β,7aα)-Hexahydro-2-(3-methoxy-4-methylphenyl)-4,7-epoxy-1H-isoindole-1,3(2H)-dione	3.05 LCMS/ 288.23 $[M+H]^+$	8
98		(3aα,4β,7β,7aα)-N-Ethyl-2-methyl-5-(octahydro-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl)-N-phenylbenzenesulfonamide	3.56 LCMS/ 441.26 $[M+H]^+$	8
99		(3aα,4β,7β,7aα)-2,6-Dibromo-4-(octahydro-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl)benzenesulfonamide	2.25 LCMS	8
100		(3aα,4β,7β,7aα)-2,4-Dimethyl-6-(octahydro-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl)-3-pyridinecarbonitrile	2.75 LCMS/ 298.23 $[M+H]^+$	8
101		(3aα,4β,7β,7aα)-2-(2,3-Dimethyl-1H-indol-5-yl)hexahydro-4,7-epoxy-1H-isoindole-1,3(2H)-dione	3.00 LCMS/ 311.26 $[M+H]^+$	8
102		(3aα,4β,7β,7aα)-2-(3-Dibenzofuranyl)hexahydro-4,7-epoxy-1H-isoindole-1,3(2H)-dione	3.72 LCMS/ 366.23 $[M+CH_3OH+H]^+$	8
103		(3aα,4β,7β,7aα)-Hexahydro-2-(2'-hydroxy[1,1':3',1"-terphenyl]-5'-yl)-4,7-epoxy-1H-isoindole-1,3(2H)-dione	3.70 LCMS/ 412.23 $[M+H]^+$	8
104		(3aα,4β,7β,7aα)-Hexahydro-2-(5,6,7,8-tetrahydro-3-hydroxy-2-naphthalenyl)-4,7-epoxy-1H-isoindole-1,3(2H)-dione	3.24 LCMS/ 312.32 $[M+H]^+$	8


153

Ex. No.	G	Compound Name	Retention Time (Min.)/ Molecular Mass	Pro. of Ex.
105		(3aα,4β,7β,7aα)-2-(2,3-Dihydro-1H-indol-6-yl)hexahydro-4,7-epoxy-1H-isoindole-1,3(2H)-dione	2.42 LCMS/ 285.29 $[M+H]^+$	8
106		(3aα,4β,7β,7aα)-2-(1,3-Dihydro-2,2-dioxidobenzo[c]thiophen-5-yl)hexahydro-4,7-epoxy-1H-isoindole-1,3(2H)-dione	1.99 LCMS/ 366.26 $[M+CH_3OH+H]^+$	8
107		(3aα,4β,7β,7aα)-Hexahydro-2-(2-hydroxy-4,5-dimethylphenyl)-4,7-epoxy-1H-isoindole-1,3(2H)-dione	2.78 LCMS/ 286.32 $[M-H]^-$	8
108		(3aα,4β,7β,7aα)-2-(2,3-Dihydro-2,2,3,3-tetrafluoro-1,4-benzodioxin-6-yl)hexahydro-4,7-epoxy-1H-isoindole-1,3(2H)-dione	3.82 LCMS/ 406.19 $[M+CH_3OH+H]^+$	8
109		(3aα,4β,7β,7aα)-Hexahydro-2-(1H-indazol-5-yl)-4,7-epoxy-1H-isoindole-1,3(2H)-dione	2.13 LCMS/ 284.23 $[M+H]^+$	8
110		(3aα,4β,7β,7aα)-2-(4-Amino-2,3,5,6-tetrafluorophenyl)-hexahydro-4,7-epoxy-1H-isoindole-1,3(2H)-dione	2.60 LCMS/ 363.22 $[M+CH_3OH+H]^+$	8
111		(3aα,4β,7β,7aα)-2-(4-Bromo-3-chlorophenyl)hexahydro-4,7-epoxy-1H-isoindole-1,3(2H)-dione	3.64 LCMS/ 389.64 $[M+CH_3OH+H]^+$	8
112		(3aα,4β,7β,7aα)-Hexahydro-2-(5-hydroxy-1-naphthalenyl)-4,7-epoxy-1H-isoindole-1,3(2H)-dione	2.48 LCMS/ 308.27 $[M-H]^-$	8

1521

Ex. No.	G	Compound Name	Retention Time (Min.)/ Molecular Mass	Pro. of Ex.
113		(3aα,4β,7β,7aα)-4-(Octahydro-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl)-2-(trifluoromethyl)benzonitrile	3.28 LCMS/ 337.16 $[M+H]^+$	8
114		(3aα,4β,7β,7aα)-2-(4-Morpholinyl)-5-(octahydro-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl)benzoic acid methyl ester	2.72 LCMS/ 387.17 $[M+H]^+$	8
115		(3aα,4β,7β,7aα)-2-Fluoro-5-(octahydro-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl)benzonitrile	2.69 LCMS/ 319.26 $[M+CH_3OH+H]^+$	8
116		(3aα,4β,7β,7aα)-2-(4-Bromophenyl)hexahydro-4,7-epoxy-1H-isoindole-1,3(2H)-dione	5.80 LCMS/ 393.0 $[M+H]^+$	8
117		(3aα,4β,7β,7aα)-Hexahydro-2-(2-naphthalenyl)-4,7-epoxy-1H-isoindole-1,3(2H)-dione	6.92 LCMS/ 333.7 $[M+H]^+$	8
118		(3aα,4β,7β,7aα)-Hexahydro-2-[3-(trifluoromethyl)phenyl]-4,7-epoxy-1H-isoindole-1,3(2H)-dione	3.27 LCMS/ 312.2 $[M+H]^+$	8
119		(3aα,4β,7β,7aα)-Hexahydro-2-(4-nitrophenyl)-4,7-epoxy-1H-isoindole-1,3(2H)-dione	2.88 LCMS/ 343.2 $[M+H]^+$	8
120		(3aα,4β,7β,7aα)-2-(9-Ethyl-9H-carbazol-3-yl)hexahydro-4,7-epoxy-1H-isoindole-1,3(2H)-dione	3.73 LCMS/ 360.1 $[M+H]^+$	8

155

Ex. No.	G	Compound Name	Retention Time (Min.)/ Molecular Mass	Pro. of Ex.
121		(3aα,4β,7β,7aα)-2-[1,2-Dihydro-8-methyl-2-oxo-4-(trifluoromethyl)-7-quinolinyl]hexahydro-4,7-epoxy-1H-isoindole-1,3(2H)-dione	3.11 LCMS/ 393.0 $[M+H]^+$	8

Examples 122 to 164






Further compounds of the present invention were prepared by procedures analogous to those described above. **Table 3** provides the compound name and structure, retention time, as well as the Example number of the procedure on which the preparation of **Table 3** was based, for the compounds of Examples 122 to 164. The chromatography techniques used to determine the compound retention times of **Table 3** are as follows:






LCMS = YMC S5 ODS column, 4.6 X 50 mm eluting with 10-90% MeOH/H_2O over 4 minutes containing 0.1% TFA; 4 mL/min, monitoring at 220 nm.

LC = YMC S5 ODS column 4.6 x 50 mm eluting with 10-90% MeOH/H_2O over 4 minutes containing 0.2% phosphoric acid, 4 mL/min, monitoring at 220 nm







156

Table 3







Ex. No.	Compound Structure	Compound Name	Retention Time Min./ Molecular Mass	Pro. of Ex.
122		(3aα,4α,7α,7aα)-Hexahydro-2-[3-(trifluoromethyl)phenyl]-4,7-epoxy-1H-isoindole-1,3(2H)-dione	2.66 LCMS	27
123		(3aα,4α,7α,7aα)-Hexahydro-2-(4-nitro-1-naphthalenyl)-4,7-epoxy-1H-isoindole-1,3(2H)-dione	2.76 LCMS	27
124		(3aα,4β,7β,7aα)-2-(4-Bromo-3-methylphenyl)-3a,4,7,7a-tetrahydro-4,7-epoxy-1H-isoindole-1,3(2H)-dione	6.36 LCMS	8
125		(3aα,4β,7β,7aα)-2-(4-Bromophenyl)-3a,4,7,7a-tetrahydro-4,7-epoxy-1H-isoindole-1,3(2H)-dione	5.72 LCMS	8
126		(3aα,4β,7β,7aα)-3a,4,7,7a-Tetrahydro-2-(2-naphthalenyl)-4,7-epoxy-1H-isoindole-1,3(2H)-dione	5.92 LCMS	8

Ex. No.	Compound Structure	Compound Name	Retention Time Min./ Molecular Mass	Pro. of Ex.
127		(3aα,4β,7β,7aα)-2-(9-Ethyl-9H-carbazol-3-yl)-3a,4,7,7a-tetrahydro-4,7-epoxy-1H-isoindole-1,3(2H)-dione	3.73 LCMS	8
128		(3aα,4β,7β,7aα)-2-[4-Fluoro-3-(trifluoromethyl)phenyl]-3a,4,7,7a-tetrahydro-4,7-epoxy-1H-isoindole-1,3(2H)-dione	3.40 LCMS	8
129		(3aα,4β,7β,7aα)-2-[1,2-Dihydro-8-methyl-2-oxo-4-(trifluoromethyl)-7-quinolinyl]-3a,4,7,7a-tetrahydro-4,7-epoxy-1H-isoindole-1,3(2H)-dione	3.14 LCMS	8
130		(3aα,4α,7α,7aα)-4-[(Acetyloxy)methyl]-2-(4-bromo-3-methylphenyl)-3a,4,7,7a-tetrahydro-4,7-epoxy-1H-isoindole-1,3(2H)-dione	2.95 LC	4
131		(3aα,4β,7β,7aα)-4-[(Acetyloxy)methyl]-2-(4-bromo-3-methylphenyl)-3a,4,7,7a-tetrahydro-4,7-epoxy-1H-isoindole-1,3(2H)-dione.	2.97 LCMS	5






158

Ex. No.	Compound Structure	Compound Name	Retention Time Min./ Molecular Mass	Pro. of Ex.
132		(3aα,4β,7β,7aα)-Hexahydro-4,7-dimethyl-2-[3-(trifluoromethyl)phenyl]-4,7-epoxy-1H-isoindole-1,3(2H)-dione	3.08 LC	20
133		(3aα,4β,7β,7aα)-4-(Octahydro-4,7-dimethyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl)-1-naphthalenecarbonitrile	3.00 LC	20
134		(3aα,4β,7β,7aα)-(Benzo[b]thiophen-3-yl)hexahydro-4,7-dimethyl-4,7-epoxy-1H-isoindole-1,3(2H)-dione	3.61 LC	20
135		(3aα,4β,7β,7aα)-Hexahydro-4,7-dimethyl-2-[4-nitro-3-(trifluoromethyl)phenyl]-4,7-epoxy-1H-isoindole-1,3(2H)-dione	3.21 LC	20
136		(3aα,4β,7β,7aα)-4-(1,3,3a,4,7,7a-Hexahydro-4,7-dimethyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl)-1-naphthalenecarbonitrile	2.94 LC	32
137		(3aα,4α,7α,7aα)-Hexahydro-4-methyl-2-(2-naphthalenyl)-4,7-epoxy-1H-isoindole-1,3(2H)-dione	2.88 LC	3






159

Ex. No.	Compound Structure	Compound Name	Retention Time Min./ Molecular Mass	Pro. of Ex.
138		(3aα,4β,7β,7aα)-2-(4-Bromo-3-methylphenyl)hexahydro-4-methyl-4,7-epoxy-1H-isoindole-1,3(2H)-dione	3.11 LC	3
139		(3aα,4β,7β,7aα)-Hexahydro-4-methyl-2-[3-(trifluoromethyl)phenyl]-4,7-epoxy-1H-isoindole-1,3(2H)-dione	2.90 LC	3
140		(3aα,4β,7β,7aα)-2-(3,5-Dichlorophenyl)hexahydro-4-methyl-4,7-epoxy-1H-isoindole-1,3(2H)-dione	3.31 LC	3
141		(3aα,4β,7β,7aα)-2-(3-Chloro-4-fluorophenyl)-hexahydro-4-methyl-4,7-epoxy-1H-isoindole-1,3(2H)-dione	2.72 LC	3
142		(3aα,4β,7β,7aα)-2-Methoxy-4-(octahydro-1,3-dioxo-4-methyl-4,7-epoxy-2H-isoindol-2-yl)-1-naphthalenecarbonitrile	2.72 LC	3
143		(3aα,4β,7β,7aα)-Hexahydro-4-methyl-2-[4-nitro-3-(trifluoromethyl)phenyl]-4,7-epoxy-1H-isoindole-1,3(2H)-dione	3.10 LC	3






160

Ex. No.	Compound Structure	Compound Name	Retention Time Min./ Molecular Mass	Pro. of Ex.
144		(3aα,4β,7β,7aα)-Hexahydro-2-[4-(1H-imidazol-1-yl)phenyl]-4-methyl-4,7-epoxy-1H-isoindole-1,3(2H)-dione	1.16 LC	3
145		(3aα,4β,7β,7aα)-2-[3-Chloro-4-(2-thiazolyl)phenyl]hexahydro-4-methyl-4,7-epoxy-1H-isoindole-1,3(2H)-dione	2.81 LC	3
146		(3aα,4α,7α,7aα)-2-(3,5-Dichlorophenyl)hexahydro-4,7-imino-1H-isoindole-1,3(2H)-dione	2.72 LC	31
147		(3aα,4α,7α,7aα)-2-(4-Bromo-1-naphthalenyl)hexahydro-4,7-imino-1H-isoindole-1,3(2H)-dione	2.95 LC	31
148		(3aα,4α,7α,7aα)-2-(4-Bromo-3-methylphenyl)hexahydro-4,7-imino-1H-isoindole-1,3(2H)-dione	2.65 LC	31







161

Ex. No.	Compound Structure	Compound Name	Retention Time Min./ Molecular Mass	Pro. of Ex.
149		(3aα,4α,7α,7aα)-Hexahydro-2-(4-nitro-1-naphthalenyl)-4,7-imino-1H-isoindole-1,3(2H)-dione	2.49 LC	31
150		(3aα,4α,7α,7aα)-8-Acetyl-2-(3,5-dichlorophenyl)hexahydro-4,7-imino-1H-isoindole-1,3(2H)-dione	3.53 LC	31
151		(3aα,4α,7α,7aα)-Octahydro-1,3-dioxo-2-[3-(trifluoromethyl)phenyl]-4,7-ethano-5H-pyrrolo[3,4-c]pyridine-5-carboxylic acid phenyl ester	3.397 LC	9
152		(3aα,4α,7α,7aα)-4-(Octahydro-1,3-dioxo-4,7-ethano-2H-pyrrolo[3,4-c]pyridin-2-yl)-1-naphthalenecarbonitrile	1.74 LC	11
153		(3aα,4α,7α,7aα)-4-(Octahydro-5-methyl-1,3-dioxo-4,7-ethano-2H-pyrrolo[3,4-c]pyridin-2-yl)-1-naphthalenecarbonitrile	1.71 LC	14

162

Ex. No.	Compound Structure	Compound Name	Retention Time Min./ Molecular Mass	Pro. of Ex.
154		(3aα,4α,7α,7aα)-2-(4-Cyano-1-naphthalenyl)octahydro-1,3-dioxo-4,7-etheno-5H-pyrrolo[3,4-c]pyridine-5-carboxylic acid phenylmethyl ester	3.40 LC	10
155		(3aα,4α,7α,7aα)-4-(Octahydro-1,3-dioxo-4,7-ethano-2H-pyrrolo[3,4-c]pyridin-2-yl)-2-(trifluoromethyl)benzonitrile	1.74 LC	11
156		(3aα,4α,7α,7aα)-4-(Octahydro-5-methyl-1,3-dioxo-4,7-ethano-2H-pyrrolo[3,4-c]pyridin-2-yl)-2-(trifluoromethyl)benzonitrile	1.65 LC	14
157		(3aα,4α,7α,7aα)-2-[4-Cyano-3-(trifluoromethyl)phenyl]octahydro-1,3-dioxo-4,7-etheno-5H-pyrrolo[3,4-c]pyridine-5-carboxylic acid phenylmethyl ester	3.53 LC	10
158		(3aα,4α,7α,7aα)-2-[4-Bromo-3-(trifluoromethyl)phenyl]tetrahydro-5-methyl-4,7-etheno-1H-pyrrolo[3,4-c]pyridine-1,3,6(2H,5H)-trione	2.95 LCMS	34

163




Ex. No.	Compound Structure	Compound Name	Retention Time Min./ Molecular Mass	Pro. of Ex.
159		(3aα,4α,7α,7aα)-Tetrahydro-5-methyl-2-[3-(trifluoromethyl)phenyl]-4,7-etheno-1H-pyrrolo[3,4-c]pyridine-1,3,6(2H,5H)-trione	2.53 LCMS	34
160		(3aα,4α,7α,7aα)-Tetrahydro-5-methyl-2-(2-naphthalenyl)-4,7-etheno-1H-pyrrolo[3,4-c]pyridine-1,3,6(2H,5H)-trione	2.58 LCMS	34
161		(1aα,2β,2aα,5aα,6β,6aα)-Hexahydro-4-[3-(trifluoromethyl)phenyl]-2,6-epoxy-3H-oxireno[f]iso-indole-3,5(4H)-dione	1.80 LCMS	28
162		(1aα,2β,2aα,5aα,6β,6aα)-4-(3,5-Dichlorophenyl)-hexahydro-2,6-epoxy-3H-oxireno[f]isoindole-3,5(4H)-dione	1.45 LCMS	28
163		(1aα,2β,2aα,5aα,6β,6aα)-Hexahydro-4-(4-nitro-1-naphthalenyl)-2,6-epoxy-3H-oxireno[f]isoindole-3,5(4H)-dione	1.52 LCMS	28
164		(1aα,2β,2aα,5aα,6β,6aα)-4-(3,4-Dichlorophenyl)-hexahydro-2,6-epoxy-3H-oxireno[f]isoindole-3,5(4H)-dione	3.21 LCMS	28

164






Examples 165 to 203

Additional compounds of the present invention were prepared and are described further below in **Table 4**. **Table 4** sets forth the compound name and structure, as well as the Example number of the procedure on which the preparation of **Table 4** was based, for the compounds of Examples 165 to 203.






Table 4

Ex. No.	Compound Structure	Compound Name	Pro. of Ex.
165		2-[4-(4-Bromo-phenoxy)phenyl]-3a,4,7,7a-tetrahydro-4,7-dimethyl-4,7-epoxy-1H-isoindole-1,3(2H)-dione	32
166		3a,4,7,7a-Tetrahydro-2-(2-methoxyphenyl)-4,7-dimethyl-4,7-epoxy-1H-isoindole-1,3(2H)-dione	32
167		[(1,2,3,3a,7,7a-Hexahydro-2-phenyl-4,7-epoxy-4H-isoindol-4-yl)methyl]carbamic acid (3,5-dimethoxyphenyl)methyl ester	21-26







165 166

Ex. No.	Compound Structure	Compound Name	Pro. of Ex.
168		2-(2,4-Dimethylphenyl)-3a,4,7,7a-tetrahydro-4-(hydroxymethyl)-4,7-epoxy-1H-isoindole-1,3(2H)-dione	21-26
169		2-(1,3-Benzodioxol-5-yl)-3a,4,7,7a-tetrahydro-4-methyl-4,7-epoxy-1H-isoindole-1,3(2H)-dione	32
170		4-[Bis(acetyloxy)methyl]-2-(3-bromophenyl)-3a,4,7,7a-tetrahydro-4,7-epoxy-1H-isoindole-1,3(2H)-dione	21-26
171		N-[[1,2,3,3a,7,7a-Hexahydro-2-(2,4,6-trimethylphenyl)-4,7-epoxy-4H-isoindol-4-yl]methyl]-2,2-dimethylpropanamide	21-26
172		3a,4,7,7a-Tetrahydro-4-(hydroxymethyl)-2-[2-(trifluoromethyl)phenyl]-4,7-epoxy-1H-isoindole-1,3(2H)-dione	21-26






166

Ex. No.	Compound Structure	Compound Name	Pro. of Ex.
173		3a,4,7,7a-Tetrahydro-4-(hydroxymethyl)-2-(1-naphthalenyl)-4,7-epoxy-1H-isoindole-1,3(2H)-dione	21-26
174		2-Chloro-5-(1,3,3a,4,7,7a-hexahydro-4,7-dimethyl-4,7-epoxy-2H-isoindol-2-yl)benzoic acid methyl ester	32
175		4-[Bis(acetyloxy)methyl]-2-(4-bromo-2-nitrophenyl)-3a,4,7,7a-tetrahydro-4,7-epoxy-1H-isoindole-1,3(2H)-dione	21-26
176		3a,4,7,7a-Tetrahydro-4-methyl-2-(4-methyl-3-nitrophenyl)-4,7-epoxy-1H-isoindole-1,3(2H)-dione	32
177		2-[2-Chloro-5-(trifluoromethyl)phenyl]-3a,4,7,7a-tetrahydro-4-methyl-4,7-epoxy-1H-isoindole-1,3(2H)-dione	32






167

Ex. No.	Compound Structure	Compound Name	Pro. of Ex.
178		2-[4-Chloro-3-(trifluoromethyl)phenyl]-3a,4,7,7a-tetrahydro-4,7-dimethyl-4,7-epoxy-1H-isoindole-1,3(2H)-dione	32
179		2-(1,3,3a,4,7,7a-Hexahydro-4-methyl-4,7-epoxy-2H-isoindol-2-yl)benzonitrile	32
180		2-(4-Fluorophenyl)-3a,4,7,7a-tetrahydro-4-methyl-4,7-epoxy-1H-isoindole-1,3(2H)-dione	32
181		2,2,2-Trifluoro-N-[(1,2,3,3a,7,7a-hexahydro-2-phenyl-4,7-epoxy-4H-isoindol-4-yl)methyl]acetamide	21-26
182		3a,4,7,7a-Tetrahydro-4,7-dimethyl-2-(4-methyl-3-nitrophenyl)-4,7-epoxy-1H-isoindole-1,3(2H)-dione	32
183		2-Chloro-5-[1,3,3a,4,7,7a-hexahydro-4-(hydroxymethyl)-4,7-epoxy-2H-isoindol-2-	21-26






168






Ex. No.	Compound Structure	Compound Name	Pro. of Ex.
		yl]benzoic acid	
184		3a,4,7,7a-Tetrahydro-4,7-dimethyl-2-(4-nitrophenyl)-4,7-epoxy-1H-isoindole-1,3(2H)-dione	32
185		3a,4,7,7a-Tetrahydro-2-(2-mercaptophenyl)-4,7-epoxy-1H-isoindole-1,3(2H)-dione	32
186		3a,4,7,7a-Tetrahydro-2-[2-[(phenylmethyl)thio]phenyl]-4,7-epoxy-1H-isoindole-1,3(2H)-dione	32
187		[[2-(4-Chlorophenyl)-1,2,3,3a,7,7a-hexahydro-4,7-epoxy-4H-isoindol-4-yl]methyl]carbamic acid 2-methylpropyl ester	21-26
188		4-(1,1-Dimethylethyl)-N-[[1,2,3,3a,7,7a-hexahydro-2-(4-methylphenyl)-4,7-epoxy-4H-isoindol-4-yl]methyl]benzamide	21-26

189

Ex. No.	Compound Structure	Compound Name	Pro. of Ex.
189		2,4-Dichloro-N-[[1,2,3,3a,7,7a-hexahydro-2-(4-nitrophenyl)-4,7-epoxy-4H-isoindol-4-yl]methyl]benzamide	21-26
190		N-[[2-(4-Chlorophenyl)-1,2,3,3a,7,7a-hexahydro-4,7-epoxy-4H-isoindol-4-yl]methyl]-2,4,6-trimethylbenzenesulfonamide	21-26
191		N-[[1,2,3,3a,7,7a-Hexahydro-2-(4-nitrophenyl)-4,7-epoxy-4H-isoindol-4-yl]methyl]-2,2-dimethylpropanamide	21-26
192		N-[(1,2,3,3a,7,7a-Hexahydro-2-phenyl-4,7-epoxy-4H-Isoindol-4-yl)methyl]-2-phenoxyacetamide	21-26
193		[(1,2,3,3a,7,7a-Hexahydro-2-phenyl-4,7-epoxy-4H-isoindol-4-yl)methyl]carbamic acid 1,1-dimethylethyl ester	21-26


170

Ex. No.	Compound Structure	Compound Name	Pro. of Ex.
194		2-(2,4-Dichlorophenoxy)-N-[[1,2,3,3a,7,7a-hexahydro-2-(4-nitrophenyl)-4,7-epoxy-4H-isoindol-4-yl]methyl]acetamide	21-26
195		N-[[1,2,3,3a,7,7a-Hexahydro-2-(4-methylphenyl)-4,7-epoxy-4H-isoindol-4-yl]methyl]-3,5-dimethoxybenzamide	21-26
196		N-[[2-(4-Chlorophenyl)-1,2,3,3a,7,7a-hexahydro-4,7-epoxy-4H-isoindol-4-yl]methyl]-2-nitrobenzenesulfonamide	21-26
197		(3aα,4β,7β,7aα)-Hexahydro-2-[(1S)-1-phenylethyl]-4,7-epoxy-1H-isoindole-1,3(2H)-dione.	8
198		(3aα,4β,7β,7aα)-Hexahydro-2-[(1S)-2-hydroxy-1-phenylethyl]-4,7-epoxy-1H-isoindole-1,3(2H)-dione.	8


Ex. No.	Compound Structure	Compound Name	Pro. of Ex.
199		(3aα,4β,7β,7aα)-2-[(1S)-2-(Acetyloxy)-1-phenylethyl]-3a,4,7,7a-tetrahydro-4,7-epoxy-1H-isoindole-1,3(2H)-dione.	8
200		(3aα,4α,7α,7aα)-3a,4,7,7a-Tetrahydro-2-[(1S)-1-phenylethyl]-4,7-epoxy-1H-isoindole-1,3(2H)-dione.	8
201		(3aα,4β,7β,7aα)-Hexahydro-2-[(1R)-1-phenylethyl]-4,7-epoxy-1H-isoindole-1,3(2H)-dione.	8
202		(3aα,4β,7β,7aα)-4-[[(Octahydro-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl)methyl]amino]benzoic acid.	8
203		(3aα,4β,7β,7aα)-Hexahydro-2-(4-morpholinylmethyl)-4,7-epoxy-1H-isoindole-1,3(2H)-dione.	8

Example 204

(3aα,4β,7β,7aα)-4-[Octahydro-4-(2-hydroxyethyl)-7-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-2-(trifluoromethyl)benzonitrile (204D/25B)




A. 2-[2-[[(1,1-Dimethylethyl)dimethylsilyl]oxy]ethyl]-5-methylfuran (204A)




To a solution of compound 21A (2.00 g, 15.9 mmol) in DMF (50 mL) was added imidazole (1.62 g, 23.9 mmol), followed by *tert*-butyldimethylsilyl chloride (2.63 g, 17.5 mmol). After 2 h at 25°C, the reaction was poured into diethyl ether (300 mL) and washed with water (1 x 100 mL), 1N HCl (1 x 100 mL), water (1 x 100 mL), brine (1 x 50 mL) and dried over anhydrous $MgSO_4$. Crude compound 204A was analyzed by LCMS and NMR and determined to be pure enough to be carried on directly to the next step. HPLC: 100% at 4.347 min (retention time) (YMC S5 ODS column 4.6 x 50 mm eluting with 10-90% aqueous methanol over 4 minutes containing 0.1% TFA, 4 mL/min, monitoring at 220 nm).

B. (3aα,4β,7β,7aα)-4-[2-[[(1,1-Dimethylethyl)dimethylsilyl]-oxy]ethyl]hexahydro-7-methyl-4,7-epoxy-1H-isobenzofuran-1,3(2H)-dione (204B)



Compound **204A** (4.0 g, 18.9 mmol) and maleic anhydride (1.42 g, 14.51 mmol) were dissolved in dichloroethane (10 mL) and stirred at 25°C for 60 hours. The volatiles were then removed in vacuo and the resulting orange oil was dissolved in absolute ethanol (50 mL) and Pd/C (10 % Pd, 1.00 g) was added. Hydrogen was then introduced via a balloon. After 3h, the reaction was filtered through celite rinsing with EtOAc and concentrated in vacuo. The crude anhydride was purified by rapid flash chromatography in SiO_2 eluting with acetone/chloroform (0 – 2 – 4% acetone) to give 1.30 g of compound **204B** as a clear oil, in addition to 3.00 g of the starting compound **204A**. Characterization by proton NMR spectroscopy showed only the exo isomer. 1H NMR, 400 MHz, CDCl3, 3.83 (2 H, t, J = 6.0 Hz), 3.22 (1 H, d, J = 8.2 Hz), 3.06 (1 H, d, J = 8.2 Hz), 1.70 – 2.25 (6 H, m), 1.55 (3 H, s), 0.82 (9 H, s), 0.00 (6 H, s).

C. (3aα,4β,7β,7aα)-4-[4-[2-[[(1,1-Dimethylethyl)dimethylsilyl]-oxy]ethyl]octahydro-7-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-2-(trifluoromethyl)benzonitrile (204C)



Compound **204B** (0.250 g, 0.8 mmol) and 4-amino-2-trifluoromethyl-benzonitrile (0.124 g, 0.668 mmol) were suspended in dry toluene (2.0 mL) in a sealed tube. $MgSO_4$ (0.200 g) and triethylamine (0.5 mL) were then added and the tube was sealed and placed in a oil bath at 125°C. After 40 h, the reaction was cooled to 25°C, filtered and concentrated in vacuo. The crude material was purified by flash chromatography on SiO_2 eluting with CH_2Cl_2 to give 0.111 g of compound **204C** as a yellow solid. HPLC: 92% at 4.203 min (retention time) (YMC S5 ODS column 4.6 x 50 mm eluting with 10-90% aqueous methanol over 4 minutes containing 0.1% TFA, 4 mL/min, monitoring at 220 nm). MS (ESI): m/z 531.1 $[M+Na]^+$.


174


D. (3aα,4β,7β,7aα)-4-[Octahydro-4-(2-hydroxyethyl)-7-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-2-(trifluoromethyl)benzonitrile (204D)

Compound **204C** (0.031 g, 0.061 mmol) was dissolved in THF (0.5 mL) and transferred to a polypropylene container followed by cooling to 0°C. HF•pyridine (~47% HF, 0.1 mL) was then added. After 15 min, the reaction was complete as determined by LC and was poured into cold sat aqueous $NaHCO_3$. The mixture was extracted with CH_2Cl_2 (3 x 10 mL). The combined organic layers were washed with 1 N HCl (1 x 20 mL) and dried over anhydrous Na_2SO_4. Compound **204D** was isolated as a yellow oil and compared to the material prepared in Example **25**. No purification was necessary.


Example 205

(3aα,4β,7β,7aα)- and (3aα,4α,7α,7aα)-4-[Octahydro-4-methyl-1,3-dioxo-7-(phenylmethyl)-4,7-epoxy-2H-isoindol-2-yl]-2-(trifluoromethyl)benzonitrile (205Ci and 205Cii, respectively)






A. 2-Methyl-5-(phenylmethyl)-furan (205A)



n-BuLi (1.8 ml, 4.51 mmol, 1.1 eq, 2.5 M in hexane) was added to a solution of 2-methyl-furan (0.37 ml, 4.10 mmol, 1 eq) in anhydrous THF (3 mL) at –25 °C. The resulting solution was stirred at room temperature for 3 h and then cooled to –15°C. Benzyl bromide (0.59 ml, 4.92 mmol, 1.2 eq), which was passed through a plug of aluminum oxide, was added and the solution was warmed to rt and stirred

overnight. Saturated NH_4Cl solution (5 mL) was added and the mixture was stirred for 1 h. The reaction mixture was then extracted by ether (2 X) and the combined organic extracts were dried and concentrated under reduced pressure. Purification by flash chromatography on silica gel eluting with hexanes gave 323 mg (46%, 1.88 mmol) of compound **205A** as colorless oil. HPLC: 95% at 3.72 min (retention time) (YMC S5 ODS column 4.6 x 50 mm, 10-90% aqueous methanol over 4 minutes containing 0.2% phosphoric acid, 4 mL/min, monitoring at 220 nm) and about 400 mg mixture of product and benzyl bromide (~2:1 by HPLC).

B. (3aα,4β,7β,7aα)- and (3aα,4α,7α,7aα)-4-[Octahydro-4-methyl-1,3-dioxo-7-(phenylmethyl)-4,7-epoxy-2H-isoindol-2-yl]-2-(trifluoromethyl) benzonitrile (205Bi and 205Bii, respectively)



A solution of compound **205A** (124 mg, 0.72 mmol, 1 eq) and 4-(2,5-dihydro-2,5-dioxo-1H-pyrrol-1-yl)-2-trifluoromethylbenzonitrile (290 mg, 1.09 mmol, 1.5 eq) in CH_2Cl_2 (2 mL) was stirred at room temperature. After 4 days, the reaction mixture was concentrated under reduced pressure. Purification by flash chromatography on silica gel eluting with CH_2Cl_2 gave 62 mg (0.14 mmol, 20 %) of a mixture of compounds **205Bi** and **205Bii** as a white solid, which was used directly in the next step. HPLC: 93% at 3.69 min (retention time) (YMC S5 ODS column 4.6 x 50 mm, 10-90% aqueous methanol over 4 minutes containing 0.2% phosphoric acid, 4 mL/min, monitoring at 220 nm).


C. (3aα,4β,7β,7aα)- and (3aα,4α,7α,7aα)-4-[Octahydro-4-methyl-1,3-dioxo-7-(phenylmethyl)-4,7-epoxy-2H-isoindol-2-yl]-2-(trifluoromethyl)-benzonitrile (205Ci and 205Cii, respectively)

176

A solution of a mixture of compounds **205Bi** and **205Bii** (62 mg, 0.14 mmol, 1 eq) and 10% Pd/C (12 mg, cat.) in EtOH (3.5 mL) was stirred under a hydrogen atmosphere at room temperature for 2 h. The reaction mixture was filtered through celite and concentrated under reduced pressure. Purification by flash chromatography on silica gel eluting with 35% EtOAc/hexanes gave 22 mg (0.05 mmol, 35 %) of compound **205Ci** and 12 mg (0.027 mmols, 19%) of compound **205Cii**. Compound **205Ci**: HPLC: 98% at 3.75 min (retention time) (YMC S5 ODS column 4.6 x 50 mm, 10-90% aqueous methanol over 4 minutes containing 0.2% phosphoric acid, 4 mL/min, monitoring at 220 nm), MS (ESI): m/z 458.2 $[M+NH_4]^+$. Compound **205Cii**: HPLC: 97% at 3.78 min (YMC S5 ODS column 4.6 x 50 mm, 10-90% aqueous methanol over 4 minutes containing 0.2% phosphoric acid, 4 mL/min, monitoring at 220 nm), MS (ESI): m/z 473.45 $[M+CH_3OH]^+$.

Example 206

(3aα,4β,7β,7aα)-2-[4-Cyano-3-(trifluoromethyl)phenyl]octahydro-7-methyl-1,3-dioxo-4,7-epoxy-4H-isoindole-4-propanenitrile (206)




A solution of compound **36** (34 mg, 0.074 mmol) and NaCN (24 mg, 0.49 mmol) in DMSO (1 mL) was heated at 100°C for 0.5 h. After cooling, the reaction mixture was poured into H_2O and the aqueous layer was extracted with EtOAc (2X). The combined organic layers were washed with H_2O (2X), dried over Na_2SO_4 and concentrated under reduced pressure. Purification by flash chromatography on SiO_2 eluting with 50% EtOAc/hexanes followed by preparative HPLC, 30.41 min (retention time) (YMC S5 ODS 30 X 250 mm, 10-90% aqueous methanol over 30 minutes containing 0.1% TFA, 25 mL/min,

monitoring at 220 nm) gave 6.6 mg (22%) of compound **206** as a white solid. HPLC: 99% at 2.89 min (retention time) (YMC S5 ODS column 4.6 x 50 mm eluting with 10-90% aqueous methanol over 4 minutes containing 0.2% phosphoric acid, 4 mL/min, monitoring at 220 nm), MS (ES): m/z 402.1 $[M-H]^-$.

Example 207


(3aα,4β,7β,7aα)-4-[Octahydro-4-methyl-7-[2-(4-morpholinyl)ethyl]-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-2-(trifluoromethyl)benzonitrile, trifluoroacetate (1:1) (207)




A solution of compound **36** (15.6 mg, 0.034 mmol) and morpholine (6 µL, 0.068 mmol) in toluene (1 mL) was heated at 100°C overnight. After cooling, the reaction mixture was concentrated under reduced pressure. Purification by flash chromatography on SiO_2 eluting with 10% $MeOH/CH_2Cl_2$ followed by preparative HPLC, 23.96 min (retention time) (YMC S5 ODS 30 X 250 mm, 10-90% aqueous methanol over 30 minutes containing 0.1% TFA, 25 mL/min, monitoring at 220 nm) gave 8.7 mg (55%) of compound **207** (TFA salt) as a white solid. HPLC: 99% at 2.02 min (retention time) (YMC S5 ODS column 4.6 x 50 mm eluting with 10-90% aqueous methanol over 4 minutes containing 0.2% phosphoric acid, 4 mL/min, monitoring at 220 nm), MS (ES): m/z 464.3 $[M+H]^+$.

Example 208

(3aα,4β,7β,7aα)-2-(5-Fluoro-1-naphthalenyl)hexahydro-4,7-dimethyl-4,7-epoxy-1H-isoindole-1,3(2H)-dione (208C)




A. 1-Fluoro-5-nitronaphthalene (208A)



To a solution of 6N HCl (12 mL) was added 1.47 g (7.83 mmol) of finely powdered 5-nitro-1-naphthylamine, as described in *J. Chem. Soc.* 1187 (1949). The mixture was cooled to 0°C and a cold solution of $NaNO_2$ (547 mg, 7.93 mmol) in 2 mL H_2O was added slowly so that the temperature was kept near 0°C. After the addition was complete, the reaction mixture was stirred for 30 min and filtered. The filtrate was cooled to 0°C and treated with cold 4.5 M $NaBF_4$ solution (5 ml) to give complete precipitation of the diazonium borofluoride. The mixture was kept at 0°C for 30 min before it was filtered and the precipitates were washed with cold 4.5 M $NaBF_4$ solution (5 mL), ice-cold ethanol (10 mL) and Et_2O (20 mL). The obtained solids were air dried to yield 1.74 g (77%) of the corresponding diazonium salt.

To 1.70 g (5.92 mmol) of the above diazonium borofluoride was added 5 g of sand and the components were thoroughly mixed. The reaction mixture was heated cautiously under reduced pressure until decomposition set in. Toward the end of the reaction the flask was further heated for 30 min to 130°C to assure complete conversion. After cooling the reaction mixture was dissolved in acetone and the contents were preabsorbed on silica gel. Purification was achieved by flash chromatography (silica gel, EtOAc in hexanes 0 to 10%) to give 449 mg (50%) of compound **208A** as a white solid.

B. 1-Amino-5-fluoronaphthalene (208B)




A solution of compound **208A** (62 mg, 0.32 mmol) in 1 mL EtOH containing 0.1 mL 12N HCl was heated to reflux. Iron powder (62 mg, 1.11 mmol) was added in small portions and heating was continued for 2 h. The mixture was cooled, neutralized with 1N NaOH solution and the aqueous layer was extracted with CH_2Cl_2. The combined organic phases were dried over $MgSO_4$ and concentrated to leave a residue which was purified by flash chromatography (silica gel, EtOAc in hexanes 40 to 80%) yielding 42 mg (80%) of compound **208B** as a yellow solid.

C. (3aα,4β,7β,7aα)-2-(5-Fluoro-1-naphthalenyl)hexahydro-4,7-dimethyl-4,7-epoxy-1H-isoindole-1,3(2H)-dione (208C)


Compound **208B** (42 mg, 0.26 mmol), compound **20A** (54 mg, 0.27 mmol), $MgSO_4$ (69 mg, 0.58 mmol) and triethylamine (191 µL, 1.37 mmol) were taken up in 2 mL of toluene and placed in a sealed tube. The sealed tube was heated to 135°C for 14 h. The cooled reaction mixture was filtered through a short pad of Celite eluting with CH_2Cl_2 and the solvent was removed under reduced pressure. The residue was purified by preparative reverse phase HPLC (YMC S5 ODS 20 x 100 mm eluting with 30-100% aqueous methanol over 10 min containing 0.1% TFA, 20 mL/min) to give 15 mg (17%) of compound **208C** as a light yellow solid. HPLC: 16% at 2.96 min & 77% at 3.06 min (retention time, atropisomers) (YMC S5 ODS column 4.6 x 50 mm eluting with 10-90% aqueous methanol over 4 minutes containing 0.2% phosphoric acid, 4 mL/min, monitoring at 220 nm), MS (ES): m/z 340.2 $[M+H]^+$.

Example 209

(3aα,4β,7β,7aα)-2-(5-Fluoro-4-nitro-1-naphthalenyl)hexahydro-4,7-dimethyl-4,7-epoxy-1H-isoindole-1,3(2H)-dione (209C)




A. N-(5-Fluoro-1-naphthalenyl)acetamide (209A)



A solution of 141 mg (0.74 mmol) of compound **208A** in 2 mL of AcOH was heated to reflux and treated with small portions of iron powder (118 mg, 2.11 mmol). The mixture was kept at reflux for 15 min before 73 µL (0.78 mmol) of Ac_2O was added. After an additional 15 min at reflux, the mixture was cooled and filtered eluting with CH_2Cl_2. The filtrate was then concentrated and the residue was purified by flash chromatography (silica gel, EtOAc in hexane 20 to 50%) to give compound **209A** (145 mg, 97%) as a white solid.

B. 1-Amino-5-fluoro-4-nitronaphthalene (209B)



Compound **209A** (133 mg, 0.66 mmol) was dissolved in 1 mL AcOH and the resulting solution was cooled to 10°C. At this temperature, 80 µL (2.00 mmol) of red fuming HNO_3 was added and stirring was continued for 15 min before the reaction was quenched by the addition of crushed ice. The aqueous layer was extracted with CH_2Cl_2 and the combined organic phases were dried over $MgSO_4$ and concentrated. The resulting residue was

181


dissolved in 3 mL EtOH, heated to reflux and treated with 0.5 mL of 40% aqueous NaOH solution. Stirring was continued for 15 min before the reaction was cooled and diluted with H_2O. The aqueous layer was extracted with CH_2Cl_2 and the combined organic phases were dried over $MgSO_4$ and concentrated. The resulting residue was purified by flash chromatography (silica gel, EtOAc in hexane 40 to 70%) to afford 36 mg (27%) of compound **209B** as a yellow solid.

C. 3aα,4β,7β,7aα)-2-(5-Fluoro-4-nitro-1-naphthalenyl)hexahydro-4,7-dimethyl-4,7-epoxy-1H-isoindole-1,3(2H)-dione (209C)

Compound **209B** (36 mg, 0.18 mmol) was reacted in a sealed tube with compound **20A** (38 mg, 0.19 mmol), $MgSO_4$ (46 mg, 0.39 mmol) and Et_3N (128 μL, 0.92 mmol) in 250 μL toluene according to the above procedure described in example **208C** to give, after purification by preparative reverse phase HPLC (YMC S5 ODS 20 x 100 mm eluting with 30-100% aqueous methanol over 10 min containing 0.1% TFA, 20 mL/min), 27 mg (40%) of compound **209C** as a yellow solid. HPLC: 8% at 2.88 min & 84% at 3.06 min (atropisomers, retention time) (YMC S5 ODS column 4.6 x 50 mm eluting with 10-90% aqueous methanol over 4 minutes containing 0.2% phosphoric acid, 4 mL/min, monitoring at 220 nm), MS (ES): m/z 402.0 $[M+H]^+$.

Example 210

(3aα,4β,7β,7aα)-2-(1,1-Dioxidobenzo[b]thiophen-3-yl)hexahydro-4,7-dimethyl-4,7-epoxy-1H-isoindole-1,3(2H)-dione (210)




*m*CPBA (160 mg, 0.641 mmol, 70% pure) was added to a solution of compound **134** (70 mg, 0.214 mmol) in CH_2Cl_2 (2 mL) at rt. After the starting

182

material was consumed, the reaction was quenched with sat. $NaHCO_3$, and extracted with CH_2Cl_2. The organic layer was washed with 1N NaOH, dried over Na_2SO_4 and concentrated under reduced pressure to give 63.9 mg (83%) of compound **210** as a white solid. HPLC: 99% at 3.81 min (retention time) (YMC S5 ODS column 4.6 x 50 mm eluting with 10-90% aqueous methanol over 4 minutes containing 0.2% phosphoric acid, 4 mL/min, monitoring at 220 nm), MS (ES): m/z 360.0 $[M+H]^+$.

Example 211

4-(1,3,3a,4,7,7a-Hexahydro-4,6,7-trimethyl-1,3-dioxo-4,7-epoxy-2H-pyrrolo[3,4-c]pyridin-2-yl)-2-(trifluoromethyl)benzonitrile (211)





2,4,5-Trimethyl oxazole (0.48 mL, 4.14 mmol) was dissolved in toluene (2.0 mL) and 4-(2,5-dihydro-2,5-dioxo-1H-pyrrol-1-yl)-2-trifluoromethyl-benzonitrile (1.0 g 3.76 mmol) was added. The reaction mixture was stirred at 75°C under nitrogen for 2.5 hrs. The solution was cooled to room temperature and the resulting precipitate was filtered and rinsed with toluene to give 0.51 g (35% yield) of compound **211** as a light grey solid. NMR analysis revelaed that compound **211** was one isomer (exo/endo) however the identity of the isomer could not be determined by NMR analysis. HPLC: 100% at 2.85 min (retention time) (YMC S5 ODS column 4.6 x 50 mm eluting with 10-90% aqueous methanol over 4 minutes containing 0.1% TFA, 4 mL/min, monitoring at 220 nm), MS (ES): m/z 378.42 $[M+H]^+$.

183

Example 212

(3aα,4β,7β,7aα)-Tetrahydro-4,7-dimethyl-2-[3-(trifluoromethyl)phenyl]-4,7-epoxy-1H-isoindole-1,3,5(2H,4H)-trione & (3aα,4α,7α,7aα)-Tetrahydro-4,7-dimethyl-2-[3-(trifluoromethyl)phenyl]-4,7-epoxy-1H-Isoindole-1,3,5(2H,4H)-trione (212i & 212ii, respectively)






2,2-Dimethyl-3(H)-furanone (0.500 g, 4.46 mmol) and 1-[3-(trifluoromethyl)phenyl]-1H-pyrrole-2,5-dione (1.07 g, 4.46 mmol) were suspended in toluene (20 mL) in a sealed tube. The mixture was heated at 110°C for 4 h and then cooled to 25°C followed by concentration *in vacuo*. The resulting residue was purified by flash chromatography on SiO_2 eluting with methylene chloride to yield 0.411 g of compound **212i** as a white solid and 0.193 g of compound **212ii** as a white solid. The structural assignments were confirmed by 1-D NOE proton NMR experiments. Compound **212i**: HPLC: 100% at 2.817 min (retention time) (YMC S5 ODS column 4.6 x 50 mm eluting with 10-90% aqueous methanol over 4 minutes containing 0.1% TFA, 4 mL/min, monitoring at 220 nm), MS (ES): m/z 376.0 $[M + Na]^+$. Compound **212ii**: HPLC: 100% at 3.013 min (retention time) (YMC S5 ODS column 4.6 x 50 mm eluting with 10-90% aqueous methanol over 4 minutes containing 0.2% phosphoric acid, 4 mL/min, monitoring at 220 nm), MS (ES): m/z 354.02 $[M+H]^+$.


Example 213

(3aα,4β,7β,7aα)-2-(5-Chloro-1-naphthalenyl)hexahydro-4,7-dimethyl-4,7-epoxy-1H-isoindole-1,3(2H)-dione (213B)

184



A. 1-Amino-5-chloronaphthalene (213A)



To a solution of 1.74 g (6.06 mmol) of the diazonium borofluoride (described in Example **208A**) in acetone (7 mL) was added 693 mg (7.00 mmol) of CuCl in small portions. After the evolution of nitrogen had ceased the acetone was removed under reduced pressure and the residue was taken up in CH_2Cl_2 (30 mL). The organic phase was washed with H_2O (30 mL), dried over $MgSO_4$, concentrated and finally purified by flash chromatography (silica gel, EtOAc in hexane 0 to 15%) to give 754 mg (70%) of 1-chloro-5-nitronaphthalene.

The above synthesized 1-chloro-5-nitronaphthalene (540 mg, 2.6 mmol) was dissolved in 10 mL AcOH, followed by treatment with 415 mg (7.43 mmol) iron powder and subsequently acylated with Ac_2O (0.26 mL, 2.73 mmol) according to the procedure described in Example **209A** to give 543 mg (95%) of 1-acetamino-5-chloronaphthalene.


A solution of the above synthesized 1-acetamino-5-chloronaphthalene (52 mg, 0.24 mmol) in 3 mL EtOH was heated to reflux and treated with 0.5 mL 40% aqueous NaOH solution. The mixture was refluxed until no more starting material could be detected, cooled and concentrated under reduced pressure. The residue was taken up in CH_2Cl_2 (50 mL) and was washed with H_2O (25 mL). The organic layer was dried over $MgSO_4$ and concentrated to leave 41 mg (98%) of compound **213A** as a white solid.

B. (3aα,4β,7β,7aα)-2-(5-Chloro-1-naphthalenyl)hexahydro-4,7-dimethyl-4,7-epoxy-1H-isoindole-1,3(2H)-dione (213B)


Compound **213A** (24 mg, 0.14 mmol) was reacted in a sealed tube with compound **20A** (29 mg, 0.15 mmol), $MgSO_4$ (36 mg, 0.30 mmol) and Et_3N (100 µL, 0.71 mmol) in 250 µL toluene according to the procedure described in Example **208C** to give, after purification by preparative reverse phase HPLC (YMC S5 ODS 20 x 100 mm eluting with 30-100% aqueous methanol over 10 min containing 0.1% TFA, 20 mL/min), 27 mg (40%) of compound **213B** as a white solid. HPLC: 98% at 1.82 min (retention time) (YMC S5 TurboPack Pro column 4.6 x 33 mm eluting with 10-90% aqueous methanol over 2 minutes containing 0.2% phosphoric acid, 4 mL/min, monitoring at 220 nm), MS (ES): m/z 356.4 $[M+H]^+$.

Example 214

(3aα,4β,7β,7aα)-2-(5-Chloro-4-nitro-1-naphthalenyl)hexahydro-4,7-dimethyl-4,7-epoxy-1H-isoindole-1,3(2H)-dione (214B)



A. 1-Amino-5-chloro-4-nitronaphthalene (214A)




1-Acetamino-5-chloronaphthalene (150 mg, 0.68 mmol, prepared as described in Example **213A**) was dissolved in 1 mL AcOH and treated with 82 µL of red fuming HNO_3 and subsequently deacylated with 1 mL 40% aqueous NaOH solution in 3 mL EtOH according to the procedure described in Example **209A** to yield 49 mg (32%) of compound **214A** as a yellow solid.

B. (3aα,4β,7β,7aα)-2-(5-Chloro-4-nitro-1-naphthalenyl)hexahydro-4,7-dimethyl-4,7-epoxy-1H-isoindole-1,3(2H)-dione (214B)


Compound **214A** (27 mg, 0.12 mmol) was reacted in a sealed tube with compound **20A** (26 mg, 0.13 mmol), $MgSO_4$ (32 mg, 0.27 mmol) and Et_3N (88 µL, 0.63 mmol) in 250 µL toluene according to the procedure described in Example **208C** to give, after purification by preparative reverse phase HPLC (YMC S5 ODS 20 x 100 mm eluting with 30-100% aqueous methanol over 10 min containing 0.1% TFA, 20 mL/min) 22 mg (45%) of compound **214B** as a yellow solid. HPLC: 24% at 3.06 min & 76% at 3.25 min (atropisomers, retention time) (YMC S5 ODS column 4.6 x 50 mm eluting with 10-90% aqueous methanol over 4 minutes containing 0.2% phosphoric acid, 4 mL/min, monitoring at 220 nm), MS (ES): m/z 418.0 $[M+NH_4]^+$.

Example 215

(3aα,4β,7β,7aα)-4-Ethylhexahydro-7-methyl-2-(4-nitro-1-naphthalenyl)-4,7-epoxy-1H-isoindole-1,3(2H)-dione (215B)



A. (3aα,4β,7β,7aα)-4-Ethylhexahydro-7-methyl-4,7-epoxyisobenzofuran-1,3-dione (215A)



2-Ethyl-5-methylfuran (1.89 mL, 15.3 mmol) was dissolved in methylene chloride (10 mL) and maleic anhydride (1.00 g, 10.2 mmol) was added. The reaction was stirred at 25°C for 18 h and then concentrated *in vacuo*. The resulting crude bicycle was dissolved in EtOAc (50 mL) and 10% Pd/C (0.40 g) was added. Hydrogen was then introduced via a balloon. After 4h, the reaction was filtered through celite, rinsing with EtOAc. Concentration

in vacuo gave the crude compound **215A** (1.93 g) as a white solid. This material was taken on directly to the next reaction without purification.


B. (3aα,4β,7β,7aα)-4-Ethylhexahydro-7-methyl-2-(4-nitro-1-naphthalenyl)-4,7-epoxy-1H-Isoindole-1,3(2H)-dione (215B)

Compound **215A** (0.168 g, 0.798 mmol) and 4-nitro-1-naphthalamine (0.10 g, 0.53 mmol) were suspended in toluene (0.8 mL) and TEA (0.2 mL) and magnesim sulfate (0.1 g) were added. The mixture was heated at 135°C in a sealed tube for 18 h. The reaction was then cooled to rt and filtered, rinsing with chloroform. Concentration gave the crude product which was purified by preparative TLC on SiO_2 eluting with methylene chloride. This gave compound **215B** (0.077 g) as a yellow solid. HPLC: 100% at 3.260 min (retention time) (YMC S5 ODS column 4.6 x 50 mm eluting with 10-90% aqueous methanol over 4 minutes containing 0.2% phosphoric acid, 4 mL/min, monitoring at 220 nm), MS (ES): m/z 381.05 $[M+H]^+$.


188

Example 216

(3aα,4β,7β,7aα)-2-(4-Cyano-1-naphthalenyl)-N-(4-fluorophenyl)octahydro-7-methyl-1,3-dioxo-4,7-epoxy-4H-isoindole-4-acetamide (216B)



A. N-(4-Fluorophenyl)-5-methyl-2-furanacetamide (216A)




5-Methyl-2-furanacetic acid (1.00 g, 7.14 mmol, synthesized as described WO 9507893, Example 19) was dissolved in CH_3CN/DMF (4:1, 25 mL), 1-[3-(dimethylamino)propyl]-3-ethylcarbodiimide (1.37 g, 7.14 mmol) and 1-hydroxy-7-azabenzotriazole (0.972 g, 7.14 mmol) were then added followed by 4-fluoroaniline (0.676 mL, 7.14 mmol). After 3 h, the reaction was diluted with EtOAc (150 mL) and washed with 1 N HCl (1 x 30 mL), sat. aq $NaHCO_3$ (1 x 30 mL), brine (1 x 40 mL) and dried over sodium sulfate. Compound **216A** (1.581 g) was isolated as a yellow foam after concentration *in vacuo*. No further purification was necessary. HPLC: 78% at 2.647 min (retention time) (YMC S5 ODS column 4.6 x 50 mm eluting with 10-90% aqueous methanol over 4 minutes containing 0.2% phosphoric acid, 4 mL/min, monitoring at 220 nm).

B. 3aα,4β,7β,7aα)-2-(4-Cyano-1-naphthalenyl)-N-(4-fluorophenyl)octahydro-7-methyl-1,3-dioxo-4,7-epoxy-4H-Isoindole-4-acetamide (216B)

Compound **216A** (0.200 g, 0.858 mmol) and 4-(2,5-dihydro-2,5-dioxo-1H-pyrrol-1-yl)-2-trifluoromethylbenzonitrile (0.164 g, 0.66 mmol) were dissolved in benzene and heated at 60°C for 14 h. The reaction was then cooled and concentrated *in vacuo*. The resulting orange oil was dissolved in EtOAc (15 mL) and 10% Pd/C (0.050 g) was added. Hydrogen was then introduced via a balloon. After 3 h, the reaction was filtered through celite rinsing with EtOAc and concentrated *in vacuo*. The resulting crude material was purified by preparative TLC on silica eluting with 5% acetone in methylene chloride to give 0.166 g of compound **216B** as a white solid. NMR spectroscopy showed only a single isomer which was determined to be exo by NOE experiments. HPLC: 95% at 3.200 min (retention time) (YMC S5 ODS column 4.6 x 50 mm eluting with 10-90% aqueous methanol over 4 minutes containing 0.2% phosphoric acid, 4 mL/min, monitoring at 220 nm), MS (ES): m/z 484.0 $[M+H]^+$.

Example 217

(3aα,4β,7β,7aα)-Hexahydro-4-methyl-2-(2-naphthalenyl)-4,7-epoxy-1H-isoindole-1,3(2H)-dione, faster eluting enantiomer & (3aα,4β,7β,7aα)-Hexahydro-4-methyl-2-(2-naphthalenyl)-4,7-epoxy-1H-isoindole-1,3(2H)-dione, slower eluting enantiomer (217I & 217II, respectively)




The racemic compound **137** was separated into the individual antipodes by chiral reverse phase liquid chromatography. A Chiralpak AD-R column (4.6 x 250 mm) was used eluting with 70% acetonitrile/30% water at 1 mL/min. UV detection at 220 nm was used. The faster eluting isomer, compound **217I** (retention time = 15.66 min), was found to be 99.9% ee and

190


the slower eluting isomer, compound **217li** (retention time = 15.66 min) was 99.6% ee by analytical chiral reverse phase chromatography.

Example 218

(3aα,4β,7β,7aα)-4-[4-[2-[[(4-Fluorophenyl)methyl]methylamino]ethyl]octahydro-7-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-2-(trifluoromethyl)benzonitrile (218B)



A. (4-Fluorobenzyl)methylamine & Bis(4-fluorobenzyl)methylamine (218A & 218A')



218A **218A'**

Compounds **218A** & **218A'** were made in accordance with the procedure described in Singer, *et. al., J. Med. Chem.* **29**; 40-44 (1986). 4-Fluorobenzyl bromide (189 mg, 1.00 mmol) was refluxed in a solution of ethanol (1.5 mL) and methylamine (5 mL, 2 M solution in MeOH) for 3 h. An additional portion of methylamine (2 mL) was added and the mixture was refluxed for an additional hour. The solution was cooled and concentrated *in vacuo*, and the residue was dissolved in a mixture of 2N HCl (3 mL) and ether (1.5 mL). The layers were separated and the aqueous layer was extracted with an additional portion of ether. The aqueous solution was chilled to 0°C, titrated to pH 11 with NaOH and extracted with CH_2Cl_2. The extracts were dried over $MgSO_4$ and concentrated to give 120 mg of a 2.5:1 mixture of compounds **218A** and compound **218A'** respectively. The crude mixture was taken on without further purification.


191

B. (3aα,4β,7β,7aα)-4-[4-[2-[[(4-Fluorophenyl)methyl]-methylamino]ethyl]octahydro-7-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-2-(trifluoromethyl)benzonitrile (218B)


A solution of compound **36** (34.3 mg, 0.075 mmol) and compounds **218A & 218A'** (21 mg, ~0.088 mmol (of **218A**)) in toluene (0.4 mL) was heated at 100°C overnight. The reaction mixture was cooled to room temperature and then concentrated under reduced pressure. Purification by flash chromatography on silica gel eluting with 25% acetone/75% CH_2Cl_2 gave 30 mg (0.058 mmol, 77.7%) of **218B** as a yellow solid. HPLC: 99% at 2.46min (retention time) (YMC S5 ODS 4.6 x 50 mm, 10-90% aqueous methanol over 4 minutes containing 0.2% phosphoric acid, monitoring at 220 nm), MS (ES): m/z 516.26 $[M+H]^+$.

Example 219

(3aα,4β,5β,6β,7β,7aα)-4-(Octahydro-4,5,6,7-tetramethyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl)-2-(trifluoromethyl)benzonitrile (219D)



A. 2,3,4,5-Tetramethylfuran (219A)




Compound **219A** was made in accordance with the procedures described in Hancock *et. al., J. Org. Chem.* **42**,1850-1856 (1977) & Amarnath, *et. al., J. Org. Chem.*, **60**, 301-307 (1995). 2-Propanone (100 mL, 1.1 mol) was refluxed over PbO_2 (26.7 g, 0.11 mol) for 28 h. After cooling to rt, the reaction mixture was filtered and the residue was washed with acetone.

192

The filtrate was concentrated under reduced pressure to remove the acetone and then distilled at 20 Torr. The fraction that came over between 100-120°C was collected to give 6.75 g (42.5%) of 3,4-dimethylhexane-2,5-dione as a light yellow oil.


A solution of 3,4-dimethylhexane-2,5-dione (3.00 g, 21.1 mmol) and *p*-toluenesulfonic acid (401 mg, 2.11 mmol) in benzene (30 mL) was heated to reflux in a Dean-Stark trap overnight. The reaction mixture was distilled at atmospheric pressure to remove the excess benzene. The remaining mixture was transferred to a smaller flask and distilled at atmospheric pressure. The fraction that came over between 80-100°C was collected to give 509 mg (19%) of compound **219A** as a light yellow oil.

B. (3aα,4β,7β,7aα)-4-Ethyl-3a,4,7,7a-tetrahydro-4,5,6,7-tetramethyl-4,7-epoxyisobenzofuran-1,3-dione (219B)



A solution of compound **219A** (400 mg, 3.22 mmol) and maleic anhydride (442 mg, 4.51 mmol) in Et_2O (1.5 mL) was stirred at rt overnight. The reaction mixture was then placed in freezer for 5 days, after which time the resulting crystals were collected and dried to give 0.26 g (37%) of compound **219B** as tan crystals. The crude compound **219B** was taken on to the next step with out further purification.

C. (3aα,4β,5α,6α,7β,7aα)-4-Ethylhexahydro-4,5,6,7-tetramethyl-4,7-epoxyisobenzofuran-1,3-dione (219C)



193

A solution of compound **219B** (120 mg, 0.545 mmol) and 10% Pd/C (24 mg, cat.) in EtOAc (2 mL) was stirred under a balloon of hydrogen at room temperature overnight. The reaction mixture was filtered through celite and concentrated under reduced pressure to give 100 mg (0.446 mmol, 81.9%) of compound **219C** as a white solid, which was carried on with no further purification.


D. (3aα,4β,5β,6β,7β,7aα)-4-(Octahydro-4,5,6,7-tetramethyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl)-2-(trifluoromethyl)benzonitrile (219D)

A solution of compound **219C** (44.4 mg, 0.2 mmol), 5-amino-2-cyanobenzotrifluoride (45 mg, 0.24 mmol), TEA (0.04 mL) and $MgSO_4$ (20 mg) in toluene (0.2 mL) was heated at 135°C overnight. The reaction mixture was cooled to room temperature, filtered and then concentrated under reduced pressure. Purification by flash chromatography on silica gel eluting with 40% EtOAc/hexanes followed by washing the resulting solid with MeOH gave 17 mg (0.043 mmol, 21.7%) of compound **219D** as a white solid. HPLC: 90% at 3.11 min (retention time) (YMC S5 ODS 4.6 x 50 mm, 10-90% aqueous methanol over 4 minutes containing 0.2% phosphoric acid, monitoring at 220 nm), MS (ES): m/z 391.2 $[M-H]^-$.

194

Example 220

(3aα,4β,7β,7aα)-4-[Octahydro-4-methyl-1,3-dioxo-7-[2-[4-(trifluoromethyl)phenoxy]ethyl]-4,7-epoxy-2H-isoindol-2-yl]-2-(trifluoromethyl)benzonitrile, faster eluting antipode & (3aα,4β,7β,7aα)-4-[Octahydro-4-methyl-1,3-dioxo-7-[2-[4-(trifluoromethyl)phenoxy]ethyl]-4,7-epoxy-2H-isoindol-2-yl]-2-(trifluoromethyl)benzonitrile, slower eluting enantiomer (220I & 220II, respectively)




The racemic compound **35** was separated into the individual antipodes by chiral normal phase liquid chromatography. A Chiralpak AD column (50 x 500 mm) was used eluting with 85% hexanes/7.5% methanol/7.5% ethanol, @ 50mL/min. UV detection at 220 nm was used. The faster eluting isomer compound **220I** (retention time = 55.86 min) was found to have 95.8% ee ($[\alpha]_D^{25}$ = -53.02°, C = 3.134 mg/cc in CH_2Cl_2) and the slower eluting isomer compound **220II** (retention time = 62.86 min) was 86% ee ($[\alpha]_D^{25}$ = +48.74°, C = 2.242 mg/cc in CH_2Cl_2) by analytical chiral normal phase chromatography.


195

Example 221

(3aα,4β,5β,7β,7aα)-4-(Octahydro-5-hydroxy-4,7-dimethyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl)-2-(trifluoromethyl)benzonitrile (221B)



A. (3aα,4β,7β,7aα)-4-(hexahydro-4,7-dimethyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl)-2-(trifluoromethyl)benzonitrile (221AI) & (3aα,4α,7α,7aα)-4-(hexahydro-4,7-dimethyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl)-2-(trifluoromethyl)benzonitrile (221AII)




A solution of 2,5-dimethylfuran (0.8 mL, 7.51 mmol) and 4-(2,5-dihydro-2,5-dioxo-1H-pyrrol-1-yl)-2-trifluoromethylbenzonitrile (synthesized as described in Example 1B) (1.00 g, 3.75 mmol) in benzene (4 mL) was heated at 60°C overnight. The reaction mixture was concentrated under reduced pressure and placed on a high vacuum pump until the oil solidified to give a 3:1 mixture (determined by LC and NMR) of compounds **221AI** & **221AII**, respectively, as a brown solid, which was used directly in the next step with out further purification.

B. (3aα,4β,5β,7β,7aα)-4-(Octahydro-5-hydroxy-4,7-dimethyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl)-2-(trifluoromethyl)benzonitrile (221B)


BH_3•THF (3.75 mL, 3.75 mmol, 1M in THF) was added to a solution of crude compounds **221Ai & 221Aii** (3.75 mmol) in THF (12.5 mL) at 0°C. After the starting material was consumed the reaction mixture was concentrated under reduced pressure. The resulting residue was then dissolved in toluene (12.5 mL), Me_3NO (845 mg, 11.25 mmol) was added and the mixture was heated to reflux overnight. The reaction mixture was then cooled to rt, added to H_2O and extracted with EtOAc (3X). The combined organic layers were dried over $MgSO_4$ and concentrated under reduced pressure. Purification by flash chromatography on SiO_2 eluting with 75% EtOAc/hexanes gave 0.354 g (25%) of compound **221B** as a tan powder. HPLC: 90% at 2.45 min (retention time) (YMC S5 ODS column 4.6 x 50 mm eluting with 10-90% aqueous methanol over 4 minutes containing 0.2% phosphoric acid, 4 mL/min, monitoring at 220 nm), MS (ES): m/z 381.11 $[M+H]^+$.

Example 222

(3aα,4β,5α,7β,7aα)-4-(Octahydro-5-hydroxy-4,7-dimethyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl)-2-(trifluoromethyl)benzonitrile (222D)




A. 3-[[(1,1-Dimethylethyl)dimethylsilyl]oxy]-2,5-dimethylfuran (222A)



2,5-Dimethyl-3(3H)-furanone (2.00 g, 17.8 mmol) was dissolved in methylene chloride (180 mL). TEA (7.43 mL, 53.5 mmol) was added followed by TBSOTf (4.92 mL, 21.4 mmol) at 25°C. After 1 h, the reaction was concentrated *in vacuo* and the resulting slurry was run through a silica gel column conditioned with 3% TEA in hexanes. The product was eluted with


3% TEA/hexanes to give 3.6 g of compound **222A** as an orange oil which was used directly in subsequent reactions.

B. (3aα,4β,7β,7aα)-4-[5-[[(1,1-Dimethylethyl)dimethylsilyl]oxy]-1,3,3a,4,7,7a-hexahydro-4,7-dimethyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-2-(trifluoromethyl)benzonitrile (222B)



4-(2,5-Dihydro-2,5-dioxo-1H-pyrrol-1-yl)-2-trifluoromethylbenzonitrile (1.00 g, 3.85 mmol) was dissolved in benzene (5.0 mL) and the compound **222A** (1.30 g, 5.77 mmol) was added. The reaction mixture was warmed to 60°C for 2 h and then cooled to 25°C. The solution was then concentrated *in vacuo* to give compound **222B** as a yellow oil which was carried on to the next reaction without purification. HPLC: 60% at 4.013 min (retention time) (YMC S5 ODS column 4.6 x 50 mm eluting with 10-90% aqueous methanol over 4 minutes containing 0.2% phosphoric acid, 4 mL/min, monitoring at 220 nm).

C. (3aα,4β,5α,7β,7aα)-4-[5-[[(1,1-Dimethylethyl)dimethylsilyl]oxy]octahydro-4,7-dimethyl-1,3-diox - 4,7-epoxy-2H-isoindol-2-yl]-2-(trifluoromethyl)benzonitrile (222C)



198

Crude compound **222B** (3.85 mmol) was dissolved in ethyl acetate (75 mL) and 10% Pd/C (1.20 g) was added. Hydrogen was then introduced via a balloon. After 24 h, the reaction was filtered through celite rinsing with ethyl acetate and concentrated *in vacuo* to give a yellow oil. The crude product was purified by flash chromatography on silica gel eluting with methylene chloride/acetone (0% - 1% - 2% acetone) to give compound **222C** as a yellow solid (0.710 g). HPLC: 100% at 4.160 min (retention time) (YMC S5 ODS column 4.6 x 50 mm eluting with 10-90% aqueous methanol over 4 minutes containing 0.2% phosphoric acid, 4 mL/min, monitoring at 220 nm), MS (ES): m/z 517.6 $[M+Na]^+$.


D. (3aα,4β,5α,7β,7aα)-4-(Octahydro-5-hydroxy-4,7-dimethyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl)-2-(trifluoromethyl)benzonitrile (222D)

Compound **222C** (0.040 g, 0.081 mmol) was dissolved in THF (1.0 mL) and HF• Pyridine (0.5 mL) was added. After 2 h, the reaction was carefully poured into cold saturated aq $NaHCO_3$. The mixture was then extracted with methylene chloride (3 x 10 mL). The combined organics were washed with 1 N HCl (1 x 10 mL) and dried over anhydrous sodium sulfate. Concentration *in vacuo* gave compound **222D** as a yellow solid (0.031 g). NOE experiments confirmed the assigned isomer. HPLC: 98% at 2.777 min (retention time) (YMC S5 ODS column 4.6 x 50 mm eluting with 10-90% aqueous methanol over 4 minutes containing 0.2% phosphoric acid, 4 mL/min, monitoring at 220 nm), MS (ES): m/z 403.06 $[M+Na]^+$.


Example 223

(αR)-α-Methoxybenzeneacetic acid, 2-[(3aα,4β,7β,7aα)-2-(4-cyano-1-naphthalenyl)octahydro-7-methyl-1,3-dioxo-4,7-epoxy-4H-isoindol-4-yl]ethyl ester (223C)

199



A. (3aα,4β,7β,7aα)-4-[4-[2-[[(1,1-Dimethylethyl)dimethylsilyl]oxy]ethyl]octahydro-7-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile (223A)




A solution of 4-amino-1-naphthalenecarbonitrile (19.2 g, 114 mmol) and maleic anhydride (14.0 g, 113 mmol) in AcOH (230 mL) was heated at 115 °C for 12 h. After cooling to rt, the reaction mixture was concentrated under reduced pressure then diluted with CH_2Cl_2 (2.5 L). The organic layer was washed 3X with H_2O (3 L), 1X with sat. aq Na_2CO_3 (1 L) and 1X with brine (1 L), dried over $MgSO_4$ and concentrated to ~200 mL under reduced pressure. Purification by flash chromatography on cation exchange resin (60 g, CUBX13M6 from United Chemical Technologies) eluting with CH_2Cl_2 gave 25.0 g (88%) of 4-(2,5-Dihydro-2,5-dioxo-1H-1-yl)-1-naphthalenecarbonitrile as a yellow solid. HPLC 96% at 2.48 min (Phenomenex-prime S5-C18 column 4.6 x 50 mm, 10-90% aqueous methanol over 4 minutes containing 0.2% phosphoric acid, 4 mL/min, monitoring at 220 nm), MS (ES): m/z 249.25 $[M+H]^+$.

4-(2,5-Dihydro-2,5-dioxo-1H-1-yl)-1-naphthalenecarbonitrile (1.00 g, 4.03 mmol) was suspended in benzene (6.0 mL) in a sealed tube and compound **204A** (1.11 g, 5.24 mmol) was added. The reaction was heated at

60°C for 16 h and then cooled to 25°C. The benzene was removed in vacuo to give a yellow solid. The solid was dissolved in ethyl acetate (40 mL) and Pd/C (10% Pd, 0.300 g) was added. Hydrogen was then introduced via a balloon. After 4 h, the reaction was filtered through celite rinsing with ethyl acetate. Concentration *in vacuo* gave a pale yellow solid which was purified by flash chromatography on silica gel eluting with acetone/chloroform (0% - 1.5% - 3% acetone) to give compound **223A** (1.53 g) as a yellow foam. HPLC: 86% at 4.173 min (retention time) (YMC S5 ODS column 4.6 x 50 mm eluting with 10-90% aqueous methanol over 4 minutes containing 0.2% phosphoric acid, 4 mL/min, monitoring at 220 nm).

B. (3aα,4β,7β,7aα)-4-[Octahydro-4-(2-hydroxyethyl)-7-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile (223B)



Compound **223A** (1.37 g, 2.97 mmol) was dissolved in THF (8.0 mL) and transferred to a polypropylene bottle and cooled to 0°C. HF•Pyridine (2.0 mL) was then added. After 20 min, the reaction was carefully poured into cold sat. aq sodium bicarbonate and extracted with methylene chloride (3 x 30 mL). The organics were then washed with 1 N HCl and dried over anhydrous sodium sulfate. Concentration *in vacuo* gave the compound **223B** (0.99 g) as a yellow foam which was not purified further. HPLC: 96% at 2.443 and 2.597 (atropisomers) min (retention time) (YMC S5 ODS column 4.6 x 50 mm eluting with 10-90% aqueous methanol over 4 minutes containing 0.2% phosphoric acid, 4 mL/min, monitoring at 220 nm), MS (ES): m/z 399.02 $[M+Na]^+$.


201

C. (αR)-α-Methoxybenzeneacetic acid, 2-[(3aα,4β,7β,7aα)-2-(4-cyano-1-naphthalenyl)octahydro-7-methyl-1,3-dioxo-4,7-epoxy-4H-isoindol-4-y]ethyl ester (223C)

Compound **223B** (0.200 g, 0.575 mmol) was added to a solution of WSDCC (0.138 g, 0.719 mmol) and (R)-mandelic acid (0.096 g, 0.575 mmol) in dichloromethane (6.0 mL). 4-DMAP (0.005 g) was then added and the reaction stirred at 25°C for 4 h. The mixture was then diluted with dichloromethane and washed with 1 N HCl (2 x 10 mL), once with sodium bicarbonate (10 mL) and dried over anhydrous sodium sulfate. Concentration *in vacuo* gave compound **223C** (0.220 g) as a yellow solid which was not purified further. HPLC: 100% at 3.283 min (retention time) (YMC S5 ODS column 4.6 x 50 mm eluting with 10-90% aqueous methanol over 4 minutes containing 0.2% phosphoric acid, 4 mL/min, monitoring at 220 nm), MS (ES): m/z 547.26 $[M+Na]^+$.

Example 224

(3aα,4β,7β,7aα)-2-(Methylthio)-4-(octahydro-4,7-dimethyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl)benzonitrile (224)




4-Amino-2-(methylthio)benzonitrile (100 mg, 0.61 mmol, synthesized as described in EP 40931 A1) was reacted in a sealed tube with compound **20A** (131 mg, 0.67 mmol), $MgSO_4$ (161 mg, 1.34 mmol) and Et_3N (0.44 mL, 3.17 mmol) in 0.50 mL toluene according to the procedure described in Example **208C** to give, after purification by preparative reverse phase HPLC

202

(YMC S5 ODS 20 x 100 mm eluting with 30-100% aqueous methanol over 10 min containing 0.1% TFA, 20 mL/min), 137 mg (0.40 mmol, 66%) of compound **224** as a white solid. HPLC: 100% at 2.73 min (retention time) (YMC S5 ODS column 4.6 x 50 mm eluting with 10-90% aqueous methanol over 4 minutes containing 0.2% phosphoric acid, 4 mL/min, monitoring at 220 nm), MS (ES): m/z 401.0 $[M-H+OAc]^-$.

Example 225

(3aα,4β,7β,7aα)-2-(Methylsulfinyl)-4-(octahydro-4,7-dimethyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl)benzonitrile (225)




To an ice-cold suspension of compound **224** (30 mg, 0.09 mmol) in 2 mL of H_2O/MeOH (1:1) was added oxone (80 mg, 0.26 mmol) in one solid portion. The resulting mixture was stirred for 4 h at 0°C before it was diluted with H_2O (10 mL) and extracted with CH_2Cl_2 (2 x 20 mL). The combined organic layers were dried and concentrated to leave a residue which was purified by filtering the material through a short pad of silica gel eluting with CH_2Cl_2 to yield 32 mg (0.09 mmol, 100%) of compound **225** as a colorless oil. HPLC: 99% at 2.01 min (retention time) (YMC S5 ODS column 4.6 x 50 mm eluting with 10-90% aqueous methanol over 4 minutes containing 0.2% phosphoric acid, 4 mL/min, monitoring at 220 nm), MS (ES): m/z 376.0 $[M+NH_4]^+$.

203

Example 226


(3aα,4β,7β,7aα)-2-(Methylsulfonyl)-4-(octahydro-4,7-dimethyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl)benzonitrile (226)




To a solution of compound **225** (48 mg, 0.14 mmol) in CH_2Cl_2 (2 mL) was added *m*CPBA (145 mg, 50% mixture, 0.42 mmol) in one solid portion. The resulting mixture was allowed to warm to room temperature and was stirred for 60 h at which time no more starting material could be detected by HPLC. The reaction was quenched by the addition of sat. $NaHCO_3$ solution (5 mL), the layers were separated and the aqueous layer was extracted with CH_2Cl_2 (20 mL). The combined organic phases were dried over $MgSO_4$ and concentrated. The remaining residue was purified by preparative reverse phase HPLC (YMC S5 ODS 20 x 100 mm eluting with 30-100% aqueous methanol over 10 min containing 0.1% TFA, 20 mL/min) to afford 48 mg (0.13 mmol, 92%) of compound **226** as a white solid. HPLC: 100% at 2.07 min (retention time) (YMC S5 ODS column 4.6 x 50 mm eluting with 10-90% aqueous methanol over 4 minutes containing 0.2% phosphoric acid, 4 mL/min, monitoring at 220 nm), MS (ES): m/z 392.0 $[M+NH_4]^+$.

Example 227

(3aα,4β,5β,7β,7aα)-7-[2-[[(1,1-Dimethylethyl)dimethylsilyl]oxy]ethyl]hexahydro-5-hydroxy-4-methyl-2-(4-nitro-1-naphthalenyl)-4,7-epoxy-1H-isoindole-1,3(2H)-dione (227B)



A. (3aα,4β,7β,7aα)-4-[2-[[(1,1-Dimethylethyl)dimethylsilyl]oxy]ethyl]-3a,4,7,7a-tetrahydro-7-methyl-2-(4-nitro-1-naphthalenyl)-4,7-epoxy-1H-isoindole-1,3(2H)-dione (227A)



A solution of compound **204A** (455 mg, 1.894 mmol, 2 eq) and 1-[4-nitronaphthalene]-1H-pyrrole-2,5-dione (254 mg, 0.947 mmol, 1 eq) (prepared as described for 4-(2,5-dihydro-2,5-dioxo-1H-1-yl)-1-naphthalenecarbonitrile, Example 223A) in benzene (2 mL) was heated at 60 °C overnight. The reaction mixture was concentrated under reduced pressure to give crude compound **227A** as a brown solid, which was used directly in the next step with out further purification.


B. (3aα,4β,5β,7β,7aα)-7-[2-[[(1,1-Dimethylethyl)dimethylsilyl]oxy]ethyl]hexahydro-5-hydroxy-4-methyl-2-(4-nitro-1-naphthalenyl)-4,7-epoxy-1H-isoindole-1,3(2H)-dione (227B)

BH_3•THF (0.95 mL, 0.95 mmol, 1M in THF, 1 eq) was added to a solution of crude compound **227A** (0.95 mmol, 1 eq) in THF (2 mL) at 0 °C. After compound **227A** was consumed, as was evident by HPLC, the reaction mixture was concentrated under reduced pressure. The resulting residue was then dissolved in toluene (2 mL), Me_3NO (71 mg, 2.84 mmol, 3 eq) was added and the mixture was heated to reflux over night. The reaction mixture

was then cooled to rt, added to H_2O and extracted with EtOAc (3X). The combined organic layers were dried over $MgSO_4$ and concentrated under reduced pressure. Purification by flash chromatography on SiO_2 eluting with a mixture of 75% EtOAc/Hexanes, gave 130.2 mg (26%) of compound **227B** as a brown solid. HPLC: 94% at 3.92 min (retention time) (YMC S5 ODS column 4.6 x 50 mm eluting with 10-90% aqueous methanol over 4 minutes containing 0.2% phosphoric acid, 4 mL/min, monitoring at 220 nm), MS (ES): m/z 527.5 $[M+H]^+$.

Example 228

(3aα,4β,5β,7β,7aα)-Hexahydro-5-hydroxy-7-(2-hydroxyethyl)-4-methyl-2-(4-nitro-1-naphthalenyl)-4,7-epoxy-1H-isoindole-1,3(2H)-dione (228)




A mixture of TBAF (0.3 mL, 0.296 mmol, 1 M solution in THF) and HF (0.3 mL, 50% in H_2O) in CH_3CN (6 mL) was added to a solution of **227B** (104 mg, 0.197 mmol) in THF (2 mL) at 0°C. The reaction mixture was stirred overnight at rt. After the starting material was consumed, as was evident by TLC, H_2O and EtOAc were added and the layers were separated. The aqueous layer was extracted with EtOAc (1X) and the combined organic layers were washed with H_2O (1X) and brine (1X), dried over Na_2SO_4 and concentrated under reduced pressure. Purification by flash chromatography on SiO_2 eluting with 5% MeOH/CH_2Cl_2 gave 61.2 mg (75%) of compound **228** as a yellow solid. HPLC: 99% at 2.47 min (retention time) (YMC S5 ODS column 4.6 x 50 mm eluting with 10-90% aqueous methanol over 4 minutes containing 0.2% phosphoric acid, 4 mL/min, monitoring at 220 nm), MS (ES): m/z 411.2 $[M-H]^-$.

206

Example 229


(3aα,4β,5β,7β,7aα)-7-[2-(4-Fluorophenoxy)ethyl]hexahydro-5-hydroxy-4-methyl-2-(4-nitro-1-naphthalenyl)-4,7-epoxy-1H-Isoindole-1,3(2H)-di ne (229)




DBAD (37.7 mg, 0.164 mmol) was added to a solution of PPh_3 (43 mg, 0.164 mmol) in THF (1 mL). After stirring for 10 mins, 4-fluorophenol (18.3 mg, 0.164 mmol) was added and the reaction mixture was stirred for a further 5 min. A solution of compound **228** (45 mg, 0.109 mmol) in THF (1 mL) was added and the mixture was stirred at rt overnight. HPLC showed the crude reaction mixture to contain mostly starting diol (compound **228**), so this mixture was added to a preformed mixture as before of PPh_3 (86 mg), DBAD (75.4 mg) and phenol (36.6 mg) in THF (4 mL) at rt. Stirring was continued until all of compound **228** was consumed. The reaction was then concentrated under reduced pressure. Purification by preparative chromatography [HPLC at 15.2 min (retention time) (YMC S5 ODS A column 20 x 100 mm, 10-90% aqueous methanol over 15 minutes containing 0.1% TFA, 20 mL/min, monitoring at 220 nm)] gave 25.0 mg (45%) of compound **229** as a light yellow solid. HPLC: 99% at 3.53 min (retention time) (YMC S5 ODS column 4.6 x 50 mm eluting with 10-90% aqueous methanol over 4 minutes containing 0.2% phosphoric acid, 4 mL/min, monitoring at 220 nm), MS (ES): m/z 505.2 $[M-H]^-$.


Example 230

(3aα,4β,5β,6β,7β,7aα)-4-(Octahydro-5,6-dihydroxy-4,7-dimethyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl)-2-(trifluoromethyl)benzonitrile & (3aα,4β,5α,6α,7β,7aα)-4-(Octahydro-5,6-dihydroxy-4,7-dimethyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl)-2-(trifluoromethyl)benzonitrile (230BI & 230BII, Respectively)





A. (3aα,4β,7β,7aα)-4-(1,3,3a,4,7,7a-Hexahydro-4,7-dimethyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl)-2-(trifluoromethyl)benzonitrile (230A)



3,5-dimethyl furan (1.23 mL, 11.54 mmol) and 4-(2,5-Dihydro-2,5-dioxo-1H-pyrrol-1-yl)-2-trifluoromethylbenzonitrile (2.00 g, 7.69 mmol) were dissolved in benzene (10 mL) and heated at 60°C for 18 h. The volatile organics were then removed *in vacuo*. The resulting crude compound **230A** was carried on without purification. HPLC: 71% at 3.007 min (retention time) (YMC S5 ODS column 4.6 x 50 mm eluting with 10-90% aqueous methanol over 4 minutes containing 0.2% phosphoric acid, 4 mL/min, monitoring at 220 nm).


B. (3aα,4β,5β,6β,7β,7aα)-4-(Octahydro-5,6-dihydroxy-4,7-dimethyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl)-2-(trifluoromethyl)benzonitrile & (3aα,4β,5α,6α,7β,7aα)-4-

(ctahydro-5,6-dihydroxy-4,7-dimethyl-1,3-dioxo-4,7-epoxy-2H-isoind l-2-yl)-2-(trifluoromethyl)benzonitrile (230BI & 230BII)

Compound **230A** (0.100 g, 0.281 mmol) was dissolved in acetone and *N*-methylmorpholine-*N*-oxide (50% aq solution, 0.100 mL, 0.42 mmol) was added. OsO_4 (4% aq solution, 0.014 mmol) was then added. After 3 h at 25°C, the reaction was complete and sodium sulfite (0.250 g) was added with vigorous stirring. After 15 min, brine (10 mL) was added and the solution was extracted with EtOAc (3 x 15 mL). The organics were dried over anhydrous sodium sulfate and then concentrated *in vacuo*. The crude diol mixture was purified by preparative TLC eluting with 18% acetone in chloroform to give 0.038 g of compound **230BI** (beta face) and 0.012 g of compound **230BII** (alpha face) as pale yellow solids. Compound **230BI**: HPLC: 100% at 2.567 min (retention time) (YMC S5 ODS column 4.6 x 50 mm eluting with 10-90% aqueous methanol over 4 minutes containing 0.2% phosphoric acid, 4 mL/min, monitoring at 220 nm), MS (ES): m/z 397.08 $[M+H]^+$. Compound **230BII**: HPLC: 100% at 2.417 min (retention time) (YMC S5 ODS column 4.6 x 50 mm eluting with 10-90% aqueous methanol over 4 minutes containing 0.2% phosphoric acid, 4 mL/min, monitoring at 220 nm), MS (ES): m/z 397.08 $[M+H]^+$.


Example 231

(3aα,4β,5β,6β,7β,7aα)-4-[Octahydro-5,6-dihydroxy-4-(hydroxyethyl)-7-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile, (231C)




209

A. (3aα,4β,7β,7aα)-4-[4-[2-[[(1,1-Dimethylethyl)dimethylsilyl]oxy]ethyl]-1,3,3a,4,7,7a-hexahydro-7-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile (231A)



Compound **204A** (29.03 g, 120 mmol) and 4-(2,5-dihydro-2,5-dioxo-1H-1-yl)-1-naphthalenecarbonitrile (20.0 g, 80.6 mmol) were suspended in benzene (80 mL) and heated to 60°C for 14 h. The mixture was then concentrated *in vacuo* at 40°C for 40 min. The resulting slurry was cooled to 25°C and then suspended in MeOH (200 mL) and stirred at rt for 30 min. The solution was then cooled to 0°C for 30 min and then filtered rinsing with cold MeOH. The resulting solid was dried *in vacuo* to give 26.1 g of crude compound **231A** as a white solid. The methanol solution was concentrated *in vacuo* and resuspended in MeOH (50 mL) and cooled to –20°C for 4 h. The solution was then filtered rinsing with cold MeOH. The resulting solid was dried *in vacuo* to give 3.8 g of compound **231A** as a white solid. HPLC: 95% at 4.227 min (retention time) (YMC S5 ODS column 4.6 x 50 mm eluting with 10-90% aqueous methanol over 4 minutes containing 0.2% phosphoric acid, 4 mL/min, monitoring at 220 nm)

B. (3aα,4β,5β,6β,7β,7aα)-4-[4-[2-[[(1,1-Dimethylethyl)dimethylsilyl]oxy]ethyl]octahydro-5,6-dihydroxy-7-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile (231B)



Compound **231A** (0.400 g, 0.851 mmol) was dissolved in acetone (9.0 mL) and *N*-methylmorpholine-*N*-oxide (50% aq solution, 0.0.150 mL, 1.28 mmol) was added. OsO_4 (4% aq solution, 0.043 mmol) was then added. After 3 h at 25°C, the reaction was complete and sodium sulfite (1.0 g) was added with vigorous stirring. After 15 minutes, brine (30 mL) was added and the solution extracted with EtOAc (3 x 50 mL). The organics were dried over anhydrous sodium sulfate and then concentrated *in vacuo*. The crude diol was purified by flash chromatography on silica eluting with 5-25% acetone in chloroform to give 0.355 g of compound **231B** as a yellow solid. HPLC: 93% at 3.903 min (retention time) (YMC S5 ODS column 4.6 x 50 mm eluting with 10-90% aqueous methanol over 4 minutes containing 0.2% phosphoric acid, 4 mL/min, monitoring at 220 nm), MS (ES): m/z 522.00 $[M+H]^+$.


C. (3aα,4β,5β,6β,7β,7aα)-4-[Octahydro-5,6-dihydroxy-4-(hydroxyethyl)-7-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile (231C)

Compound **231B** (0.400 g, 0.766 mmol) was dissolved in THF (5.0 mL) and transferred to a polypropylene bottle and cooled to 0°C. HF• Pyridine (1.0 mL) was then added. After 20 min, the reaction was carefully poured into cold sat. aq sodium bicarbonate and extracted with methylene chloride (3 x 30 mL). The organics were then washed once with 1 N HCl and dried over anhydrous sodium sulfate. Concentration *in vacuo* gave the compound **231C** (0.290 g) as a yellow foam which was not purified further. HPLC: 92% at 2.273 and 2.423 (atropisomers) min (retention time) (YMC S5 ODS column 4.6 x 50 mm eluting with 10-90% aqueous methanol over 4 minutes containing 0.2% phosphoric acid, 4 mL/min, monitoring at 220 nm), MS (ES): m/z 409.10 $[M+H]^+$.


211

Example 232

(3aα,4β,5β,6β,7β,7aα)-4-[Octahydro-5,6-dihydroxy-4-methyl-1,3-dioxo-7-[2-[4-(trifluoromethyl)phenoxy]ethyl]-4,7-epoxy-2H-isoindol-2-yl]-2-(trifluoromethyl)benzonitrile, (232C)




A. 2-Methyl-5-[2-[4-(trifluoromethyl)phenoxy]ethyl]furan (232A)



To a solution of triphenylphosphine (1.56 g, 5.95 mmol) in THF (40 mL) was added DBAD (1.37 g, 5.95 mmol). After 10 min, 4-trifluoromethylphenol (0.964 g , 5.95 mmol) was added. After 10 additional minutes, compound **21A** (0.500 g, 3.97 mmol) was added. After 14 h at 25°C, the reaction was concentrated *in vacuo* and purified by flash chromatography on silica eluting with chloroform to give 0.713 g of compound **232A** as a clear oil.

B. (3aα,4β,7β,7aα)-4-[1,3,3a,4,7,7a-hexahydro-4-methyl-1,3-dioxo-7-[2-[4-(trifluoromethyl)phenoxy]ethyl]-4,7-epoxy-2H-isoindol-2-yl]-2-(trifluoromethyl)benzonitrile (232B)



Compound **232A** (0.301 g, 1.15 mmol) and 4-(2,5-dihydro-2,5-dioxo-1H-pyrrol-1-yl)-2-trifluoromethylbenzonitrile (0.220 g, 0.846 mmol) were

212

suspended in benzene (1.5 mL) and heated to 60°C for 14 h. The mixture was then concentrated *in vacuo* at 40°C for 40 minutes. The crude product was purified by flash chromatography on silica eluting with 10 – 0% hexanes in methylene chloride to give 0.199 g of compound **232B** as a yellow solid. Compound **232B** was characterized as the exo diastereomer by NOE experiments. HPLC: 94% at 3.993 min (retention time) (YMC S5 ODS column 4.6 x 50 mm eluting with 10-90% aqueous methanol over 4 minutes containing 0.2% phosphoric acid, 4 mL/min, monitoring at 220 nm).


C. (3aα,4β,5β,6β,7β,7aα)-4-[Octahydro-5,6-dihydroxy-4-methyl-1,3-dioxo-7-[2-[4-(trifluoromethyl)phenoxy]ethyl]-4,7-epoxy-2H-isoindol-2-yl]-2-(trifluoromethyl)benzonitrile, (232C)

Compound **232B** (0.075 g, 0.140 mmol) was dissolved in acetone (2.0 mL) and N-methylmorpholine-N-oxide (50% aq solution, 0.025 mL, 0.21 mmol) was added. OsO_4 (4% aq solution, 0.007 mmol) was then added. After 3 h at 25°C, the reaction was complete and sodium sulfite (0.25 g) was added with vigorous stirring. After 15 minutes, brine (5 mL) was added and the solution extracted with EtOAc (3 x 10 mL). The organics were dried over anhydrous sodium sulfate and then concentrated *in vacuo*. The crude diol was purified by preparative TLC on silica gel, eluting with 10% acetone in chloroform to give 0.038 g of compound **232C** as a yellow solid. HPLC: 98% at 3.747 min (retention time) (YMC S5 ODS column 4.6 x 50 mm eluting with 10-90% aqueous methanol over 4 minutes containing 0.2% phosphoric acid, 4 mL/min, monitoring at 220 nm), MS (ES): m/z 593.08 $[M+Na]^+$.

213

Example 233


(3aα,4β,5β,5aβ,8aβ,8bα)-4-(Decahydro-5-hydroxy-4-methyl-1,3-dioxo-4,8a-epoxy-2H-furo[3,2-e]isoindol-2-yl)-1-naphthalenecarbonitrile, (233)




To a solution of triphenylphosphine (0.072 g, 0.276 mmol) in THF (3.0 mL) was added DBAD (0.063 g, 0.276 mmol). After 10 min, 4-cyanophenol (0.033 g , 0.276 mmol) was added. After 10 additional minutes, compound **231C** (0.075 g, 0.184 mmol) was added. After 3 h at 25°C, the reaction was concentrated *in vacuo* and purified by preparative TLC on silica gel, eluting with 15% acetone in chloroform to give 0.068 g of compound **233** as a white solid. HPLC: 95% at 2.430 and 2.560 min (atropisomers) (retention time) (YMC S5 ODS column 4.6 x 50 mm, 10-90% aqueous methanol over 4 minutes containing 0.2% phosphoric acid, 4 mL/min, monitoring at 220 nm), MS (ES): m/z 391.09 $[M+H]^+$.

Example 234

(3aα,4β,7β,7aα)-2-(4-Cyano-1-naphthalenyl)octahydro-7-methyl-1,3-dioxo-4,7-epoxy-4H-isoindole-4-acetic acid, (234B)



A. (3aα,4β,7β,7aα)-2-(4-Cyano-1-naphthalenyl)-1,2,3,3a,7,7a-hexahydro-7-methyl-1,3-dioxo-4,7-epoxy-4H-isoindole-4-acetic acid (234A)



214


5-Methyl-2-furanacetic acid (0.500 g, 3.57 mmol) and 4-(2,5-dihydro-2,5-dioxo-1H-1-yl)-1-naphthalenecarbonitrile (0.899 g, 3.57 mmol) were dissolved in benzene (3.0 mL) and heated at 60°C for 2 h and then cooled to 25°C. After 12 h, a white solid precipitated out of solution and was filt red and rinsed with diethyl ether to yield 1.20 g of compound **234A** as a light yellow solid. NMR showed only one diastereomer. HPLC: 86% at 2.767 min (retention time) (YMC S5 ODS column 4.6 x 50 mm, 10-90% aqueous methanol over 4 minutes containing 0.2% phosphoric acid, 4 mL/min, monitoring at 220 nm), MS (ES): m/z 389.45 $[M+H]^+$.

B (3aα,4β,7β,7aα)-2-(4-Cyano-1-naphthalenyl)octahydro-7-methyl-1,3-dioxo-4,7-epoxy-4H-isoindole-4-acetic acid, (234B)

Compound **234A** (1.1 g, 2.82 mmol) was dissolved in EtOH/EtOAc (1:1, 50 mL) and Pd/C (10% Pd, 0.4 g) was added followed by H_2 via a balloon. After 5 h at 25°C, the reaction was filtered through celite rinsing with EtOAc and concentrated *in vacuo* to yield 1.00 g of compound **234B** as a yellow solid. HPLC: 80% at 2.84 min (retention time) (YMC S5 ODS column 4.6 x 50 mm, 10-90% aqueous methanol over 4 minutes containing 0.2% phosphoric acid, 4 mL/min, monitoring at 220 nm), MS (ES): m/z 391.1 $[M+H]^+$.

Example 235

(3aα,4β,7β,7aα)-2-(4-Cyano-1-naphthalenyl)octahydro-7-methyl-1,3-dioxo-4,7-epoxy-4H-isoindole-4-acetic acid, methyl ester, (235)




Compound **234B** (0.050 g, 0.125 mmol) was dissolved in acetonitrile (2.0 mL), then DCC (0.025 g, 0.125 mmol) was added followed by HOAc

215

(0.018 g, 0.125 mmol). 4-Fluorobenzyl alcohol (0.014 mL, 0.125 mmol) was added and the reaction was stirred for 3 h. The reaction was then concentrated in vacuo and purified by preparative reverse phase HPLC (YMC S5 ODS 20 x 100 mm, 10-90% aqueous methanol over 15 min containing 0.1% TFA, 20 mL/min, monitoring at 220 nm). Purification yielded 0.040 g of compound **235** as a white solid, rather than the expected benzyl ester. None of the anticipated benzyl ester was observed by NMR or LC-MS. HPLC: 100% at 3.033 min (retention time) (YMC S5 ODS column 4.6 x 50 mm, 10-90% aqueous methanol over 4 minutes containing 0.2% phosphoric acid, 4 mL/min, monitoring at 220 nm), MS (ES): m/z 405.51 $[M+H]^+$.

Example 236

(3aα,4β,7β,7aα)-2-(4-Cyano-1-naphthalenyl)-N-[(4-fluorophenyl)methyl]octahydro-7-methyl-1,3-dioxo-4,7-epoxy-4H-isoindole-4-acetamide, (236)




Compound **234B** (0.100 g, 0.256 mmol) was dissolved in acetonitrile (4.0 mL). HOAc (0.035 g, 0.256 mmol) and DCC (0.049 g, 0.256 mmol) were then added followed by 4-fluorobenzylamine (0.030 mL, 0.256 mmol). After 4 h at 25°C, the reaction was concentrated *in vacuo* and purified by preparative HPLC (YMC S5 ODS 20 x 100 mm, 10-90% aqueous methanol over15 minutes containing 0.1% TFA, 20 mL/min, monitoring at 220 nm) to yield 0.085 g of compound **236** as a white solid. HPLC: 100% at 3.277 min (retention time) (YMC S5 ODS column 4.6 x 50 mm, 10-90% aqueous methanol over 4 minutes containing 0.2% phosphoric acid, 4 mL/min, monitoring at 220 nm), MS (ES): m/z 498.43 $[M+H]^+$.


216

Example 237

(3aα,4β,7β,7aα)-N-[2-[2-(4-Cyano-1-naphthalenyl)octahydro-7-methyl-1,3-dioxo-4,7-epoxy-4H-isoindol-4-yl]ethyl]-4-fluorobenzamide, (237B)



A. 4-Fluoro-N-[2-(5-methyl-2-furanyl)ethyl]benzamide (237A)



4-Fluorophenylacetyl chloride (0.29 mL, 2.44 mmol) was added dropwise to a solution of β-(5-methyl-2-furanyl)ethanamine (300 mg, 2.44 mmol, made according to the procedure of Yur'ev, Yu. K. *et. al. J. Gen. Chem. USSR (Engl. Transl.)* 33, 3444-8 (1963)) in THF (2.5 mL) at rt, then Et_3N (0.34 mL, 2.44 mmol) was added dropwise. Once the starting material was consumed, as was evident by HPLC, the reaction was quenched with H_2O and extracted with CH_2Cl_2. The combined organic layers were dried over $MgSO_4$ and concentrated under reduced pressure. Purification by flash chromatography eluting with 0%-50% EtOAc/hexane gradient gave 523 mg (95%) of compound 237A as a white solid. HPLC: 99% at 2.84 min (retention time) (Phenomenex-prime S5-C18 column 4.6 x 50 mm eluting with 10-90% aqueous methanol over 4 minutes containing 0.2% phosphoric acid, 4 mL/min, monitoring at 220 nm), MS (ES): m/z 248.15 $[M+H]^+$.


B. (3aα,4β,7β,7aα)-N-[2-[2-(4-Cyano-1-naphthalenyl)octahydro-7-methyl-1,3-dioxo-4,7-epoxy-4H-isoindol-4-yl]ethyl]-4-fluorobenzamide, (237B)

217

A solution of compound **237A** (221.5 mg, 0.896 mmol) and 4-(2,5-dihydro-2,5-dioxo-1H-1-yl)-1-naphthalenecarbonitrile (222.4 mg, 0.896 mmol) in benzene (4 mL) was heated at 60 °C overnight. The reaction mixture was concentrated under reduced pressure and dissolved in EtOAc (30 mL). 10% Pd/C (50 mg) was added and the mixture was stirred under a hydrogen balloon overnight. The reaction mixture was filtered through a pad of celite and concentrated under reduced pressure. Purification by flash chromatography eluting with 25%-75% EtOAc/hexane gradient gave 160.3 mg (36%) of compound **237B** as an off-white solid. HPLC: 97% at 3.13 & 3.23 min (retention time) (Phenomenex-prime S5-C18 column 4.6 x 50 mm eluting with 10-90% aqueous methanol over 4 minutes containing 0.2% phosphoric acid, 4 mL/min, monitoring at 220 nm), MS (ES): m/z 498.11 $[M+H]^+$.

Example 238

[3aR-(3aα,4β,7β,7aα)]-4-[Octahydro-4-(2-hydroxyethyl)-7-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile & [3aS-(3aα,4β,7β,7aα)]-4-[Octahydro-4-(2-hydroxyethyl)-7-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile. (238I & 238II)




Racemic compound **223B** was separated into its enantiomers by preparative chiral HPLC (CHIRALPAK AD 5 x 50 cm column; eluting with 20% MeOH/EtOH (1:1) in heptane (isocratic) at 50 mL/min, @ 220 nm) to give the faster eluting compound **238I** (Chiral HPLC: 13.54 min; CHIRALPAK AD 4.6 x 250 mm column; eluting with 20% MeOH/EtOH (1:1) in heptane at 1 mL/min) and the slower eluting compound **238II** (Chiral HPLC: 14.99 min; CHIRALPAK AD 4.6 x 250 mm column; eluting with 20% MeOH/EtOH (1:1) in heptane at 1 mL/min). The absolute conformation for compounds **238I** & **238II** was not established. For simplicity in nomenclature, compound **238I** is designated herein as having an "R" configuration and compound **238II** as

having an "S" configuration. Enantiomerically pure products derived from compound **238l** are designated herein as having a "R" configuration and enantiomerically pure products derived from compound **238li** are designated herein as having an "S" configuration.

Example 239

[3aR-(3aα,4β,7β,7aα)]-4-[4-[2-(3-Fluorophenoxy)ethyl]octahydro-7-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile & [3aS-(-(3aα,4β,7β,7aα)]-4-[4-[2-(3-Fluorophenoxy)ethyl]octahydro-7-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile, (239l & 239li)




To a solution of triphenylphosphine (0.0524 g, 0.20 mmol) in THF (2.0 mL) was added DBAD (0.046 g, 0.2 mmol). After 10 min, 3-fluorophenol (0.018 mL, 0.2 mmol) was added. After 10 additional minutes, enantiomerically pure compound **238l** (0.050 g, 0.133 mmol) was added. After 3 h at 25°C, the reaction was concentrated *in vacuo* and purified by preparative HPLC (YMC S5 ODS 20 x 100 mm, 10-90% aqueous methanol over 15 minutes containing 0.2% TFA, 20 mL/min, monitoring at 220 nm) to give 0.031 g of compound **239l** as a white solid. This process was repeated with enantiomerically pure compound **238ll** to yield compound **239ll**. Compound **239l**: HPLC: 100% at 3.80 min (retention time) (YMC S5 ODS column 4.6 x 50 mm, 10-90% aqueous methanol over 4 minutes containing 0.2% phosphoric acid, 4 mL/min, monitoring at 220 nm), MS (ES): m/z 471.65 $[M+H]^+$, $[\alpha]_D^{25}$ = -47.371 (c = 4.412 mg/cc, CH_2Cl_2). Compound **239ll**: HPLC: 100% at 3.80 min (retention time) (YMC S5 ODS column 4.6 x 50 mm, 10-90% aqueous methanol over 4 minutes containing 0.2% phosphoric acid,

4 mL/min, monitoring at 220 nm), MS (ES): m/z 471.65 $[M+H]^+$, $[\alpha]_D^{25}$ = +24.3 (c = 4.165 mg/cc, CH_2Cl_2).

Example 240


(4-Fluorophenyl)carbamic acid, 2-[(3aα,4β,7β,7aα)-2-(4-cyano-1-naphthalenyl)octahydro-7-methyl-1,3-dioxo-4,7-epoxy-4H-isoindol-4-yl]ethyl ester, (240)



Compound **223B** (0.100 g, 0.279 mmol) was dissolved in dichloroethane (3.0 mL) and 4-fluorophenylisocyanate (0.048 mL, 0.419 mmol) was added followed by heating to 60°C. After 2 h, the reaction was cooled to 25°C and diluted with methylene chloride. The mixture was washed once with sat. aq sodium bicarbonate (20 mL) and then the organics were dried over anhydrous sodium sulfate. The crude material was purified by flash chromatography on silica eluting with 15% acetone in chloroform to give 0.098 g of compound **240** as a yellow foam. HPLC: 98% at 3.320 and 3.457 min (atropisomers) (retention time) (YMC S5 ODS column 4.6 x 50 mm, 10-90% aqueous methanol over 4 minutes containing 0.2% phosphoric acid, 4 mL/min, monitoring at 220 nm), MS (ES): m/z 514.13 $[M+H]^+$.


Example 241

(3aα,4β,7β,7aα)-4-[Octahydro-4-(2-hydroxyethyl)-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile, (241D)




220

A. 2-[2-[[(1,1-Dimethlethyl)dimethylsilyl]oxy]ethyl]furan (241A)



2-(2-Hydroxyethyl)furan (1.00 g, 8.93 mmol, Example **255A**) was dissolved in DMF at 25°C and imidazole (0.790 g, 11.61 mmol) was added. TBSCl (1.35 g, 8.93 mmol) was then added by portions over 5 minutes. After 2 h, the reaction was poured into diethyl ether (300 mL) and washed sequentially with water (1 x 100 mL), 1 N HCl (1 x 100 mL), and brine (1 x 100 mL). The combined organics were then dried over magnesium sulfate and concentrated *in vacuo*. Compound **241A** was isolated as a clear oil (1.77 g) and was taken on without purification. HPLC: 100% at 4.233 min (retention time) (YMC S5 ODS column 4.6 x 50 mm, 10-90% aqueous methanol over 4 minutes containing 0.2% phosphoric acid, 4 mL/min, monitoring at 220 nm).


B. (3aα,4β,7β,7aα)-4-[4-[2-[[(1,1-Dimethylethyl)dimethylsilyl]oxy]ethyl]-1,3,3a,4,7,7a-hexahydro-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile (241B)



4-(2,5-Dihydro-2,5-dioxo-1H-1-yl)-1-naphthalenecarbonitrile (0.721 g, 3.40 mmol) was suspended in benzene (5.0 mL) in a sealed tube and compound **241A** (1.00 g, 4.42 mmol) was added. The reaction was heated at 60°C for 16 h and then cooled to 25°C. The benzene was removed *in vacuo* to give a yellow solid. The crude material was purified by flash chromatography on silica eluting with 1-5% acetone in chloroform to give 1.37

g of compound **241B** as a yellow solid. NMR experiments confirmed exo isomer assignment. HPLC: 100% at 4.030 and 4.110 (atropsiomers) min (retention time) (YMC S5 ODS column 4.6 x 50 mm, 10-90% aqueous methanol over 4 minutes containing 0.2% phosphoric acid, 4 mL/min, monitoring at 220 nm).

C. (3aα,4β,7β,7aα)-4-[4-[2-[[(1,1-Dimethylethyl)dimethylsilyl]oxy]ethyl]octahydro-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile (241C)



The compound **241B** (0.500 g, 1.14 mmol) was dissolved in ethyl acetate (40 mL) and Pd/C (10% Pd, 0.200 g) was added. Hydrogen was then introduced via a balloon. After 4 h, the reaction was filtered through celite, rinsed with ethyl acetate and concentration *in vacuo* to yield a pale yellow solid, which was purified by flash chromatography on silica gel eluting with acetone/chloroform (0% - 1.5% - 3% acetone) to give compound **241C** (0.450 g) as a yellow foam.


D. (3aα,4β,7β,7aα)-4-[Octahydro-4-(2-hydroxyethyl)-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile, (241D)

Compound **241C** (0.283 g, 0.50 mmol) was dissolved in a solution of 2% 12N HCl in absolute ethanol (10 mL). After 1 h, the reaction was quenched with sat. aq sodium bicarbonate and extracted with methylene chloride (4 x 20 mL). The combined organics were dried over sodium sulfate and concentrated *in vacuo* to give 0.211 g of compound **241D** as a white solid. HPLC: 100% at 2.14 min (retention time) (YMC S5 ODS column 4.6 x


50 mm, 10-90% aqueous methanol over 4 minutes containing 0.2% phosphoric acid, 4 mL/min, monitoring at 220 nm), MS (ES): m/z 363.45 $[M+H]^+$.

Example 242

(3aα,4β,6β,7β,7aα)-4-[4-[2-(4-Cyanophenoxy)ethyl]octahydro-6-hydroxy-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile, (242C)



A. (3aα,4β,6β,7β,7aα)-4-[4-[2-[[(1,1-Dimethylethyl)dimethylsilyl]oxy]ethyl]octahydro-6-hydroxy-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile (242A)




Compound **241B** (1.00 g, 2.28 mmol) and Wilkinson's catalyst (0.105 g, 0.114 mmol) were stirred rapidly under vacuum at 25°C for 1 h and then purged with N_2. THF (30 mL) was then added followed by catechol borane (0.487 mL, 4.57 mmol) after the olefin was completely dissolved. After 1 h, the reaction was cooled to 0°C and a pH 7.2 phosphate buffer (33 mL) was added followed by EtOH (13 mL) and H_2O_2 (30% aq soln, 3.0 g). After 3 h at 0°C the reaction was complete by LC and the mixture was extracted with methylene chloride (3 x 50 mL). The combined organics were washed with a 1:1 mixture of 10% sodium sulfite/1N NaOH (50 mL) and once with brine (50

223

mL). All aqueous phases were combined and extracted with methylene chloride (50 mL) and the organic phase combined with the previous extractions. All the organics were then dried over anhydrous sodium sulfate and then concentrated *in vacuo*. The crude material was purified by flash chromatography on silica eluting with 10-20% acetone in chloroform to give 0.634 g of compound **242A** as a white foam. HPLC: 96% at 3.797 min (retention time) (YMC S5 ODS column 4.6 x 50 mm, 10-90% aqueous methanol over 4 minutes containing 0.2% phosphoric acid, 4 mL/min, monitoring at 220 nm), MS (ES): m/z 493.13 $[M+H]^+$.

B. (3aα,4β,6β,7β,7aα)-4-[Octahydro-6-hydroxy-4-(2-hydroxyethyl)-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile (242B)



Compound **242A** (0.400 g, 0.813 mmol) was dissolved in a solution of 2% 12N HCl in absolute ethanol (10 mL). After 1 h, the reaction was quenched with sat. aq sodium bicarbonate and extracted with EtOAc (4 x 20 mL). The combined organics were dried over sodium sulfate and concentrated *in vacuo* to give 0.305 g of compound **242B** as a white solid. HPLC: 90% at 2.043 min (retention time) (YMC S5 ODS column 4.6 x 50 mm, 10-90% aqueous methanol over 4 minutes containing 0.2% phosphoric acid, 4 mL/min, monitoring at 220 nm), MS (ES): m/z 379.09 $[M+H]^+$.


224


C. (3aα,4β,5β,7β,7aα)-4-[4-[2-(4-Cyanophenoxy)ethyl]octahydro-6-hydroxy-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile, (242C)

To a solution of triphenylphosphine (0.054 g, 0.207 mmol) in THF (2.0 mL) was added DBAD (0.048 g, 0.207 mmol). After 10 min, 4-cyanophenol (0.025 g, 0.207 mmol) was added. After 10 additional minutes, compound **242B** (0.050 g, 0.138 mmol) was added. After 3 h at 25°C, the reaction was concentrated *in vacuo* and purified by preparative TLC on silica eluting with 25% acetone/chloroform to give 0.056 g of compound **242C** as a white solid. HPLC: 90% at 2.987 min (retention time) (YMC S5 ODS column 4.6 x 50 mm, 10-90% aqueous methanol over 4 minutes containing 0.2% phosphoric acid, 4 mL/min, monitoring at 220 nm), MS (ES): m/z 480.10 $[M+H]^+$.


Example 243

[3aS-(3aα,4β,5β,7β,7aα)]-4-[Octahydro-5-hydroxy-7-(2-hydroxyethyl)-4-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile & [3aR-(3aα,4β,5β,7β,7aα)]-4-[Octahydro-5-hydroxy-7-(2-hydroxyethyl)-4-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile, (243DI & 243DII)






A. (3aα,4β,7β,7aα)-4-[4-[2-[[(1,1-Dimethylethyl)dimethylsilyl]oxy]ethyl]-1,3,3a,4,7,7a-hexahydro-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile (243A)



4-(2,5-Dihydro-2,5-dioxo-1H-1-yl)-1-naphthalenecarbonitrile (18.3 g, 68.7 mmol) was added to a solution of compound **204A** (26.6 g, 110.6 mmol) in benzene (75 mL) and heated to 60°C overnight. After cooling to rt, the reaction mixture was concentrated under reduced pressure. The residue was treated with MeOH (250 mL) with stirring at 0°C for 10 min. The resulting solid was filtered, washed with cold MeOH (2 X 10 mL) and dried to give 26.7 g (79.5%) of compound **243A** as a yellow solid. HPLC analysis of the above solid revealed it to be 95% pure (HPLC conditions: 95% at 2.48 min (Phenomenex-prime S5-C18 column, 4.6 x 50 mm, 10%-90% aqueous methanol over 4 minute gradient with 0.2% H_3PO_4, detecting at 220 nm)). The filtrate was then concentrated under reduced pressure and the resulting solid was chromatographed, eluting with 3% acetone/$CHCl_3$, to give an additional 4.36 g of compound **243A** (13%), giving a total final yield of 92.5%.

B. (3aα,4β,5β,7β,7aα)-4-[7-[2-[[(1,1-Dimethylethyl)dimethylsilyl]oxy]ethyl]octahydro-5-hydroxy-4-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile (243B)




A mixture of **243A** (10 g, 20.46 mmol) and $RhCl(PPh_3)_3$ (0.947 mg, 1.02 mmol) was evacuated and filled with argon (3X). THF (200 mL) was added and once all particulates had dissolved, catecholborane (4.4 mL, 40.93 mmol) was slowly added dropwise. When the formation of product ceased, as was determined by HPLC, the reaction mixture was cooled to 0°C and quenched with phosphate buffer (330 mL, pH 7.2) then EtOH (130 mL) and

226

H_2O_2 (300 mL, 30% aq sol) were added. Once boronate was consumed, the mixture was extracted with CH_2Cl_2 (3X) and the combined organic layers were washed with 1N NaOH, 10% aq $NaHSO_3$ (1:1, 1X) and brine (1X). The combined washes was extracted with CH_2Cl_2 (1X) and the combined organic layers were dried over Na_2SO_4. Purification by flash chromatography on silica gel eluting with 10% to 30% acetone/$CHCl_3$ gradient over 25 min gave 7.1 g (68%) of **243B** as a light yellow solid. HPLC conditions: 98% at 3.82 min (Phenomenex-prime S5-C18 column 4.6 x 50 mm, 10%-90% aqueous methanol over 4 minute gradient with 0.2% H_3PO_4, detecting at 220 nm).

C. **[3aR-(3aα,4β,5β,7β,7aα)]-4-[7-[2-[[(1,1-Dimethylethyl)dimethylsilyl]oxy]ethyl]octahydro-5-hydroxy-4-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile & [3aS-(3aα,4β,5β,7β,7aα)]-4-[7-[2-[[(1,1-Dimethylethyl)dimethylsilyl]oxy]ethyl]octahydro-5-hydroxy-4-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile (243CI & 243CII)**



The racemic compound **243B** was separated into the individual enantiomers by chiral normal phase liquid chromatography. A Chiralpak OD column (50 x 500 mm) was used, eluting with 13% EtOH/hexanes over 99 min at 50mL/min detecting at 220 nm. The faster eluting isomer compound **243CI** had a retention time = 45 min and the slower eluting isomer compound **243CII** had a retention time = 66 min.

D. **[3aS-(3aα,4β,5β,7β,7aα)]-4-[Octahydro-5-hydroxy-7-(2-hydroxyethyl)-4-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile & [3aR-(3aα,4β,5β,7β,7aα)]-4-[Octahydro-**

5-hydroxy-7-(2-hydroxyethyl)-4-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile, (243Di & 243Dii)

Compound **243Ci** (0.84g, 2.14 mmol) was dissolved in 2% 12 N HCl/EtOH (20 mL), stirred for 5 minutes and concentrated under reduced pressure. Purification by flash chromatography on silica gel eluting with 5-10% MeOH/CH_2Cl_2 gave 0.57 g (88%) of **243Di**. Compound **243Di** which came from the faster eluting isomer (**243Ci**) was found to be 99.7% ee by analytical chiral normal phase chromatography. HPLC conditions: 99.7% at 2.17 min (Chiralcel OJ 44.6 X 250 mm, 10 micron, 40°C, isocratic 80% Heptane / 20% EtOH/MeOH (1:1), 1.0 mL/min., detection at 288 nm).


Compound **243Cii** (0.86 g, 2.19 mmol) was dissolved in 2% 12N HCl/EtOH (20 mL), stirred for 5 minutes and concentrated under reduced pressure. Purification by flash chromatography on silica gel eluting with 5-10% MeOH/CH_2Cl_2 gave 0.60 g (90%) of **243Dii**. Compound **243Dii** which came from the slower eluting isomer (**243Cii**) was found to have 87.1% ee by analytical chiral normal phase chromatography. HPLC conditions: 87.1% at 18.4 min (Chiralcel OJ 44.6 X 250 mm, 10 micron, 40°C, isocratic 80% heptane / 20% EtOH/MeOH (1:1), 1.0 mL/min., detection at 288 nm).


The absolute conformation for compounds **243Di** & **243Dii** was not determined. For simplicity in nomenclature, compound **243Di** is designated herein as having an "S" configuration and compound **243Dii** as having an "R" configuration. Enantiomerically pure products derived from compound **243Di** are designated herein as having an "S" configuration and enantiomerically pure products derived from compound **243Dii** are designated herein as having an "R" configuration

228

Example 244

[3aS-(3aα,4β,5β,7β,7aα)]-4-[7-[2-(4-Cyanophenoxy)ethyl]octahydro-5-hydroxy-4-methyl-1,3-dioxo-4,7-epoxy-2H-Isoindol-2-yl]-1-naphthalenecarbonitrile & [3aR-(3aα,4β,5β,7β,7aα)]-4-[7-[2-(4-Cyanophenoxy)ethyl]octahydro-5-hydroxy-4-methyl-1,3-dioxo-4,7-epoxy-2H-Isoindol-2-yl]-1-naphthalenecarbonitrile, (244I & 244II)





DBAD (26 mg, 0.115 mmol) was added to a solution of PPh_3 (30 mg, 0.115 mmol) in THF (0.65 mL). After stirring for 10 min, 4-cyanophenol (13.6 mg, 0.115 mmol) was added and the reaction mixture was stirred for a further 5 min. Compound **243DI** (30 mg, 0.076 mmol) was added and the mixture was stirred at rt for 1 h. The reaction was concentrated under reduced pressure. Purification by flash chromatography on silica gel eluting with 30% acetone/70% $CHCl_3$ gave 23.1 mg (0.047 mmol, 61.7%) of compound **244I**. HPLC conditions: 95% at 3.06 min (YMC S5 ODS 4.6X50 mm, 10%-90% aqueous methanol over 4 minute gradient with 0.2% H_3PO_4, detecting at 220 nm). MS (ES): m/z 494.09 $[M+H]^+$. $[\alpha]_D$ = 53.30°, C = 4.5 mg/cc in THF, @ 589 nm)


DBAD (26 mg, 0.115 mmol) was added to a solution of PPh_3 (30mg, 0.115 mmol) in THF (0.65 mL). After stirring for 10 min, 4-cyanophenol (13.6 mg, 0.115 mmol) was added and the reaction mixture was stirred for a further 5 min. Compound **243DII** (30 mg, 0.076 mmol) was added and the mixture was stirred at rt for 1 h. The reaction was concentrated under reduced pressure. Purification by flash chromatography on silica gel eluting with 30% acetone/70% $CHCl_3$ gave 20.3 mg (0.041 mmol, 54.2%) of compound **244II**. HPLC conditions: 90% at 3.07 min (YMC S5 ODS 4.6X50 mm, 10%-90%

229

aqueous methanol over 4 minute gradient with 0.2% H_3PO_4, detecting at 220 nm). MS (ES): m/z 494.09 $[M+H]^+$. $[\alpha]_D$ = -42.87°, C = 6.6 mg/cc in THF, @ 589 nm)

Example 245

(3aα,4β,7β,7aα)-4-[4-[2-(4-Cyanophenoxy)ethyl]-7-ethyloctahydro-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile. (245D)




A. 2-Ethyl-5-(2-hydroxyethyl)furan (245A)



n-BuLi (2.5 M in hexane, 4.4 mL, 11 mmol) was added to a solution of 2-ethylfuran (1.05 mL, 10 mmol) in THF (10 mL) at –25°C. The solution was warmed to rt and stirred for 3 h. Ethylene oxide (0.75 mL) was added at –78°C. The reaction was stirred for 0.5 h at –15°C and overnight at rt. Aqueous sat. NH_4Cl was added and the mixture was extracted with ether (3X). The combined extracts were washed with water (1X) and brine (1X) and dried over Na_2SO_4. Purification by flash chromatography on silica gel eluting with 30% EtOAc/70% hexane gave 1.12 g (8.02 mmol, 80.2%) of compound 245A as a yellow oil.


B. (3aα,4β,7β,7aα)-4-[4-Ethyl-1,3,3a,4,7,7a-hexahydro-7-(2-hydroxyethyl)-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile (245B)



230

A solution of compound **245A** (280 mg, 2.00 mmol) and the 4-(2,5-dihydro-2,5-dioxo-1H-1-yl)-1-naphthalenecarbonitrile (496 mg, 2.00 mmol) in benzene (2 mL) was stirred at 60°C for 2 h. The reaction mixture was concentrated under reduced pressure. The yellow solid, compound **245B**, was used directly in the next step.

C. (3aα,4β,7β,7aα)-4-[4-Ethyloctahydro-7-(2-hydroxyethyl)-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile (245C)



A mixture of compound **245B** (764 mg, 1.97 mmol) and 10% Pd/C (115 mg, cat.) in EtOAc (36 mL) was stirred under a hydrogen atmosphere at rt for 2 h. The reaction mixture was filtered through celite and concentrated under reduced pressure to give 779 mg of crude compound **245C**. Purification of this crude product by flash chromatography on silica gel eluting with 70% EtOAc/30% hexane gave 235 mg (0.6 mmol, 30.1%) of compound **245C**. HPLC conditions: 99% at 2.84 min (YMC S5 ODS 4.6X50 mm, 10%-90% aqueous methanol over 4 minute gradient with 0.2% H_3PO_4, detecting at 220 nm). MS (ES): m/z 391.12 $[M+H]^+$.

D. (3aα,4β,7β,7aα)-4-[4-[2-(4-Cyanophenoxy)ethyl]-7-ethyloctahydro-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile (245D)


DBAD (44.2 mg, 0.192 mmol) was added to a solution of PPh_3 (50.4 mg, 0.192 mmol) in THF (1 mL). After stirring for 10 mins, 4-cyanophenol (23 mg, 0.192 mmol) was added and the reaction mixture was stirred for an additional 5 mins. Compound **245C** (50 mg, 0.128 mmol) was added and the

231

mixture was stirred at rt for 2 h. The reaction was concentrated under reduced pressure. Purification by flash chromatography on silica gel eluting with 40% EtOAc/60% hexane gave 43 mg (0.087 mmol, 68.4%) of compound **245D** as a white solid. HPLC conditions: 99% at 3.65 min (YMC S5 ODS 4.6X50 mm, 10%-90% aqueous methanol over 4 minute gradient with 0.2% H_3PO_4, detecting at 220 nm). MS (ES): m/z 492.16 $[M+H]^+$.

Example 246

(3aα,4β,7β,7aα)-4-[2-(Acetyloxy)ethyl]-2-(4-cyano-1-naphthalenyl)hexahydro-7-methyl-4,7-epoxy-1H-isoindole-1,3(2H)-dione, (246)




Compound **223B** (0.100 g, 0.279 mmol) was dissolved in methylene chloride (3.0 mL) at 25°C and pyridine (0.071 mL, 0.837 mmol) and 4-DMAP (1.0 mg) were added. Acetic anhydride (0.053 mL, 0.559 mmol) was then added and the reaction was stirred for 20 h at 25°C. After 20 h, sat. aq sodium bicarbonate was added and the reaction was stirred for 30 min. The mixture was then extracted with methylene chloride (2 x 20 mL). The organics were then washed once with 1N HCl (10 mL) and then dried over anhydrous sodium sulfate. After concentration *in vacuo*, the crude material was purified by preparative TLC on silica eluting with 12% acetone in chloroform to give 0.073 g of compound **246** as a yellow foam. HPLC: 95% at 2.837 and 3.027 min (atropisomers) (retention time) (YMC S5 ODS column 4.6 x 50 mm, 10-90% aqueous methanol over 4 minutes containing 0.2% phosphoric acid, 4 mL/min, monitoring at 220 nm), MS (ES): m/z 441.10 $[M+Na]^+$.

232

Example 247


(3aα,4β,7β,7aα)-4-[Octahydro-4-methyl-1,3-dioxo-7-(2-oxoethyl)-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile, (247)



Oxalyl chloride (2.0 M soln, 1.73 mL, 3.5 mmol) was added to dry methylene chloride (10 mL) and cooled to –78°C. DMSO (0.283 mL, 3.99 mmol) was then added dropwise with the evolution of gas. After 15 min, compound **223B** (1.00 g, 2.66 mmol) was then added in methylene chloride (10 mL). After 15 min, TEA (1.10 mL, 7.98 mmol) was added and the reaction was slowly warmed to 25°C. Water (30 mL) was then added and the mixture was diluted with methylene chloride (100 mL). The organics were then washed once with 1 N HCl (30 mL), once with water (30 mL) and once with brine (30 mL) and then dried over anhydrous sodium sulfate. The crude product was isolated by concentration *in vacuo* to yield compound **247** as an orange foam. Crude compound **247** was taken on directly to the next reaction. HPLC: 100% at 2.70 min (retention time) (YMC S5 ODS column 4.6 x 50 mm, 10-90% aqueous methanol over 4 minutes containing 0.2% phosphoric acid, 4 mL/min, monitoring at 220 nm), MS (ES): m/z 483.65 $[M+H]^+$.

Example 248


[3aα,4β(E),7β,7aα]-4-[4-[3-(4-Cyanophenyl)-2-propenyl]octahydro-7-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile & [3aα,4β(Z),7β,7aα]-4-[4-[3-(4-Cyanophenyl)-2-propenyl]octahydro-7-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile (248I & 248II)



(4-cyanobenzyl)-triphenylphosphonium chloride (0.072 g, 0.174 mmol) was suspended in THF (2.0 mL) and cooled to 0°C. n-BuLi (1.6 M soln, 0.092 mL, 0.147 mmol) was then added dropwise resulting in a homogenous solution. The solution warmed to 25°C for 15 min and then cooled to 0°C. Compound **247** (0.050 g, 0.134 mmol) was then added in THF. After 1 h, the reaction was quenched with sat. aq ammonium chloride and then extracted with methylene chloride (3 x 20 mL). The combined organics were dried over anhydrous sodium sulfate and then concentrated *in vacuo*. The crude material was purified by preparative TLC eluting with 5% acetone in chloroform to give 0.010 g of a mixture of compounds **248I & 248II** as a white solid. A 1:1 mixture of E and Z olefin isomers characterized by NMR spectroscopy. HPLC: 100% at 3.517 min (retention time) (YMC S5 ODS column 4.6 x 50 mm, 10-90% aqueous methanol over 4 minutes containing 0.2% phosphoric acid, 4 mL/min, monitoring at 220 nm), MS (ES): m/z 474.2 $[M+H]^+$.

Example 249

(3aα,4β,7β,7aα)-4-[4-[3-(4-Cyanophenyl)propyl]octahydro-7-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile, (249)




The mixture of compounds **248I & 248II** (0.008 g, 0.017 mmol) was dissolved in EtOH (3.0 mL) and Pd/C (10% Pd, 0.008 g) was added. H_2 was

then introduced via a balloon. After 18 h, the reaction was filtered through celite, eluting with EtOAc, followed by concentration *in vacuo*. Compound **249** was isolated as a white solid (0.007 g). HPLC: 90% at 3.520 min (retention time) (YMC S5 ODS column 4.6 x 50 mm, 10-90% aqueous methanol over 4 minutes containing 0.2% phosphoric acid, 4 mL/min, monitoring at 220 nm), MS (ES): m/z 476.13 $[M+H]^+$.

Example 250

(3aα,4β,7β,7aα)-4-[4-[2-[(6-Chloro-1,2-benzisoxazol-3-yl)oxy]ethyl]octahydro-7-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile, (250)




To a solution of PPh_3 (52 mg, 0.20 mmol) in 0.5 mL THF was added DBAD (46 mg, 0.20 mmol) as one solid portion. The resulting mixture was stirred for 10 min before 6-chloro-3-hydroxy-1,2-benzisoxazole (34 mg, 0.20 mmol) was added. Stirring was continued for 10 min before a solution of compound **223B** (50 mg, 0.13 mmol) in 0.5 mL THF was introduced via canula. The resulting mixture was stirred at ambient temperature for 24 h, concentrated and purified by preparative reverse phase HPLC (YMC S5 ODS 20 x 100 mm column; eluting with 30-100% aqueous MeOH containing 0.1% TFA over 10 min at 20 mL/min) to yield a white solid. The obtained solids were dissolved in CH_2Cl_2, washed with sat. $NaHCO_3$ solution, dried over Na_2SO_4 and concentrated to yield 50 mg (71%) of compound **250** as a colorless oil. HPLC: 26% at 3.89 min and 74% at 4.02 min (mixture of atropisomers, retention time) (YMC S5 ODS column 4.6 x 50 mm Ballistic, 10-90% aqueous methanol over 4 minutes containing 0.2% H_3PO_4, 4 mL/min, monitoring at 220 nm), MS (ES): m/z 528.4 $[M+H]^+$.

235

Example 251


(3aα,4β,7β,7aα)-4-[Octahydro-4-methyl-7-[2-[(6-nitro-1H-indazol-3-yl)oxy]ethyl]-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile, (251)



To a solution of compound **223B** (50 mg, 0.13 mmol) in toluene (1 mL) was added ADDP (50 mg, 0.20 mmol), 6-nitro-3-indazolinone (36 mg, 0.20 mmol) and n-Bu_3P (50 μL, 0.2 mmol). The resulting mixture was heated to 80°C for 24 h, concentrated and purified by a combination of preparative reverse phase HPLC (YMC S5 ODS 20 x 100 mm column; eluting with 30-100% aqueous MeOH containing 0.1% TFA over 10 min at 20 mL/min) and flash chromatography (silica gel, 25% acetone in $CHCl_3$) to give 17 mg (25%) of compound **251** as a yellow solid. HPLC: 24% at 3.60 min and 76% at 3.74 min (mixture of atropisomers, retention time) (YMC S5 ODS column 4.6 x 50 mm Ballistic, 10-90% aqueous methanol over 4 minutes containing 0.2% H_3PO_4, 4 mL/min, monitoring at 220 nm), MS (ES): m/z 537.6 $[M+H]^+$.

Example 252

[3aS-(3aα,4β,5β,7β,7aα)]-4-[7-[2-(1,2-Benzisoxazol-3-yloxy)ethyl]octahydro-5-hydroxy-4-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile, (252)




PPh_3 (47 mg, 0.18 mmol), DBAD (41 mg, 0.18 mmol), 3-hydroxy-1,2-benzisoxazole (24 mg, 0.18 mmol) and compound **243DI** (35 mg, 0.09 mmol) were

reacted according to the procedure given for compound **250**. Purification was achieved by reverse phase HPLC (YMC S5 ODS 20 x 100 mm column; eluting with 30-100% aqueous MeOH containing 0.1% TFA over 10 min at 20 mL/min) to yield a white solid. The obtained solids were dissolved in CH_2Cl_2, washed with sat. $NaHCO_3$ solution, dried over Na_2SO_4 and concentrated furnishing 29 mg (64%) of compound **252** as a colorless oil. HPLC: 96% at 3.29 min (mixture of atropisomers, retention time) (YMC S5 ODS column 4.6 x 50 mm Ballistic, 0-100% aqueous methanol over 4 minutes containing 0.2% H_3PO_4, 4 mL/min, monitoring at 220 nm), MS (ES): m/z 510.2 $[M+H]^+$.

Example 253

[3aR-(3aα,4β,5β,7β,7aα)]-4-[7-[2-(1,2-Benzisoxazol-3-yloxy)ethyl]octahydro-5-hydroxy-4-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile, (253)




PPh_3 (47 mg, 0.18 mmol), DBAD (41 mg, 0.18 mmol), 3-hydroxy-1,2-benzisoxazole (24 mg, 0.18 mmol) and compound **243DII** (35 mg, 0.09 mmol) were reacted according to the procedure given for compound **250**. Purification was achieved by reverse phase HPLC (YMC S5 ODS 20 x 100 mm column; eluting with 30-100% aqueous MeOH containing 0.1% TFA over 10 min at 20 mL/min) to yield a white solid. The obtained solids were dissolved in CH_2Cl_2, washed with sat. $NaHCO_3$ solution, dried over Na_2SO_4 and concentrated furnishing 23 mg (51%) of compound **253** as a colorless oil. HPLC: 95% at 3.29 min (mixture of atropisomers, retention time) (YMC S5 ODS column 4.6 x 50 mm Ballistic, 0-100% aqueous methanol over 4 minutes containing 0.2% H_3PO_4, 4 mL/min, monitoring at 220 nm), MS (ES): m/z 510.4 $[M+H]^+$.


237

Example 254

(3aα,4β,5β,7β,7aα)]-4-(Octahydro-5-hydroxy-4,7-dimethyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl)-2-(trifluoromethyl)benzonitrile &

(3aα,4β,5β,7β,7aα)]-4-(Octahydro-5-hydroxy-4,7-dimethyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl)-2-(trifluoromethyl)benzonitrile, (254I & 254II)







Racemic compound **221B** was separated into its enantiomers by preparative chiral HPLC (CHIRALPAK AD 5 x 50 cm column; eluting with 20% MeOH/EtOH (1:1) in heptane (isocratic) at 50 mL/min) to give the faster eluting compound **254I** (Chiral HPLC: 10.02 min; CHIRALPAK AD 4.6 x 250 mm column; eluting with 20% MeOH/EtOH (1:1) in heptane at 1 mL/min) and the slower eluting **254II** (Chiral HPLC: 14.74 min; CHIRALPAK AD 4.6 x 250 mm column; eluting with 20% MeOH/EtOH (1:1) in heptane at 1 mL/min).

Example 255


(3aα,4β,7β,7aα)-2-(4-Cyano-1-naphthalenyl)octahydro-1,3-dioxo-7-[2-(phenylmethoxy)ethyl]-4,7-epoxy-4H-isoindole-4-propanenitrile &

(3aα,4α,7α,7aα)-2-(4-Cyano-1-naphthalenyl)octahydro-1,3-dioxo-7-[2-(phenylmethoxy)ethyl]-4,7-epoxy-4H-isoindole-4-propanenitrile, (255HI & 255HII)






A. 2-(2-Hydroxyethyl)furan (255A)




2-(2-Hydroxyethyl)furan was made in accordance with the following reference: Harmata, M, *et al. J. Org. Chem.* 60, 5077-5092 (1995). *n*-BuLi (2.5 M in hexane, 44 mL, 110 mmol) was added to a solution of furan (8 mL, 110 mmol) in 100 mL of THF at –78°C. The solution was stirred at 0°C for 4 h and then ethylene oxide (7.5 mL) was added at –78°C. The reaction mixture was stirred at –15°C for 1 h and then overnight at rt. The reaction was quenched with sat. NH_4Cl and extracted with ether (3X). The combined extracts were washed with water (1X) and brine (1X). The ether solution was dried over Na_2SO_4 and concentrated under reduced pressure. Purification by flash chromatography on silica gel eluting with 40% EtOAc/60% hexane gave 5.4 g (48.2 mmol, 43.8%) of compound **255A** as a light brown oil.

B. 2-[2-[[(1,1-Dimethlethyl)dimethylsilyl]oxy]ethyl]furan (255B)



Imidazole (3.65 g, 53.6 mmol) and TBSCl (6.47 g, 42.9 mmol) were added to the solution of compound **255A** (4.00 g, 35.7 mmol) in 50 mL of DMF. The mixture was stirred at rt for 2 h and then the reaction mixture was poured into ether. The ether solution was washed with water (1X), 1 N HCl (1X), water (1X) and brine (1X). The organic layer was dried over Na_2SO_4 and concentrated under reduced pressure. Purification by flash chromatography on silica gel eluting with 30% CH_2Cl_2/70% hexane gave 7.4 g (32.7 mmol, 91.7%) of 255B as a colorless oil.

C. 2-[2-[[(1,1-Dimethlethyl)dimethylsilyl]oxy]ethyl]-5-(2-hydroxyethyl)furan (255C)




t-BuLi (1.2 M in pentane, 10 mL, 16.99 mmol) was added to a stirred solution of **255B** (3.49 g, 15.44 mmol) in 13 mL of THF at –78°C dropwise. The mixture was stirred for an additional 4 h at 0°C. Ethylene oxide (1.05 mL) was added at –78°C to

239


the reaction solution. The mixture was warmed to rt and stirred overnight. Aqueous sat. NH_4Cl was added and most of the THF was removed under reduced pressure. The mixture was extracted with ether (3X) and the combined organic layers were washed with water (1X) and brine (1X) and dried over Na_2SO_4. Purification by flash chromatography on silica gel eluting with 5% EtOAc/95% CH_2Cl_2 gave 2.8 g (10.4 mmol, 67%) of compound 255C as a yellow oil.

D. 2-[2-[[(1,1-Dimethlethyl)dimethylsilyl]oxy]ethyl]-5-[2-(phenylmethoxy)ethyl]furan (255D)




The alcohol **255C** (1.00 g, 3.7 mmol) in 12 mL of THF was treated with 60% NaH (177.8 mg, 4.44 mmol), benzyl bromide (0.53 mL, 4.44 mmol) and tetrabutylammonium iodide (50 mg, 5%) for 3 h at rt. Water was added and the mixture was extracted with EtOAc (3X). The combined extracts were washed with water (1X) and brine (1X) and dried over Na_2SO_4. Purification by flash chromatography on silica gel eluting with 20% hexane/80% CH_2Cl_2 gave 1.10 g (3.05 mmol, 82.6%) of compound **255D** as a yellow oil.

E. 2-(2-Hydroxyethyl)-5-[2-(phenylmethoxy)ethyl]furan (255E)



Tetrabutylammonium fluoride (1.0M in THF, 3.06 mL, 3.06 mmol) was added to the solution of compound **255D** (1.1 g, 3.06 mmol) in 10 mL of THF at 0°C. The reaction mixture was stirred at rt for 10 minutes, quenched by sat. NH_4Cl and extracted with ether (3X). The combined extracts were dried over Na_2SO_4. Purification by flash chromatography on silica gel eluting with 10% EtOAc/90% CH_2Cl_2 gave 750 mg (3.05 mmol, 99.6%) of compound 255E as a light yellow oil.


F. 5-[2-(Phenylmethoxy)ethyl]furan-2-propanenitrile (255F)



240

DEAD (1.285 mL, 8.17 mmol) was added to a stirred solution of Ph_3P (2.14 g, 8.17 mmol) in 12 mL of dry THF at 0°C. The solution was stirred for 30 min at rt and compound **255E** (670 mg, 2.72 mmol) was added. The reaction was stirred for 15 min and acetone cyanohydrin (0.745 mL, 8.17 mmol) was added at –15°C. The reaction was stirred for 30 min at –15°C, then at rt overnight. The mixture was then concentrated under reduced pressure. Purification by flash chromatography on silica gel eluting with 100% CH_2Cl_2 gave 180 mg (0.705 mmol, 26%) of compound **255F** as a colorless oil.

G. **(3aα,4β,7β,7aα)-2-(4-Cyano-1-naphthalenyl)-1,2,3,3a,7,7a-hexahydro-1,3-dioxo-7-[2-(phenylmethoxy)ethyl]-4,7-epoxy-4H-isoindole-4-propanenitrile (255G)**



A solution of compound **255F** (180 mg, 0.706 mmol) and 4-(2,5-dihydro-2,5-dioxo-1H-1-yl)-1-naphthalenecarbonitrile (263 mg, 1.06 mmol) in CH_2Cl_2 (3 mL) was stirred at rt for 3 days. The reaction mixture was concentrated under reduced pressure. Purification by flash chromatography on silica gel eluting with 5% EtOAc/CH_2Cl_2 gave 318 mg (0.63 mmol, 89.6%) of compound **255G** as a light gray solid which was used directly in the next step.


H. **(3aα,4β,7β,7aα)-2-(4-Cyano-1-naphthalenyl)octahydro-1,3-dioxo-7-[2-(phenylmethoxy)ethyl]-4,7-epoxy-4H-isoindole-4-propanenitrile & (3aα,4α,7α,7aα)-2-(4-Cyano-1-naphthalenyl)octahydro-1,3-dioxo-7-[2-(phenylmethoxy)ethyl]-4,7-epoxy-4H-isoindole-4-propanenitrile (255HI & 255HII)**

241

A mixture of compound **255G** (318 mg, 0.63 mmol) and 10% Pd/C (64 mg) in EtOH (10 mL) and EtOAc (5 mL) was stirred under a hydrogen atmosphere at rt overnight. The reaction mixture was filtered through celite and concentrated under reduced pressure to give 320 mg of crude compounds **255HI & 255HII**. Purification of 25 mg of this crude product by flash chromatography on silica gel eluting with 55% EtOAc/hexane gave 6.5 mg (0.013 mmol, 26% (based on 25 mg)) of compound **255HI** & 8.1 mg (0.016 mmol, 32.4% (based on 25 mg)) of compound **255HII**. Compound **255HI**: HPLC conditions: 98% at 3.57 min (YMC S5 ODS 4.6X50 mm, 10%-90% aqueous methanol over 4 minute gradient with 0.2% H_3PO_4, detecting at 220 nm, MS (ES): m/z 506.15 $[M+H]^+$. Compound **255HII**: HPLC conditions: 98% at 3.51 min (YMC S5 ODS 4.6X50 mm, 10%-90% aqueous methanol over 4 minute gradient with 0.2% H_3PO_4, detecting at 220 nm), MS (ES): m/z 506.15 $[M+H]^+$.

Example 256

(3aα,4β,7β,7aα)-2-(4-Cyano-1-naphthalenyl)octahydro-7-(2-hydroxyethyl)-1,3-dioxo-4,7-epoxy-4H-isoindole-4-propanenitrile & (3aα,4α,7α,7aα)-2-(4-Cyano-1-naphthalenyl)octahydro-7-(2-hydroxyethyl)-1,3-dioxo-4,7-epoxy-4H-isoindole-4-propanenitrile, (256I & 256II)




A mixture of compounds **255HI & 255HII** (200 mg, 0.396 mmol) and $PdCl_2$ (8.4 mg, cat.) in EtOH (1 mL) and EtOAc (3 mL) was stirred under a hydrogen atmosphere (30 psi) at rt overnight. The reaction mixture was filtered through celite and concentrated under reduced pressure. Purification by flash chromatography on silica gel eluting with 5% $MeOH/CH_2Cl_2$ followed

242

by a second column eluting with 100% EtOAc gave 28.9 mg (0.0696 mmol, 17.6%) of compound **256ii** and 26.5 mg (0.0639 mmol, 16.1%) of compound **256i**. Compound **256ii**: HPLC conditions: 90% at 2.44 min (YMC S5 ODS 4.6X50 mm, 10%-90% aqueous methanol over 4 minute gradient with 0.2% H_3PO_4, detecting at 220 nm.), MS (ES): m/z 416.11 $[M+H]^+$. Compound **256i**: HPLC conditions: 99% at 2.47 min (YMC S5 ODS 4.6X50 mm, 10%-90% aqueous methanol over 4 minute gradient with 0.2% H_3PO_4, detecting at 220 nm), MS (ES): m/z 416.11 $[M+H]^+$.

Example 257

(3aα,4β,7β,7aα)-2-(4-Cyano-1-naphthalenyl)-7-[2-(4-fluorophenoxy)ethyl]octahydro-1,3-dioxo-4,7-epoxy-4H-isoindole-4-propanenitrile. (257)




DBAD (15 mg, 0.065 mmol) was added to a solution of PPh_3 (17 mg, 0.065 mmol) in THF (0.3 mL). After stirring for 10 mins, 4-fluorophenol (7.33 mg, 0.065 mmol) was added and the reaction mixture was stirred for a further 5 mins. Compound **256i** (18.1 mg, 0.044 mmol) was added and the mixture was stirred at rt for 3 h. The reaction was concentrated under reduced pressure. Purification by flash chromatography on silica gel eluting with 60% EtOAc/30% hexane gave 5.9 mg (0.0116 mmol, 26.34%) of compound **257**. HPLC conditions: 98% at 3.59 min (YMC S5 ODS 4.6X50 mm, 10%-90% aqueous methanol over 4 minute gradient with 0.2% H_3PO_4, detecting at 220 nm). MS (ES): m/z 510.14 $[M+H]^+$.


243

Example 258

(3aα,4β,7β,7aα)-2-(7-Chloro-2,1,3-benzoxadiazol-4-yl)hexahydro-4,7-dimethyl-4,7-epoxy-1H-isoindole-1,3(2H)-dione, (258)



A. 4-Amino-7-chloro-2,1,3-benzoxadiazole (258A)




A solution of 1.0 g (5.02 mmol) of 4-chloro-7-nitrobenzofurazan in 20 mL AcOH, 10 mL EtOAc and 2 mL H_2O was heated to 50°C and treated with iron powder (1.4 g, 251 mmol). The mixture was heated at 80°C for 30 min and then allowed to cool to rt. The mixture was filtered through celite eluting with EtOAc. The filtrate was washed with sat. aq $NaHCO_3$, dried over $MgSO_4$, and concentrated to give compound **258A** (0.80 g, 94%) as a red solid.

B. (3aα,4β,7β,7aα)-2-(7-Chloro-2,1,3-benzoxadiazol-4-yl)hexahydro-4,7-dimethyl-4,7-epoxy-1H-isoindole-1,3(2H)-dione, (258B)

Compound **258A** (42 mg, 0.25 mmol) was reacted in a sealed tube with compound **20A** (73.5 mg, 0.375 mmol), $MgSO_4$ (75 mg, 0.625 mmol) and Et_3N (170 µL, 1.25 mmol) in 250 µL toluene according to the above procedure described in example **208C** to give after purification by preparative reverse phase HPLC (YMC S5 ODS 20 x 100 mm eluting with 30-100% aqueous methanol containing 0.1% TFA over 12 min, 20 mL/min) 23 mg (26%) of compound **258B** as a yellow solid. HPLC: 97.6% at 2.87 min (retention time) (YMC S5 ODS column 4.6 x 50 mm eluting with 10-90% aqueous methanol containing 0.2% phosphoric acid over 4 minutes , 4 mL/min, monitoring at 220 nm), MS (DCI): m/z 347.9 $[M]^{+\cdot}$.

Example 259


(3aα,4β,7β,7aα)-2-(7-Chloro-2-methyl-4-benzofuranyl)hexahydro-4,7-dimethyl-4,7-epoxy-1H-isoindole-1,3(2H)-dione, (259)




7-Chloro-2-methyl-4-benzofuranamine (38 mg, 0.25 mmol, prepared in accordance with the procedure described by Enomoto and Takemura in EP 0476697 A1) was reacted in a sealed tube with compound **20A** (73.5 mg, 0.375 mmol), $MgSO_4$ (75 mg, 0.625 mmol) and Et_3N (170 µL, 1.25 mmol) in 250 µL toluene according to the procedure described in example **208C** to give, after purification by preparative reverse phase HPLC (YMC S5 ODS 20 x 100 mm eluting with 30-100 aqueous methanol containing 0.1% TFA over 12 min, 20 mL/min), 42 mg (47%) of compound **259** as a white solid. HPLC: 98% at 3.45 min (retention time) (YMC S5 ODS column 4.6 x 50 mm eluting with 10-90% aqueous methanol over 4 minutes containing 0.2% phosphoric acid, 4 mL/min, monitoring at 220 nm), MS (DCI): m/z 359.9 $[M]^{+\cdot}$.

Example 260

(3aα,4β,7β,7aα)-2-(7-Chloro-2-methylbenzo[b]thiophen-4-yl)hexahydro-4,7-dimethyl-4,7-epoxy-1H-isoindole-1,3(2H)-dione, (260)




A. 1-Chloro-2-(2-chloro-allylsulfanyl)-4-nitro-benzene (260A)



215

A solution of 2-chloro-5-nitro-benzenethiol (1.0 g, 5.27 mmol, prepared in accordance with the procedure described by Still *et. al., Synth. Comm.* **13**, 1181 (1983)) in 15 mL DMF was treated with 2,3-dichloropropene (693 μL, 7.52 mmol) and K_2CO_3 (433 mg, 3.13 mmol). The mixture was heated at 80°C for 2 h and then allowed to cool to rt. EtOAc (200 mL) and H_2O (100 mL) were added. The organic phase was washed with H_2O (2 x 250 mL), saturated aqueous NaCl (100 mL), dried over $MgSO_4$, and concentrated. The crude material was purified by flash column chromatography on silica gel eluting with 20% EtOAc in hexanes to give compound **260A** (1.09 g, 89%) as an orange oil.

B. 4-Amino-7-chloro-2-methylbenzo[b]thiophene (260B)



A solution of 1.09 g (4.67 mmol) of compound **260A** in 20 mL AcOH with 10 mL EtOAc and 2 mL H_2O was heated to 80°C and treated with iron powder (1.3 g, 23.4 mmol). The mixture was heated at 80°C for 40 min and then allowed to cool to rt. The mixture was filtered through celite eluting with EtOAc. The filtrate was washed with sat. aq $NaHCO_3$, dried over $MgSO_4$, and concentrated *in vacuo*. N,N-diethylaniline (10 mL) was added, and the reaction was heated at 215°C for 6 h. After cooling to rt, 1N aqueous HCl (20 mL) was added, and the reaction was stirred at room temperature for 2h. The mixture was extracted with EtOAc (3 x 30 mL). The organic phase was washed with saturated aqueous $NaHCO_3$, dried over $MgSO_4$, and concentrated. The crude material was purified by flash column chromatography on silica gel eluting with 25% EtOAc in hexanes to give compound **260B** (320 mg, 35%) as a beige solid.


246

C. (3aα,4β,7β,7aα)-2-(7-Chloro-2-methylbenzo[b]thiophen-4-yl)hexahydro-4,7-dimethyl-4,7-epoxy-1H-isoindole-1,3(2H)-dione, (260C)

Compound **260B** (49 mg, 0.25 mmol) was reacted in a sealed tube with compound **20A** (73.5 mg, 0.38 mmol), $MgSO_4$ (75 mg, 0.63 mmol) and Et_3N (170 μL, 1.25 mmol) in 250 μL toluene according to the procedure described in example **208C** to give, after purification by preparative reverse phase HPLC (YMC S5 ODS 20 x 100 mm eluting with 30-100% aqueous methanol over 12 min containing 0.1% TFA, 20 mL/min), 28 mg (30%) of compound **260C** as a pale yellow solid. HPLC: 96% at 3.18 min (retention time) (YMC S5 ODS column 4.6 x 50 mm eluting with 10-90% aqueous methanol over 4 minutes containing 0.2% phosphoric acid, 4 mL/min, monitoring at 220 nm), MS (DCI): m/z 376.0 $[M]^{+\cdot}$.

Example 261

[3aα,4β(E),7β,7aα]-4-[2-(4-Cyano-1-naphthalenyl)octahydro-7-methyl-1,3-dioxo-4,7-epoxy-4H-isoindol-4-yl]-2-butenoic acid, phenylmethyl ester, (261)




Compound **247** (0.500 g, 0.134 mmol) was dissolved in THF (20 mL) and benzyl(triphenylphosphoranylidene) (0.55 g, 0.134 mmol) was added. The reaction mixture was stirred at 67°C for 2 h and then concentrated under reduced pressure. Purification by flash chromatography on SiO_2 eluting with 5% acetone/95% $CHCl_3$ gave 0.65 g of compound **261** as a yellow solid. HPLC: 99% at 3.717 min (retention time) (YMC S5 ODS column 4.6 x 50 mm

eluting with 10-90% aqueous methanol over 4 minutes containing 0.2% phosphoric acid, 4 mL/min, monitoring at 220 nm), MS (ES): m/z 507.1 $[M+H]^+$.

Example 262


(3aα,4β,7β,7aα)-2-(4-Cyano-1-naphthalenyl)octahydro-7-methyl-1,3-dioxo-4,7-epoxy-4H-isoindole-4-butanoic acid, (262)



Compound **261** (0.60 g, 1.19 mmol) was dissolved in EtOH/EtOAc (5mL/5mL) and 10% Pd/C (0.30 g) was added. Hydrogen was then introduced via a balloon. After 8 h the reaction was filtered through celite and then concentrated under reduced pressure to give compound **262** (0.47 g) as a white solid. HPLC: 98% at 2.81 min (retention time) (YMC S5 ODS column 4.6 x 50 mm eluting with 10-90% aqueous methanol over 4 minutes containing 0.2% phosphoric acid, 4 mL/min, monitoring at 220 nm), MS (ES): m/z 419.1 $[M+H]^+$.

Example 263


(3aα,4β,7β,7aα)-2-(4-Cyano-1-naphthalenyl)-N-(4-fluorophenyl)octahydro-7-methyl-1,3-dioxo-4,7-epoxy-4H-isoindole-4-butanamide, (263)



Compound **262** (0.030 g, 0.072 mmol) was dissolved in CH_3CN (1 mL). DCC (0.014 g, 0.072 *mmol*) and HOAc (0.0098 g, 0.072 *mmol*) were then added, followed by 4-flouroaniline (0.007 mL, 0.072 mmol). The reaction mixture was stirred under argon for 14 h and the crude material was dissolved in MeOH, purified by preparative HPLC (YMC VP-ODS column, 20 x 100 mm, eluting with 20% B to 100% B in 15 minutes and hold @ 100%B for 10 minutes). Compound **263** (0.020 g) was isolated as white solid. HPLC: 100% at 3.217 min (retention time) (YMC S5 ODS column 4.6 x 50 mm eluting with 10-90% aqueous methanol over 4 minutes containing 0.2% phosphoric acid, 4 mL/min, monitoring at 220 nm), MS (ES): m/z 512.1 $[M+H]^+$.

Example 264

[3aS-(3aα,4β,5β,7β,7aα)]-4-[7-[2-(Acetyloxy)ethyl]octahydro-5-hydroxy-4-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile & [3aR-(3aα,4β,5β,7β,7aα)]-4-[Octahydro-5-hydroxy-7-(2-hydroxyethyl)-4-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile, (264 & 243DII)



A racemic mixture of compounds **243DI & 243DII** (1.90 gram) were dissolved in 100 mL of anhydrous THF in a 2 L flask. Anhydrous *tert*-butyl-methyl ether (900 mL) and vinyl acetate (40 mL) were transferred into the flask with stirring and lipase (20 g, typeII, crude, from porcine pancreas; Sigma, Cat# L3126) was added. The reaction mixture was stirred for 21 hr at rt at which point an additional 5 grams of the lipase and 20 mL of vinyl acetate were added. The reaction was stirred at rt for an additional 19 h, stored at 4°C without stirring for 36 h and then stirred at rt for another 22 h

249

(until the desired % ee was apparent by chiral HPLC). To monitor the reaction, 200 uL of the mixture was withdrawn and centrifuged. The supernatant (100 uL) was dried under nitrogen and the resulting residue was dissolved in 100 uL of EtOH and subjected to HPLC analysis:

1) Reverse phase HPLC: Column, YMC-ODS AQ 150x4.6; flow rate, 1.2 mL/min; sample size, 10 uL
solvent A,: 1 mM HCl in water; solvent B, MeCN; monitored at 300 nm
Gradient:

Time(min)	0	8	8.5	9.5	10	12
B%	30	60	85	85	30	30


2) Chiral-HPLC: Column, CHIRALCEL OJ 4.6 x 250 mm
mobile phase, Hexane/MeOH/EtOH (8:1:1)
flow rate, 1 mL/min; sample size, 20 uL
monitored at both 220 and 300 nm
performed at 25°C & 40°C.
(for ee% determination of reaction mixture)

The enzyme was removed by filtration and filtrate was concentrated under vacuum. The resulting mixture was dissolved in $CHCl_3$ and adsorbed onto silica gel (63-200 microns). These solids were applied to a VLC funnel (3 cm I.D., VLC is vacuum liquid chromatography using glass funnels having 24/40 joints at the bottom) containing a 5 cm bed height of silica gel (25-40 microns) and a step gradient was carried out. The gradient was 100% $CHCl_3$ in the first 3 fractions, followed by $CHCl_3$-1% MeOH (3 fractions), $CHCl_3$-2% MeOH (3 fractions), $CHCl_3$-3% MeOH (3 fractions), $CHCl_3$-4% MeOH (3 fractions), and finally with $CHCl_3$-5% MeOH (3 fractions). The volume of the fractions was 100 mL until reaching $CHCl_3$-3% MeOH and from that point on it was 200 mL. Compound **264** elutes in the last two fractions of 100% $CHCl_3$ and until the first fraction of $CHCl_3$-2% MeOH. Compound **243DII** elutes starting with the second fraction of $CHCl_3$-2% MeOH, and continues to the first fraction of $CHCl_3$-5% MeOH. The crude compound **243DII** contained a

small amount of a colored impurity which was removed by a Sephadex column [LH-20 swollen in $CHCl_3$-MeOH (2:1), column (2.5 cm I.D. & 90 cm long) to yield 632 mg of compound **243DII**. Compound **264**: HPLC conditions: 98% at 7.2 min (method 1), chiral HPLC conditions: 29.0 min @ 25°C (method 2). Compound **243DIi**: HPLC conditions: 98% at 4.6 min (method 1), chiral HPLC conditions: 96% ee at 25.7 min (@ 25°C) & 19.8 min (@ 40°C) (method 2).

Example 265


(3aα,4β,7β,7aα(E)]-4-[Octahydro-4-methyl-1,3-dioxo-7-(4-oxo-4-phenyl-2-butenyl)-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile, (265)



The compound **247** (0.050 g, 0.134 mmol) was dissolved in THF (1.5 mL) and (phenacylidene)triphenylphosphorane (0.051 g, 0.134 mmol) was added. The reaction mixture was stirred at 67°C for 24 h and then cooled to 23°C and concentrated *in vacuo*. The crude material was then purified by preparative HPLC. (YMC VP-ODS column, 20 x 100 mm, eluting with 20% B to 100%B in 15 minutes and hold @ 100%B for 10 minutes.) to give compound **265** (0.040 g) as white solid. HPLC: 100% at 3.503 min (retention time) (YMC S5 ODS column 4.6 x 50 mm eluting with 10-90% aqueous methanol over 4 minutes containing 0.2% phosphoric acid, 4 mL/min, monitoring at 220 nm), MS (ES): m/z 477.1 $[M+H]^+$.

Example 266


(3aα,4β,7β,7aα(E)]-4-[Octahydro-4-methyl-1,3-dioxo-7-(4-oxo-4-phenyl-2-butenyl)-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile, (266)



Compound **265** (0.010 g, 0.021 mmol) was dissolved in EtOH (2.0 mL) and Pd/C (10% Pd, 0.005 g) was added. Hydrogen was then introduced via a balloon and the reaction was stirred at 25°C for 3 h. The reaction was then filtered through celite rinsing with EtOAc and concentrated *in vacuo* to give compound **266** as a tan solid (0.009 g). No purification was necessary. HPLC: 100% at 3.38 min (retention time) (YMC S5 ODS column 4.6 x 50 mm eluting with 10-90% aqueous methanol over 4 minutes containing 0.2% phosphoric acid, 4 mL/min, monitoring at 220 nm), MS (ES): m/z 503.2 $[M+Na]^+$.

Examples 267 to 378

Additional compounds of the present invention were prepared by procedures analogous to those described above. The compounds of Examples 267 to 378 have the following structure (L is a bond):





where G, R^7, the compound name, retention time, molecular mass, and the procedure employed, are set forth in **Table 5**. The absolute configuration for the following compounds was not determined. For simplicity in nomenclature, compound **238i** is designated herein as having an "R"

252







configuration and compound **238li** as having an "S" configuration. Enantiomerically pure products derived from compound **238l** are designated herein as having an "R" configuration and enantiomerically pure products derived from compound **238li** are designated herein as having an "S" configuration.

The chromatography techniques used to determine the compound retention times of **Table 5** are as follows: **LCMS** = YMC S5 ODS column, 4.6 X 50 mm eluting with 10-90% MeOH/H_2O over 4 minutes containing 0.1% TFA; 4 mL/min, monitoring at 220 nm. **LCMS*** = YMC S5 ODS column, 4.6 X 50 mm eluting with 10-90% MeOH/H_2O over 2 minutes containing 0.1% TFA; 4 mL/min, monitoring at 220 nm. **LC** = YMC S5 ODS column 4.6 x 50 mm eluting with 10-90% MeOH/H_2O over 4 minutes containing 0.2% phosphoric acid, 4 mL/min, monitoring at 220 nm. The molecular mass of the compounds listed in **Table 5** were determined by MS (ES) by the formula m/z.







Table 5.

Ex. No	G	R'	Compound Name	Retention Time Min./ Molecular Mass	Procedure of Ex.
267			(3aα,4β,7β,7aα)-(4-[7-[2-(4-Bromophenoxy)ethyl]octahydro-4-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-2-(trifluoromethyl)benzonitrile..	3.97 LCMS 549.0 $[M+H]^+$	204, 35






253

Ex. No	G	R^7	Compound Name	Retention Time Min./ Molecular Mass	Procedure of Ex.
268			(3aα,4β,7β,7aα)-4-[Octahydro-7-[2-(4-iodophenoxy)ethyl]-4-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-2-(trifluoromethyl)benzonitrile.	4.09 LCMS 597.0 $[M+H]^+$	204, 35
269			(3aα,4β,7β,7aα)-4-[Octahydro-4-methyl-1,3-dioxo-7-[2-[4-(trifluoromethyl)phenoxy]ethyl]-4,7-epoxy-2H-isoindol-2-yl]-2-(trifluoromethyl)benzonitrile.	3.95 LC	204, 35
270			(3aα,4β,7β,7aα)-4-[Octahydro-7-[2-(4-methoxyphenoxy)ethyl]-4-methyl-1,3-dioxo-4,7-epoxy-2H-	3.66 LC	204, 35






254

Ex. No	G	R'	Compound Name	Retention Time Min./ Molecular Mass	Procedure of Ex.
			isoindol-2-yl]-2-(trifluoromethyl)benzonitrile.		
271			(3aα,4β,7β,7aα)-4-[7-[2-(4-Ethoxyphenoxy)ethyl]octahydro-4-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-2-(trifluoromethyl)benzonitrile.	3.81 LC	204, 35
272			(3aα,4β,7β,7aα)-4-[7-[2-(4-Chlorophenoxy)ethyl]octahydro-4-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-2-(trifluoromethyl)benzonitrile.	3.97 LCMS 522.2 $[M+H]^+$	204, 35
273			(3aα,4β,7β,7aα)-4-[2-[2-[4-Cyano-3-(trifluoromethyl)phenyl]octahydro-7-methyl-1,3-dioxo-4,7-	3.77 LCMS 529.12 $[M+H]^+$	204, 35







255

Ex. No	G	R^7	Compound Name	Retention Time Min./ Molecular Mass	Procedure of Ex.
			epoxy-4H-isoindol-4-yl]ethoxy]benzoic acid, methyl ester.		
274			(3aα,4β,7β,7aα)-Hexahydro-4-(2-hydroxyethyl)-7-methyl-2-(3-methyl-4-nitrophenyl)-4,7-epoxy-1H-isoindole-1,3(2H)-dione.	2.44 LC	204, 35
275			(3aα,4β,7β,7aα)-4-[Octahydro-4-methyl-1,3-dioxo-7-[2-[4-(trifluoromethoxy)phenoxy]ethyl]-4,7-epoxy-2H-isoindol-2-yl]-2-(trifluoromethyl)benzonitrile.	3.97 LC	204, 35
276		CH_3	(3aα,4β,7β,7aα)-2-(3,5-Dichlorophenyl)hexahydro-4,7-dimethyl-	3.31 LCMS 341.2 $[M+H]^+$	20







256

Ex. No	G	R^7	Compound Name	Retention Time Min./ Molecular Mass	Procedure of Ex.
			4,7-epoxy-1H-isoindole-1,3(2H)-dione.		
277		CH_3	(3aα,4β,7β,7aα)-Hexahydro-4,7-dimethyl-2-(4-nitro-1-naphthalenyl)-4,7-epoxy-1H-isoindole-1,3(2H)-dione.	3.04 LCMS	20
278			(3aα,4β,7β,7aα)-4-[Octahydro-4-methyl-1,3-dioxo-7-[2-[4-(phenylmethoxy)phenoxy]ethyl]-4,7-epoxy-2H-isoindol-2-yl]-2-(trifluoromethyl)benzonitrile.	4.06 LC	204, 35
279			(3aα,4β,7β,7aα)-Hexahydro-4-(2-hydroxyethyl)-7-methyl-2-(4-nitro-1-naphthalenyl)-4,7-epoxy-1H-isoindole-1,3(2H)-dione.	2.607 & 2.743 rotational isomers LC	204, 35





257

Ex. No	G	R^7	Compound Name	Retention Time Min./ Molecular Mass	Procedure of Ex.
280			(3aα,4β,7β,7aα)-4-[2-(4-Fluorophenoxy)ethyl]hexahydro-7-methyl-2-(3-methyl-4-nitrophenyl)-4,7-epoxy-1H-isoindole-1,3(2H)-dione.	3.68 LC	204, 35
281			(3aα,4β,7β,7aα)-4-[Octahydro-4-methyl-1,3-dioxo-7-[2-[4-[(trifluoromethyl)thio]phenoxy]ethyl]-4,7-epoxy-2H-isoindol-2-yl]-2-(trifluoromethyl)benzonitrile.	4.11 LC	204, 35
282			(3aα,4β,7β,7aα)-4-[Octahydro-4-methyl-7-[2-(4-nitrophenoxy)ethyl]-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-2-	3.68 LC	204, 35







258







Ex. No	G	R⁷	Compound Name	Retention Time Min./ Molecular Mass	Procedure of Ex.
			(trifluoromethyl)benzonitrile.		
283			(3aα,4β,7β,7aα)-4-[2-(4-Fluorophenoxy)ethyl]hexahydro-7-methyl-2-(4-nitro-1-naphthalenyl)-4,7-epoxy-1H-isoindole-1,3(2H)-dione.	3.68 & 3.80 rotational isomers LC	204, 35
284			(3aα,4β,7β,7aα)-4-[Octahydro-7-methyl-1,3-dioxo-7-[2-[2-(trifluoromethyl)phenoxy]ethyl]-4,7-epoxy-2H-isoindol-2-yl]-2-(trifluoromethyl)benzonitrile.	3.89 LC	204, 35
285			(3aα,4β,7β,7aα)-4-[4-[2-(2-Bromophenoxy)ethyl]octahydro-7-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-2-	3.91 LC	204, 35

259






Ex. No	G	R^7	Compound Name	Retention Time Min./ Molecular Mass	Procedure of Ex.
			(trifluoromethyl)benzonitrile.		
286			(3aα,4β,7β,7aα)-4-[4-[2-(3-Fluorophenoxy)ethyl]octahydro-7-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-2-(trifluoromethyl)benzonitrile.	3.78 LC	204, 35
287		H	(3aα,4β,7β,7aα)-Hexahydro-2-[4-(1H-imidazol-1-yl)phenyl]-4-methyl-4,7-epoxy-1H-isoindole-1,3(2H)-dione.	1.16 LC	3
288		H	(3aα,4β,7β,7aα)-2-[3-Chloro-4-(2-thiazolyl)phenyl]hexahydro-4-methyl-4,7-epoxy-1H-isoindole-1,3(2H)-dione.	2.81 LC	3

250




Ex. No	G	R^7	Compound Name	Retention Time Min./ Molecular Mass	Procedure of Ex.
289		CH_3	(3aα,4β,7β,7aα)-Hexahydro-4,7-dimethyl-2-(3-methyl-4-nitrophenyl)-4,7-epoxy-1H-isoindole-1,3(2H)-dione.	2.74 LC	20
290		CH_3	(3aα,4β,7β,7aα)-Hexahydro-4,7-dimethyl-2-(2-methyl-4-nitrophenyl)-4,7-epoxy-1H-isoindole-1,3(2H)-dione.	2.71 LC	20
291			(3aα,4β,7β,7aα)-2-(3,5-Dichlorophenyl)hexahydro-4-(2-hydroxyethyl)-7-methyl-4,7-epoxy-1H-isoindole-1,3(2H)-dione.	2.98 LC	204
292			(3aα,4β,7β,7aα)-2-(3,5-Dichlorophenyl)-4-[2-(4-fluorophenoxy)ethyl]hexahyd	4.03 LC	204, 35

Ex. No	G	R^7	Compound Name	Retention Time Min./ Molecular Mass	Procedure of Ex.
			ro-7-methyl-4,7-epoxy-1H-isoindole-1,3(2H)-dione.		
293			(3aα,4β,7β,7aα)-4-[Octahydro-4-[2-(4-hydroxyphenoxy)ethyl]-7-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-2-(trifluoromethyl)benzonitrile.	3.25 LC	204, 35
294			(3aα,4β,7β,7aα)-4-[4-[2-(4-Cyanophenoxy)ethyl]octahydro-7-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-2-(trifluoromethyl)benzonitrile.	3.51 LC	204, 35
295			(3aα,4β,7β,7aα)-4-[Octahydro-4-methyl-1,3-dioxo-7-[2-[3-	3.85 LC	204, 35






262

Ex. No	G	R^7	Compound Name	Retention Time Min./ Molecular Mass	Procedure of Ex.
			(trifluoromethyl)phenoxy]ethyl]-4,7-epoxy-2H-isoindol-2-yl]-2-(trifluoromethyl)benzonitrile.		
296			(3aα,4β,7β,7aα)-4-[4-[2-(3-Bromophenoxy)ethyl]octahydro-7-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-2-(trifluoromethyl)benzonitrile.	3.84 LC	204, 35
297			(3aα,4β,7β,7aα)-4-[4-[(4-Fluorophenyl)methyl]octahydro-7-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-2-(trifluoromethyl)benzonitrile.	3.73 LC	205
298		CH_3	(3aα,4β,7β,7aα)-2-(1,6-Dihydro-1-methyl-6-oxo-	1.61 LC	20





263







Ex. No	G	R⁷	Compound Name	Retention Time Min./ Molecular Mass	Procedure of Ex.
			3-pyridinyl)hexahydro-4,7-dimethyl-4,7-epoxy-1H-isoindole-1,3(2H)-dione.		
299		CH_3	(3aα,4β,7β,7aα)-Hexahydro-4,7-dimethyl-2-(1-methyl-6-oxo-3-piperidinyl)-4,7-epoxy-1H-isoindole-1,3(2H)-dione.	1.73 LC	20
300			(3aα,4β,7β,7aα)-4-[4-[2-(3-Cyanophenoxy)ethyl]octahydro-7-methyl-1,3-dioxo-4,7-epoxy-2H-Isoindol-2-yl]-2-(trifluoromethyl)benzonitrile.	3.46 LC	20





264






Ex. No	G	R'	Compound Name	Retention Time Min./ Molecular Mass	Procedure of Ex.
301			(3aα,4β,7β,7aα)-4-[2-[4-Cyano-3-(trifluoromethyl)phenyl]octahydro-7-methyl-1,3-dioxo-4,7-epoxy-4H-isoindol-4-yl]ethoxy]benzoic acid, phenylmethyl ester.	4.01 LC	204, 35
302			(3aα,4β,7β,7aα)-4-[Octahydro-4-methyl-1,3-dioxo-7-(2-phenoxyethyl)-4,7-epoxy-2H-isoindol-2-yl]-2-(trifluoromethyl)benzonitrile.	3.57 LC	204, 35
303		CH_3	(3aα,4β,7β,7aα)-2-(3,5-Dichloro-4-nitrophenyl)hexahydro-4,7-dimethyl-4,7-epoxy-1H-isoindole-1,3(2H)-dione.	3.40 LC	20

265





Ex. No	G	R^7	Compound Name	Retention Time Min./ Molecular Mass	Procedure of Ex.
304		CH_3	(3aα,4β,7β,7aα)-2-(3,5-Dichloro-4-hydroxyphenyl)hexahydro-4,7-dimethyl-4,7-epoxy-1H-isoindole-1,3(2H)-dione.	2.58 LC	20
305		CH_3	(3aα,4β,7β,7aα)-2-(5-Fluoro-1-naphthalenyl)hexahydro-4,7-dimethyl-4,7-epoxy-1H-isoindole-1,3(2H)-dione.	2.96 & 3.06 rotational isomers LC	20
306		CH_3	(3aα,4β,7β,7aα)-Hexahydro-4,7-dimethyl-2-(1-naphthalenyl)-4,7-epoxy-1H-isoindole-1,3(2H)-dione.	2.60 & 2.73 rotational isomers LC	20
307		CH_3	(3aα,4β,7β,7aα)-Hexahydro-2-[3-methoxy-4-(5-oxazolyl)phenyl]-4,7-	2.62 rotational isomers LC	20

Ex. No	G	R'	Compound Name	Retention Time Min./ Molecular Mass	Procedure of Ex.
			dimethyl-4,7-epoxy-1H-isoindole-1,3(2H)-dione.		
308			(3aα,4β,7β,7aα)-Hexahydro-4-[2-(4-methoxyphenoxy)ethyl]-7-methyl-2-(4-nitro-1-naphthalenyl)-4,7-epoxy-1H-Isoindole-1,3(2H)-dione.	3.42 & 3.55 rotational isomers LC	204, 35
309			(3aα,4β,7β,7aα)-Hexahydro-4-methyl-2-(4-nitro-1-naphthalenyl)-7-[2-[4-(trifluoromethyl)phenoxy]ethyl]-4,7-epoxy-1H-Isoindole-1,3(2H)-dione.	3.81 & 3.93 rotational isomers LC	204, 35
310			(3aα,4β,7β,7aα)-Hexahydro-4-methyl-2-(4-nitro-1-naphthalenyl)-7-[2-(4-nitrophenoxy)	3.48 & 3.61 rotational isomers LC	204, 35







Ex. No	G	R'	Compound Name	Retention Time Min./ Molecular Mass	Procedure of Ex.
			ethyl]-4,7-epoxy-1H-isoindole-1,3(2H)-dione.		
311		CH_3	(3aα,4β,7β,7aα)-2-(1,6-Dihydro-1,4-dimethyl-6-oxo-3-pyridinyl)hexahydro-4,7-dimethyl-4,7-epoxy-1H-isoindole-1,3(2H)-dione.	1.89 LC	20
312			(3aα,4β,7β,7aα)-4-[Octahydro-7-methyl-2-(4-nitro-1-naphthalenyl)-1,3-dioxo-4,7-epoxy-4H-isoindol-4-yl]ethoxy]benzonitrile.	3.63 LC	204, 35
313		CH_3	(3aα,4β,7β,7aα)-4-(Octahydro-4,7-dimethyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl)-	2.38 LC	20

Ex. No	G	R'	Compound Name	Retention Time Min./ Molecular Mass	Procedure of Ex.
			1,2-benzenedicarbonitrile.		
314			(3aα,4β,7β,7aα)-4-(2-Bromoethyl)hexahydro-7-methyl-2-(4-nitro-1-naphthalenyl)-4,7-epoxy-1H-isoindole-1,3(2H)-dione.	3.52 LC	36
315			(3aα,4β,7β,7aα)-4-[4-[2-(4-Cyanophenoxy)ethyl]octahydro-7-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile.	3.19 & 3.35 rotational isomers LC	223, 35
316			(3aα,4β,7β,7aα)-4-[Octahydro-4-[2-(4-methoxyphenoxy)ethyl]-7-methyl-1,3-dioxo-4,7-epoxy-2H-	3.34 & 3.50 rotational isomers LC	223, 35





269





Ex. No	G	R⁷	Compound Name	Retention Time Min./ Molecular Mass	Procedure of Ex.
			isoindol-2-yl]-1-naphthalenecarbonitrile.		
317			(3aα,4β,7β,7aα)-4-[Octahydro-4-[2-(3-methoxyphenoxy)ethyl]-7-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile.	3.34 & 3.50 rotational isomers LC	223, 35
318			(3aα,4β,7β,7aα)-4-[4-[2-(3-Fluorophenoxy)ethyl]octahydro-7-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile.	3.46 & 3.61 rotational isomers LC	223, 35

270




Ex. No	G	R'	Compound Name	Retention Time Min./ Molecular Mass	Procedure of Ex.
319			(3aα,4β,7β,7aα)-4-[Octahydro-4-methyl-7-[2-[3-(4-morpholinyl)phenoxy]ethyl]-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile.	3.01 & 3.18 rotational Isomers LC	223, 35
320			(3aα,4β,7β,7aα)-4-[Octahydro-4-methyl-7-[2-[4-nitro-3-(trifluoromethyl)phenoxy]ethyl]-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile.	3.70 & 3.83 rotational Isomers LC	223, 35
321			(3aα,4β,7β,7aα)-4-[4-[2-(3-Cyanophenoxy)ethyl]octahydro-7-methyl-1,3-dioxo-4,7-epoxy-2H-	3.39 & 3.55 rotational Isomers LC	223, 35

271






Ex. No	G	R'	Compound Name	Retention Time Min./ Molecular Mass	Procedure of Ex.
			isoindol-2-yl]-1-naphthalenecarbonitrile.		
322		CH_3	(3aα,4β,7β,7aα)-2-(2,3-Dihydro-3-methyl-2-oxo-6-benzothiazolyl)hexahydro-4,7-dimethyl-4,7-epoxy-1H-isoindole-1,3(2H)-dione.	2.34 rotational isomers LC	20
323		CH_3	(3aα,4β,7β,7aα)-2-(2,3-Dihydro-2-oxo-6-benzothiazolyl)hexahydro-4,7-dimethyl-4,7-epoxy-1H-isoindole-1,3(2H)-dione.	2.16 LC	20
324			(3aα,4β,7β,7aα)-4-[4-[2-[3-(Dimethylamino)phenoxy]ethyl]octahydro-7-methyl-1,3-dioxo-4,7-epoxy-2H-	2.63 & 2.79 rotational isomers LC	223, 35

Ex. No	G	R^7	Compound Name	Retention Time Min./ Molecular Mass	Procedure of Ex.
			isoindol-2-yl]-1-naphthalenecarbonitrile.		
325			(3aα,4β,7β,7aα)-4-[2-[4-Cyano-3-(trifluoromethyl)phenyl]octahydro-7-methyl-1,3-dioxo-4,7-epoxy-4H-isoindol-4-yl]ethoxy]-1,2-benzenedicarbonitrile.	3.42 rotational isomers LC	223, 35
326		CH_3	(3aα,4β,7β,7aα)-N-[2-Cyano-5-(octahydro-4,7-dimethyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl)phenyl]acetamide.	1.94 LC	20
327		CH_3	(3aα,4β,7β,7aα)-4-(Octahydro-4,7-dimethyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl)-	3.52 LC	20







223



Ex. No	G	R^7	Compound Name	Retention Time Min./ Molecular Mass	Procedure of Ex.
			2-(trifluoromethoxy)benzonitrile.		
328		CH_3	(3aα,4β,7β,7aα)-2-Methoxy-4-(octahydro-4,7-dimethyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl)benzonitrile.	2.47 LC	20
329		CH_3	(3aα,4β,7β,7aα)-2-[4-(4,5-Dichloro-1H-imidazol-1-yl)phenyl]hexahydro-4,7-dimethyl-4,7-epoxy-1H-isoindole-1,3(2H)-dione.	3.09 LC	20
330		CH_3	(3aα,4β,7β,7aα)-2-[4-(4-Bromo-1-methyl-1H-pyrazol-3-yl)phenyl]hexahydro-4,7-dimethyl-4,7-epoxy-1H-isoindole-1,3(2H)-dione.	3.04 LC	20

274





Ex. No	G	R^7	Compound Name	Retention Time Min./ Molecular Mass	Procedure of Ex.
331			(3aα,4β,7β,7aα)-4-[Octahydro-4-(2-hydroxyethyl)-7-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile.	2.44 & 2.60 rotational isomers LC	223, 35
332		CH_3	(3aα,4β,7β,7aα)-2-Iodo-4-(Octahydro-4,7-dimethyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl)benzonitrile.	2.78 rotational isomers LC	20
333			(3aα,4β,7β,7aα)-4-[4-[2-(4-Fluorophenoxy)ethyl]octahydro-7-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile.	3.39 & 3.53 rotational isomers LC	223, 35





225

Ex. No	G	R'	Compound Name	Retention Time Min./ Molecular Mass	Procedure of Ex.
334			(3aα,4β,7β,7aα)-4-[Octahydro-4-methyl-1,3-dioxo-7-[2-[4-(trifluoromethyl)phenoxy]ethyl]-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile.	3.66 & 3.78 rotational isomers LC	223, 35
335			(3aα,4β,7β,7aα)-4-[4-[2-(4-Cyano-3-fluorophenoxy)ethyl]octahydro-7-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile.	3.26 & 3.41 rotational isomers LC	223, 35
336			(3aα,4β,7β,7aα)-4-[Octahydro-4-methyl-1,3-dioxo-7-[2-[2,3,5,6-tetrafluoro-4-(trifluoromethyl)phenoxy]ethy	3.94 & 4.01 rotational isomers LC	223, 35





Ex. No	G	R'	Compound Name	Retention Time Min./ Molecular Mass	Procedure of Ex.
			l]-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile.		
337		CH_3	(3aα,4β,7β,7aα)-Hexahydro-4,7-dimethyl-2-[4-(1H-1,2,4-triazol-3-yl)phenyl]-4,7-epoxy-1H-isoindole-1,3(2H)-dione.	2.06 LC	20
338		CH_3	(3aα,4β,7β,7aα)-2-[4-(4,5-Dihydro-5-oxo-1,2,4-oxadiazol-3-yl)phenyl]hexahydro-4,7-dimethyl-4,7-epoxy-1H-isoindole-1,3(2H)-dione.	2.42 LC	20
339		CH_3	(3aα,4β,7β,7aα)-Hexahydro-2-[3-methoxy-4-(2-oxazolyl)phenyl]-4,7-dimethyl-4,7-epoxy-1H-	2.51 LC	20





277





Ex. No	G	R^7	Compound Name	Retention Time Min./ Molecular Mass	Procedure of Ex.
			isoindole-1,3(2H)-dione.		
340		CH_3	(3aα,4β,7β,7aα)-Hexahydro-2-(4-hydroxy-1-naphthalenyl)-4,7-dimethyl-4,7-epoxy-1H-isoindole-1,3(2H)-dione.	2.30 LC	20
341		CH_3	(3aα,4β,7β,7aα)-Hexahydro-2-(8-hydroxy-5-quinolinyl)-4,7-dimethyl-4,7-epoxy-1H-isoindole-1,3(2H)-dione, trifluoroacetate (1:1).	1.49 LC	20
342			(3aα,4β,7β,7aα)-4-[Octahydro-4-methyl-1,3-dioxo-7-[2-[methyl(phenylmethyl)amino]ethyl]-4,7-epoxy-2H-isoindol-2-yl]-2-(trifluoromethy	2.42 LC	223, 35





Ex. No	G	R^7	Compound Name	Retention Time Min./ Molecular Mass	Procedure of Ex.
			l)benzonitrile.		
343		CH_3	(3aα,4β,7β,7aα)-Hexahydro-4,7-dimethyl-2-(5-quinolinyl)-4,7-epoxy-1H-isoindole-1,3(2H)-dione.	1.69 LC	20
344		CH_3	(3aα,4β,7β,7aα)-5-(Octahydro-4,7-dimethyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl)-2-pyridinecarbonitrile.	2.18 LC	20
345		CH_3	(3aα,4β,7β,7aα)-5-(Octahydro-4,7-dimethyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl)-8-quinolinecarbonitrile.	2.31 LC	20
346		CH_3	(3aα,4β,7β,7aα)-2-(5-Bromo-4-nitro-	3.10 & 3.29 rotational isomers LC	20

279





Ex. No	G	R'	Compound Name	Retention Time Min./ Molecular Mass	Procedure of Ex.
			1-naphthalenyl)hexahydro-4,7-dimethyl-4,7-epoxy-1H-isoindole-1,3(2H)-dione.		
347		CH_3	(3aα,4β,7β,7aα)-2-(5-Bromo-1-naphthalenyl)hexahydro-4,7-dimethyl-4,7-epoxy-1H-isoindole-1,3(2H)-dione.	3.28 & 3.40 rotational isomers LC	20
348		CH_3	(3aα,4β,7β,7aα)-Hexahydro-4,7-dimethyl-2-[8-(trifluoromethyl)-4-quinolinyl]-4,7-epoxy-1H-isoindole-1,3(2H)-dione.	3.08 LC	20
349			4-Fluorobenzoic acid, 2-[(3aα,4β,7β,7aα)-2-(4-cyano-1-naphthalenyl)octahydro-7-	3.64 & 3.77 rotational isomers LC	223

Ex. No	G	R'	Compound Name	Retention Time Min./ Molecular Mass	Procedure of Ex.
			methyl-1,3-dioxo-4,7-epoxy-4H-isoindol-4-y]ethyl ester.		
350			Benzeneacetic acid, 2-[(3aα,4β,7β,7aα)-2-(4-cyano-1-naphthalenyl)octahydro-7-methyl-1,3-dioxo-4,7-epoxy-4H-isoindol-4-y]ethyl ester.	3.53 & 3.67 rotational isomers LC	223
351			4-Fluorobenzeneacetic acid, 2-[(3aα,4β,7β,7aα)-2-(4-cyano-1-naphthalenyl)octahydro-7-methyl-1,3-dioxo-4,7-epoxy-4H-isoindol-4-y]ethyl ester.	3.53 & 3.66 rotational isomers LC	223







Ex. No	G	R'	Compound Name	Retention Time Min./ Molecular Mass	Procedure of Ex.
352			(3aα,4β,7β,7aα)-Hexahydro-4-methyl-7-[2-[4-(methylsulfonyl)phenoxy]ethyl]-2-(4-nitro-1-naphthalenyl)-4,7-epoxy-1H-isoindole-1,3(2H)-dione.	3.31 LC	223, 35
353		CH_3	(3aα,4β,7β,7aα)-Hexahydro-2-(2-naphthalenyl)-4,7-dimethyl-4,7-epoxy-1H-isoindole-1,3(2H)-dione.	2.94 LC	20
354		CH_3	(3aα,4β,7β,7aα)-2-(4-Chloro-1-naphthalenyl)hexahydro-4,7-dimethyl-4,7-epoxy-1H-isoindole-1,3(2H)-dione.	3.22 & 3.34 rotational isomers LC	20

Ex. No	G	R^7	Compound Name	Retention Time Min./ Molecular Mass	Procedure of Ex.
355			(3aα,4β,7β,7aα)-N-[(4-Chlorophenyl)methyl]-2-(4-cyano-1-naphthalenyl)octahydro-7-methyl-1,3-dioxo-4,7-epoxy-4H-isoindole-4-acetamide.	3.52 LC	237
356			4,7,7-Trimethyl-3-oxo-2-oxabicyclo[2.2.1]heptane-1-carboxylic acid, 2-[(3aα,4β,7β,7aα)-2-(4-cyano-1-naphthalenyl)octahydro-7-methyl-1,3-dioxo-4,7-epoxy-4H-isoindol-4-yl]ethyl ester.	3.45 LC	223







283

Ex. No	G	R'	Compound Name	Retention Time Min./ Molecular Mass	Procedure of Ex.
357			(αS)- α-Methoxy-α-(trifluoromethyl)benzeneacetic acid, 2-[(3aα,4β,7β,7aα)-2-(4-cyano-1-naphthalenyl)octahydro-7-methyl-1,3-dioxo-4,7-epoxy-4H-isoindol-4-y]ethyl ester.	3.91 LC	223
358			(αR)- α-Methoxy-α-(trifluoromethyl)benzeneacetic acid, 2-[(3aα,4β,7β,7aα)-2-(4-cyano-1-naphthalenyl)octahydro-7-methyl-1,3-dioxo-4,7-epoxy-4H-isoindol-4-y]ethyl ester.	2.00 LC	223





284

Ex. No	G	R^7	Compound Name	Retention Time Min./ Molecular Mass	Procedure of Ex.
359			(3aα,4β,7β,7aα)-4-[Octahydro-4-methyl-7-[2-[(7-methyl-1,2-benzisoxazol-3-yl)oxy]ethyl]-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile.	3.79 & 3.92 LC Rotationale Isomers	250
360			(3aα,4β,7β,7aα)-4-[4-[2-(1,2-Benzisoxazol-3-yloxy)ethyl]octahydro-7-methyl-1,3-dioxo-4,7-epoxy-2H-Isoindol-2-yl]-1-naphthalenecarbonitrile.	3.55 & 3.70 LC Rotationale Isomers	250
361			(3aα,4β,7β,7aα)-4-[2-(Benzoyloxy)ethyl]-2-(4-cyano-1-naphthalenyl)hexahydro-7-	3.51 & 3.66 LC Rotationale isomers	223






285

Ex. No	G	R^7	Compound Name	Retention Time Min./ Molecular Mass	Procedure of Ex.
			methyl-4,7-epoxy-1H-isoindole-1,3(2H)-dione.		
362			(3aα,4β,7β,7aα)-2-(4-Cyano-1-naphthalenyl)-4-[2-[(4-nitrobenzoyl)oxy]ethyl]hexahydro-7-methyl-4,7-epoxy-1H-isoindole-1,3(2H)-dione.	3.52 & 3.67 LC Rotationale isomers	223
363			4-Chlorobenzoic acid, 2-[(3aα,4β,7β,7aα)-2-(4-cyano-1-naphthalenyl)octahydro-7-methyl-1,3-dioxo-4,7-epoxy-4H-isoindol-4-yl]ethyl ester.	3.79 LC	223
364			[3aα,4β,7β,7aα(E)]-4-[Octahydro-4-methyl-7-[3-(1-naphthalenyl)-	4.14 LC 499.13 $[M+H]^+$	248







286

Ex. No	G	R'	Compound Name	Retention Time Min./ Molecular Mass	Procedure of Ex.
			2-propenyl]-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile.		
365			(3aα,4β,7β,7aα)-4-[Octahydro-4-methyl-7-[3-(1-naphthalenyl)propyl]-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile.	4.14 LC 501.14 $[M+H]^+$	248, 249
366		CH_3	(3aα,4β,7β,7aα)-Hexahydro-4,7-dimethyl-2-(2-methyl-6-quinolinyl)-4,7-epoxy-1H-isoindole-1,3(2H)-dione.	1.25 LC 337.0 $[M+H]^+$	20
367		CH_3	(3aα,4β,7β,7aα)-Hexahydro-2-(5-isoquinolinyl)-4,7-dimethyl-4,7-epoxy-1H-	1.06 & 1.29 LC Rotationale Isomers 323.0 $[M+H]^+$	20









287

Ex. No	G	R'	Compound Name	Retention Time Min./ Molecular Mass	Procedure of Ex.
			isoindole-1,3(2H)-dione.		
368		CH_3	(3aα,4β,7β,7aα)-2-(6-Benzothiazolyl)hexahydro-4,7-dimethyl-4,7-epoxy-1H-isoindole-1,3(2H)-dione.	2.15 LC 329.0 $[M+H]^+$	20
369			[3aα,4β,7β,7aα(E)]-4-[Octahydro-4-methyl-1,3-dioxo-7-(4-oxo-4-phenyl-2-butenyl)-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile.	3.50 LC 482.14 $[M+H]^+$	248
370			(3aα,4β,7β,7aα)-2-(4-Cyano-1-naphthalenyl)octahydro-N-(2-hydroxyphenyl)-7-methyl-1,3-dioxo-4,7-epoxy-4H-isoindole-4-acetamide.	3.07 LC 482.14 $[M+H]^+$	236



288

Ex. No	G	R'	Compound Name	Retention Time Min./ Molecular Mass	Procedure of Ex.
371			[3aα,4β(E),7β, 7aα]-4-[Octahydro-4-methyl-7-[3-(6-methyl-2-pyridinyl)-2-propenyl]-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile.	2.28 LC 464.19 $[M+H]^+$	248
372			(3aα,4β,7β,7aα)-4-[Octahydro-4-methyl-7-[3-(6-methyl-2-pyridinyl)propyl]-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile.	2.19 LC 466.32 $[M+H]^+$	248, 249
373			[3aR-(3aα,4β,7β,7aα)]-4-[Octahydro-4-[2-(3-methoxyphenoxy)ethyl]-7-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-1-	3.73 LC 483.65 $[M+H]^+$	238I, 239I

289


Ex. No	G	R^7	Compound Name	Retention Time Min./ Molecular Mass	Procedure of Ex.
			naphthalenecarbonitrile.		
374			[3aS-(3aα,4β,7β,7aα)]-4-[Octahydro-4-[2-(3-methoxyphenoxy)ethyl]-7-methyl-1,3-dioxo-4,7-epoxy-2H-Isoindol-2-yl]-1-naphthalenecarbonitrile.	3.73 LC	238ii, 239ii
375			[3aR-(3aα,4β,7β,7aα)]-4-[4-[2-(4-Cyanophenoxy)ethyl]octahydro-7-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile.	3.33 & 3.49 LC Rotationale Isomers	238l, 239l
376			[3aS-(3aα,4β,7β,7aα)]-4-[4-[2-(4-Cyanophenoxy)ethyl]octahydro-7-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile.	3.73 LC 483.65 $[M+H]^+$	238ii, 239ii
377			[3aα,4β(E),7β,7aα]-4-[4-[3-(1H-Benzimidazol-2-yl)-2-propenyl]octahydro-7-methyl-1,3-dioxo-4,7-epoxy-2H-	2.48 LC 489.26 $[M+H]^+$	248

290

Ex. No	G	R^7	Compound Name	Retention Time Min./ Molecular Mass	Procedure of Ex.
			isoindol-2-yl]-1-naphthalenecarbonitrile		
378			(3aα,4β,7β,7aα)-4-[4-[3-(1H-Benzimidazol-2-yl)propyl]octahydro-7-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile	2.37 LC 491.26 $[M+H]^+$	249

Examples 379 to 381

Additional compounds of the present invention were prepared by procedures analogous to those described above. The compounds of Examples 379 to 381 have the following structure (L is a bond):







where G, R^7, the compound name, retention time, molecular mass, and the procedure employed, are set forth in **Table 6**. The chromatography techniques used to determine the compound retention times of **Table 6** are as follows: **LCMS** = YMC S5 ODS column, 4.6 X 50 mm eluting with 10-90% MeOH/H_2O over 4 minutes containing 0.1% TFA; 4 mL/min, monitoring at 220 nm. **LCMS*** = YMC S5 ODS column, 4.6 X 50 mm eluting with 10-90% MeOH/H_2O over 2 minutes containing 0.1% TFA; 4 mL/min, monitoring at 220 nm. **LC** = YMC S5 ODS column 4.6 x 50 mm eluting

291

with 10-90% MeOH/H_2O over 4 minutes containing 0.2% phosphoric acid, 4 mL/min, monitoring at 220 nm.

The molecular mass of the compounds listed in **Table 6** were determined by MS (ES) by the formula m/z.

Table 6

Ex. No	G	R^7	Compound Name	Retention Time Min./ Molecular Mass	Procedure of Ex.
379			(3aα,4α,7α,7aα)-4-[4-[(4-Fluorophenyl)methyl]octahydro-7-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-2-(trifluoromethyl)benzonitrile.	3.75 LC	205
380		CH_3	(3aα,4α,7α,7aα)-Hexahydro-4,7-dimethyl-2-(1-methyl-6-oxo-3-piperidinyl)-4,7-epoxy-1H-isoindole-1,3(2H)-dione.	1.88 LC	27
381		CH_3	(3aα,4α,7α,7aα)-2-(1,6-Dihydro-1,4-dimethyl-6-oxo-3-	1.91 LC	27

292



Ex. No	G	R^7	Compound Name	Retention Time Min./ Molecular Mass	Procedure of Ex.
			pyridinyl)hexahydro-4,7-dimethyl-4,7-epoxy-1H-isoindole-1,3(2H)-dione.		

Examples 382 to 383

Additional compounds of the present invention were prepared by procedures analogous to those described above. The compounds of Examples 382 to 383 have the structure, compound name, retention time, molecular mass, and were prepared by the procedure employed, set forth in the following Table 7. The chromatography techniques used to determine the compound retention times of Table 7 are as follows: LCMS = YMC S5 ODS column, 4.6 X 50 mm eluting with 10-90% MeOH/H_2O over 4 minutes containing 0.1% TFA; 4 mL/min, monitoring at 220 nm. LCMS* = YMC S5 ODS column, 4.6 X 50 mm eluting with 10-90% MeOH/H_2O over 2 minutes containing 0.1% TFA; 4 mL/min, monitoring at 220 nm. LC = YMC S5 ODS column 4.6 x 50 mm eluting with 10-90% MeOH/H_2O over 4 minutes containing 0.2% phosphoric acid, 4 mL/min, monitoring at 220 nm. The molecular mass of the compounds listed in Table 7 were determined by MS (ES) by the formula m/z.


293

Table 7

Ex. No.	Structure	Compound Name	Retention Time Min.	Procedure of Example
382		(3aα,4β,7β,7aα)-2-[4-Cyano-3-(trifluoromethyl)phenyl]octahydro-1,3-dioxo-7-[2-(phenylmethoxy)ethyl]-4,7-epoxy-4H-isoindole-4-propanenitrile.	3.63 LC	255
383		(3aα,4β,7β,7aα)-2-[4-Cyano-3-(trifluoromethyl)phenyl]octahydro-1,3-dioxo-7-[2-(phenylmethoxy)ethyl]-4,7-epoxy-4H-isoindole-4-propanenitrile	3.64 LC	255

Examples 384 to 418

Additional compounds of the present invention were prepared by procedures analogous to those described above. The compounds of Examples 384 to 418 have the following structure (L is a bond):





294







where G, R^7, the compound name, retention time, molecular mass, and the procedure employed, are set forth in **Table 8**. The absolute configuration for the following compounds was not determined. For simplicity in nomenclature, compound **243DI** is designated herein as having an "S" configuration and compound **243DII** as having an "R" configuration. Enantiomerically pure products derived from compound **243DI** are designated herein as having an "S" configuration and enantiomerically pure products derived from compound **243DII** are designated herein as having an "R" configuration.

The chromatography techniques used to determine the compound retention times of **Table 8** are as follows: **LCMS** = YMC S5 ODS column, 4.6 X 50 mm eluting with 10-90% MeOH/H_2O over 4 minutes containing 0.1% TFA; 4 mL/min, monitoring at 220 nm. **LCMS*** = YMC S5 ODS column, 4.6 X 50 mm eluting with 10-90% MeOH/H_2O over 2 minutes containing 0.1% TFA; 4 mL/min, monitoring at 220 nm. **LC** = YMC S5 ODS column 4.6 x 50 mm eluting with 10-90% MeOH/H_2O over 4 minutes containing 0.2% phosphoric acid, 4 mL/min, monitoring at 220 nm. The molecular mass of the compounds listed in **Table 8** were determined by MS (ES) by the formula m/z.





Table 8







Ex. No	G	R^7	Compound Name	Retention Time Min./ Molecular Mass	Procedure of Ex.
384			(3aα,4β,7β,7aα) -4-[7-[2-(4-Cyanophenoxy) ethyl]octahydro-5-hydroxy-4-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-	3.18 LC 494.40 $[M+H]^+$	227, 228, 229

295







Ex. No	G	R^7	Compound Name	Retention Time Min./ Molecular Mass	Procedure of Ex.
			y]-1-naphthalenecarbonitrile.		
385			[3aS-(3aα,4β,7β,7aα)]-4-[7-[2-(1,3-Benzodioxol-5-yloxy)ethyl]octahydro-5-hydroxy-4-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile.	3.19 LC 571.3 [M-H+OAc]⁻	234Di, 243i
386			[3aR-(3aα,4β,7β,7aα)]-4-[7-[2-(1,3-Benzodioxol-5-yloxy)ethyl]octahydro-5-hydroxy-4-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile.	3.22 LC 571.2 [M-H+OAc]⁻	234Dii, 243ii
387			[3aS-(3aα,4β,7β,7aα)]-4-[7-[2-[(5-Chloro-2-pyridinyl)oxy]ethyl]octahydro-5-	3.37 LC 562.2 [M-H+OAc]⁻	234Di, 243i





296

Ex. No	G	R^7	Compound Name	Retention Time Min./ Molecular Mass	Procedure of Ex.
			hydroxy-4-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile.		
388			[3aR-(3aα,4β,7β,7aα)]-4-[7-[2-[(5-Chloro-2-pyridinyl)oxy]ethyl]octahydro-5-hydroxy-4-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile.	3.37 LC 504.0 $[M+H]^+$	234Dii, 243II
389			[3aS-(3aα,4β,7β,7aα)]-4-[7-[2-(4-Chlorophenoxy)ethyl]octahydro-5-hydroxy-4-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile.	3.51 LC 503.08 $[M+H]^+$	234DI, 243I





Ex. No	G	R'	Compound Name	Retention Time Min./ Molecular Mass	Procedure of Ex.
390			[3aR-(3aα,4β,7β,7aα)]-4-[7-[2-(4-Chlorophenoxy)ethyl]octahydro-5-hydroxy-4-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile.	3.51 LC 503.08 $[M+H]^+$	234Dii, 243ii
391			[3aS-(3aα,4β,7β,7aα)]-4-[7-[2-(4-Acetylphenoxy)ethyl]octahydro-5-hydroxy-4-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile.	3.05 LC 511.13 $[M+H]^+$	234Di, 243l
392			[3aR-(3aα,4β,7β,7aα)]-4-[7-[2-(4-Acetylphenoxy)ethyl]octahydro-5-hydroxy-4-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-	3.05 LC 503.13 $[M+H]^+$	234Dii, 243ii

298







Ex. No	G	R'	Compound Name	Retention Time Min./ Molecular Mass	Procedure of Ex.
			y]-1-naphthalenecarbonitrile.		
393			[3aS-(3aα,4β,7β,7aα)]-4-[7-[2-(3-Cyanophenoxy)ethyl]octahydro-5-hydroxy-4-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-y]-1-naphthalenecarbonitrile.	3.09 LC 494.13 $[M+H]^+$	234Di, 243l
394			[3aR-(3aα,4β,7β,7aα)]-4-[7-[2-(3-Cyanophenoxy)ethyl]octahydro-5-hydroxy-4-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-y]-1-naphthalenecarbonitrile.	3.09 LC 494.13 $[M+H]^+$	234Dii, 243ii
395			[3aS-(3aα,4β,7β,7aα)]-4-[Octahydro-5-hydroxy-4-methyl-1,3-dioxo-7-[2-	3.85 LC 523.17 $[M+H]^+$	234Di, 243l

Ex. No	G	R7	Compound Name	Retention Time Min./ Molecular Mass	Procedure of Ex.
			[(5,6,7,8-tetrahydro-1-naphthalenyl)oxy]ethyl]-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile.		
396			[3aR-(3aα,4β,7β,7aα)]-4-[Octahydro-5-hydroxy-4-methyl-1,3-dioxo-7-[2-[(5,6,7,8-tetrahydro-1-naphthalenyl)oxy]ethyl]-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile.	3.85 LC 523.17 [M+H]+	234Dii, 243ii
397			[3aS-(3aα,4β,7β,7aα)]-4-[Octahydro-5-hydroxy-4-methyl-1,3-dioxo-7-[2-[(5,6,7,8-tetrahydro-5-oxo-1-naphthalenyl)oxy]ethyl]-4,7-	3.29 LC 537.13 [M+H]+	234Di, 243i





300

Ex. No	G	R⁷	Compound Name	Retention Time Min./ Molecular Mass	Procedure of Ex.
			epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile.		
398			[3aR-(3aα,4β,7β,7aα)]-4-[Octahydro-5-hydroxy-4-methyl-1,3-dioxo-7-[2-[(5,6,7,8-tetrahydro-5-oxo-1-naphthalenyl)oxy]ethyl]-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile.	3.29 LC 537.13 $[M+H]^+$	234DII, 243Ii
399			[3aS-(3aα,4β,7β,7aα)]-4-[7-[2-(4-Fluorophenoxy)ethyl]octahydro-5-hydroxy-4-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile.	3.28 LC 487.11 $[M+H]^+$	234Di, 243I







301

Ex. No	G	R^7	Compound Name	Retention Time Min./ Molecular Mass	Procedure of Ex.
400			[3aR-(3aα,4β,7β,7aα)]-4-[7-[2-(4-Fluorophenoxy) ethyl]octahydro-5-hydroxy-4-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile.	3.27 LC 487.11 $[M+H]^+$	234DII, 243ii
401			[3aS-(3aα,4β,7β,7aα)]-4-[Octahydro-5-hydroxy-4-methyl-7-[2-[(4-methyl-2-oxo-2H-1-benzopyran-7-yl)oxy]ethyl]-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile.	3.15 LC 551.15 $[M+H]^+$	234DI, 243I
402			[3aR-(3aα,4β,7β,7aα)]-4-[Octahydro-5-hydroxy-4-methyl-7-[2-[(4-methyl-2-oxo-2H-1-	3.16 LC 551.10 $[M+H]^+$	234DII, 243ii





302

Ex. No	G	R^7	Compound Name	Retention Time Min./ Molecular Mass	Procedure of Ex.
			benzopyran-7-yl)oxy]ethyl]-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile.		
403			[3aS-(3aα,4β,7β,7aα)]-4-[7-[2-(3,5-Dimethoxyphenoxy)ethyl]octahydro-5-hydroxy-4-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile.	3.28 LC 529.19 $[M+H]^+$	234Di, 243I
404			[3aR-(3aα,4β,7β,7aα)]-4-[7-[2-(3,5-Dimethoxyphenoxy)ethyl]octahydro-5-hydroxy-4-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile.	3.26 LC 529.12 $[M+H]^+$	234Dii, 243II





303







Ex. No	G	R^7	Compound Name	Retention Time Min./ Molecular Mass	Procedure of Ex.
405			[3aR-(3aα,4β,7β,7aα)]-]-4-[7-[2-(4-Chloro-3-methylphenoxy)ethyl]octahydro-5-hydroxy-4-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile.	3.68 LC 517.33 $[M+H]^+$	234Dii, 243ii
406			[3aR-(3aα,4β,7β,7aα)]-4-[7-[2-(4-Cyano-2,3-difluorophenoxy)ethyl]octahydro-5-hydroxy-4-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile.	3.23 LC 530.13 $[M+H]^+$	234Dii, 243ii
407			[3aS-(3aα,4β,7β,7aα)]-4-[7-[2-[(5-Chloro-1,2-benzisoxazol-3-yl)oxy]ethyl]octahydro-5-	3.59 LC 602.1 $[M-H+OAc]^-$	243Di, 252





304

Ex. No	G	R^7	Compound Name	Retention Time Min./ Molecular Mass	Procedure of Ex.
			hydroxy-4-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile.		
408			[3aR-(3aα,4β,7β,7aα)]-4-[7-[2-[(5-Chloro-1,2-benzisoxazol-3-yl)oxy]ethyl]octahydro-5-hydroxy-4-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile.	3.57 LC 602.0 $[M-H+OAc]^-$	243Dii, 253
409			[3aR-(3aα,4β,7β,7aα)]-3-[2-[2-(4-Cyano-1-naphthalenyl)octahydro-6-hydroxy-7-methyl-1,3-dioxo-4,7-epoxy-4H-isoindol-4-yl]ethoxy]-5-isoxazolecarbox	2.90 LC 518.27 $[M+H]^+$	243Dii, 253







305

Ex. No	G	R^7	Compound Name	Retention Time Min./ Molecular Mass	Procedure of Ex.
			ylic acid, methyl ester.		
410			[3aR-(3aα,4β,7β,7aα)]-4-[Octahydro-5-hydroxy-4-methyl-1,3-dioxo-7-[2-[4-(1H-1,2,4-triazol-1-yl)phenoxy]ethyl]-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile.	2.93 LC 536.30 $[M+H]^+$	243Dii, 244ii
411			[3aS-(3aα,4β,7β,7aα)]-4-[7-[2-[(7-Chloro-4-quinolinyl)oxy]ethyl]octahydro-5-hydroxy-4-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile, trifluoroacetate (1:1).	2.52 LC 554.13 $[M+H]^+$	243Di, 244i





Ex. No	G	R'	Compound Name	Retention Time Min./ Molecular Mass	Procedure of Ex.
412			[3aR-(3aα,4β,7β,7aα)]-4-[7-[2-[(7-Chloro-4-quinolinyl)oxy]ethyl]octahydro-5-hydroxy-4-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile, trifluoroacetate (1:1).	2.53 LC 554.27 $[M+H]^+$	243Dii, 244ii
413			[3aR-(3α,4β,5β,7β,7aα)]-4-[7-[2-(2-Benzoxazolyloxy)ethyl]octahydro-5-hydroxy-4-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile	3.13 LC 568.1 $[M-H+OAc]^-$	243Dii, 244ii
414			[3aR-(3α,4β,5β,7β,7aα)]-4-[Octahydro-5-hydroxy-4-methyl-7-[2-[(9-	2.34 LC 525.2 $[M+H]^+$	243Dii, 244ii

Ex. No	G	R'	Compound Name	Retention Time Min./ Molecular Mass	Procedure of Ex.
			methyl-9H-purin-8-yl)oxy]ethyl]-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile		
415			[3aR-(3α,4β,5β,7β,7aα)]-4-[Octahydro-5-hydroxy-4-methyl-7-[2-[(1-methyl-1H-indazol-3-yl)oxy]ethyl]-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile	3.33 LC	251,253
416			[3aS-(3α,4β,5β,7β,7aα)]-4-[Octahydro-5-hydroxy-4-methyl-7-[2-[4-(1,2,3-thiadiazol-5-yl)phenoxy]ethyl]-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile	3.17 LC 553.10 $[M+H]^+$	243Dii, 244il

308

Ex. No	G	R^7	Compound Name	Retention Time Min./ Molecular Mass	Procedure of Ex.
417			[3aR-(3α,4β,5β,7β,7aα)]-4-[Octahydro-5-hydroxy-4-methyl-7-[2-[4-(1,2,3-thiadiazol-5-yl)phenoxy]ethyl]-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile	3.20 LC 553.25 $[M+H]^+$	243Dii, 244ii
418			[3aS-(3α,4β,5β,7β,7aα)]-4-[Octahydro-5-hydroxy-4-methyl-1,3-dioxo-7-[2-[[5-(trifluoromethyl)-2-pyridinyl]oxy]ethyl]-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile	3.45 LC 538.23 $[M+H]^+$	243Dii, 244ii
419			[3aR-(3α,4β,5β,7β,7aα)]-4-[Octahydro-5-hydroxy-4-methyl-1,3-dioxo-7-[2-[[5-	3.45 LC 538.23 $[M+H]^+$	243Dii, 244ii

309


Ex. No	G	R^7	Compound Name	Retention Time Min./ Molecular Mass	Procedure of Ex.
			(trifluoromethyl)-2-pyridinyl]oxy]ethyl]-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile		
420			[3aS-(3α,4β,5β,7β,7aα)]-4-[7-[2-[(6-Chloro-2-methyl-4-pyrimidinyl)oxy]ethyl]octahydro-5-hydroxy-4-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile	3.02 LC	243DII, 244II
421			[3aR-(3α,4β,5β,7β,7aα)]-4-[7-[2-[(6-Chloro-2-methyl-4-pyrimidinyl)oxy]ethyl]octahydro-5-hydroxy-4-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-	3.02 LC	243DII, 244II

310


Ex. No	G	R'	Compound Name	Retention Time Min./ Molecular Mass	Procedure of Ex.
			yl]-1-naphthalenecarbonitrile		

Example 422

(3aα,4β,7β,7aα)-2-(7-Bromo-2,1,3-benzoxadiazol-4-yl)hexahydro-4,7-dimethyl-4,7-epoxy-1H-isoindole-1,3(2H)-dione (422C)



A. 4-Bromo-7-nitrobenzofurazan (422A)




To a solution of 2,6-dibromoaniline (1.0 g, 4.0 mmol) in $CHCl_3$ (8 mL) was added a suspension of *m*CPBA (70% by HPLC, 1.4 g, 8.0 mmol) in $CHCl_3$ (8 mL) and the resulting mixture was stirred for 24 h at rt. The reaction mixture was diluted with $CHCl_3$ and washed successively with 2% $Na_2S_2O_3$ solution, 5% Na_2CO_3 solution and brine. The organic layer was dried over Na_2SO_4 and concentrated under reduced pressure to leave a solid, which was suspended, into DMSO (15 mL). To this suspension was added a solution of NaN_3 (272 mg, 4.19 mmol) in DMSO (15 mL) at rt. The resulting mixture was stirred at rt until most of the nitrogen had evolved and was then quickly heated to 120°C for 3 min. The reaction mixture was cooled and poured onto crushed ice (100 g). After standing for 1 h the precipitates were filtered off,

311

dried in *vacuo* and redissolved in concentrated H_2SO_4 (5 mL). To this solution was added a solution of $NaNO_3$ (400 mg, 4.7 mmol) in 50% H_2SO_4 (1.6 mL) and the temperature was maintained at 60°C. After the addition was complete, the mixture was heated to 85°C for 30 min, cooled to rt and poured onto crushed ice (40 g). EtOAc was added, the layers were separated and the aqueous layer was extracted with EtOAc. The combined organic layers were dried over Na_2SO_4 and concentrated to leave a solid which was purified by flash chromatography (silica gel, EtOAc (20%) in hexanes) affording compound **422A** (785 mg, 81%) as a tan solid.

B. 4-Bromo-7-aminobenzofurazan (422B)



A solution of compound **422A** (563 mg, 2.31 mmol) in AcOH (5 mL) was heated to 70°C and Fe^0 powder (258 mg, 4.62 mmol) was added in one portion. The resulting dark reaction mixture was stirred for 15 min, cooled to rt and concentrated under reduced pressure. The residue was taken up in EtOAc and the resulting solution was washed with sat. Na_2CO_3 solution. The organic layer was dried over Na_2SO_4, concentrated and purified by flash chromatography (silica gel, EtOAc in hexanes 10 to 60%) yielding compound **422B** (470 mg, 95%) as a red solid.


C. (3aα,4β,7β,7aα)-2-(7-Bromo-2,1,3-benzoxadiazol-4-yl)hexahydro-4,7-dimethyl-4,7-epoxy-1H-isoindole-1,3(2H)-dione (422C)

A mixture of compound **422B** (43 mg, 0.20 mmol), compound **20A** (45 mg, 0.23 mmol), $MgSO_4$ (60 mg, 0.50 mmol), Et_3N (139 µL, 1.0 mmol) and 1,2-dimethoxyethane (300 µL) were placed in a sealed tube and heated to

135 °C for 14 h. After cooling to rt the mixture was filtered through celite eluting with MeOH to yield a dark solid which was purified by flash chromatography (silica gel, EtOAc in hexanes 5 to 40%) furnishing compound **422C** (42 mg, 54%) as a yellow solid. HPLC: 99% at 2.96 min (retention time) (YMC S5 ODS column 4.6 x 50 mm Ballistic, 10-90% aqueous methanol over 4 minutes containing 0.2% H_3PO_4, 4 mL/min, monitoring at 220 nm). ^1H NMR (acetone-d_6, 400 MHz): δ = 8.00 (d, *J* = 7.5 Hz, 1H), 7.45 (d, *J* = 7.5 Hz, 1H), 3.31 (s, 2H), 1.98-1.93 (m, 2H), 1.74-1.69 (m, 2H), 1.57 (s, 6H).

Example 423

(3aα,4β,7β,7aα)-7-[Octahydro-4,7-dimethyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-2,1,3-benzoxadiazole-4-carbonitrile (423)




To a solution of compound **422C** (42 mg, 0.11 mmol) in DMA (1 mL) was added CuCN (20 mg, 0.22 mmol) and the resulting mixture was heated to 150°C for 5 h. The mixture was allowed to cool to rt and partitioned between EtOAc and aqueous NaCN solution (5 g/50 mL). The layers were separated and the aqueous layer was extracted once with EtOAc. The combined organic phases were dried over Na_2SO_4, concentrated and purified by flash chromatography (silica gel, EtOAc in hexanes 20 to 70%) to give compound **423** (13 mg, 35%) as a yellow oil. HPLC: 99% at 2.66 min (retention time) (YMC S5 ODS column 4.6 x 50 mm Ballistic, 10-90% aqueous methanol over 4 minutes containing 0.2% H_3PO_4, 4 mL/min, monitoring at 220 nm), MS (ES): m/z 396.9 [M-H+OAc]$^-$.


3B

Example 424

(3aα,4β,7β,7aα)-7-[Octahydro-4,7-dimethyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-2,1,3-benzothiadiazole-4-carbonitrile (424B)



A. 4-Cyano-7-amino-benzothiadiazole (424A)



A solution of 2-cyano-5-nitrophenylenediamine (78 mg, 0.44 mmol, prepared as described in WO 0076501) in $SOCl_2$ (2 mL) was heated to reflux for 3 h. The resulting mixture was allowed to cool to rt and was then poured into ice/water. CH_2Cl_2 was added, the layers were separated and the aqueous layer was extracted twice with CH_2Cl_2. The combined organic phases were dried over $MgSO_4$, concentrated and purified by flash chromatography (silica gel, EtOAc in hexanes 50%) to give 4-cyano-7-nitrobenzothiadiazole. This material was dissolved in AcOH (2 mL) containing EtOAc (1 mL) and H_2O (0.2 mL) and heated to 70 °C. At this temperature Fe^0 powder (78 mg, 1.41 mmol) was added in one solid portion and the dark mixture was stirred for 20 min and then cooled to rt. The reaction mixture was filtered through Celite eluting with EtOAc, washed with sat. Na_2CO_3 solution, dried over $MgSO_4$ and concentrated. Purification was achieved by flash chromatography (silica gel, EtOAc in hexanes 20 to 70%) to yield compound **424A** (47 mg, 61%) as a brown solid.


B. (3aα,4β,7β,7aα)-7-[Octahydro-4,7-dimethyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-2,1,3-benzothiadiazole-4-carbonitrile (424B)

314


A mixture of compound **424A** (35 mg, 0.20 mmol), compound **20A** (45 mg, 0.23 mmol), $MgSO_4$ (60 mg, 0.50 mmol), Et_3N (139 µL, 1.0 mmol) and DME (200 µL) was placed in a sealed tube and heated to 135 °C for 14 h. After cooling to rt the mixture was filtered through Celite eluting with MeOH to yield a dark solid which was purified by a combination of flash chromatography (silica gel, EtOAc in hexanes 10 to 50%) and reverse phase preparative HPLC (YMC S5 ODS 20 x 100 mm eluting with 27-100% aqueous methanol over 10 min containing 0.1% TFA, 20 mL/min) furnishing compound **424B** (36 mg, 51%) as a yellow solid. HPLC: 98% at 2.45 min (retention time) (YMC S5 ODS column 4.6 x 50 mm Ballistic, 10-90% aqueous methanol over 4 minutes containing 0.2% H_3PO_4, 4 mL/min, monitoring at 220 nm), MS (DCI): m/z 355.0 $[M+H]^+$.

Example 425

(3aα,4β,7β,7aα)-N-[2-[2-(4-Cyano-1-naphthalenyl)octahydro-7-methyl-1,3-dioxo-4,7-epoxy-4H-isoindol-4-yl]ethyl]-4-fluoro-N-methylbenzamide (425B)



A. 4-Fluoro-N-methyl-N-[2-(5-methyl-furan-2-yl)-ethyl]-benzamide (425A)



NaH (60% dispersion in oil, 65 mg, 1.63 mmol) was added portion-wise to a solution of 4-fluoro-N-[2-(5-methyl-2-furanyl)ethyl]benzamide (269 mg, 1.09 mmol, 237A) in THF (5 mL). After gas evolution ceased, iodomethane (0.14 mL, 2.18 mmol) was added drop-wise. Once HPLC analysis showed the reaction to be 50% complete, the mixture was concentrated under reduced pressure and resubjected to

315


the above conditions. After all the starting material was consumed, H_2O was added and the resulting mixture was extracted with EtOAc (2 X 5 mL). The combined organic layers were dried over Na_2SO_4 and concentrated under reduced pressure. Purification by flash chromatography eluting with 20% acetone/$CHCl_3$ gave 238 mg (84%) of compound 425A. HPLC: 98% at 2.94 min (retention time) (Phenomenex-prime S5-C18 column 4.6 x 50 mm eluting with 10-90% aqueous methanol over 4 minutes containing 0.2% phosphoric acid, 4 mL/min, monitoring at 220 nm), MS (ES): m/z [M+H] = 262.38.

B. (3aα,4β,7β,7aα)-N-[2-[2-(4-Cyano-1-naphthalenyl)octahydro-7-methyl-1,3-dioxo-4,7-epoxy-4H-isoindol-4-yl]ethyl]-4-fluoro-N-methylbenzamide (425B)

A solution of compound 425A (183 mg, 0.75 mmol) and 4-(2,5-dihydro-2,5-dioxo-1H-1-yl)-1-naphthalenecarbonitrile (174 mg, 0.75 mmol) in benzene (1 mL) was heated at 60°C for 15 hr. The reaction mixture was concentrated under reduced pressure to give 357 mg crude intermediate. The crude intermediate (156 mg) was dissolved in EtOAc (6 mL) and 10% Pd/C (16 mg) was added and the mixture was stirred under a hydrogen balloon overnight. The reaction mixture was filtered through a pad of celite and concentrated under reduced pressure. Purification by reverse phase preparative chromatography (YMC S5 ODS 20 X 100 mm, 20-100% aqueous methanol over 15 minutes containing 0.1% TFA, 20 mL/min, monitoring at 220 nm) gave 160.3 mg (72%) of compound 425B as an off-white solid. HPLC: 99% at 3.23 min (retention time) (Phenomenex-prime S5-C18 column 4.6 x 50 mm eluting with 10-90% aqueous methanol over 4 minutes containing 0.2% phosphoric acid, 4 mL/min, monitoring at 220 nm), MS (ES): m/z [M+H] = 512.19.


Example 426

(3aα,4β,7β,7aα)-Hexahydro-4,7-dimethyl-2-[4-(2,2,2-trifluoro-1-hydroxyethyl)phenyl]-4,7-epoxy-1H-isoindole-1,3(2H)-dione (426B)



316

A. 1-(4-Amino-phenyl)-2,2,2-trifluoro-ethanol (426A)



Compound 426A was made according to the procedure described in Stewart, R. *et. al., Can. J. Chem.* 58, 2491-2496 (1980). $NaBH_4$ (47 mg, 1.235 mmol) was added to a solution of p-aminotrifluoroacetophenone (155.7 mg, 0.823 mmol, synthesized as described by Klabunde, K. J. *et. al., J. Org. Chem.* 35, 1711-1712 (1970)) in isopropanol (3 mL) at rt. After 30 min the reaction was quenched with phosphate buffer (pH 7.2), diluted with H_2O and extracted with EtOAc (2 X 10 mL). The combined organic layers were dried over Na_2SO_4 and concentrated under reduced pressure to give 154 mg (98%) of compound 426A as a tan solid. The material was used directly in the next step without purification. HPLC: 99% at 0.42 min (retention time) (YMC S5 ODS column 4.6 x 50 mm eluting with 10-90% aqueous methanol over 4 minutes containing 0.2% phosphoric acid, 4 mL/min, monitoring at 220 nm), MS (ES): m/z [M+H] = 192.13.


B. (3aα,4β,7β,7aα)-Hexahydro-4,7-dimethyl-2-[4-(2,2,2-trifluoro-1-hydroxyethyl)phenyl]-4,7-epoxy-1H-isoindole-1,3(2H)-dione (426B)

A mixture of compound 426A (75.3 mg, 0.394), compound 20A (51.5 mg, 0.262 mmol), triethylamine (0.15 mL) and $MgSO_4$ (50 mg) in toluene (1 mL) was heated in a sealed tube to 135°C for 15 hr. The mixture was filtered and concentrated under reduced pressure. Purification by reverse phase preparative chromatography (YMC S5 ODS 20 X 100 mm, 20-100% aqueous methanol over 15 minutes containing 0.1% TFA, 20 mL/min, monitoring at 220 nm) gave 63.1 mg (65%) of compound 426B as a white solid. HPLC: 98% at 2.49 min (retention time) (Phenomenex-prime S5-C18 column 4.6 x 50 mm eluting with 10-90% aqueous methanol over 4 minutes containing 0.2% phosphoric acid, 4 mL/min, monitoring at 220 nm), MS (ES): m/z [M+H] = 370.16.

317

Example 427

(3aα,4β,7β,7aα)-4-[4-[2-[[(1,1-Dimethylethyl)dimethylsilyl]oxy]ethyl]-1,3,3a,4,7,7a-hexahydro-7-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-2-(trifluoromethyl)benzonitrile & (3aα,4α,7α,7aα)-4-[4-[2-[[(1,1-Dimethylethyl)dimethylsilyl]oxy]ethyl]-1,3,3a,4,7,7a-hexahydro-7-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-2-(trifluoromethyl)benzonitrile (427I & 427II)




Compound **204A** (2.00 g, 8.50 mmol) and 4-(2,5-Dihydro-2,5-dioxo-1H-pyrrol-1-yl)-2-trifluoromethylbenzonitrile (1.50 g, 5.60 mmol) were mixed in benzene (5.0 mL) and heated at 60 °C for 14 h, then cooled to 25 °C. The solvent was removed at 40°C under vacuum for 1 h to give the crude material which was purified by flash chromatography on SiO_2 eluting with 0.5% EtOAc/CH_2Cl_2 to give 2.0 g of compound **427I** and 1.3 g of compound **427II**, both as light brown solids. Compound **427I**: HPLC: 95% at 4.200 min (retention time) (YMC S5 ODS column 4.6 x 50 mm eluting with 10-90% aqueous methanol over 4 minutes containing 0.2% phosphoric acid, 4 mL/min, monitoring at 220 nm), MS (ES): m/z 507.1 $[M+H]^+$. Compound **427II**: HPLC: 95% at 4.20 min (retention time) (YMC S5 ODS column 4.6 x 50 mm eluting with 10-90% aqueous methanol over 4 minutes containing 0.2% phosphoric acid, 4 mL/min, monitoring at 220 nm), MS (ES): m/z 507.1 $[M+H]^+$.

Example 428

[3aR-(3aα,4β,5β,7β,7aα)]-4-[7-[2-[[(1,1-Dimethylethyl)dimethylsilyl]oxy]ethyl]octahydro-5-hydroxy-4-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-2-(trifluoromethyl)benzonitrile & [3aS-

318

(3aα,4β,5β,7β,7aα)]-4-[7-[2-[[(1,1-Dimethylethyl)dimethylsilyl]oxy]ethyl]octahydro-5-hydroxy-4-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-2-(trifluoromethyl)benzonitrile (428I & 428II)



Compound **427I** (1.40 g, 2.77 mmol) and $RhCl(PPh_3)_3$ (0.128 g, 0.14 mmol) were mixed in a flask. The flask was then evacuated and filled with argon three times, followed by the syringe addition of THF (3.0 mL). Once all particulates were dissolved, catecholborane (0.59 mL, 5.54 mmol) was added dropwise. The reaction mixture was stirred at 25°C under argon for 30 min, then cooled to 0 °C. Phosphate buffer (pH=7, 20 mL) was added, followed by EtOH (10 mL), 30% H_2O_2/H_2O (2 mL). The reaction mixture was stirred at 0°C for 3 h, then extracted with dichloromethane (3 x 25 mL). The combined organic layers were washed with 1 N NaOH (25 mL), 10% Na_2SO_3 (25 mL) and brine (25 mL). The crude material was then concentrated and purified by flash chromatography on SiO_2 eluting with 2% $EtOAc/CH_2Cl_2$ to 10% $EtOAc/CH_2Cl_2$ to give 0.63 g of a racemic mixture of compounds **428I & 428II** as a light yellow solid. HPLC: 99% at 3.867 min (retention time) (YMC S5 ODS column 4.6 x 50 mm eluting with 10-90% aqueous methanol over 4 minutes containing 0.2% phosphoric acid, 4 mL/min, monitoring at 220 nm), MS (ES): m/z 525.1 [M+H]

The racemic mixture of compounds **428I & 428II** was separated by normal phase preparative chiral HPLC using a Chiracel OD column (5 cm x 50 cm), eluting with 13% solvent B (EtOH) in solvent A (Hexane), flow rate: 50 mL/min. Compound **428I** eluted from 34 min to 38 min and compound **428II** eluted from 44 min to 49 min. Enantiomeric excess was determined by


319

chiral HPLC. Compound **428I**: >99% ee (12.576 min (retention time) (Chiralcel OJ column 4.6 x 250 mm eluting with isocratic 85% heptane / 15% MeOH/ethanol (1:1), 1 mL/min, monitoring at 220 nm, 40°C). Compound **428II**: 99% ee (18.133 min (retention time) (Chiralcel OJ column 4.6 x 250 mm eluting with isocratic 85% heptane / 15% MeOH/ethanol (1:1), 1 mL/min, monitoring at 220 nm, 40°C).

The absolute configurations for compounds **428I** & **428II** were not established. For simplicity in nomenclature, compound **428I** is designated herein as having an "R" configuration and compound **428II** as having an "S" configuration. Enantiomerically pure products derived from compound **428I** are designated herein as having a "R" configuration and enantiomerically pure products derived from compound **428II** are designated herein as having an "S" configuration.

Example 429

[3aR-(3aα,4β,5β,7β,7aα)]-4-[Octahydro-5-hydroxy-7-(2-hydroxyethyl)-4-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-2-(trifluoromethyl)benzonitrile & [3aS-(3aα,4β,5β,7β,7aα)]-4-[Octahydro-5-hydroxy-7-(2-hydroxyethyl)-4-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-2-(trifluoromethyl)benzonitrile (429I & 429II)




Compound **428I** (180 mg; 0.34 mmol) was dissolved in 2% HCl/EtOH (5.0 mL). After 30 min, saturated $NaHCO_3$ was added and the aqueous layer was extracted with dichloromethane (20 mL x 3), washed with brine and dried over Na_2SO_4 to give 135 mg of compound **429I** as a white solid. HPLC: 99% at 2.257 min (retention time) (YMC S5 ODS column 4.6 x 50 mm eluting with

10-90% aqueous methanol over 4 minutes containing 0.2% phosphoric acid, 4 mL/min, monitoring at 220 nm), MS (ES): m/z 411.1 $[M+H]^+$.

The above procedure was repeated with compound **428ii** to yield the desired diol compound **429II** in similar yield.

Example 430


[3aR-(3aα,4β,5β,7β,7aα)]-4-[7-[2-[(5-Chloro-2-pyridinyl)oxy]ethyl]octahydro-5-hydroxy-4-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-2-(trifluoromethyl)benzonitrile (430)



Triphenylphosphine (0.026 g, 0.098 mmol) and DBAD (0.023 g, 0.098 mmol) were mixed in THF (0.5 mL). After allowing the previous mixture to react for 15 min, 2-hydroxy-6-chloropyridine (0.016 g, 0.100 mmol) was added, the mixture was allowed to stir for 10 min and compound **429I** (0.020 g, 0.049 mmol) was added. The reaction mixture was stirred at 25°C for 2 h and then the crude material was purified by preparative TLC, eluting with 10% acetone/$CHCl_3$ to give 0.014 g of compound **430** as a light brown solid. HPLC: 100% at 3.370 min (retention time) (YMC S5 ODS column 4.6 x 50 mm eluting with 10-90% aqueous methanol over 4 minutes containing 0.1% TFA, 4 mL/min, monitoring at 220 nm), MS (ES): m/z 522.08 $[M+H]^+$.

Example 431


[3aS-(3aα,4β,5β,7β,7aα)]-4-[7-[2-[(5-Chloro-2-pyridinyl)oxy]ethyl]octahydro-5-hydroxy-4-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-2-(trifluoromethyl)benzonitrile (431)



Triphenylphosphine (0.026 g, 0.098 mmol) and DBAD (0.023 g, 0.098 mmol) were mixed in THF (0.5 mL). After allowing the previous mixture to react for 15 min, 2-hydroxy-6-chloropyridine (0.016 g, 0.100 mmol) was added, the mixture was allowed to stir for 10 min and compound **429ii** (0.020 g, 0.049 mmol) was added. The reaction mixture was stirred at 25°C for 2 h and then the crude material was purified by preparative TLC, eluting with 10% acetone/$CHCl_3$ to give 0.015 g of compound **431** as a light brown solid. HPLC: 100% at 3.370 min (retention time) (YMC S5 ODS column 4.6 x 50 mm eluting with 10-90% aqueous methanol over 4 minutes containing 0.1% TFA, 4 mL/min, monitoring at 220 nm), MS (ES): m/z 522.08 $[M+H]^+$.

Example 432

(3aα,4β,7β,7aα)-2-(4-Cyano-1-naphthalenyl)octahydro-N-(2-hydroxyphenyl)-7-methyl-1,3-dioxo-4,7-epoxy-4H-isoindole-4-butanamide (432)




Compound **262** (0.100 g, 0.239 mmol) was dissolved in DMF (anhydrous, 1.5 mL), BOP (0.211 g, 0.478 mmol) was added followed by 2-aminophenol (0.052 g, 0.478 mmol) and N-methyl morpholine (0.052 mL, 0.478 mmol). The reaction mixture was stirred at 25 °C under argon for 3 h, then the crude material was purified by reverse phase preparative-HPLC

(YMC S5 ODS 20 X 100 mm, 20-100% aqueous methanol over 15 minutes containing 0.1% TFA, 20 mL/min, monitoring at 220 nm) to give 0.060 g of compound **432** as a light brown solid. HPLC: 100% at 3.037 min (retention time) (YMC S5 ODS column 4.6 x 50 mm eluting with 10-90% aqueous methanol over 4 minutes containing 0.1% TFA, 4 mL/min, monitoring at 220 nm), MS (ES): m/z 510.34 $[M+H]^+$.

Example 433

(3aα,4β,7β,7aα)-4-[4-[3-(2-Benzoxazolyl)propyl]octahydro-7-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile (433)




Triphenylphosphine (0.031 g, 0.118 mmol) and DBAD (0.027 g, 0.118 mmol) were mixed in THF (0.5 mL). After allowing the previous mixture to react for 15 min, compound **432** (0.030 g, 0.059 mmol) was added. The reaction mixture was stirred at 25°C for 2 h and then the crude material was purified by reverse phase preparative-HPLC (YMC S5 ODS 20 X 100 mm, 20-100% aqueous methanol over 15 minutes containing 0.1% TFA, 20 mL/min, monitoring at 220 nm) to give 0.018 g of compound **433** as a light brown solid. HPLC: 100% at 3.357 min (retention time) (YMC S5 ODS column 4.6 x 50 mm eluting with 10-90% aqueous methanol over 4 minutes containing 0.1% TFA, 4 mL/min, monitoring at 220 nm), MS (ES): m/z 492.37 $[M+H]^+$.


323

Example 434

(3aα,4β,5β,7β,7aα)-4-[4-Ethyloctahydro-5-hydroxy-7-(2-hydroxyethyl)-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile (434C)




A. tert-Butyl-[2-(5-ethyl-furan-2-yl)-ethoxy]-dimethyl-silane (434A)



Imidazole (255 mg, 3.75 mmol) and TBSCl (414 mg, 2.75 mmol) were added to the solution of 245A (350 mg, 2.5 mmol) in DMF (4 mL). The mixture was stirred at rt for 15 hr and then 100 mg (0.66 mmol) of additional TBSCl was added to drive the reaction to completion. After stirring for an additional hour, the reaction mixture was diluted with diethylether (100 mL) and washed with water (20 mL), 1 N HCl (20 mL), water (20 mL) and brine (20 mL). The organic layer was dried over Na_2SO_4 and concentrated under reduced pressure to give 509 mg of compound 434A (80.3%) as a yellow oil.

B. (3aα,4β,7β,7aα)-4-[4-[2-[[(1,1-Dimethylethyl)-dimethylsilyl]oxy]ethyl]- 4-ethyl-1,3,3a,4,7,7a-hexahydro-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile (434B)



A solution of compound **434A** (509 mg, 2.00 mmol) and 4-(2,5-dihydro-2,5-dioxo-1H-1-yl)-1-naphthalenecarbonitrile (498 mg, 2.00 mmol) in benzene (2 mL) was heated at 60°C for 18 h. The reaction mixture was concentrated under reduced pressure to give 992 mg (99%) of crude compound **434B**, which was used directly in the next step without further purification.


C. (3aα,4β,5β,7β,7aα)-4-[4-Ethyloctahydro-5-hydroxy-7-(2-hydroxyethyl)-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile (434C)

A mixture of compound **434B** (992 mg, 1.98 mmol) and $RhCl_2(PPh_3)_3$ (183 mg, 0.198 mmol) was evacuated and filled with argon (3X). THF (20 mL) was added and once all particulates had dissolved, catecholborane (0.42 mL, 3.96 mmol) was slowly added dropwise. When the formation of product ceased, as was determined by HPLC, the reaction mixture was cooled to 0°C and quenched with phosphate buffer (34 mL, pH 7.2) followed by the addition of EtOH (19 mL) and H_2O_2 (2.9 mL, 30% aq sol). After 2 h, additional phosphate buffer (6.8 mL, pH 7.2), EtOH (3.8 mL) and H_2O_2 (0.6 mL) were added. The reaction mixture was stirred at rt for 3 h. Once the boronate intermediate was consumed, the mixture was extracted with CH_2Cl_2 (300 mL) and the combined organic layers were washed with 1N NaOH, 10% aq $NaHSO_3$ and brine. The combined organic layers were dried over Na_2SO_4. Purification by flash chromatography on silica gel eluting with 10% MeOH/CH_2Cl_2 gave 75 mg (9.3%) of compound **434C** as a gray solid. HPLC conditions: 97% at 2:43 min (Phenomenex-prime S5-C18 column 4.6 x 50 mm, 10%-90% aqueous methanol over 4 minute gradient with 0.2% H_3PO_4, detecting at 220 nm). MS (ES): m/z 407.18 $[M+H]^+$.

325

Example 435

(3aα,4β,5β,7β,7aα)-4-[7-[2-(4-Cyanophenoxy)ethyl]-4-ethyloctahydro-5-hydroxy-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile (435)




DBAD (39.6 mg, 0.172 mmol) was added to a solution of PPh_3 (45.1 mg, 0.172 mmol) in THF (0.8 mL). After stirring for 10 min, 4-cyanophenol (20.5 mg, 0.172 mmol) was added and the reaction mixture was stirred for an additional 5 min. Compound **434C** (25.0 mg, 0.062 mmol) was added and the mixture was stirred at rt for 2 h. The reaction was concentrated under reduced pressure. Purification by Prep TLC eluting with 10% acetone/$CHCl_3$ gave 18.1 mg (0.036 mmol, 57.6%) of compound **435**. HPLC conditions: 96% at 3.15 min (YMC S5 ODS 4.6 X 50 mm, 10%-90% aqueous methanol over 4 minute gradient with 0.2% H_3PO_4, detecting at 220 nm). MS (ES): m/z 508.14 $[M+H]^+$.

Example 436

(3aα,4β,7β,7aα)-2-(4-Cyano-1-naphthyalenyl)octahydro-N-(2-hydroxyphenyl)-7-methyl-1,3-dioxo-4,7-expoxy-4H-isoindole-4-ethanamide (436)


326



Compound **234B** (0.100 g, 0.256 mmol) was dissolved in DMF (anhydrous, 1.5 mL), BOP (0.225 g, 0.51 mmol) was added followed by 2-aminophenol (0.056 g, 0.51 mmol) and N-methyl morpholine (0.056 mL, 0.51 mmol). The reaction mixture was stirred at 25°C under argon for 3 h, then the crude material was purified by reverse phase preparative-HPLC (YMC S5 ODS 20 X 100 mm, 20-100% aqueous methanol over 15 minutes containing 0.1% TFA, 20 mL/min, monitoring at 220 nm) to give 0.078 g of compound **436** as a light brown solid. HPLC: 100% at 3.037 min (retention time) (YMC S5 ODS column 4.6 x 50 mm eluting with 10-90% aqueous methanol over 4 minutes containing 0.1% TFA, 4 mL/min, monitoring at 220 nm), MS (ES): m/z 482.34 $[M+H]^+$.

Example 437

(3aα,4β,7β,7aα)-4-[4-(2-Benzoxazolylmethyl)octahydro-7-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile (437)




Triphenylphosphine (0.082 g, 0.312 mmol) and DBAD (0.072 g, 0.312 mmol) were mixed in THF (0.5 mL). After allowing the previous mixture to react for 15 mins, compound **436** (0.075 g, 0.156 mmol) was added. The

327

reaction mixture was stirred at 25°C for 2 h and then the crude material was purified by reverse phase preparative-HPLC (YMC S5 ODS 20 X 100 mm, 20-100% aqueous methanol over 15 minutes containing 0.1% TFA, 20 mL/min, monitoring at 220 nm) to give 0.052 g of compound **437** as a light brown solid. HPLC: 100% at 3.443 min (retention time) (YMC S5 ODS column 4.6 x 50 mm eluting with 10-90% aqueous methanol over 4 minutes containing 0.1% TFA, 4 mL/min, monitoring at 220 nm), MS (ES): m/z 464.18 $[M+H]^+$.

Example 438

(3aα,4β,7β,7aα)-Hexahydro-4,7-dimethyl-2-[4-[2,2,2-trifluoro-1-hydroxy-1-(trifluoromethyl)ethyl]phenyl]-4,7-epoxy-1H-isoindole-1,3(2H)-dione (438)




A mixture of 2-(4'-aminophenyl)-1,1,1,3,3,3-hexafluoro-2-propanol (95.7 mg, 0.369), compound 20A (48.3 mg, 0.246 mmol), triethylamine (0.15 mL) and $MgSO_4$ (50 mg) in toluene (1 mL) was heated in a sealed tube to 135 °C overnight. The mixture was filtered and concentrated under reduced pressure. Purification by reverse phase preparative chromatography (YMC S5 ODS 20 X 100 mm, 20-100% aqueous methanol over 15 minutes containing 0.1% TFA, 20 mL/min, monitoring at 220 nm) gave 44.0 mg (41%) of compound **438** as a white solid. HPLC: 99% at 3.10 min (retention time) (Phenomenex-prime S5-C18 column 4.6 x 50 mm eluting with 10-90% aqueous methanol over 4 minutes containing 0.2% phosphoric acid, 4 mL/min, monitoring at 220 nm), MS (ES): m/z [M+H] = 438.14.

Examples 439 to 454

Additional compounds of the present invention were prepared by procedures analogous to those described above. The compounds of Examples 439 to 454 have the following structure (L is a bond):

328











where G, R^7, the compound name, retention time, molecular mass, and the procedure employed, are set forth in **Table 9**. The absolute configuration for the following compounds was not determined. For simplicity in nomenclature, compound **243DI** is designated herein as having an "S" configuration and compound **243DII** as having an "R" configuration. Enantiomerically pure products derived from compound **243DI** are designated herein as having an "S" configuration and enantiomerically pure products derived from compound **243DII** are designated herein as having an "R" configuration. Similarly, compound 428i is designated herein as having an "S" configuration and compound 428ii as having an "R" configuration. Enantiomerically pure products derived from compound 428i are designated herein as having an "S" configuration and enantiomerically pure products derived from compound 428ii are designated herein as having an "R" configuration.

The chromatography techniques used to determine the compound retention times of **Table 9** are as follows: **LCMS** = YMC S5 ODS column, 4.6 X 50 mm eluting with 10-90% MeOH/H_2O over 4 minutes containing 0.1% TFA; 4 mL/min, monitoring at 220 nm. **LCMS*** = YMC S5 ODS column, 4.6 X 50 mm eluting with 10-90% MeOH/H_2O over 2 minutes containing 0.1% TFA; 4 mL/min, monitoring at 220 nm. **LC** = YMC S5 ODS column 4.6 x 50 mm eluting with 10-90% MeOH/H_2O over 4 minutes containing 0.2% phosphoric acid, 4 mL/min, monitoring at 220 nm. The molecular mass of the compounds listed in **Table 9** were determined by MS (ES) by the formula m/z.



319

Table 9





Ex. No	G	R'	Compound Name	Retention Time Min./ Molecular Mass	Procedure of Ex.
439			[3aR-(3aα,4β,5β,7β,7aα)]-4-[Octahydro-5-hydroxy-4-methyl-7-[2-[(1-methyl-1H-indazol-3-yl)oxy]ethyl]-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile	3.33 LC 523.3 $[M+H]^+$	251, 253
440			[3aR-(3aα,4β,5β,7β,7aα)]-4-[Octahydro-5-hydroxy-4-methyl-7-[2-[(9-methyl-9H-purin-8-yl)oxy]ethyl]-1,3-dioxo-4,7-epoxy-2H-	2.34 LC 525.2 $[M+H]^+$	251, 253

Ex. No	G	R'	Compound Name	Retention Time Min./ Molecular Mass	Procedure of Ex.
			isoindol-2-yl]-1-naphthalenecarbonitrile		
441			[3aR-(3aα,4β,5β,7β,7aα)]-4-[Octahydro-5-hydroxy-4-methyl-1,3-dioxo-7-[2-[[1-(phenylmethyl)-1H-indazol-3-yl]oxy]ethyl]-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile	3.73 LC	243Dii, 244Dii
442			[3aR-(3aα,4β,5β,7β,7aα)]-4-[Octahydro-5-hydroxy-4-methyl-1,3-dioxo-7-[2-[[1-(phenylmethyl)	3.37 LC	251, 253





331





Ex. No	G	R'	Compound Name	Retention Time Min./ Molecular Mass	Procedure of Ex.
			-1H-pyrazolo[3,4-d]pyrimidin-3-yl]oxy]ethyl]-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile		
443			[3aS-(3aα,4β,5β,7β,7aα)]-4-[Octahydro-5-hydroxy-4-methyl-1,3-dioxo-7-[2-[[5-(trifluoromethyl)-2-pyridinyl]oxy]ethyl]-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile	3.45 LC 538.23 $[M+H]^+$	243Di, 244Di

332





Ex. No	G	R'	Compound Name	Retention Time Min./ Molecular Mass	Procedure of Ex.
444			[3aR-(3aα,4β,5β,7β,7aα)]-4-[Octahydro-5-hydroxy-4-methyl-1,3-dioxo-7-[2-[[5-(trifluoromethyl)-2-pyridinyl]oxy]ethyl]-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile	3.46 LC 538.24 $[M+H]^+$	243Dii, 244Dii
445			[3aR-(3aα,4β,5β,7β,7aα)]-N-[4-[2-[2-(4-Cyano-1-naphthalenyl)octahydro-5-hydroxy-4-methyl-1,3-dioxo-4,7-epoxy-7H-isoindol-7-yl]ethoxy]phen	2.747 LC 526.28 $[M+H]^+$	243Dii, 244Dii

333



Ex. No	G	R^7	Compound Name	Retention Time Min./ Molecular Mass	Procedure of Ex.
			yl]acetamide		
446			[3aR-(3aα,4β,5β,7β,7aα)]-4-[7-[2-(2,4-Dichlorophenoxy)ethyl]octahydro-5-hydroxy-4-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile	3.71 LC 537.17 $[M+H]^+$	243DII, 244DII
447			[3aR-(3aα,4β,5β,7β,7aα)]-4-[7-[2-[3,5-Bis(trifluoromethyl)phenoxy]ethyl]octahydro-5-hydroxy-4-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-	3.89 LC 605.25 $[M+H]^+$	243DII, 244DII

Ex. No	G	R^7	Compound Name	Retention Time Min./ Molecular Mass	Procedure of Ex.
			1-naphthalenecarbonitrile		
448			[3aS-(3aα,4β,5β,7β,7aα)]-4-[Octahydro-5-hydroxy-4-methyl-1,3-dioxo-7-[2-[4-(1,2,3-thiadiazol-5-yl)phenoxy]ethyl]-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile	3.14 LC 553.1 $[M+H]^+$	243Di, 244Di
449			[3aR-(3aα,4β,5β,7β,7aα)]-4-[Octahydro-5-hydroxy-4-methyl-1,3-dioxo-7-[2-[4-(1,2,3-thiadiazol-5-	3.15 LC 553.23 $[M+H]^+$	243Dii, 244Dii





335

Ex. No	G	R^7	Compound Name	Retention Time Min./ Molecular Mass	Procedure of Ex.
			yl)phenoxy]ethyl]-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile		
450			[3aR-(3aα,4β,5β,7β,7aα)]-4-[7-[2-[(5,7-Dichloro-8-quinolinyl)oxy]ethyl]octahydro-5-hydroxy-4-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile, trifluoroacetate (1:1)	3.70 LC 588.26 $[M+H]^+$	243Dii, 244Dii
451			[3aS-(3aα,4β,5β,7β,7aα)]-4-[7-[2-(4-	3.087 LC 512.13 $[M+H]^+$	431

336

Ex. No	G	R^7	Compound Name	Retention Time Min./ Molecular Mass	Procedure of Ex.
			Cyanophenoxy)ethyl]octahydr o-5-hydroxy-4-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-2-(trifluoromethyl)benzonitrile		
452			[3aS-(3aα,4β,5β,7β, 7aα)]-4-[7-[2-[(5-Chloro-1,2-benzisoxazol-3-yl)oxy]ethyl]oct ahydro-5-hydroxy-4-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-2-(trifluoromethyl)benzonitrile	3.563 LC 562.08 $[M+H]^+$	431

337


Ex. No	G	R⁷	Compound Name	Retention Time Min./ Molecular Mass	Procedure of Ex.
453			[3aR-(3aα,4β,5β,7β,7aα)]-4-[7-[2-[(5-Chloro-1,2-benzisoxazol-3-yl)oxy]ethyl]octahydro-5-hydroxy-4-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-2-(trifluoromethyl)benzonitrile	3.57 LC 562.08 $[M+H]^+$	430
454			[3aR-(3aα,4β,5β,7β,7aα)]-4-[7-[2-(4-Cyanophenoxy)ethyl]octahydro-5-hydroxy-4-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-	3.087 LC 512.08 $[M+H]^+$	430

336

Ex. No	G	R^7	Compound Name	Retention Time Min./ Molecular Mass	Procedure of Ex.
			2-(trifluoromethyl)benzonitrile		

Examples 455 to 457

Additional compounds of the present invention were prepared by procedures analogous to those described above. The compounds of Examples 455 to 457 have the following structure (L is a bond):







where G, R^7, the compound name, retention time, molecular mass, and the procedure employed, are set forth in **Table 10**. The absolute configuration for the following compounds was not determined. For simplicity in nomenclature, compound **238i** is designated herein as having an "R" configuration and compound **238ii** as having an "S" configuration. Enantiomerically pure products derived from compound **238i** are designated herein as having an "R" configuration and enantiomerically pure products derived from compound **238ii** are designated herein as having an "S" configuration.

The chromatography techniques used to determine the compound retention times of **Table 10** are as follows: **LCMS** = YMC S5 ODS column, 4.6 X 50 mm eluting with 10-90% MeOH/H_2O over 4 minutes containing 0.1% TFA; 4 mL/min, monitoring at 220 nm. **LCMS*** = YMC S5 ODS column, 4.6 X 50 mm eluting with



339

10-90% MeOH/H_2O over 2 minutes containing 0.1% TFA; 4 mL/min, monitoring at 220 nm. LC = YMC S5 ODS column 4.6 x 50 mm eluting with 10-90% MeOH/H_2O over 4 minutes containing 0.2% phosphoric acid, 4 mL/min, monitoring at 220 nm. The molecular mass of the compounds listed in Table 10 were determined by MS (ES) by the formula m/z.

Table 10


Ex. No	G	R'	Compound Name	Retention Time Min./ Molecular Mass	Procedure of Ex.
455			(3aα,4β,5β,7β,7aα)-4-[Octahydro-4-methyl-1,3-dioxo-7-(4-oxo-4-phenylbutyl)-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile	3.53 LC 479.35 $[M+H]^+$	265, 249
456			(3aα,4β,5β,7β,7aα)-4-[Octahydro-4-methyl-7-[3-[5-(1-methylethyl)-	3.547 LC 484.28 $[M+H]^+$	248, 249


340

Ex. No	G	R'	Compound Name	Retention Time Min./ Molecular Mass	Procedure of Ex.
			2-oxazolyl]propyl]-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile		
457			[3aα,4β,5β,7β,7aα(E)]-4-[Octahydro-4-methyl-7-[3-[5-(1-methylethyl)-2-oxazolyl]-2-propenyl]-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile	3.66 LC 482.28 $[M+H]^+$	248, 249

Example 458

(3aα,4β,5β,7β,7aα)-4-(Octahydro-5-hydroxy-4,7-dimethyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl)-2-(trifluoromethyl)benzonitrile & (3aα,4β,5α,7β,7aα)-4-(Octahydro-5-hydroxy-4,7-dimethyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl)-2-(trifluoromethyl)benzonitrile (221B & 222D)





Compound **20B** was converted to compounds **221B** and **222D** (also synthesized as compounds **221B** and **222D**) by biotransformation.

Compound **20B** was hydroxylated by *Amycolatopsis orientalis* (ATCC 43491). A 1 ml culture from a frozen vial was used to inoculate 100 ml medium in a 500 mL portion Erlenmeyer flask and the flask was incubated at 28°C, at 200 rpm for 3 days. A 10 mL portion of this culture was used to inoculate 100 mL medium in a 500 ml Erlenmeyer flask and the flask was incubated at 28°C, at 200 rpm for 1 day. 10 mL portions of the 1-day culture were distributed to each of three 50 ml flasks. Compound **20B** (3 mg in 0.1 mL methanol) was added to each culture and the incubations were continued for 3 days. The culture broth in each flask was extracted with 20 mL ethyl acetate, and the pooled ethyl acetate extracts were evaporated to dryness at 40 °C under a nitrogen stream. The residue was dissolved in 1.2 mL methanol and analyzed by HPLC, LC/MS and LC/NMR. The solution contained 2.5 mg of remaining Compound **20B**, 1.6 mg of compound **221B**, and 1.3 mg of compound **222D**. MS and NMR analyses were in agreement with the structures shown above.

Medium: 0.5% toasted nutrisoy, 2% glucose, 0.5% yeast extract, 0.5% K_2HPO_4, 0.5% NaCl, adjusted to pH 7 with HCl (R. V. Smith and J. P. Rosazza, Arch. Biochem. Biophys., **161**, 551-558 (1974)

HPLC Analysis

Column: Phenomenex Luna C18, 150x2 mm, 5μ

mobile phase: solvent A: 95% 20 mM ammonium acetate pH 5.1, 5% acetonitrile

solvent B: 95% acetonitrile, 5% 20 mM ammonium acetate pH 5.1

linear gradient going from 100% solvent A to 5% solvent A in 25 minutes followed by equilibration at 100% solvent A for 8 minutes.

temperature: 40 °C

detection: 250 nm

injection volume: 1 μL

retention times: compound **20B**, 20.8 min; compound **221B**, 16.5 min; compound **222D**, 17.8 min

HPLC Conditions

Chiral HPLC conditions were employed for the separation of enantiomers and achiral HPLC conditions were employed for the separation of diastereomers of the hydroxylated analogs of compound **20B** (i.e., compounds **221B** and **222D** and compounds **254i** and **254ii**)

Two methods were used under chiral HPLC conditions, reverse phase (RP) for chiral analysis of biotransformation products in biological samples and normal phase (NP) for non-biological samples.

Chiral RP-HPLC Condition

Column:	CHIRALPAK AD-R	
	4.6 x 250 mm, 10 μ	
Temperature:	40°C	
Injection Volume:	5 or 20 μL	
Mobile Phase:	A:	MeCN
	B:	H_2O
	Isocratic, 30% of A, 18 min.	
Flow Rate:	1 mL/min.	
UV Detection:	242 nm	

343 348

Chiral NP-HPLC Condition

Column:	CHIRALPAK AD	
	4.6 x 250 mm, 10 μ	
Temperature:	25°C	
Injection Volume:	5 or 20 μL	
Mobile Phase:	A:	Heptane
	B:	MeOH/Ethanol (1:1)
	Isocratic, 80% of A, 20 min.	
Flow Rate:	1 mL/min.	
UV Detection:	242 nm	

Under these conditions compounds **254I** and **254II** had retention times of 8.5 minutes and 9.85 minutes, respectively.

Reverse phase HPLC was employed for the separation of the diastereomeric compounds **221B** and **222D**:

Mobile Phase:

Solvent A: 95% 20 mM ammonium acetate pH 5.1, 5% acetonitrile
Solvent B: 95 % acetonitrile, 5% 20 mM ammonium acetate pH 5.1

Gradient:

Linear gradient going from 100% solvent A to 5% solvent A in 25 minutes followed by equilibration at 100% solvent A for 8 minutes. Total run time of 36 minutes.

Flow Rate:

0.2 ml/min

Column:

Phenomenex Luna 5 micron C_{18} 150X2.0 mm id

Detection:


UV detection at 242 nm

344

Under these conditions, compounds **221B** and **222D** had retention times of 18.983 min and 20.362 min, respectively.

Example 459

(3aα,4β,5β,7β,7aα)-4-[Octahydro-5-hydroxy-7-(2-hydroxyethyl)-4-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile (459)



Compounds **223A** and **331** were converted to compound **459** by biotransformation.

Microbial hydroxylation of compound 223A

1. Reaction

To a 500 mL flask containing 100 ml of the transformation medium was added one frozen vial (approximately 2 ml) of *Streptomyces griseus* ATCC 10137. The transformation medium was prepared as follows: to a 2 L plastic beaker was added 20 g of dextrose, 5.0 g of yeast extract, 5.0 g of soybean meal, 5.0 g of sodium chloride, 5.0 g of potassium phosphate (diabasic) and 1 L of deionized water, and the mixture was stirred at room temperature for 3 to 30 min. The pH of the mixture was then adjusted to 7.0 with 1 N HCl or 1 N NaOH. The resulting mixture was dispensed into 500 ml flasks (100 ml per flask). The flasks were covered with Bio/Wrap and autoclaved at 121°C for 15 min. and cooled down to room temperature before use.

The culture was incubated at 28°C and at 250 rpm for 24 hours. Ten mL of the resulting culture was transferred to a 50 mL flask, to which 1 mg of compound **223A** in 0.2 ml ethanol was added. The flask was incubated at 28°C and 250 rpm for 24 hours, and the reaction culture was extracted with EtOAc (10 ml). The EtOAc extract was dried under N_2 and the residue was dissolved in 1 ml of MeOH (reaction extract).

345

2. Product analysis

HPLC:

10 μL of the reaction extract was injected into HPLC column (YMC ODS-AQ C-18 column, 150 x 6.0 mm i.d.). The column was eluted with 1 mM HCl in water/CH_3CN at 1.2 mL/min flow rate: 30 to 60% CH_3CN over 8 min, 60 to 85% CH_3CN over 0.5 min, 85% CH_3CN for 1 min, 85 to 30% CH_3CN over 0.5 min. The eluents were monitored at 300 nm. Two major peaks with about a 1 to 1 area ratio were observed, which had the same UV spectra as those of compounds **459** and **331**, and had retention times of 4.55 min and 7.23 min, respectively, matching the retention times of authentic samples of compound **459** (4.53 min) and compound **331** (7.2 min).

LC/MS

The reaction extract: two major UV peaks.

Peak 1, Tr 4.68 min: 391 $[M+H]^+$, 343, 319, 303, 289

Peak 2, Tr 5.35 min: 375 $[M+H]^+$, 345

Authentic samples

Compound **459**, Tr 4.82 min: 391 $[M+H]^+$, 343, 319, 289

Compound **331**, Tr 5.48 min: 375 $[M+H]^+$, 345

Microbial hydroxylation of Compound 331

To a 500 mL flask containing 100 ml of the transformation medium was added one frozen vial (approximately 2 ml) of *Streptomyces griseus* ATCC 10137. The transformation medium was prepared as follows: to a 2 L plastic beaker was added 20 g of dextrose, 5.0 g of yeast extract, 5.0 g of soybean meal, 5.0 g of sodium chloride, 5.0 g of potassium phosphate (dibasic) and one L of deionized water, and the mixture was stirred at room temperature for 3 to 30 min. The pH of the mixture was then adjusted to 7.0 with 1 N HCl or 1 N NaOH. The resulting mixture was dispensed into 500 mL flasks (100 ml


per flask). The flasks were covered with Bio/Wrap and autoclaved at 121°C for 15 min. and cooled down to room temperature before use.

The culture was incubated at 28°C and 250 rpm for 3 days. One mL of the resulting culture was added to a 500 mL flask containing 100 mL of the transformation medium and the flask was incubated at 28°C and 250 rpm for 24 hours. Ten mL of the resulting culture was transferred to a 50 mL flask, to which 1 mg of compound 331 in 0.2 mL ethanol was added. The flask was incubated at 28°C and 250 rpm for 23 hours. HPLC analysis showed that the peak area ratio of compound 459 to compound 331 in the reaction culture was about 1.1/1.

347

Example 460


(1aα,2β,2aα,5aα,6βb,6aα)-4-[2-[2-[[(1,1-Dimethylethyl)dimethylsilyl]oxy]ethyl]octahydro-6-methyl-3,5-dioxo-2,6-epoxy-4H-oxireno[f]isoindol-4-yl]-1-naphthalenecarbonitrile (460)



Compound **231A** (2.00 g, 4.10 mmol) was dissolved in dicholomethane (40 ml) and cooled to 0°C. mCPBA (2.36 g, 8.20 mmol) was added. The reaction mixture was then warmed up to room temperature and stirred under argon for 18 hours, followed by the addition of 10% Na_2SO_3 (25 ml) and saturated $NaHCO_3$ (25 ml). After stirring for 20 minutes, the organic layer was separated and the aqueous layer was extracted with dicholomethane (3 x 50 ml). The combined organic layers were washed with brine, dried over Na_2SO_4 and concentrated to give 2.0 g compound **460** as light yellow solid. HPLC: 99% at 4.00 min (retention time) (Phenomenex-prime S5-C18 column 4.6 x 50 mm eluting with 10-90% aqueous methanol over 4 minutes containing 0.2% phosphoric acid, 4 mL/min, monitoring at 220 nm), MS (ES): m/z [M+H] = 505.19

Example 461

[3aR-(3aα,4β,7β,7aα)]-4-[4-Ethyloctahydro-7-(2-hydroxyethyl)-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile & [3aS-(3aα,4β,7β,7aα)]-4-[4-Ethyloctahydro-7-(2-hydroxyethyl)-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitril (461I & 461II)




The racemic mixture of compounds **245C** was separated by normal phase preparative chiral HPLC using a Chiracel AD column (5 cm x 50 cm), eluting with 20% solvent B (50% MeOH/EtOH) in solvent A (Heptane), flow

rate: 50 mL/min. Compound **461I** eluted from 80 min to 100 min and compound **461II** eluted from 125 min to 150 min.

The absolute conformation for compounds **461I** and **461II** was not determined. For simplicity in nomenclature, compound **461I** is designated herein as having an "R" configuration and compound **461ii** as having an "S" configuration. Enantiomerically pure products derived from compound **461I** are designated herein as having an "R" configuration and enantiomerically pure products derived from compound **461II** are designated herein as having an "S" configuration.

Example 462

[3aR-(3aα,4β,7β,7aα)]-4-[4-[2-(4-Cyanophenoxy)ethyl]-7-ethyloctahydro-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile (462)




DBAD (29.5 mg, 0.128 mmol) was added to a solution of PPh_3 (33.6 mg, 0.128 mmol) in THF (0.5 mL). After stirring for 10 mins, 4-cyanophenol (15.2 mg, 0.128 mmol) was added and the reaction mixture was stirred for an additional 5 mins. Compound **461I** (18.3 mg, 0.047 mmol) was added and the mixture was stirred at rt for 2 h. The reaction was concentrated under reduced pressure. Purification by flash chromatography on silica gel eluting with 40% EtOAc/hexane gave 16.9 mg (0.034 mmol, 73.2%) of compound **462**. HPLC conditions: 98% at 3.64 min (YMC S5 ODS 4.6 X 50 mm, 10%-90% aqueous methanol over 4 minute gradient with 0.2% H_3PO_4, detecting at 220 nm). MS (ES): m/z 492.23 $[M+H]^+$.

Example 463

[3aS-(3aα,4β,7β,7aα)]-4-[4-[2-(4-Cyanophenoxy)ethyl]-7-ethyloctahydro-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile (463)

349




DBAD (29.5 mg, 0.128 mmol) was added to a solution of PPh_3 (33.6 mg, 0.128 mmol) in THF (0.5 mL). After stirring for 10 mins, 4-cyanophenol (15.2 mg, 0.128 mmol) was added and the reaction mixture was stirred for an additional 5 mins. Compound **461II** (18.3 mg, 0.047 mmol) was added and the mixture was stirred at rt for 2 h. The reaction was concentrated under reduced pressure. Purification by flash chromatography on silica gel eluting with 40% EtOAc/hexane gave 18.1 mg (0.037 mmol, 78.4%) of compound **463**. HPLC conditions: 97% at 3.63 min (YMC S5 ODS 4.6 X 50 mm, 10%-90% aqueous methanol over 4 minute gradient with 0.2% H_3PO_4, detecting at 220 nm). MS (ES): m/z 492.17 $[M+H]^+$.

350

Claims

We claim:

1. A compound of the following formula:



(Ia)

wherein the symbols have the following meanings and are, for each occurrence, independently selected:

G is an aryl or heterocyclo group, where said group is mono- or polycyclic, and which is optionally substituted at one or more positions;

Z_1 is O, S, NH, or NR^6;

Z_2 is O, S, NH, or NR^6;

A_1 is CR^7 or N;

A_2 is CR^7 or N;

Y' is J-J'-J" where J is $(CR^7R^{7'})n$ and n = 0-3, J' is a bond or O, S, S=O, SO_2, NH, NR^7, $CR^7R^{7'}$, R^2P=O, R^2P=S, R^2OP=O, R^2NHP=O, OP=OOR^2, OP=$ONHR^2$, OSO_2, NHNH, $NHNR^6$, NR^6NH, N=N, cycloalkyl or substituted cycloalkyl, cycloalkenyl or substituted cycloalkenyl, or heterocyclo or substituted heterocyclo, and J" is $(CR^7R^{7'})n$ and n = 0-3, where Y is not a bond; and

W' is $CR^7R^{7'}$—$CR^7R^{7'}$, $CR^7R^{7'}$—C=O, NR^9—$CR^7R^{7'}$, N=CR^8, N=N, NR^9—$NR^{9'}$, cycloalkyl or substituted cycloalkyl, cycloalkenyl or substituted cycloalkenyl, heterocyclo or substituted heterocyclo, or aryl or substituted aryl, wherein, when W' is not NR^9—$CR^7R^{7'}$, N=CR^8, N=N, NR^9—$NR^{9'}$, or heterocyclo or

substituted heterocyclo, then J' must be O, S, S=O, SO_2, NH, NR^7, $OP=OOR^2$, $OP=ONHR^2$, OSO_2, NHNH, $NHNR^6$, NR^6NH, or N=N; or alternatively,

Y' is NR^7-$CR^7R^{7'}$ and W' is $CR^8=CR^{8'}$; or, alternatively,

Y' is $CR^7R^{7'}$-C=O and W' is NR^9-$CR^7R^{7'}$;

Q_1 is H, alkyl or substituted alkyl, alkenyl or substituted alkenyl, cycloalkyl or substituted cycloalkyl, cycloalkenyl or substituted cycloalkenyl, heterocycloalkyl or substituted heterocycloalkyl, arylalkyl or substituted arylalkyl, alkynyl or substituted alkynyl, aryl or substituted aryl, heterocyclo or substituted heterocyclo, halo, CN, $R^1OC=O$, $R^4C=O$, $R^5R^6NC=O$, $HOCR^7R^{7'}$, nitro, R^1OCH_2, R^1O, NH_2, $C=OSR^1$, SO_2R^1 or NR^4R^5;

Q_2 is H, alkyl or substituted alkyl, alkenyl or substituted alkenyl, cycloalkyl or substituted cycloalkyl, cycloalkenyl or substituted cycloalkenyl, heterocycloalkyl or substituted heterocycloalkyl, arylalkyl or substituted arylalkyl, alkynyl or substituted alkynyl, aryl or substituted aryl, heterocyclo or substituted heterocyclo, halo, CN, $R^1OC=O$, $R^4C=O$, $R^5R^6NC=O$, $HOCR^7R^{7'}$, nitro, R^1OCH_2, R^1O, NH_2, $C=OSR^1$, SO_2R^1 or NR^4R^5;

L is a bond, $(CR^7R^{7'})n$, NH, NR^5 or $NR^5(CR^7R^{7'})n$, where n = 0-3;

R^1 and $R^{1'}$ are each independently H, alkyl or substituted alkyl, cycloalkyl or substituted cycloalkyl, cycloalkenyl or substituted cycloalkenyl, heterocyclo or substituted heterocyclo, cycloalkylalkyl or substituted cycloalkyalkyl, cycloalkenylalkyl or substituted cycloalkenylalkyl, heterocycloalkyl or substituted heterocycloalkyl, aryl or substituted aryl, arylalkyl or substituted arylalkyl;

R^2 is alkyl or substituted alkyl, cycloalkyl or substituted cycloalkyl, cycloalkenyl or substituted cycloalkenyl, heterocyclo or substituted heterocyclo, cycloalkylalkyl or substituted cycloalkylalkyl, cycloalkenylalkyl or substituted cycloalkenylalkyl, heterocycloalkyl or substituted heterocycloalkyl, aryl or substituted aryl, arylalkyl or substituted arylalkyl;

R^3 and $R^{3'}$ are each independently H, alkyl or substituted alkyl, cycloalkyl or substituted cycloalkyl, cycloalkenyl or substituted cycloalkenyl, heterocyclo or substituted heterocyclo, cycloalkylalkyl or substituted cycloalkylalkyl,

352

cycloalkenylalkyl or substituted cycloalkenylalkyl, heterocycloalkyl or substituted heterocycloalkyl, aryl or substituted aryl, arylalkyl or substituted arylalkyl, halo, CN, hydroxylamine, hydroxamide, alkoxy or substituted alkoxy, amino, NR^1R^2, thiol, alkylthio or substituted alkylthio;

R^4 is H, alkyl or substituted alkyl, cycloalkyl or substituted cycloalkyl, cycloalkenyl or substituted cycloalkenyl, heterocyclo or substituted heterocyclo, cycloalkylalkyl or substituted cycloalkylalkyl, cycloalkenylalkyl or substituted cycloalkenylalkyl, heterocycloalkyl or substituted heterocycloalkyl, aryl or substituted aryl, arylalkyl or substituted arylalkyl, $R^1C{=}O$, $R^1NHC{=}O$, SO_2OR^1, or $SO_2NR^1R^{1'}$;

R^5 is alkyl or substituted alkyl, cycloalkyl or substituted cycloalkyl, cycloalkenyl or substituted cycloalkenyl, heterocyclo or substituted heterocyclo, cycloalkylalkyl or substituted cycloalkylalkyl, cycloalkenylalkyl or substituted cycloalkenylalkyl, heterocycloalkyl or substituted heterocycloalkyl, aryl or substituted aryl, arylalkyl or substituted arylalkyl, $R^1C{=}O$, $R^1NHC{=}O$, SO_2R^1, SO_2OR^1, or $SO_2NR^1R^{1'}$;

R^6 is alkyl or substituted alkyl, cycloalkyl or substituted cycloalkyl, cycloalkenyl or substituted cycloalkenyl, heterocyclo or substituted heterocyclo, cycloalkylalkyl or substituted cycloalkylalkyl, cycloalkenylalkyl or substituted cycloalkenylalkyl, heterocycloalkyl or substituted heterocycloalkyl, aryl or substituted aryl, arylalkyl or substituted arylalkyl, CN, OH, OR^1, $R^1C{=}O$, $R^1NHC{=}O$, SO_2R^1, SO_2OR^1, or $SO_2NR^1R^{1'}$;

R^7 and $R^{7'}$ are each independently H, alkyl or substituted alkyl, alkenyl or substituted alkenyl, cycloalkyl or substituted cycloalkyl, cycloalkenyl or substituted cycloalkenyl, heterocyclo or substituted heterocyclo, cycloalkylalkyl or substituted cycloalkylalkyl, cycloalkenylalkyl or substituted cycloalkenylalkyl, heterocycloalkyl or substituted heterocycloalkyl, aryl or substituted aryl, arylalkyl or substituted arylalkyl, halo, CN, OR^1, nitro, hydroxylamine, hydroxylamide, amino, NHR^4, NR^2R^5, NOR^1, thiol, alkylthio or substituted alkylthio, $R^1C{=}O$, $R^1OC{=}O$, $R^1NHC{=}O$, SO_2R^1, SOR^1, $PO_3R^1R^{1'}$, $R^1R^{1'}NC{=}O$, $C{=}OSR^1$, SO_2R^1, SO_2OR^1, or $SO_2NR^1R^{1'}$, or, wherein

A_1 or A_2 contains a group R^7 and W contains a group R^7, said R^7 groups of A_1 or A_2 and W together form a heterocyclic ring;

R^8 and $R^{8'}$ are each independently H, alkyl or substituted alkyl, alkenyl or substituted alkenyl, cycloalkyl or substituted cycloalkyl, cycloalkenyl or substituted cycloalkenyl, heterocyclo or substituted heterocyclo, cycloalkylalkyl or substituted cycloalkyalkyl, cycloalkenylalkyl or substituted cycloalkenylalkyl, heterocycloalkyl or substituted heterocycloalkyl, aryl or substituted aryl, arylalkyl or substituted arylalkyl, nitro, halo, CN, OR^1, amino, NHR^4, NR^2R^5, NOR^1, alkylthio or substituted alkylthio, $C{=}OSR^1$, $R^1OC{=}O$, $R^1C{=}O$, $R^1NHC{=}O$, $R^1R^{1'}NC{=}O$, SO_2OR^1, $S{=}OR^1$, SO_2R^1, $PO_3R^1R^{1'}$, or $SO_2NR^1R^{1'}$; and

R^9 and $R^{9'}$ are each independently H, alkyl or substituted alkyl, alkenyl or substituted alkenyl, cycloalkyl or substituted cycloalkyl, cycloalkenyl or substituted cycloalkenyl, heterocyclo or substituted heterocyclo, cycloalkylalkyl or substituted cycloalkylalkyl, cycloalkenylalkyl or substituted cycloalkenylalkyl, heterocycloalkyl or substituted heterocycloalkyl, aryl or substituted aryl, arylalkyl or substituted arylalkyl, CN, OH, OR^1, $R^1C{=}O$, $R^1OC{=}O$, $R^1NHC{=}O$, SO_2R^1, SO_2OR^1, or $SO_2NR^1R^{1'}$;

with the provisos that:

(1) when Y' is -O-, Q_1 and Q_2 are hydrogen, Z_1 and Z_2 are O, W' is $-CH_2-CH_2-$, and A_1 and A_2 are CH, then G-L is not phenyl, monosubstituted phenyl or phenyl which is substituted with two or more of the following groups: methoxy, halo, NO_2, methyl, CH_3-S-, OH, CO_2H, trifluoromethyl, $-C(O)-C_6H_5$, NH_2, 4-7-epoxy, hexahydro-1H-isoindole-1,3(2H)dione, or $-C(O)-CH_3$;

(2) when Y' is -O-, Q_1 and Q_2 are hydrogen, Z_1 and Z_2 are O, W' is CH_2-CH_2, and one of A_1 and A_2 is CH and the other is CR^7, then G-L is not unsubstituted phenyl;

(3) when Y' is -O-, Q_1 and Q_2 are hydrogen, Z_1 and Z_2 are O, W' is CH_2-CH_2, and one of A_1 and A_2 is CH and the other is $C-CH_3$, then G-L is not phenyl substituted with chloro and/or methyl;

354

(4) when Y' is -O- or -S-, Q_1 and Q_2 are hydrogen, Z_1 and Z_2 are O, W' is CH_2-CH_2, and one of A_1 and A_2 is CH and the other is CH or C-alkyl, then G-L is not N-substituted piperazine-alkyl- or N-substituted imidazolidine-alkyl-;

(5) when Y' is -O-; Q_1 and Q_2 are hydrogen, Z_1 and Z_2 are O, W' is CH_2-CH_2, and A_1 and A_2 are CH, then G-L is not oxazole or triazole;

(6) when Y' is -O-; Q_1 and Q_2 are hydrogen or methyl, Z_1 and Z_2 are O, W' is CH_2-CH_2, and A_1 and A_2 are CH or C-CH_3, then G-L is not thiazole or substituted thiazole;

(7) when Y' contains a group J' selected from S, S=O, SO_2, NH, NR^7, R^2P=O, R^2P=S, R^2OP=O, R^2NHP=O, OP=OOR^2, OP=$ONHR^2$, OSO_2, NHNH, NHR^6, NR^6NH or N=N, W' is CR^7R^7- CR^7R^7, and Z_1 and Z_2 are O, then G-L is not unsubstituted phenyl;

(8) when Y is NR^7, W' is unsubstituted or substituted phenyl, and Q_1 and Q_2 are hydrogen, then Z_1 and Z_2 are not O;

(9) when Y' is —O—, Q_1 and Q_2 are hydrogen, Z_1 and Z_2 are O, W' is dihydroisoxazole bearing an optionally substituted phenyl group, and A_1 and A_2 are CH, then G-L is not unsubstituted phenyl or dichlorophenyl;

(10) when Y' is O, Q_1 and Q_2 are hydrogen, Z_1 and Z_2 are O, W' is ethylene oxide, and A_1 and A_2 are CH, then G-L is not methylphenyl or chlorophenyl;

(11) when Y' is NR^7—CR^7R^7, W' is CR^8=CR^8, Q_1 and Q_2 are hydrogen, A_1 and A_2 are CH, C-CH_3, C-CH_2-C_6H_5 or C-CH_2-CH_3, and Z_1 and Z_2 are O, then G-L is not unsubstituted phenyl, monosubstituted phenyl or methylpyridinyl;

(12) when Y' is CR^7R^7—C=O, , W' is NR^9—CR^7R^7, Q_1 and Q_2 are hydrogen, A_1 and A_2 are CH, and Z_1 and Z_2 are O, then G-L is not unsubstituted phenyl;

(13) when Y' is CHR^7—NR^7 where R^7 is unsubstituted phenyl, methoxy or ethoxy and R^7 is unsubstituted phenyl, methyl or -C(O)-C_6H_5, W' is dimethoxyphenylene or unsubstituted phenylene, Z_1 and Z_2 are O, Q_1 and Q_2 are hydrogen, A_1 and A_2 are CH, C-CN, C-C(O)-C_6H_5, or -C(O)-dimethoxyphenyl, then G-L is not unsubstituted phenyl;

(14) the compound of formula Ia is not 6,10-epithio-4H-thieno-[3',4':5,6]cyclooct[1,2-*f*]isoindole-7,9(5H,8H)dione, 8-(3,5-dichlorophenyl)-

355

6,6a,9a,10,11,12,-hexahydro-1,3,6,10-tetramethyl-2,2,13-trioxide, (6R,6aR,9aS,10S);

(15) when Y' is O, W' is $-CH_2-CH_2-$, Q_1 and Q_2 are methyl, Z_1 and Z_2 are O, and A_1 and A_2 are CH, then G-L is not unsubstituted phenyl, phenyl substituted with methoxy, phenyl-alkyl-, or morpholine-alkyl, nor is the compound bridged to itself through a group L which is alkylene to form a bis compound;

(16) when Y' is –O-, Q_1 and Q_2 are hydrogen, Z_1 and Z_2 are O, W' is CR^7R^7-CR^7R^7, and A_1 and A_2 are CH, then G-L is not an unsubstituted phenyl group; and

(17) when Y' is –O-, Q_1 and Q_2 are hydrogen, Z_1 and Z_2 are O, W' is cyclopentyl, cyclohexyl, 3-phenyl-2-isoxazoline or CR^7R^7-CR^7R^7 where R^7 and $R^{7'}$ are each independently defined as Cl, Br, H and 4-butyrolactone and R^7 and $R^{7'}$ are not all simultaneously H, and A_1 and A_2 are CH, then G-L is not an unsubstituted naphthyl ring or a monosubstituted phenyl ring, where said substituent is methoxy, Br, Cl, NO_2, methyl, ethyl, CH_2-phenyl, S-phenyl, or O-phenyl.

2. The compound of Claim 1 wherein

G is an aryl or heterocyclo group, where said group is mono- or polycyclic, and which is optionally substituted at one or more positions;

Z_1 is O, S, NH, or NR^6;

Z_2 is O, S, NH, or NR^6;

A_1 is CR^7 or N;

A_2 is CR^7 or N;

Y' is J-J'-J" where J is $(CR^7R^{7'})n$ and n = 0-3, J' is a bond or O, S, S=O, SO_2, NH, NR^7, $CR^7R^{7'}$, R^2P=O, R^2P=S, R^2OP=O, R^2NHP=O, OP=OOR^2, OP=$ONHR^2$, OSO_2, NHNH, $NHNR^6$, NR^6NH, N=N, cycloalkyl or substituted cycloalkyl, cycloalkenyl or substituted cycloalkenyl, or heterocyclo or substituted heterocyclo, and J" is $(CR^7R^{7'})n$ and n = 0-3, where Y' is not a bond;

356

W' is $CR^7R^{7'}$—$CR^7R^{7'}$, $CR^7R^{7'}$—C=O, NR^9—$CR^7R^{7'}$, N=CR^8, N=N, NR^9—$NR^{9'}$, cycloalkyl or substituted cycloalkyl, cycloalkenyl or substituted cycloalkenyl, heterocyclo or substituted heterocyclo, or aryl or substituted aryl, wherein, when W' is not NR^9—$CR^7R^{7'}$, N=CR^8, N=N, NR^9—$NR^{9'}$, or heterocyclo or substituted heterocyclo, then J' must be O, S, S=O, SO_2, NH, NR^7, OP=OOR^2, OP=ONHR^2, OSO_2, NHNH, $NHNR^6$, NR^6NH, or N=N;

Q_1 is H, alkyl or substituted alkyl, alkenyl or substituted alkenyl, cycloalkyl or substituted cycloalkyl, cycloalkenyl or substituted cycloalkenyl, heterocycloalkyl or substituted heterocycloalkyl, arylalkyl or substituted arylalkyl, alkynyl or substituted alkynyl, aryl or substituted aryl, heterocyclo or substituted heterocyclo, halo, CN, R^1OC=O, R^4C=O, R^5R^6NC=O, $HOCR^7R^{7'}$, nitro, R^1OCH_2, R^1O, NH_2, or NR^4R^5;

Q_2 is H, alkyl or substituted alkyl, alkenyl or substituted alkenyl, cycloalkyl or substituted cycloalkyl, cycloalkenyl or substituted cycloalkenyl, heterocycloalkyl or substituted heterocycloalkyl, arylalkyl or substituted arylalkyl, alkynyl or substituted alkynyl, aryl or substituted aryl, heterocyclo or substituted heterocyclo, halo, CN, R^1OC=O, R^4C=O, R^5R^6NC=O, $HOCR^7R^{7'}$, nitro, R^1OCH_2, R^1O, NH_2, or NR^4R^5;

L is a bond, $(CR^7R^{7'})n$, NH, NR^5 or $NR^5(CR^7R^{7'})n$, where n = 0-3;

R^1 and $R^{1'}$ are each independently H, alkyl or substituted alkyl, cycloalkyl or substituted cycloalkyl, cycloalkenyl or substituted cycloalkenyl, heterocyclo or substituted heterocyclo, cycloalkylalkyl or substituted cycloalkyalkyl, cycloalkenylalkyl or substituted cycloalkenylalkyl, heterocycloalkyl or substituted heterocycloalkyl, aryl or substituted aryl, arylalkyl or substituted arylalkyl;

R^2 is alkyl or substituted alkyl, cycloalkyl or substituted cycloalkyl, cycloalkenyl or substituted cycloalkenyl, heterocyclo or substituted heterocyclo, cycloalkylalkyl or substituted cycloalkylalkyl, cycloalkenylalkyl or substituted cycloalkenylalkyl, heterocycloalkyl or substituted heterocycloalkyl, aryl or substituted aryl, arylalkyl or substituted arylalkyl;

357

R^3 and $R^{3'}$ are each independently H, alkyl or substituted alkyl, cycloalkyl or substituted cycloalkyl, cycloalkenyl or substituted cycloalkenyl, heterocyclo or substituted heterocyclo, cycloalkylalkyl or substituted cycloalkylalkyl, cycloalkenylalkyl or substituted cycloalkenylalkyl, heterocycloalkyl or substituted heterocycloalkyl, aryl or substituted aryl, arylalkyl or substituted arylalkyl, halo, CN, hydroxylamine, hydroxamide, alkoxy or substituted alkoxy, amino, NR^1R^2, thiol, alkylthio or substituted alkylthio;

R^4 is H, alkyl or substituted alkyl, cycloalkyl or substituted cycloalkyl, cycloalkenyl or substituted cycloalkenyl, heterocyclo or substituted heterocyclo, cycloalkylalkyl or substituted cycloalkylalkyl, cycloalkenylalkyl or substituted cycloalkenylalkyl, heterocycloalkyl or substituted heterocycloalkyl, aryl or substituted aryl, arylalkyl or substituted arylalkyl, $R^1C{=}O$, $R^1NHC{=}O$, or $SO_2NR^1R^{1'}$;

R^5 is alkyl or substituted alkyl, cycloalkyl or substituted cycloalkyl, cycloalkenyl or substituted cycloalkenyl, heterocyclo or substituted heterocyclo, cycloalkylalkyl or substituted cycloalkylalkyl, cycloalkenylalkyl or substituted cycloalkenylalkyl, heterocycloalkyl or substituted heterocycloalkyl, aryl or substituted aryl, arylalkyl or substituted arylalkyl, $R^1C{=}O$, $R^1NHC{=}O$, SO_2R^1, or $SO_2NR^1R^{1'}$;

R^6 is alkyl or substituted alkyl, cycloalkyl or substituted cycloalkyl, cycloalkenyl or substituted cycloalkenyl, heterocyclo or substituted heterocyclo, cycloalkylalkyl or substituted cycloalkylalkyl, cycloalkenylalkyl or substituted cycloalkenylalkyl, heterocycloalkyl or substituted heterocycloalkyl, aryl or substituted aryl, arylalkyl or substituted arylalkyl, CN, OH, OR^1, $R^1C{=}O$, $R^1NHC{=}O$, SO_2R^1, or $SO_2NR^1R^{1'}$;

R^7 and $R^{7'}$ are each independently H, alkyl or substituted alkyl, alkenyl or substituted alkenyl, cycloalkyl or substituted cycloalkyl, cycloalkenyl or substituted cycloalkenyl, heterocyclo or substituted heterocyclo, cycloalkylalkyl or substituted cycloalkylalkyl, cycloalkenylalkyl or substituted cycloalkenylalkyl, heterocycloalkyl or substituted heterocycloalkyl, aryl or substituted aryl, arylalkyl or substituted arylalkyl, halo, CN, OR^1, nitro,

hydroxylamine, hydroxylamide, amino, NHR^4, NR^2R^5, NOR^1, thiol, alkylthio or substituted alkylthio, $R^1C{=}O$, $R^1OC{=}O$, $R^1NHC{=}O$, SOR^1, $PO_3R^1R^{1'}$, $R^1R^{1'}NC{=}O$, $C{=}OSR^1$, SO_2R^1, or $SO_2NR^1R^{1'}$;

R^8 and $R^{8'}$ are each independently H, alkyl or substituted alkyl, alkenyl or substituted alkenyl, cycloalkyl or substituted cycloalkyl, cycloalkenyl or substituted cycloalkenyl, heterocyclo or substituted heterocyclo, cycloalkylalkyl or substituted cycloalkyalkyl, cycloalkenylalkyl or substituted cycloalkenylalkyl, heterocycloalkyl or substituted heterocycloalkyl, aryl or substituted aryl, arylalkyl or substituted arylalkyl, nitro, halo, CN, OR^1, amino, NHR^4, NR^2R^5, NOR^1, alkylthio or substituted alkylthio, $C{=}OSR^1$, $R^1OC{=}O$, $R^1C{=}O$, $R^1NHC{=}O$, $R^1R^{1'}NC{=}O$, $S{=}OR^1$, SO_2R^1, $PO_3R^1R^{1'}$, or $SO_2NR^1R^{1'}$;

R^9 and $R^{9'}$ are each independently H, alkyl or substituted alkyl, cycloalkyl or substituted cycloalkyl, cycloalkenyl or substituted cycloalkenyl, heterocyclo or substituted heterocyclo, cycloalkylalkyl or substituted cycloalkylalkyl, cycloalkenylalkyl or substituted cycloalkenylalkyl, heterocycloalkyl or substituted heterocycloalkyl, aryl or substituted aryl, arylalkyl or substituted arylalkyl, CN, OH, OR^1, $R^1C{=}O$, $R^1OC{=}O$, $R^1NHC{=}O$, or $SO_2NR^1R^{1'}$;

with the provisos (1) to (17) of said formula Ia, and further where (i) when Y' is -O- and W' is $CR^7R^{7'}{-}{-}CR^7R^{7'}$, A_1 and A_2 are not simultaneously CH; and (ii) when L is a bond, G is not an unsubstituted phenyl group.

3. The compound of Claim 1, wherein

G is an aryl or heterocyclo group, where said group is mono- or polycyclic, and which is optionally substituted at one or more positions;

Z_1 is O;

Z_2 is O;

A_1 is CR^7;

A_2 is CR^7;

359

Y' is J-J'-J" where J is $(CR^7R^{7'})n$ and n = 0-3, J' is a bond or O, S, S=O, SO_2, NH, NR^7, $CR^7R^{7'}$, $R^2P=O$, $R^2P=S$, $R^2OP=O$, $R^2NHP=O$, $OP=OOR^2$, $OP=ONHR^2$, OSO_2, NHNH, $NHNR^6$, NR^6NH, N=N, cycloalkyl or substituted cycloalkyl, cycloalkenyl or substituted cycloalkenyl, or heterocyclo or substituted heterocyclo, and J" is $(CR^7R^{7'})n$ and n = 0-3, where Y' is not a bond;

W' is $CR^7R^{7'}$—$CR^7R^{7'}$, $CR^7R^{7'}$—C=O, NR^9—$CR^7R^{7'}$, N=CR^8, N=N, NR^9—$NR^{9'}$, cycloalkyl or substituted cycloalkyl, cycloalkenyl or substituted cycloalkenyl, heterocyclo or substituted heterocyclo, or aryl or substituted aryl, wherein, when W' is not NR^9—$CR^7R^{7'}$, N=CR^8, N=N, NR^9—$NR^{9'}$, or heterocyclo or substituted heterocyclo, then J' must be O, S, S=O, SO_2, NH, NR^7, $OP=OOR^2$, $OP=ONHR^2$, OSO_2, NHNH, $NHNR^6$, NR^6NH, or N=N;

Q_1 is H, alkyl or substituted alkyl, alkenyl or substituted alkenyl, cycloalkyl or substituted cycloalkyl, cycloalkenyl or substituted cycloalkenyl, heterocycloalkyl or substituted heterocycloalkyl, arylalkyl or substituted arylalkyl, alkynyl or substituted alkynyl, aryl or substituted aryl, heterocyclo or substituted heterocyclo, halo, CN, $R^4C=O$, $R^5R^6NC=O$, $HOCR^7R^{7'}$, nitro, R^1OCH_2, R^1O, NH_2, or NR^4R^5;

Q_2 is H, alkyl or substituted alkyl, alkenyl or substituted alkenyl, cycloalkyl or substituted cycloalkyl, cycloalkenyl or substituted cycloalkenyl, heterocycloalkyl or substituted heterocycloalkyl, arylalkyl or substituted arylalkyl, alkynyl or substituted alkynyl, aryl or substituted aryl, heterocyclo or substituted heterocyclo, halo, CN, $R^4C=O$, $R^5R^6NC=O$, $HOCR^7R^{7'}$, nitro, R^1OCH_2, R^1O, NH_2, or NR^4R^5;

L is a bond;

R^1 and $R^{1'}$ are each independently H, alkyl or substituted alkyl, cycloalkyl or substituted cycloalkyl, cycloalkenyl or substituted cycloalkenyl, heterocyclo or substituted heterocyclo, cycloalkylalkyl or substituted cycloalkyalkyl, cycloalkenylalkyl or substituted cycloalkenylalkyl, heterocycloalkyl or substituted heterocycloalkyl, aryl or substituted aryl, arylalkyl or substituted arylalkyl;

360

R^2 is alkyl or substituted alkyl, cycloalkyl or substituted cycloalkyl, cycloalkenyl or substituted cycloalkenyl, heterocyclo or substituted heterocyclo, cycloalkylalkyl or substituted cycloalkylalkyl, cycloalkenylalkyl or substituted cycloalkenylalkyl, heterocycloalkyl or substituted heterocycloalkyl, aryl or substituted aryl, arylalkyl or substituted arylalkyl;

R^3 and $R^{3'}$ are each independently H, alkyl or substituted alkyl, cycloalkyl or substituted cycloalkyl, cycloalkenyl or substituted cycloalkenyl, heterocyclo or substituted heterocyclo, cycloalkylalkyl or substituted cycloalkylalkyl, cycloalkenylalkyl or substituted cycloalkenylalkyl, heterocycloalkyl or substituted heterocycloalkyl, aryl or substituted aryl, arylalkyl or substituted arylalkyl, halo, CN, alkoxy or substituted alkoxy, amino, NR^1R^2, alkylthio or substituted alkylthio;

R^4 is H, alkyl or substituted alkyl, cycloalkyl or substituted cycloalkyl, cycloalkenyl or substituted cycloalkenyl, heterocyclo or substituted heterocyclo, cycloalkylalkyl or substituted cycloalkylalkyl, cycloalkenylalkyl or substituted cycloalkenylalkyl, heterocycloalkyl or substituted heterocycloalkyl, aryl or substituted aryl, arylalkyl or substituted arylalkyl, $R^1C{=}O$, $R^1NHC{=}O$, or $SO_2NR^1R^{1'}$;

R^5 is alkyl or substituted alkyl, cycloalkyl or substituted cycloalkyl, cycloalkenyl or substituted cycloalkenyl, heterocyclo or substituted heterocyclo, cycloalkylalkyl or substituted cycloalkylalkyl, cycloalkenylalkyl or substituted cycloalkenylalkyl, heterocycloalkyl or substituted heterocycloalkyl, aryl or substituted aryl, arylalkyl or substituted arylalkyl, $R^1C{=}O$, $R^1NHC{=}O$, SO_2R^1, or $SO_2NR^1R^{1'}$;

R^6 is alkyl or substituted alkyl, cycloalkyl or substituted cycloalkyl, cycloalkenyl or substituted cycloalkenyl, heterocyclo or substituted heterocyclo, cycloalkylalkyl or substituted cycloalkylalkyl, cycloalkenylalkyl or substituted cycloalkenylalkyl, heterocycloalkyl or substituted heterocycloalkyl, aryl or substituted aryl, arylalkyl or substituted arylalkyl, CN, OH, OR^1, $R^1C{=}O$, $R^1NHC{=}O$, SO_2R^1, or $SO_2NR^1R^{1'}$;

361

R^7 and $R^{7'}$ are each independently H, alkyl or substituted alkyl, alkenyl or substituted alkenyl, cycloalkyl or substituted cycloalkyl, cycloalkenyl or substituted cycloalkenyl, heterocyclo or substituted heterocyclo, cycloalkylalkyl or substituted cycloalkylalkyl, cycloalkenylalkyl or substituted cycloalkenylalkyl, heterocycloalkyl or substituted heterocycloalkyl, aryl or substituted aryl, arylalkyl or substituted arylalkyl, halo, CN, OR^1, nitro, amino, NHR^4, NR^2R^5, alkylthio or substituted alkylthio, $R^1C{=}O$, $R^1NHC{=}O$, SO_2R^1, $R^1R^{1'}NC{=}O$, or $SO_2NR^1R^{1'}$;

R^8 and $R^{8'}$ are each independently H, alkyl or substituted alkyl, alkenyl or substituted alkenyl, cycloalkyl or substituted cycloalkyl, cycloalkenyl or substituted cycloalkenyl, heterocyclo or substituted heterocyclo, cycloalkylalkyl or substituted cycloalkyalkyl, cycloalkenylalkyl or substituted cycloalkenylalkyl, heterocycloalkyl or substituted heterocycloalkyl, aryl or substituted aryl, arylalkyl or substituted arylalkyl, nitro, halo, CN, OR^1, amino, NHR^4, NR^2R^5, alkylthio or substituted alkylthio, $R^1C{=}O$, $R^1NHC{=}O$, $R^1R^{1'}NC{=}O$, SO_2R^1, or $SO_2NR^1R^{1'}$; and

R^9 and $R^{9'}$ are each independently H, alkyl or substituted alkyl, cycloalkyl or substituted cycloalkyl, cycloalkenyl or substituted cycloalkenyl, heterocyclo or substituted heterocyclo, cycloalkylalkyl or substituted cycloalkylalkyl, cycloalkenylalkyl or substituted cycloalkenylalkyl, heterocycloalkyl or substituted heterocycloalkyl, aryl or substituted aryl, arylalkyl or substituted arylalkyl, CN, OH, OR^1, $R^1C{=}O$, $R^1NHC{=}O$, or $SO_2NR^1R^{1'}$;

with the provisos (1) to (17) of said formula Ia, and further where (i) when Y' is -O- and W' is $CR^7R^{7'}{-}CR^7R^7$, A_1 and A_2 are not simultaneously CH; and (ii) when L is a bond, G is not an unsubstituted phenyl group.

4. A compound selected from the group consisting of:

(3aα,4α,7α,7aα)-2-(4-Bromo-3-methylphenyl)tetrahydro-4,7-ethanothiopyrano[3,4-c]pyrrole-1,3,8(2H,4H)-trione (1C);

362

(3aα,4α,7α,7aα)-2-(4-Bromo-3-methylphenyl)tetrahydro-4,7-ethanothiopyrano[3,4-c]pyrrole-1,3,8(2H,4H)-trione 5,5-dioxide (2);
(3aα,4β,7β,7aα)-2-(3-Chlorophenyl)hexahydro-4-methyl-4,7-epoxy-1H-isoindole-1,3(2H)-dione (3);
(3aα,4α,7α,7aα)- and (3aα,4β,7β,7aα)-4-[(Acetyloxy)methyl]-3a,4,7,7a-tetrahydro-2-[3-(trifluoromethyl)phenyl]-4,7-epoxy-1H-isoindole-1,3(2H)-dione (4i & 4ii, respectively);
(3aα,4α,7α,7aα)- and (3aα,4β,7β,7aα)-4-[(Acetyloxy)methyl]-Hexahydro-2-[3-(trifluoromethyl)phenyl]-4,7-epoxy-1H-isoindole-1,3(2H)-dione (5i & 5ii, respectively);
(3aα,4α,7α,7aα)- and (3aα,4β,7β,7aα)-3a,4,7,7a-Tetrahydro-5-(hydroxymethyl)-2-[3-(trifluoromethyl)phenyl]-4,7-epoxy-1H-isoindole-1,3(2H)-dione (6i & 6ii, respectively);
(3aα,4α,7α,7aα)-3a,4,7,7a-Tetrahydro-5-(hydroxymethyl)-4-methyl-2-[3-(trifluoromethyl)phenyl]-4,7-epoxy-1H-isoindole-1,3(2H)-dione (7);
(3aα,4β,7β,7aα)-2-[3,5-Bis(trifluoromethyl)phenyl]hexahydro-4,7-epoxy-1H-isoindole-1,3(2H)-dione (8);
(3aα,4α,7α,7aα)-2-(4-Bromophenyl)octahydro-1,3-dioxo-4,7-etheno-5H-pyrrolo[3,4-c]pyridine-5-carboxylic acid phenyl ester (9);
(3aα,4α,7α,7aα)-2-(4-Bromophenyl)octahydro-1,3-dioxo-4,7-etheno-5H-pyrrolo[3,4-c]pyridine-5-carboxylic acid phenylmethyl ester (10);
(3aα,4α,7α,7aα)-Hexahydro-2-[3-(trifluoromethyl)phenyl]-4,7-ethano-1H-pyrrolo[3,4-c]pyridine-1,3(2H)-dione trifluoroacetate (11);
(3aα,4α,7α,7aα)-5-Acetylhexahydro-2-[3-(trifluoromethyl)phenyl]-4,7-ethano-1H-pyrrolo[3,4-c]pyridine-1,3(2H)-dione (12);
(3aα,4α,7α,7aα)-5-Benzoylhexahydro-2-[3-(trifluoromethyl)phenyl]-4,7-ethano-1H-pyrrolo[3,4-c]pyridine-1,3(2H)-dione (13);
(3aα,4α,7α,7aα)-Hexahydro-5-methyl-2-[3-(trifluoromethyl)phenyl]-4,7-ethano-1H-pyrrolo[3,4-c]pyridine-1,3(2H)-dione (14);

(3aα,4α,7α,7aα)-Hexahydro-5-(phenylmethyl)-2-[3-(trifluoromethyl)phenyl]-4,7-ethano-1H-pyrrolo[3,4-c]pyridine-1,3(2H)-dione trifluoroacetate (15);

(3aα,4α,7α,7aα)-Hexahydro-5-propyl-2-[3-(trifluoromethyl)phenyl]-4,7-ethano-1H-pyrrolo[3,4-c]pyridine-1,3(2H)-dione trifluoroacetate (16);

(3aα,4α,4aβ,5aβ,6α,6aα)-2-[4-Cyano-3-(trifluoromethyl)phenyl]decahydro-1,3-dioxo-4,6-(iminomethano)cycloprop[f]isoindole-7-carboxylic acid phenylmethyl ester (17);

(3aα,4α,4aβ,5aβ,6α,6aα)-4-[Decahydro-1,3-dioxo-4,6-(iminomethano)cycloprop[f]isoindol-2-yl]-2-(trifluoromethyl)benzonitrile (18);

(3aα,4α,4aβ,5aβ,6α,6aα)-4-[Decahydro-7-methyl-1,3-dioxo-4,6-(iminomethano)cycloprop[f]isoindol-2-yl]-2-(trifluoromethyl)benzonitrile (19);

(3aα,4β,7β,7aα)-4-(Octahydro-4,7-dimethyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl)-2-(trifluoromethyl)benzonitrile (20B);

(3aα,4β,7β,7aα)-N-[4-[[2-[2-[4-Cyano-3-(trifluoromethyl)phenyl]octahydro-7-methyl-1,3-dioxo-4,7-epoxy-4H-isoindol-4-yl]ethyl]thio]phenyl]acetamide (21E);

(3aα,4β,7β,7aα)-N-[4-[[2-[2-[4-Cyano-3-(trifluoromethyl)phenyl]octahydro-7-methyl-1,3-dioxo-4,7-epoxy-4H-isoindol-4-yl]ethyl]sulfinyl]phenyl]acetamide (22);

(3aα,4β,7β,7aα)-N-[4-[[2-[2-[4-Cyano-3-(trifluoromethyl)phenyl]octahydro-7-methyl-1,3-dioxo-4,7-epoxy-4H-isoindol-4-yl]ethyl]sulfonyl]phenyl]acetamide (23);

(3aα,4β,7β,7aα)- and (3aα,4α,7α,7aα)-N-[2-[2-[4-Cyano-3-(trifluoromethyl)phenyl]octahydro-7-methyl-1,3-dioxo-4,7-epoxy-4H-isoindol-4-yl]ethyl]benzenesulfonamide (24Ci & 24Cii, respectively);

(3aα,4β,7β,7aα)-4-[Octahydro-4-(2-hydroxyethyl)-7-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-2-(trifluoromethyl)benzonitrile (25B);

(3aα,4α,7α,7aα)- and (3aα,4β,7β,7aα)-N-[4-[2-[2-[4-Cyano-3-(trifluoromethyl)phenyl]octahydro-7-methyl-1,3-dioxo-4,7-epoxy-4H-isoindol-4-yl]ethoxy]phenyl]acetamide (26Ci & 26Cii, respectively);

(3aα,4α,7α,7aα)-Hexahydro-2-(2-naphthalenyl)-4,7-epoxy-1H-isoindole-1,3(2H)-dione (27D);

(1aα,2β,2aα,5aα,6β,6aα)-Hexahydro-4-(2-naphthalenyl)-2,6-epoxy-3H-oxireno[f]isoindole-3,5(4H)-dione (28B);

(3aα,4α,7α,7aα)-2-[4-Bromo-3-(trifluoromethyl)phenyl]-3a,4,7,7a-tetrahydro-4,7-dimethyl-4,7-epithio-1H-isoindole-1,3(2H)-dione 8-oxide (29);

(3aα,4α,7α,7aα)-2-[4-Bromo-3-(trifluoromethyl)phenyl]-3a,4,7,7a-tetrahydro-4,7-epithio-1H-isoindole-1,3(2H)-dione 8-oxide (30);

(3aα,4α,7α,7aα)-Hexahydro-2-[3-(trifluoromethyl)phenyl]-4,7-imino-1H-isoindole-1,3(2H)-dione (31D);

(3aα,4β,7β,7aα)- and (3aα,4α,7α,7aα)-3a,4,7,7a-Tetrahydro-4,7-dimethyl-2-[3-(trifluoromethyl)phenyl]-4,7-epoxy-1H-isoindole-1,3(2H)-dione (32i & 32ii, respectively);

(3aα,4α,7α,7a α)-Hexahydro-4,7-dimethyl-2-[3-(trifluoromethyl)phenyl]-4,7-epoxy-1H-isoindole-1,3(2H)-dione (33);

(3aα,4α,7α,7aα)-Tetrahydro-5-methyl-2-(4-nitro-1-naphthalenyl)-4,7-etheno-1H-pyrrolo[3,4-c]pyridine-1,3,6(2H,5H)-trione (34B);

(3aα,4β,7β,7aα)-4-[4-[2-(4-Fluorophenoxy)ethyl]octahydro-7-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-2-(trifluoromethyl)benzonitrile (35);

(3aα,4β,7β,7aα)-4-[4-(2-Bromoethyl]octahydro-7-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-2-(trifluoromethyl)benzonitrile (36);

(3aα,4β,7β,7aα)-Hexahydro-4,7-dimethyl-2-(3-methyl-4-nitrophenyl)-4,7-epoxy-1H-isoindole-1,3(2H)-dione (37);

(3aα,4β,7β,7aα)-2-(2-Fluorenyl)hexahydro-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

(3aα,4β,7β,7aα)-2-[3-Chloro-4-(4-morpholinyl)phenyl]hexahydro-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

(3aα,4β,7β,7aα)-2-(2,3-Dihydro-1H-inden-5-yl)hexahydro-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

365

(3aα,4β,7β,7aα)-2-(4-Bromo-1-naphthalenyl)hexahydro-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

(3aα,4β,7β,7aα)-2-(4-Chloro-1-naphthalenyl)hexahydro-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

(3aα,4β,7β,7aα)-2-(5-Amino-1-naphthalenyl)hexahydro-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

3aα,4β,7β,7aα)-Hexahydro-2-(7-hydroxy-1-naphthalenyl)-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

(3aα,4β,7β,7aα)-Hexahydro-2-(4-nitro-1-naphthalenyl)-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

(3aα,4β,7β,7aα)-Hexahydro-2-(1H-indol-5-yl)-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

(3aα,4β,7β,7aα)-Hexahydro-2-(1H-indazol-6-yl)-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

(3aα,4β,7β,7aα)-2-(1,3-Benzodioxol-5-yl)hexahydro-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

(3aα,4β,7β,7aα)-2-[4-Amino-3-(trifluoromethyl)phenyl]hexahydro-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

(3aα,4β,7β,7aα)-2-(3-Chloro-4-iodophenyl)hexahydro-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

(3aα,4β,7β,7aα)-Hexahydro-2-(8-quinolinyl)-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

(3aα,4β,7β,7aα)-2-(2,3-Dihydro-1,4-benzodioxin-6-yl)hexahydro-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

(3aα,4β,7β,7aα)-Hexahydro-2-[2-oxo-4-(trifluoromethyl)-2H-1-benzopyran-7-yl]-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

(3aα,4β,7β,7aα)-Hexahydro-2-(4-methyl-2-oxo-2H-1-benzopyran-7-yl)-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

(3aα,4β,7β,7aα)-2-(2,5-Dimethoxy-4-nitrophenyl)hexahydro-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

366

(3aα,4β,7β,7aα)-2,3,5,6-Tetrafluoro-4-(octahydro-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl)benzonitrile;

(3aα,4β,7β,7aα)-Hexahydro-2-(2,4,5-trifluorophenyl)-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

(3aα,4β,7β,7aα)-Hexahydro-2-(2,4,5-trichlorophenyl)-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

(3aα,4β,7β,7aα)-2-(2-Amino-4,5-dichlorophenyl)hexahydro-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

(3aα,4β,7β,7aα)-2-(3,4-Difluorophenyl)hexahydro-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

(3aα,4β,7β,7aα)-1-Acetyl-2,3-dihydro-6-(octahydro-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl)-1H-indole;

(3aα,4β,7β,7aα)-2-(3-Chloro-4-fluorophenyl)hexahydro-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

(3aα,4β,7β,7aα)-2-(3,4-Dichlorophenyl)hexahydro-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

(3aα,4β,7β,7aα)-Hexahydro-2-(3,4,5-trichlorophenyl)-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

(3aα,4β,7β,7aα)-2-(3-Chloro-4-methoxyphenyl)hexahydro-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

(3aα,4β,7β,7aα)-2-(3-Chloro-4-methylphenyl)hexahydro-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

(3aα,4β,7β,7aα)-Hexahydro-2-(2-methyl-1-naphthalenyl)-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

(3aα,4β,7β,7aα)-2-(4-Chloro-3-methylphenyl)hexahydro-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

(3aα,4β,7β,7aα)-2-(3,4-Dimethylphenyl)hexahydro-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

(3aα,4β,7β,7aα)-2-[4-Bromo-3-(trifluoromethyl)phenyl]hexahydro-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

367

(3aα,4β,7β,7aα)-2-(4-Bromo-3-methylphenyl)hexahydro-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

(3aα,4β,7β,7aα)-2-(4-Fluoro-3-nitrophenyl)hexahydro-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

(3aα,4β,7β,7aα)-2-[4-Fluoro-3-(trifluoromethyl)phenyl]hexahydro-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

(3aα,4β,7β,7aα)-2-(4-Chloro-3-nitrophenyl)hexahydro-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

(3aα,4β,7β,7aα)-2-[4-Chloro-3-(trifluoromethyl)phenyl]hexahydro-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

(3aα,4β,7β,7aα)-2-(4-Chloro-2-methoxy-5-methylphenyl)hexahydro-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

(3aα,4β,7β,7aα)-2-(4-Amino-3-nitrophenyl)hexahydro-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

(3aα,4β,7β,7aα)-Hexahydro-2-(4-methyl-3-nitrophenyl)-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

(3aα,4β,7β,7aα)-2-(3,4-Dimethoxyphenyl)hexahydro-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

(3aα,4β,7β,7aα)-Hexahydro-2-(3-hydroxy-4-methoxyphenyl)-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

(3aα,4β,7β,7aα)-Hexahydro-2-(4-methyl-5-nitro-2-pyridinyl)-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

(3aα,4β,7β,7aα)-2-Chloro-4-(octahydro-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl)-α-phenylbenzeneacetonitrile;

(3aα,4β,7β,7aα)-Hexahydro-2-(2-methoxy-3-dibenzofuranyl)-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

(3aα,4β,7β,7aα)-Hexahydro-2-(2,3,4-trifluorophenyl)-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

368

(3aα,4β,7β,7aα)-2-(2,3-Dihydro-2-methyl-1,3-dioxo-1H-isoindol-5-yl)hexahydro-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

(3aα,4β,7β,7aα)-2-(4-Bromo-2,3,5,6-tetrafluorophenyl)hexahydro-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

(3aα,4β,7β,7aα)-Hexahydro-2-(2-hydroxy-1-naphthalenyl)-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

(3aα,4β,7β,7aα)-2-[2,5-Dichloro-4-(1H-pyrrol-1-yl)phenyl]hexahydro-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

(3aα,4β,7β,7aα)-Hexahydro-2-[4-(methoxymethyl)-2-oxo-2H-1-benzopyran-7-yl]-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

(3aα,4β,7β,7aα)-2-(6-Benzothiazolyl)hexahydro-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

(3aα,4β,7β,7aα)-2-Methoxy-4-(octahydro-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl)benzoic acid methyl ester;

(3aα,4β,7β,7aα)-2-Methyl-5-(octahydro-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl)benzonitrile;

(3aα,4β,7β,7aα)-Hexahydro-2-(2-oxo-2H-1-benzopyran-6-yl)-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

(3aα,4β,7β,7aα)-Hexahydro-2-(2,3,5,6-tetramethyl-4-nitrophenyl)-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

(3aα,4β,7β,7aα)-Hexahydro-2-(2,4,5-trimethylphenyl)-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

(3aα,4β,7β,7aα)-2-(4-Fluoro-3-methylphenyl)hexahydro-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

(3aα,4β,7β,7aα)-Hexahydro-2-(3-methoxy-4-methylphenyl)-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

(3aα,4β,7β,7aα)-N-Ethyl-2-methyl-5-(octahydro-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl)-N-phenylbenzenesulfonamide;

(3aα,4β,7β,7aα)-2,6-Dibromo-4-(octahydro-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl)benzenesulfonamide;

(3aα,4β,7β,7aα)-2,4-Dimethyl-6-(octahydro-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl)-3-pyridinecarbonitrile;

(3aα,4β,7β,7aα)-2-(2,3-Dimethyl-1H-indol-5-yl)hexahydro-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

(3aα,4β,7β,7aα)-2-(3-Dibenzofuranyl)hexahydro-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

(3aα,4β,7β,7aα)-Hexahydro-2-(2'-hydroxy[1,1':3',1"-terphenyl]-5'-yl)-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

(3aα,4β,7β,7aα)-Hexahydro-2-(5,6,7,8-tetrahydro-3-hydroxy-2-naphthalenyl)-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

(3aα,4β,7β,7aα)-2-(2,3-Dihydro-1H-indol-6-yl)hexahydro-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

(3aα,4β,7β,7aα)-2-(1,3-Dihydro-2,2-dioxidobenzo[c]thiophen-5-yl)hexahydro-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

(3aα,4β,7β,7aα)-Hexahydro-2-(2-hydroxy-4,5-dimethylphenyl)-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

(3aα,4β,7β,7aα)-2-(2,3-Dihydro-2,2,3,3-tetrafluoro-1,4-benzodioxin-6-yl)hexahydro-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

(3aα,4β,7β,7aα)-Hexahydro-2-(1H-indazol-5-yl)-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

(3aα,4β,7β,7aα)-2-(4-Amino-2,3,5,6-tetrafluorophenyl)hexahydro-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

(3aα,4β,7β,7aα)-2-(4-Bromo-3-chlorophenyl)hexahydro-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

(3aα,4β,7β,7aα)-Hexahydro-2-(5-hydroxy-1-naphthalenyl)-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

(3aα,4β,7β,7aα)-4-(Octahydro-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl)-2-(trifluoromethyl)benzonitrile;

(3aα,4β,7β,7aα)-2-(4-Morpholinyl)-5-(octahydro-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl)benzoic acid methyl ester;

(3aα,4β,7β,7aα)-2-Fluoro-5-(octahydro-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl)benzonitrile;

(3aα,4β,7β,7aα)-Hexahydro-2-(2-naphthalenyl)-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

(3aα,4β,7β,7aα)-2-(9-Ethyl-9H-carbazol-3-yl)hexahydro-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

(3aα,4β,7β,7aα)-2-[1,2-Dihydro-8-methyl-2-oxo-4-(trifluoromethyl)-7-quinolinyl]hexahydro-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

(3aα,4α,7α,7aα)-Hexahydro-2-[3-(trifluoromethyl)phenyl]-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

(3aα,4α,7α,7aα)-Hexahydro-2-(4-nitro-1-naphthalenyl)-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

(3aα,4β,7β,7aα)-2-(4-Bromo-3-methylphenyl)-3a,4,7,7a-tetrahydro-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

(3aα,4β,7β,7aα)-3a,4,7,7a-Tetrahydro-2-(2-naphthalenyl)-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

(3aα,4β,7β,7aα)-2-(9-Ethyl-9H-carbazol-3-yl)-3a,4,7,7a-tetrahydro-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

(3aα,4β,7β,7aα)-2-[4-Fluoro-3-(trifluoromethyl)phenyl]-3a,4,7,7a-tetrahydro-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

(3aα,4β,7β,7aα)-2-[1,2-Dihydro-8-methyl-2-oxo-4-(trifluoromethyl)-7-quinolinyl]-3a,4,7,7a-tetrahydro-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

(3aα,4α,7α,7aα)-4-[(Acetyloxy)methyl]-2-(4-bromo-3-methylphenyl)-3a,4,7,7a-tetrahydro-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

(3aα,4β,7β,7aα)-4-[(Acetyloxy)methyl]-2-(4-bromo-3-methylphenyl)-3a,4,7,7a-tetrahydro-4,7-epoxy-1H-isoindole-1,3(2H)-dione.;

(3aα,4β,7β,7aα)-Hexahydro-4,7-dimethyl-2-[3-(trifluoromethyl)phenyl]-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

(3aα,4β,7β,7aα)-4-(Octahydro-4,7-dimethyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl)-1-naphthalenecarbonitrile;

(3aα,4β,7β,7aα)-(Benzo[b]thiophen-3-yl)hexahydro-4,7-dimethyl-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

(3aα,4β,7β,7aα)-Hexahydro-4,7-dimethyl-2-[4-nitro-3-(trifluoromethyl)phenyl]-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

(3aα,4β,7β,7aα)-4-(1,3,3a,4,7,7a-Hexahydro-4,7-dimethyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl)-1-naphthalenecarbonitrile;

(3aα,4α,7α,7aα)-Hexahydro-4-methyl-2-(2-naphthalenyl)-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

(3aα,4β,7β,7aα)-2-(4-Bromo-3-methylphenyl)hexahydro-4-methyl-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

(3aα,4β,7β,7aα)-Hexahydro-4-methyl-2-[3-(trifluoromethyl)phenyl]-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

(3aα,4β,7β,7aα)-2-(3,5-Dichlorophenyl)hexahydro-4-methyl-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

(3aα,4β,7β,7aα)-2-(3-Chloro-4-fluorophenyl)hexahydro-4-methyl-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

(3aα,4β,7β,7aα)-2-Methoxy-4-(octahydro-1,3-dioxo-4-methyl-4,7-epoxy-2H-isoindol-2-yl)-1-naphthalenecarbonitrile;

(3aα,4β,7β,7aα)-Hexahydro-4-methyl-2-[4-nitro-3-(trifluoromethyl)phenyl]-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

(3aα,4β,7β,7aα)-Hexahydro-2-[4-(1H-imidazol-1-yl)phenyl]-4-methyl-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

(3aα,4β,7β,7aα)-2-[3-Chloro-4-(2-thiazolyl)phenyl]hexahydro-4-methyl-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

(3aα,4α,7α,7aα)-2-(3,5-Dichlorophenyl)hexahydro-4,7-imino-1H-isoindole-1,3(2H)-dione;

(3aα,4α,7α,7aα)-2-(4-Bromo-1-naphthalenyl)hexahydro-4,7-imino-1H-isoindole-1,3(2H)-dione;

(3aα,4α,7α,7aα)-2-(4-Bromo-3-methylphenyl)hexahydro-4,7-imino-1H-isoindole-1,3(2H)-dione;

(3aα,4α,7α,7aα)-Hexahydro-2-(4-nitro-1-naphthalenyl)-4,7-imino-1H-isoindole-1,3(2H)-dione;

(3aα,4α,7α,7aα)-8-Acetyl-2-(3,5-dichlorophenyl)hexahydro-4,7-imino-1H-isoindole-1,3(2H)-dione;

(3aα,4α,7α,7aα)-Octahydro-1,3-dioxo-2-[3-(trifluoromethyl)phenyl]-4,7-ethano-5H-pyrrolo[3,4-c]pyridine-5-carboxylic acid phenyl ester;

(3aα,4α,7α,7aα)-4-(Octahydro-1,3-dioxo-4,7-ethano-2H-pyrrolo[3,4-c]pyridin-2-yl)-1-naphthalenecarbonitrile;

(3aα,4α,7α,7aα)-4-(Octahydro-5-methyl-1,3-dioxo-4,7-ethano-2H-pyrrolo[3,4-c]pyridin-2-yl)-1-naphthalenecarbonitrile;

(3aα,4α,7α,7aα)-2-(4-Cyano-1-naphthalenyl)octahydro-1,3-dioxo-4,7-etheno-5H-pyrrolo[3,4-c]pyridine-5-carboxylic acid phenylmethyl ester;

(3aα,4α,7α,7aα)-4-(Octahydro-1,3-dioxo-4,7-ethano-2H-pyrrolo[3,4-c]pyridin-2-yl)-2-(trifluoromethyl)benzonitrile;

(3aα,4α,7α,7aα)-4-(Octahydro-5-methyl-1,3-dioxo-4,7-ethano-2H-pyrrolo[3,4-c]pyridin-2-yl)-2-(trifluoromethyl)benzonitrile;

(3aα,4α,7α,7aα)-2-[4-Cyano-3-(trifluoromethyl)phenyl]octahydro-1,3-dioxo-4,7-etheno-5H-pyrrolo[3,4-c]pyridine-5-carboxylic acid phenylmethyl ester;

(3aα,4α,7α,7aα)-2-[4-Bromo-3-(trifluoromethyl)phenyl]tetrahydro-5-methyl-4,7-etheno-1H-pyrrolo[3,4-c]pyridine-1,3,6(2H,5H)-trione;

(3aα,4α,7α,7aα)-Tetrahydro-5-methyl-2-[3-(trifluoromethyl)phenyl]-4,7-etheno-1H-pyrrolo[3,4-c]pyridine-1,3,6(2H,5H)-trione;

(3aα,4α,7α,7aα)-Tetrahydro-5-methyl-2-(2-naphthalenyl)-4,7-etheno-1H-pyrrolo[3,4-c]pyridine-1,3,6(2H,5H)-trione;

(1aα,2β,2aα,5aα,6β,6aα)-Hexahydro-4-[3-(trifluoromethyl)phenyl]-2,6-epoxy-3H-oxireno[f]isoindole-3,5(4H)-dione;

(1aα,2β,2aα,5aα,6β,6aα)-4-(3,5-Dichlorophenyl)hexahydro-2,6-epoxy-3H-oxireno[f]isoindole-3,5(4H)-dione;

(1aα,2β,2aα,5aα,6β,6aα)-Hexahydro-4-(4-nitro-1-naphthalenyl)-2,6-epoxy-3H-oxireno[f]isoindole-3,5(4H)-dione;

(1aα,2β,2aα,5aα,6β,6aα)-4-(3,4-Dichlorophenyl)hexahydro-2,6-epoxy-3H-oxireno[f]isoindole-3,5(4H)-dione;

2-[4-(4-Bromophenoxy)phenyl]-3a,4,7,7a-tetrahydro-4,7-dimethyl-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

3a,4,7,7a-Tetrahydro-2-(2-methoxyphenyl)-4,7-dimethyl-4,7-epoxy-1H-isoindole-1,3(2H)-;

[(1,2,3,3a,7,7a-Hexahydro-2-phenyl-4,7-epoxy-4H-isoindol-4-yl)methyl]carbamic acid (3,5-dimethoxyphenyl)methyl ester;

2-(2,4-Dimethylphenyl)-3a,4,7,7a-tetrahydro-4-(hydroxymethyl)-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

2-(1,3-Benzodioxol-5-yl)-3a,4,7,7a-tetrahydro-4-methyl-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

4-[Bis(acetyloxy)methyl]-2-(3-bromophenyl)-3a,4,7,7a-tetrahydro-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

N-[[1,2,3,3a,7,7a-Hexahydro-2-(2,4,6-trimethylphenyl)-4,7-epoxy-4H-Isoindol-4-yl]methyl]-2,2-dimethylpropanamide;

3a,4,7,7a-Tetrahydro-4-(hydroxymethyl)-2-[2-(trifluoromethyl)phenyl]-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

3a,4,7,7a-Tetrahydro-4-(hydroxymethyl)-2-(1-naphthalenyl)-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

2-Chloro-5-(1,3,3a,4,7,7a-hexahydro-4,7-dimethyl-4,7-epoxy-2H-isoindol-2-yl)benzoic acid methyl ester;

4-[Bis(acetyloxy)methyl]-2-(4-bromo-2-nitrophenyl)-3a,4,7,7a-tetrahydro-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

3a,4,7,7a-Tetrahydro-4-methyl-2-(4-methyl-3-nitrophenyl)-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

2-[2-Chloro-5-(trifluoromethyl)phenyl]-3a,4,7,7a-tetrahydro-4-methyl-4,7-epoxy-1H-Isoindole-1,3(2H)-dione;

2-[4-Chloro-3-(trifluoromethyl)phenyl]-3a,4,7,7a-tetrahydro-4,7-dimethyl-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

2-(1,3,3a,4,7,7a-Hexahydro-4-methyl-4,7-epoxy-2H-isoindol-2-yl)benzonitrile;

374

2-(4-Fluorophenyl)-3a,4,7,7a-tetrahydro-4-methyl-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

2,2,2-Trifluoro-N-[(1,2,3,3a,7,7a-hexahydro-2-phenyl-4,7-epoxy-4H-isoindol-4-yl)methyl]acetamide;

3a,4,7,7a-Tetrahydro-4,7-dimethyl-2-(4-methyl-3-nitrophenyl)-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

2-Chloro-5-[1,3,3a,4,7,7a-hexahydro-4-(hydroxymethyl)-4,7-epoxy-2H-isoindol-2-yl]benzoic acid;

3a,4,7,7a-Tetrahydro-4,7-dimethyl-2-(4-nitrophenyl)-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

3a,4,7,7a-Tetrahydro-2-(2-mercaptophenyl)-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

3a,4,7,7a-Tetrahydro-2-[2-[(phenylmethyl)thio]phenyl]-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

[[2-(4-Chlorophenyl)-1,2,3,3a,7,7a-hexahydro-4,7-epoxy-4H-isoindol-4-yl]methyl]carbamic acid 2-methylpropyl ester;

4-(1,1-Dimethylethyl)-N-[[1,2,3,3a,7,7a-hexahydro-2-(4-methylphenyl)-4,7-epoxy-4H-isoindol-4 yl]methyl]benzamide;

2,4-Dichloro-N-[[1,2,3,3a,7,7a-hexahydro-2-(4-nitrophenyl)-4,7-epoxy-4H-isoindol-4-yl]methyl]benzamide;

N-[[2-(4-Chlorophenyl)-1,2,3,3a,7,7a-hexahydro-4,7-epoxy-4H-isoindol-4-yl]methyl]-2,4,6-trimethylbenzenesulfonamide;

[(1,2,3,3a,7,7a-Hexahydro-2-phenyl-4,7-epoxy-4H-isoindol-4-yl)methyl]carbamic acid 1,1-dimethylethyl ester;

N-[(1,2,3,3a,7,7a-Hexahydro-2-phenyl-4,7-epoxy-4H-isoindol-4-yl)methyl]-2-phenoxyacetamide;

N-[[1,2,3,3a,7,7a-Hexahydro-2-(4-nitrophenyl)-4,7-epoxy-4H-isoindol-4-yl]methyl]-2,2-dimethylpropanamide;

2-(2,4-Dichlorophenoxy)-N-[[1,2,3,3a,7,7a-hexahydro-2-(4-nitrophenyl)-4,7-epoxy-4H-isoindol-4-yl]methyl]acetamide;

N-[[1,2,3,3a,7,7a-Hexahydro-2-(4-methylphenyl)-4,7-epoxy-4H-isoindol-4-yl]methyl]-3,5-dimethoxybenzamide;

N-[[2-(4-Chlorophenyl)-1,2,3,3a,7,7a-hexahydro-4,7-epoxy-4H-isoindol-4-yl]methyl]-2-nitrobenzenesulfonamide;

(3aα,4β,7β,7aα)-Hexahydro-2-[(1S)-1-phenylethyl]-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

(3aα,4β,7β,7aα)-Hexahydro-2-[(1S)-2-hydroxy-1-phenylethyl]-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

(3aα,4β,7β,7aα)-2-[(1S)-2-(Acetyloxy)-1-phenylethyl]-3a,4,7,7a-tetrahydro-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

(3aα,4α,7α,7aα)-3a,4,7,7a-Tetrahydro-2-[(1S)-1-phenylethyl]-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

(3aα,4β,7β,7aα)-Hexahydro-2-[(1R)-1-phenylethyl]-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

(3aα,4β,7β,7aα)-4-[[[(Octahydro-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl)methyl]amino]benzoic acid;

(3aα,4β,7β,7aα)-Hexahydro-2-(4-morpholinylmethyl)-4,7-epoxy-1H-isoindole-1,3(2H)-dione

(3aα,4β,7β,7aα)-4-[Octahydro-4-(2-hydroxyethyl)-7-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-2-(trifluoromethyl)benzonitrile;

(3aα,4β,7β,7aα)- and (3aα,4α,7α,7aα)-4-[Octahydro-4-methyl-1,3-dioxo-7-(phenylmethyl)-4,7-epoxy-2H-isoindol-2-yl]-2-(trifluoromethyl)benzonitrile;

(3aα,4β,7β,7aα)-(4-[7-[2-(4-Bromophenoxy)ethyl]octahydro-4-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-2-(trifluoromethyl)benzonitrile;

(3aα,4β,7β,7aα)-4-[Octahydro-7-[2-(4-iodophenoxy)ethyl]-4-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-2-(trifluoromethyl)benzonitrile;

(3aα,4β,7β,7aα)-4-[Octahydro-4-methyl-1,3-dioxo-7-[2-[4-(trifluoromethyl)phenoxy]ethyl]-4,7-epoxy-2H-isoindol-2-yl]-2-(trifluoromethyl)benzonitrile;

(3aα,4β,7β,7aα)-4-[Octahydro-7-[2-(4-methoxyphenoxy)ethyl]-4-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-2-(trifluoromethyl)benzonitrile;

(3aα,4β,7β,7aα)-4-[7-[2-(4-Ethoxyphenoxy)ethyl]octahydro-4-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-2-(trifluoromethyl)benzonitrile;

(3aα,4β,7β,7aα)-4-[7-[2-(4-Chlorophenoxy)ethyl]octahydro-4-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-2-(trifluoromethyl)benzonitrile;

(3aα,4β,7β,7aα)-4-[2-[2-[4-Cyano-3-(trifluoromethyl)phenyl]octahydro-7-methyl-1,3-dioxo-4,7-epoxy-4H-isoindol-4-yl]ethoxy]benzoic acid, methyl ester;

(3aα,4β,7β,7aα)-Hexahydro-4-(2-hydroxyethyl)-7-methyl-2-(3-methyl-4-nitrophenyl)-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

(3aα,4β,7β,7aα)-4-[Octahydro-4-methyl-1,3-dioxo-7-[2-[4-(trifluoromethoxy)phenoxy]ethyl]-4,7-epoxy-2H-isoindol-2-yl]-2-(trifluoromethyl)benzonitrile;

(3aα,4β,7β,7aα)-2-(3,5-Dichlorophenyl)hexahydro-4,7-dimethyl-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

(3aα,4β,7β,7aα)-Hexahydro-4,7-dimethyl-2-(4-nitro-1-naphthalenyl)-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

(3aα,4β,7β,7aα)-2-[4-Cyano-3-(trifluoromethyl)phenyl]octahydro-7-methyl-1,3-dioxo-4,7-epoxy-4H-isoindole-4-propanenitrile;

(3aα,4β,7β,7aα)-4-[Octahydro-4-methyl-7-[2-(4-morpholinyl)ethyl]-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-2-(trifluoromethyl)benzonitrile, trifluoroacetate;

(3aα,4β,7β,7aα)-2-(5-Fluoro-1-naphthalenyl)hexahydro-4,7-dimethyl-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

(3aα,4β,7β,7aα)-2-(5-Fluoro-4-nitro-1-naphthalenyl)hexahydro-4,7-dimethyl-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

(3aα,4β,7β,7aα)-2-(1,1-Dioxidobenzo[b]thiophen-3-yl)hexahydro-4,7-dimethyl-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

4-(1,3,3a,4,7,7a-Hexahydro-4,6,7-trimethyl-1,3-dioxo-4,7-epoxy-2H-pyrrolo[3,4-c]pyridin-2-yl)-2-(trifluoromethyl)benzonitrile;

(3aα,4β,7β,7aα)-Tetrahydro-4,7-dimethyl-2-[3-(trifluoromethyl)phenyl]-4,7-epoxy-1H-isoindole-1,3,5(2H,4H)-trione;

(3aα,4α,7α,7aα)-Tetrahydro-4,7-dimethyl-2-[3-(trifluoromethyl)phenyl]-4,7-epoxy-1H-isoindole-1,3,5(2H,4H)-trione;

(3aα,4β,7β,7aα)-2-(5-Chloro-1-naphthalenyl)hexahydro-4,7-dimethyl-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

(3aα,4β,7β,7aα)-2-(5-Chloro-4-nitro-1-naphthalenyl)hexahydro-4,7-dimethyl-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

(3aα,4β,7β,7aα)-4-Ethylhexahydro-7-methyl-2-(4-nitro-1-naphthalenyl)-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

(3aα,4β,7β,7aα)-2-(4-Cyano-1-naphthalenyl)-N-(4-fluorophenyl)octahydro-7-methyl-1,3-dioxo-4,7-epoxy-4H-isoindole-4-acetamide;

(3aα,4β,7β,7aα)-Hexahydro-4-methyl-2-(2-naphthalenyl)-4,7-epoxy-1H-isoindole-1,3(2H)-dione, faster eluting enantiomer;

(3aα,4β,7β,7aα)-Hexahydro-4-methyl-2-(2-naphthalenyl)-4,7-epoxy-1H-isoindole-1,3(2H)-dione, slower eluting enantiomer;

(3aα,4β,7β,7aα)-4-[4-[2-[[(4-Fluorophenyl)methyl]methylamino]ethyl]octahydro-7-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-2-(trifluoromethyl)benzonitrile;

(3aα,4β,5β,6β,7β,7aα)-4-(Octahydro-4,5,6,7-tetramethyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl)-2-(trifluoromethyl)benzonitrile;

(3aα,4β,7β,7aα)-4-[Octahydro-4-methyl-1,3-dioxo-7-[2-[4-(trifluoromethyl)phenoxy]ethyl]-4,7-epoxy-2H-isoindol-2-yl]-2-(trifluoromethyl)benzonitrile, faster eluting antipode;

(3aα,4β,7β,7aα)-4-[Octahydro-4-methyl-1,3-dioxo-7-[2-[4-(trifluoromethyl)phenoxy]ethyl]-4,7-epoxy-2H-isoindol-2-yl]-2-(trifluoromethyl)benzonitrile, slower eluting enantiomer;

(3aα,4β,5β,7β,7aα)-4-(Octahydro-5-hydroxy-4,7-dimethyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl)-2-(trifluoromethyl)benzonitrile;

(3aα,4β,5α,7β,7aα)-4-(Octahydro-5-hydroxy-4,7-dimethyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl)-2-(trifluoromethyl)benzonitrile;

(αR)-α-Methoxybenzeneacetic acid, 2-[(3aα,4β,7β,7aα)-2-(4-cyano-1-naphthalenyl)octahydro-7-methyl-1,3-dioxo-4,7-epoxy-4H-isoindol-4-y]ethyl ester;

(3aα,4β,7β,7aα)-2-(Methylthio)-4-(octahydro-4,7-dimethyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl)benzonitrile;

(3aα,4β,7β,7aα)-2-(Methylsulfinyl)-4-(octahydro-4,7-dimethyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl)benzonitrile;

(3aα,4β,7β,7aα)-2-(Methylsulfonyl)-4-(octahydro-4,7-dimethyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl)benzonitrile;

(3aα,4β,5β,7β,7aα)-7-[2-[[(1,1-Dimethylethyl)dimethylsilyl]oxy]ethyl]hexahydro-5-hydroxy-4-methyl-2-(4-nitro-1-naphthalenyl)-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

(3aα,4β,5β,7β,7aα)-Hexahydro-5-hydroxy-7-(2-hydroxyethyl)-4-methyl-2-(4-nitro-1-naphthalenyl)-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

(3aα,4β,5β,7β,7aα)-7-[2-(4-Fluorophenoxy)ethyl]hexahydro-5-hydroxy-4-methyl-2-(4-nitro-1-naphthalenyl)-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

(3aα,4β,5β,6β,7β,7aα)-4-(Octahydro-5,6-dihydroxy-4,7-dimethyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl)-2-(trifluoromethyl)benzonitrile;

(3aα,4β,5α,6α,7β,7aα)-4-(Octahydro-5,6-dihydroxy-4,7-dimethyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl)-2-(trifluoromethyl)benzonitrile;

3aα,4β,5β,6β,7β,7aα)-4-[Octahydro-5,6-dihydroxy-4-(hydroxyethyl)-7-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile;

(3aα,4β,5β,6β,7β,7aα)-4-[Octahydro-5,6-dihydroxy-4-methyl-1,3-dioxo-7-[2-[4-(trifluoromethyl)phenoxy]ethyl]-4,7-epoxy-2H-isoindol-2-yl]-2-(trifluoromethyl)benzonitrile;

(3aα,4β,5β,5aβ,8aβ,8bα)-4-(Decahydro-5-hydroxy-4-methyl-1,3-dioxo-4,8a-epoxy-2H-furo[3,2-e]isoindol-2-yl)-1-naphthalenecarbonitrile;

379

(3aα,4β,7β,7aα)-2-(4-Cyano-1-naphthalenyl)octahydro-7-methyl-1,3-dioxo-4,7-epoxy-4H-isoindole-4-acetic acid;

(3aα,4β,7β,7aα)-2-(4-Cyano-1-naphthalenyl)octahydro-7-methyl-1,3-dioxo-4,7-epoxy-4H-isoindole-4-acetic acid, methyl ester;

(3aα,4β,7β,7aα)-2-(4-Cyano-1-naphthalenyl)-N-[(4-fluorophenyl)methyl]octahydro-7-methyl-1,3-dioxo-4,7-epoxy-4H-isoindole-4-acetamide;

(3aα,4β,7β,7aα)-N-[2-[2-(4-Cyano-1-naphthalenyl)octahydro-7-methyl-1,3-dioxo-4,7-epoxy-4H-isoindol-4-yl]ethyl]-4-fluorobenzamide;

[3aR-(3aα,4β,7β,7aα)]-4-[Octahydro-4-(2-hydroxyethyl)-7-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile;

[3aS-(3aα,4β,7β,7aα)]-4-[Octahydro-4-(2-hydroxyethyl)-7-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile;

[3aR-(3aα,4β,7β,7aα)]-4-[4-[2-(3-Fluorophenoxy)ethyl]octahydro-7-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile;

[3aS-(-(3aα,4β,7β,7aα)]-4-[4-[2-(3-Fluorophenoxy)ethyl]octahydro-7-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile;

(4-Fluorophenyl)carbamic acid, 2-[(3aα,4β,7β,7aα)-2-(4-cyano-1-naphthalenyl)octahydro-7-methyl-1,3-dioxo-4,7-epoxy-4H-isoindol-4-y]ethyl ester;

(3aα,4β,7β,7aα)-4-[Octahydro-4-(2-hydroxyethyl)-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile;

(3aα,4β,6β,7β,7aα)-4-[4-[2-(4-Cyanophenoxy)ethyl]octahydro-6-hydroxy-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile;

[3aS-(3aα,4β,5β,7β,7aα)]-4-[Octahydro-5-hydroxy-7-(2-hydroxyethyl)-4-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile;

[3aR-(3aα,4β,5β,7β,7aα)]-4-[Octahydro-5-hydroxy-7-(2-hydroxyethyl)-4-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile;

(3aα,4β,7β,7aα)-4-[4-[2-(4-Cyanophenoxy)ethyl]-7-ethyloctahydro-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile;

(3aα,4β,7β,7aα)-4-[2-(Acetyloxy)ethyl]-2-(4-cyano-1-naphthalenyl)hexahydro-7-methyl-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

(3aα,4β,7β,7aα)-4-[Octahydro-4-methyl-1,3-dioxo-7-(2-oxoethyl)-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile;

[3aα,4β(E),7β,7aα]-4-[4-[3-(4-Cyanophenyl)-2-propenyl]octahydro-7-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile;

[3aα,4β(Z),7β,7aα]-4-[4-[3-(4-Cyanophenyl)-2-propenyl]octahydro-7-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile;

(3aα,4β,7β,7aα)-4-[4-[3-(4-Cyanophenyl)propyl]octahydro-7-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile;

(3aα,4β,7β,7aα)-4-[4-[2-[(6-Chloro-1,2-benzisoxazol-3-yl)oxy]ethyl]octahydro-7-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile;

(3aα,4β,7β,7aα)-4-[Octahydro-4-methyl-7-[2-[(6-nitro-1H-indazol-3-yl)oxy]ethyl]-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile;

[3aS-(3aα,4β,5β,7β,7aα)]-4-[7-[2-(1,2-Benzisoxazol-3-yloxy)ethyl]octahydro-5-hydroxy-4-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile;

[3aR-(3aα,4β,5β,7β,7aα)]-4-[7-[2-(1,2-Benzisoxazol-3-yloxy)ethyl]octahydro-5-hydroxy-4-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile;

(3aα,4β,5β,7β,7aα)]-4-(Octahydro-5-hydroxy-4,7-dimethyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl)-2-(trifluoromethyl)benzonitrile;

(3aα,4β,5β,7β,7aα)]-4-(Octahydro-5-hydroxy-4,7-dimethyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl)-2-(trifluoromethyl)benzonitrile;

(3aα,4β,7β,7aα)-2-(4-Cyano-1-naphthalenyl)octahydro-1,3-dioxo-7-[2-(phenylmethoxy)ethyl]-4,7-epoxy-4H-isoindole-4-propanenitrile;

(3aα,4α,7α,7aα)-2-(4-Cyano-1-naphthalenyl)octahydro-1,3-dioxo-7-[2-(phenylmethoxy)ethyl]-4,7-epoxy-4H-isoindole-4-propanenitrile;

(3aα,4β,7β,7aα)-2-(4-Cyano-1-naphthalenyl)octahydro-7-(2-hydroxyethyl)-1,3-dioxo-4,7-epoxy-4H-isoindole-4-propanenitrile;

(3aα,4α,7α,7aα)-2-(4-Cyano-1-naphthalenyl)octahydro-7-(2-hydroxyethyl)-1,3-dioxo-4,7-epoxy-4H-isoindole-4-propanenitrile;

(3aα,4β,7β,7aα)-2-(4-Cyano-1-naphthalenyl)-7-[2-(4-fluorophenoxy)ethyl]octahydro-1,3-dioxo-4,7-epoxy-4H-isoindole-4-propanenitrile;

(3aα,4β,7β,7aα)-2-(7-Chloro-2,1,3-benzoxadiazol-4-yl)hexahydro-4,7-dimethyl-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

(3aα,4β,7β,7aα)-2-(7-Chloro-2-methyl-4-benzofuranyl)hexahydro-4,7-dimethyl-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

(3aα,4β,7β,7aα)-2-(7-Chloro-2-methylbenzo[b]thiophen-4-yl)hexahydro-4,7-dimethyl-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

[3aα,4β(E),7β,7aα]-4-[2-(4-Cyano-1-naphthalenyl)octahydro-7-methyl-1,3-dioxo-4,7-epoxy-4H-isoindol-4-yl]-2-butenoic acid, phenylmethyl ester;

(3aα,4β,7β,7aα)-2-(4-Cyano-1-naphthalenyl)octahydro-7-methyl-1,3-dioxo-4,7-epoxy-4H-isoindole-4-butanoic acid;

(3aα,4β,7β,7aα)-2-(4-Cyano-1-naphthalenyl)-N-(4-fluorophenyl)octahydro-7-methyl-1,3-dioxo-4,7-epoxy-4H-isoindole-4-butanamide;

[3aS-(3aα,4β,5β,7β,7aα)]-4-[7-[2-(Acetyloxy)ethyl]octahydro-5-hydroxy-4-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile;

[3aR-(3aα,4β,5β,7β,7aα)]-4-[Octahydro-5-hydroxy-7-(2-hydroxyethyl)-4-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile;

(3aα,4β,7β,7aα(E)]-4-[Octahydro-4-methyl-1,3-dioxo-7-(4-oxo-4-phenyl-2-butenyl)-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile;

(3aα,4β,7β,7aα(E)]-4-[Octahydro-4-methyl-1,3-dioxo-7-(4-oxo-4-phenyl-2-butenyl)-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile;

(3aα,4β,7β,7aα)-(4-[7-[2-(4-Bromophenoxy)ethyl]octahydro-4-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-2-(trifluoromethyl)benzonitrile;

(3aα,4β,7β,7aα)-4-[Octahydro-7-[2-(4-iodophenoxy)ethyl]-4-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-2-(trifluoromethyl)benzonitrile;

382

(3aα,4β,7β,7aα)-4-[Octahydro-4-methyl-1,3-dioxo-7-[2-[4-(trifluoromethyl)phenoxy]ethyl]-4,7-epoxy-2H-isoindol-2-yl]-2-(trifluoromethyl)benzonitrile;

(3aα,4β,7β,7aα)-4-[Octahydro-7-[2-(4-methoxyphenoxy)ethyl]-4-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-2-(trifluoromethyl)benzonitrile;

(3aα,4β,7β,7aα)-4-[7-[2-(4-Ethoxyphenoxy)ethyl]octahydro-4-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-2-(trifluoromethyl)benzonitrile;

(3aα,4β,7β,7aα)-4-[7-[2-(4-Chlorophenoxy)ethyl]octahydro-4-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-2-(trifluoromethyl)benzonitrile;

(3aα,4β,7β,7aα)-4-[2-[2-[4-Cyano-3-(trifluoromethyl)phenyl]octahydro-7-methyl-1,3-dioxo-4,7-epoxy-4H-isoindol-4-yl]ethoxy]benzoic acid, methyl ester;

(3aα,4β,7β,7aα)-Hexahydro-4-(2-hydroxyethyl)-7-methyl-2-(3-methyl-4-nitrophenyl)-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

(3aα,4β,7β,7aα)-4-[Octahydro-4-methyl-1,3-dioxo-7-[2-[4-(trifluoromethoxy)phenoxy]ethyl]-4,7-epoxy-2H-isoindol-2-yl]-2-(trifluoromethyl)benzonitrile;

(3aα,4β,7β,7aα)-2-(3,5-Dichlorophenyl)hexahydro-4,7-dimethyl-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

(3aα,4β,7β,7aα)-Hexahydro-4,7-dimethyl-2-(4-nitro-1-naphthalenyl)-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

(3aα,4β,7β,7aα)-4-[Octahydro-4-methyl-1,3-dioxo-7-[2-[4-(phenylmethoxy)phenoxy]ethyl]-4,7-epoxy-2H-isoindol-2-yl]-2-(trifluoromethyl)benzonitrile;

(3aα,4β,7β,7aα)-Hexahydro-4-(2-hydroxyethyl)-7-methyl-2-(4-nitro-1-naphthalenyl)-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

(3aα,4β,7β,7aα)-4-[2-(4-Fluorophenoxy)ethyl]hexahydro-7-methyl-2-(3-methyl-4-nitrophenyl)-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

383

(3aα,4β,7β,7aα)-4-[Octahydro-4-methyl-1,3-dioxo-7-[2-[4-[(trifluoromethyl)thio]phenoxy]ethyl]-4,7-epoxy-2H-isoindol-2-yl]-2-(trifluoromethyl)benzonitrile;

(3aα,4β,7β,7aα)-4-[Octahydro-4-methyl-7-[2-(4-nitrophenoxy)ethyl]-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-2-(trifluoromethyl)benzonitrile;

(3aα,4β,7β,7aα)-4-[2-(4-Fluorophenoxy)ethyl]hexahydro-7-methyl-2-(4-nitro-1-naphthalenyl)-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

(3aα,4β,7β,7aα)-4-[Octahydro-7-methyl-1,3-dioxo-7-[2-[2-(trifluoromethyl)phenoxy]ethyl]-4,7-epoxy-2H-isoindol-2-yl]-2-(trifluoromethyl)benzonitrile;

(3aα,4β,7β,7aα)-4-[4-[2-(2-Bromophenoxy)ethyl]octahydro-7-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-2-(trifluoromethyl)benzonitrile;

(3aα,4β,7β,7aα)-4-[4-[2-(3-Fluorophenoxy)ethyl]octahydro-7-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-2-(trifluoromethyl)benzonitrile;

(3aα,4β,7β,7aα)-Hexahydro-2-[4-(1H-imidazol-1-yl)phenyl]-4-methyl-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

(3aα,4β,7β,7aα)-2-[3-Chloro-4-(2-thiazolyl)phenyl]hexahydro-4-methyl-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

(3aα,4β,7β,7aα)-Hexahydro-4,7-dimethyl-2-(3-methyl-4-nitrophenyl)-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

(3aα,4β,7β,7aα)-Hexahydro-4,7-dimethyl-2-(2-methyl-4-nitrophenyl)-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

(3aα,4β,7β,7aα)-2-(3,5-Dichlorophenyl)hexahydro-4-(2-hydroxyethyl)-7-methyl-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

(3aα,4β,7β,7aα)-2-(3,5-Dichlorophenyl)-4-[2-(4-fluorophenoxy)ethyl]hexahydro-7-methyl-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

(3aα,4β,7β,7aα)-4-[Octahydro-4-[2-(4-hydroxyphenoxy)ethyl]-7-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-2-(trifluoromethyl)benzonitrile;

(3aα,4β,7β,7aα)-4-[4-[2-(4-Cyanophenoxy)ethyl]octahydro-7-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-2-(trifluoromethyl)benzonitrile;

(3aα,4β,7β,7aα)-4-[Octahydro-4-methyl-1,3-dioxo-7-[2-[3-(trifluoromethyl)phenoxy]ethyl]-4,7-epoxy-2H-isoindol-2-yl]-2-(trifluoromethyl)benzonitrile;

(3aα,4β,7β,7aα)-4-[4-[2-(3-Bromophenoxy)ethyl]octahydro-7-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-2-(trifluoromethyl)benzonitrile;

(3aα,4β,7β,7aα)-4-[4-[(4-Fluorophenyl)methyl]octahydro-7-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-2-(trifluoromethyl)benzonitrile;

(3aα,4β,7β,7aα)-2-(1,6-Dihydro-1-methyl-6-oxo-3-pyridinyl)hexahydro-4,7-dimethyl-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

(3aα,4β,7β,7aα)-Hexahydro-4,7-dimethyl-2-(1-methyl-6-oxo-3-piperidinyl)-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

(3aα,4β,7β,7aα)-4-[4-[2-(3-Cyanophenoxy)ethyl]octahydro-7-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-2-(trifluoromethyl)benzonitrile;

(3aα,4β,7β,7aα)-4-[2-[4-Cyano-3-(trifluoromethyl)phenyl]octahydro-7-methyl-1,3-dioxo-4,7-epoxy-4H-isoindol-4-yl]ethoxy]benzoic acid, phenylmethyl ester;

(3aα,4β,7β,7aα)-4-[Octahydro-4-methyl-1,3-dioxo-7-(2-phenoxyethyl)-4,7-epoxy-2H-isoindol-2-yl]-2-(trifluoromethyl)benzonitrile;

(3aα,4β,7β,7aα)-2-(3,5-Dichloro-4-nitrophenyl)hexahydro-4,7-dimethyl-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

(3aα,4β,7β,7aα)-2-(3,5-Dichloro-4-hydroxyphenyl)hexahydro-4,7-dimethyl-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

(3aα,4β,7β,7aα)-2-(5-Fluoro-1-naphthalenyl)hexahydro-4,7-dimethyl-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

(3aα,4β,7β,7aα)-Hexahydro-4,7-dimethyl-2-(1-naphthalenyl)-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

(3aα,4β,7β,7aα)-Hexahydro-2-[3-methoxy-4-(5-oxazolyl)phenyl]-4,7-dimethyl-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

(3aα,4β,7β,7aα)-Hexahydro-4-[2-(4-methoxyphenoxy)ethyl]-7-methyl-2-(4-nitro-1-naphthalenyl)-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

(3aα,4β,7β,7aα)-Hexahydro-4-methyl-2-(4-nitro-1-naphthalenyl)-7-[2-[4-(trifluoromethyl)phenoxy]ethyl]-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

(3aα,4β,7β,7aα)-Hexahydro-4-methyl-2-(4-nitro-1-naphthalenyl)-7-[2-(4-nitrophenoxy)ethyl]-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

(3aα,4β,7β,7aα)-2-(1,6-Dihydro-1,4-dimethyl-6-oxo-3-pyridinyl)hexahydro-4,7-dimethyl-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

(3aα,4β,7β,7aα)-4-[Octahydro-7-methyl-2-(4-nitro-1-naphthalenyl)-1,3-dioxo-4,7-epoxy-4H-isoindol-4-yl]ethoxy]benzonitrile;

(3aα,4β,7β,7aα)-4-(Octahydro-4,7-dimethyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl)-1,2-benzenedicarbonitrile;

(3aα,4β,7β,7aα)-4-(2-Bromoethyl)hexahydro-7-methyl-2-(4-nitro-1-naphthalenyl)-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

(3aα,4β,7β,7aα)-4-[4-[2-(4-Cyanophenoxy)ethyl]octahydro-7-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile;

(3aα,4β,7β,7aα)-4-[Octahydro-4-[2-(4-methoxyphenoxy)ethyl]-7-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile;

(3aα,4β,7β,7aα)-4-[Octahydro-4-[2-(3-methoxyphenoxy)ethyl]-7-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile;

(3aα,4β,7β,7aα)-4-[4-[2-(3-Fluorophenoxy)ethyl]octahydro-7-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile;

(3aα,4β,7β,7aα)-4-[Octahydro-4-methyl-7-[2-[3-(4-morpholinyl)phenoxy]ethyl]-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile;

(3aα,4β,7β,7aα)-4-[Octahydro-4-methyl-7-[2-[4-nitro-3-(triflouoromethyl)phenoxy]ethyl]-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile;

(3aα,4β,7β,7aα)-4-[4-[2-(3-Cyanophenoxy)ethyl]octahydro-7-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile;

386

(3aα,4β,7β,7aα)-2-(2,3-Dihydro-3-methyl-2-oxo-6-benzothiazolyl)hexahydro-4,7-dimethyl-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

(3aα,4β,7β,7aα)-2-(2,3-Dihydro-2-oxo-6-benzothiazolyl)hexahydro-4,7-dimethyl-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

(3aα,4β,7β,7aα)-4-[4-[2-[3-(Dimethylamino)phenoxy]ethyl]octahydro-7-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile;

(3aα,4β,7β,7aα)-4-[2-[4-Cyano-3-(trifluoromethyl)phenyl]octahydro-7-methyl-1,3-dioxo-4,7-epoxy-4H-isoindol-4-yl]ethoxy]-1,2-benzenedicarbonitrile;

(3aα,4β,7β,7aα)-N-[2-Cyano-5-(octahydro-4,7-dimethyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl)phenyl]acetamide;

(3aα,4β,7β,7aα)-4-(Octahydro-4,7-dimethyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl)-2-(trifluoromethoxy)benzonitrile;

(3aα,4β,7β,7aα)-2-Methoxy-4-(octahydro-4,7-dimethyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl)benzonitrile;

(3aα,4β,7β,7aα)-2-[4-(4,5-Dichloro-1H-imidazol-1-yl)phenyl]hexahydro-4,7-dimethyl-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

(3aα,4β,7β,7aα)-2-[4-(4-Bromo-1-methyl-1H-pyrazol-3-yl)phenyl]hexahydro-4,7-dimethyl-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

(3aα,4β,7β,7aα)-4-[Octahydro-4-(2-hydroxyethyl)-7-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile;

(3aα,4β,7β,7aα)-2-Iodo-4-(Octahydro-4,7-dimethyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl)benzonitrile;

(3aα,4β,7β,7aα)-4-[4-[2-(4-Fluorophenoxy)ethyl]octahydro-7-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile;

(3aα,4β,7β,7aα)-4-[Octahydro-4-methyl-1,3-dioxo-7-[2-[4-(trifluoromethyl)phenoxy]ethyl]-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile;

(3aα,4β,7β,7aα)-4-[4-[2-(4-Cyano-3-fluorophenoxy)ethyl]octahydro-7-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile;

387

(3aα,4β,7β,7aα)-4-[Octahydro-4-methyl-1,3-dioxo-7-[2-[2,3,5,6-tetrafluoro-4-(trifluoromethyl)phenoxy]ethyl]-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile;

(3aα,4β,7β,7aα)-Hexahydro-4,7-dimethyl-2-[4-(1H-1,2,4-triazol-3-yl)phenyl]-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

(3aα,4β,7β,7aα)-2-[4-(4,5-Dihydro-5-oxo-1,2,4-oxadiazol-3-yl)phenyl]hexahydro-4,7-dimethyl-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

(3aα,4β,7β,7aα)-Hexahydro-2-[3-methoxy-4-(2-oxazolyl)phenyl]-4,7-dimethyl-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

(3aα,4β,7β,7aα)-Hexahydro-2-(4-hydroxy-1-naphthalenyl)-4,7-dimethyl-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

(3aα,4β,7β,7aα)-Hexahydro-2-(8-hydroxy-5-quinolinyl)-4,7-dimethyl-4,7-epoxy-1H-isoindole-1,3(2H)-dione, trifluoroacetate;

(3aα,4β,7β,7aα)-4-[Octahydro-4-methyl-1,3-dioxo-7-[2-[methyl(phenylmethyl)amino]ethyl]-4,7-epoxy-2H-isoindol-2-yl]-2-(trifluoromethyl)benzonitrile;

(3aα,4β,7β,7aα)-Hexahydro-4,7-dimethyl-2-(5-quinolinyl)-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

(3aα,4β,7β,7aα)-5-(Octahydro-4,7-dimethyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl)-2-pyridinecarbonitrile;

(3aα,4β,7β,7aα)-5-(Octahydro-4,7-dimethyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl)-8-quinolinecarbonitrile;

(3aα,4β,7β,7aα)-2-(5-Bromo-4-nitro-1-naphthalenyl)hexahydro-4,7-dimethyl-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

(3aα,4β,7β,7aα)-2-(5-Bromo-1-naphthalenyl)hexahydro-4,7-dimethyl-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

(3aα,4β,7β,7aα)-Hexahydro-4,7-dimethyl-2-[8-(trifluoromethyl)-4-quinolinyl]-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

4-Fluorobenzoic acid, 2-[(3aα,4β,7β,7aα)-2-(4-cyano-1-naphthalenyl)octahydro-7-methyl-1,3-dioxo-4,7-epoxy-4H-isoindol-4-y]ethyl ester;

Benzeneacetic acid, 2-[(3aα,4β,7β,7aα)-2-(4-cyano-1-naphthalenyl)octahydro-7-methyl-1,3-dioxo-4,7-epoxy-4H-isoindol-4-y]ethyl ester;

4-Fluorobenzeneacetic acid, 2-[(3aα,4β,7β,7aα)-2-(4-cyano-1-naphthalenyl)octahydro-7-methyl-1,3-dioxo-4,7-epoxy-4H-isoindol-4-y]ethyl ester;

(3aα,4β,7β,7aα)-Hexahydro-4-methyl-7-[2-[4-(methylsulfonyl)phenoxy]ethyl]-2-(4-nitro-1-naphthalenyl)-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

(3aα,4β,7β,7aα)-Hexahydro-2-(2-naphthalenyl)-4,7-dimethyl-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

(3aα,4β,7β,7aα)-2-(4-Chloro-1-naphthalenyl)hexahydro-4,7-dimethyl-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

(3aα,4β,7β,7aα)-N-[(4-Chlorophenyl)methyl]-2-(4-cyano-1-naphthalenyl)octahydro-7-methyl-1,3-dioxo-4,7-epoxy-4H-isoindole-4-acetamide;

4,7,7-Trimethyl-3-oxo-2-oxabicyclo[2.2.1]heptane-1-carboxylic acid, 2-[(3aα,4β,7β,7aα)-2-(4-cyano-1-naphthalenyl)octahydro-7-methyl-1,3-dioxo-4,7-epoxy-4H-isoindol-4-y]ethyl ester;

(αS)- α-Methoxy-α-(trifluoromethyl)benzeneacetic acid, 2-[(3aα,4β,7β,7aα)-2-(4-cyano-1-naphthalenyl)octahydro-7-methyl-1,3-dioxo-4,7-epoxy-4H-isoindol-4-y]ethyl ester;

(αR)- α-Methoxy-α-(trifluoromethyl)benzeneacetic acid, 2-[(3aα,4β,7β,7aα)-2-(4-cyano-1-naphthalenyl)octahydro-7-methyl-1,3-dioxo-4,7-epoxy-4H-isoindol-4-y]ethyl ester;

(3aα,4β,7β,7aα)-4-[Octahydro-4-methyl-7-[2-[(7-methyl-1,2-benzisoxazol-3-yl)oxy]ethyl]-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile;

(3aα,4β,7β,7aα)-4-[4-[2-(1,2-Benzisoxazol-3-yloxy)ethyl]octahydro-7-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile;

(3aα,4β,7β,7aα)-4-[2-(Benzoyloxy)ethyl]-2-(4-cyano-1-naphthalenyl)hexahydro-7-methyl-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

(3aα,4β,7β,7aα)-2-(4-Cyano-1-naphthalenyl)-4-[2-[(4-nitrobenzoyl)oxy]ethyl]hexahydro-7-methyl-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

4-Chlorobenzoic acid, 2-[(3aα,4β,7β,7aα)-2-(4-cyano-1-naphthalenyl)octahydro-7-methyl-1,3-dioxo-4,7-epoxy-4H-isoindol-4-y]ethyl ester;

[3aα,4β,7β,7aα(E)]-4-[Octahydro-4-methyl-7-[3-(1-naphthalenyl)-2-propenyl]-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile;

(3aα,4β,7β,7aα)-4-[Octahydro-4-methyl-7-[3-(1-naphthalenyl)propyl]-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile;

(3aα,4β,7β,7aα)-Hexahydro-4,7-dimethyl-2-(2-methyl-6-quinolinyl)-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

(3aα,4β,7β,7aα)-Hexahydro-2-(5-isoquinolinyl)-4,7-dimethyl-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

(3aα,4β,7β,7aα)-2-(6-Benzothiazolyl)hexahydro-4,7-dimethyl-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

[3aα,4β,7β,7aα(E)]-4-[Octahydro-4-methyl-1,3-dioxo-7-(4-oxo-4-phenyl-2-butenyl)-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile;

(3aα,4β,7β,7aα)-2-(4-Cyano-1-naphthalenyl)octahydro-N-(2-hydroxyphenyl)-7-methyl-1,3-dioxo-4,7-epoxy-4H-isoindole-4-acetamide;

[3aα,4β(E),7β,7aα]-4-[Octahydro-4-methyl-7-[3-(6-methyl-2-pyridinyl)-2-propenyl]-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile;

(3aα,4β,7β,7aα)-4-[Octahydro-4-methyl-7-[3-(6-methyl-2-pyridinyl)propyl]-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile;

[3aR-(3aα,4β,7β,7aα)]-4-[Octahydro-4-[2-(3-methoxyphenoxy)ethyl]-7-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile;

[3aS-(3aα,4β,7β,7aα)]-4-[Octahydro-4-[2-(3-methoxyphenoxy)ethyl]-7-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile;

390

[3aR-(3aα,4β,7β,7aα)]-4-[4-[2-(4-Cyanophenoxy)ethyl]octahydro-7-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile;

[3aS-(3aα,4β,7β,7aα)]-4-[4-[2-(4-Cyanophenoxy)ethyl]octahydro-7-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile;

(3aα,4α,7α,7aα)-4-[4-[(4-Fluorophenyl)methyl]octahydro-7-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-2-(trifluoromethyl)benzonitrile;

(3aα,4α,7α,7aα)-Hexahydro-4,7-dimethyl-2-(1-methyl-6-oxo-3-piperidinyl)-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

(3aα,4α,7α,7aα)-2-(1,6-Dihydro-1,4-dimethyl-6-oxo-3-pyridinyl)hexahydro-4,7-dimethyl-4,7-epoxy-1H-isoindole-1,3(2H)-dione;

(3aα,4β,7β,7aα)-2-[4-Cyano-3-(trifluoromethyl)phenyl]octahydro-1,3-dioxo-7-[2-(phenylmethoxy)ethyl]-4,7-epoxy-4H-isoindole-4-propanenitrile;

(3aα,4β,7β,7aα)-2-[4-Cyano-3-(trifluoromethyl)phenyl]octahydro-1,3-dioxo-7-[2-(phenylmethoxy)ethyl]-4,7-epoxy-4H-isoindole-4-propanenitrile;

(3aα,4β,7β,7aα)-4-[7-[2-(4-Cyanophenoxy)ethyl]octahydro-5-hydroxy-4-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile;

[3aS-(3aα,4β,7β,7aα)]-4-[7-[2-(1,3-Benzodioxol-5-yloxy)ethyl]octahydro-5-hydroxy-4-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile;

[3aR-(3aα,4β,7β,7aα)]-4-[7-[2-(1,3-Benzodioxol-5-yloxy)ethyl]octahydro-5-hydroxy-4-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile;

[3aS-(3aα,4β,7β,7aα)]-4-[7-[2-[(5-Chloro-2-pyridinyl)oxy]ethyl]octahydro-5-hydroxy-4-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile;

[3aR-(3aα,4β,7β,7aα)]-4-[7-[2-[(5-Chloro-2-pyridinyl)oxy]ethyl]octahydro-5-hydroxy-4-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile;

[3aS-(3aα,4β,7β,7aα)]-4-[7-[2-(4-Chlorophenoxy)ethyl]octahydro-5-hydroxy-4-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile;

[3aR-(3aα,4β,7β,7aα)]-4-[7-[2-(4-Chlorophenoxy)ethyl]octahydro-5-hydroxy-4-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile;

[3aS-(3aα,4β,7β,7aα)]-4-[7-[2-(4-Acetylphenoxy)ethyl]octahydro-5-hydroxy-4-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile;

[3aR-(3aα,4β,7β,7aα)]-4-[7-[2-(4-Acetylphenoxy)ethyl]octahydro-5-hydroxy-4-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile;

[3aS-(3aα,4β,7β,7aα)]-4-[7-[2-(3-Cyanophenoxy)ethyl]octahydro-5-hydroxy-4-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile;

[3aR-(3aα,4β,7β,7aα)]-4-[7-[2-(3-Cyanophenoxy)ethyl]octahydro-5-hydroxy-4-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile;

[3aS-(3aα,4β,7β,7aα)]-4-[Octahydro-5-hydroxy-4-methyl-1,3-dioxo-7-[2-[(5,6,7,8-tetrahydro-1-naphthalenyl)oxy]ethyl]-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile;

[3aR-(3aα,4β,7β,7aα)]-4-[Octahydro-5-hydroxy-4-methyl-1,3-dioxo-7-[2-[(5,6,7,8-tetrahydro-1-naphthalenyl)oxy]ethyl]-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile;

[3aS-(3aα,4β,7β,7aα)]-4-[Octahydro-5-hydroxy-4-methyl-1,3-dioxo-7-[2-[(5,6,7,8-tetrahydro-5-oxo-1-naphthalenyl)oxy]ethyl]-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile;

[3aR-(3aα,4β,7β,7aα)]-4-[Octahydro-5-hydroxy-4-methyl-1,3-dioxo-7-[2-[(5,6,7,8-tetrahydro-5-oxo-1-naphthalenyl)oxy]ethyl]-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile;

[3aS-(3aα,4β,7β,7aα)]-4-[7-[2-(4-Fluorophenoxy)ethyl]octahydro-5-hydroxy-4-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile;

[3aR-(3aα,4β,7β,7aα)]-4-[7-[2-(4-Fluorophenoxy)ethyl]octahydro-5-hydroxy-4-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile;

[3aS-(3aα,4β,7β,7aα)]-4-[Octahydro-5-hydroxy-4-methyl-7-[2-[(4-methyl-2-oxo-2H-1-benzopyran-7-yl)oxy]ethyl]-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile;

392

[3aR-(3aα,4β,7β,7aα)]-4-[Octahydro-5-hydroxy-4-methyl-7-[2-[(4-methyl-2-oxo-2H-1-benzopyran-7-yl)oxy]ethyl]-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile;

[3aS-(3aα,4β,7β,7aα)]-4-[7-[2-(3,5-Dimethoxyphenoxy)ethyl]octahydro-5-hydroxy-4-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile;

[3aR-(3aα,4β,7β,7aα)]-4-[7-[2-(3,5-Dimethoxyphenoxy)ethyl]octahydro-5-hydroxy-4-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile;

[3aR-(3aα,4β,7β,7aα)]-]-4-[7-[2-(4-Chloro-3-methylphenoxy)ethyl]octahydro-5-hydroxy-4-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile;

[3aR-(3aα,4β,7β,7aα)]-4-[7-[2-(4-Cyano-2,3-difluorophenoxy)ethyl]octahydro-5-hydroxy-4-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile;

[3aS-(3aα,4β,7β,7aα)]-4-[7-[2-[(5-Chloro-1,2-benzisoxazol-3-yl)oxy]ethyl]octahydro-5-hydroxy-4-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile;

[3aR-(3aα,4β,7β,7aα)]-4-[7-[2-[(5-Chloro-1,2-benzisoxazol-3-yl)oxy]ethyl]octahydro-5-hydroxy-4-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile;

[3aR-(3aα,4β,7β,7aα)]-3-[2-[2-(4-Cyano-1-naphthalenyl)octahydro-6-hydroxy-7-methyl-1,3-dioxo-4,7-epoxy-4H-isoindol-4-yl]ethoxy]-5-isoxazolecarboxylic acid, methyl ester;

[3aR-(3aα,4β,7β,7aα)]-4-[Octahydro-5-hydroxy-4-methyl-1,3-dioxo-7-[2-[4-(1H-1,2,4-triazol-1-yl)phenoxy]ethyl]-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile;

[3aS-(3aα,4β,7β,7aα)]-4-[7-[2-[(7-Chloro-4-quinolinyl)oxy]ethyl]octahydro-5-hydroxy-4-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile, trifluoroacetate;

393

[3aR-(3aα,4β,7β,7aα)]-4-[7-[2-[(7-Chloro-4-quinolinyl)oxy]ethyl]octahydro-5-hydroxy-4-methyl-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile, trifluoroacetate;

(1aα,2β,2aα,5aα,6βb,6aα)-4-[2-[2-[[(1,1-dimethylethyl)-dimethylsilyl]oxy]ethyl]octahydro- 6-methyl-3,5-dioxo-2,6-epoxy-4H-oxireno[f]isoindol-4-yl]-1-naphthalenecarbonitrile;


[3aR-(3aα,4β,7β,7aα)]-4-[4-Ethyloctahydro-7-(2-hydroxyethyl)-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile;

[3aS-(3aα,4β,7β,7aα)]-4-[4-Ethyloctahydro-7-(2-hydroxyethyl)-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitril;

[3aR-(3aα,4β,7β,7aα)]-4-[4-[2-(4-Cyanophenoxy)ethyl]-7-ethyloctahydro-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile; and

[3aS-(3aα,4β,7β,7aα)]-4-[4-[2-(4-Cyanophenoxy)ethyl]-7-ethyloctahydro-1,3-dioxo-4,7-epoxy-2H-isoindol-2-yl]-1-naphthalenecarbonitrile.

5. A pharmaceutical composition capable of treating a NHR - associated condition, comprising a compound of the following formula I or a pharmaceutically acceptable salt thereof, and a pharmaceutically acceptable carrier:



(I)

wherein the symbols have the following meanings and are, for each occurrence, independently selected:

G is an aryl or heterocyclo group, where said group is mono- or polycyclic, and which is optionally substituted at one or more positions;

Z_1 is O, S, NH, or NR^6;

Z_2 is O, S, NH, or NR^6;

A_1 is CR^7 or N;

A_2 is CR^7 or N;

Y is J-J'-J" where J is $(CR^7R^{7'})$n and n = 0-3, J' is a bond or O, S, S=O, SO_2, NH, NR^7, C=O, OC=O, NR^1C=O, $CR^7R^{7'}$, $C=CR^8R^{8'}$, R^2P=O, R^2P=S, R^2OP=O, R^2NHP=O, $OP=OOR^2$, $OP=ONHR^2$, $OP=OR^2$, OSO_2, $C=NR^7$, NHNH, $NHNR^6$, NR^6NH, N=N, cycloalkyl or substituted cycloalkyl, cycloalkenyl or substituted cycloalkenyl, heterocyclo or substituted heterocyclo or aryl or substituted aryl, and J" is $(CR^7R^{7'})$n and n = 0-3, where Y is not a bond;

W is $CR^7R^{7'}$—$CR^7R^{7'}$, $CR^8=CR^{8'}$, $CR^7R^{7'}$—C=O, NR^9—$CR^7R^{7'}$, N=CR^8, N=N, NR^9—$NR^{9'}$, S—$CR^7R^{7'}$, SO—$CR^7R^{7'}$, SO_2—$CR^7R^{7'}$, cycloalkyl or substituted cycloalkyl, cycloalkenyl or substituted cycloalkenyl, heterocyclo or substituted heterocyclo, or aryl or substituted aryl, wherein when W is not NR^9—$CR^7R^{7'}$, N=CR^8, N=N, NR^9—$NR^{9'}$, S—$CR^7R^{7'}$, SO—$CR^7R^{7'}$, SO_2—$CR^7R^{7'}$, or heterocyclo or substituted heterocyclo, then J' must be O, S, S=O, SO_2, NH, NR^7, OC=O, NR^1C=O, $OP=OOR^2$, $OP=ONHR^2$, OSO_2, NHNH, $NHNR^6$, NR^6NH, or N=N;

Q_1 is H, alkyl or substituted alkyl, alkenyl or substituted alkenyl, cycloalkyl or substituted cycloalkyl, cycloalkenyl or substituted cycloalkenyl, heterocycloalkyl or substituted heterocycloalkyl, arylalkyl or substituted arylalkyl, alkynyl or substituted alkynyl, aryl or substituted aryl, heterocyclo or substituted heterocyclo, halo, CN, R^1OC=O, R^4C=O, R^5R^6NC=O, $HOCR^7R^{7'}$, nitro, R^1OCH_2, R^1O, NH_2, $C=OSR^1$, SO_2R^1 or NR^4R^5;

Q_2 is H, alkyl or substituted alkyl, alkenyl or substituted alkenyl, cycloalkyl or substituted cycloalkyl, cycloalkenyl or substituted cycloalkenyl, heterocycloalkyl or substituted heterocycloalkyl, arylalkyl or substituted arylalkyl, alkynyl or substituted alkynyl, aryl or substituted aryl, heterocyclo or substituted heterocyclo, halo, CN, R^1OC=O, R^4C=O, R^5R^6NC=O, $HOCR^7R^{7'}$, nitro, R^1OCH_2, R^1O, NH_2, $C=OSR^1$, SO_2R^1 or NR^4R^5;

395 390

L is a bond, $(CR^7R^{7'})n$, NH, NR^5, $NH(CR^7R^{7'})n$ or $NR^5(CR^7R^{7'})n$, where n = 0-3;

R^1 and $R^{1'}$ are each independently H, alkyl or substituted alkyl, cycloalkyl or substituted cycloalkyl, cycloalkenyl or substituted cycloalkenyl, heterocyclo or substituted heterocyclo, cycloalkylalkyl or substituted cycloalkyalkyl, cycloalkenylalkyl or substituted cycloalkenylalkyl, heterocycloalkyl or substituted heterocycloalkyl, aryl or substituted aryl, arylalkyl or substituted arylalkyl;

R^2 is alkyl or substituted alkyl, cycloalkyl or substituted cycloalkyl, cycloalkenyl or substituted cycloalkenyl, heterocyclo or substituted heterocyclo, cycloalkylalkyl or substituted cycloalkylalkyl, cycloalkenylalkyl or substituted cycloalkenylalkyl, heterocycloalkyl or substituted heterocycloalkyl, aryl or substituted aryl, arylalkyl or substituted arylalkyl;

R^3 and $R^{3'}$ are each independently H, alkyl or substituted alkyl, cycloalkyl or substituted cycloalkyl, cycloalkenyl or substituted cycloalkenyl, heterocyclo or substituted heterocyclo, cycloalkylalkyl or substituted cycloalkylalkyl, cycloalkenylalkyl or substituted cycloalkenylalkyl, heterocycloalkyl or substituted heterocycloalkyl, aryl or substituted aryl, arylalkyl or substituted arylalkyl, halo, CN, hydroxylamine, hydroxamide, alkoxy or substituted alkoxy, amino, NR^1R^2, thiol, alkylthio or substituted alkylthio;

R^4 is H, alkyl or substituted alkyl, cycloalkyl or substituted cycloalkyl, cycloalkenyl or substituted cycloalkenyl, heterocyclo or substituted heterocyclo, cycloalkylalkyl or substituted cycloalkylalkyl, cycloalkenylalkyl or substituted cycloalkenylalkyl, heterocycloalkyl or substituted heterocycloalkyl, aryl or substituted aryl, arylalkyl or substituted arylalkyl, $R^1C{=}O$, $R^1NHC{=}O$, SO_2OR^1, or $SO_2NR^1R^{1'}$;

R^5 is alkyl or substituted alkyl, cycloalkyl or substituted cycloalkyl, cycloalkenyl or substituted cycloalkenyl, heterocyclo or substituted heterocyclo, cycloalkylalkyl or substituted cycloalkylalkyl, cycloalkenylalkyl or substituted cycloalkenylalkyl, heterocycloalkyl or substituted heterocycloalkyl, aryl or substituted aryl, arylalkyl or substituted arylalkyl, $R^1C{=}O$, $R^1NHC{=}O$, SO_2R^1, SO_2OR^1, or $SO_2NR^1R^{1'}$;

390

R^6 is alkyl or substituted alkyl, cycloalkyl or substituted cycloalkyl, cycloalkenyl or substituted cycloalkenyl, heterocyclo or substituted heterocyclo, cycloalkylalkyl or substituted cycloalkylalkyl, cycloalkenylalkyl or substituted cycloalkenylalkyl, heterocycloalkyl or substituted heterocycloalkyl, aryl or substituted aryl, arylalkyl or substituted arylalkyl, CN, OH, OR^1, $R^1C{=}O$, $R^1NHC{=}O$, SO_2R^1, SO_2OR^1, or $SO_2NR^1R^{1'}$;

R^7 and $R^{7'}$ are each independently H, alkyl or substituted alkyl, alkenyl or substituted alkenyl, cycloalkyl or substituted cycloalkyl, cycloalkenyl or substituted cycloalkenyl, heterocyclo or substituted heterocyclo, cycloalkylalkyl or substituted cycloalkylalkyl, cycloalkenylalkyl or substituted cycloalkenylalkyl, heterocycloalkyl or substituted heterocycloalkyl, aryl or substituted aryl, arylalkyl or substituted arylalkyl, halo, CN, OR^1, nitro, hydroxylamine, hydroxylamide, amino, NHR^4, NR^2R^5, NOR^1, thiol, alkylthio or substituted alkylthio, $R^1C{=}O$, $R^1OC{=}O$, $R^1NHC{=}O$, SO_2R^1, SOR^1, $PO_3R^1R^{1'}$, $R^1R^{1'}NC{=}O$, $C{=}OSR^1$, SO_2R^1, SO_2OR^1, or $SO_2NR^1R^{1'}$, or, wherein A_1, or A_2 contains a group R^7 and W contains a group R^7, said R^7 groups of A_1 or A_2 and W together form a heterocyclic ring;

R^8 and $R^{8'}$ are each independently H, alkyl or substituted alkyl, alkenyl or substituted alkenyl, cycloalkyl or substituted cycloalkyl, cycloalkenyl or substituted cycloalkenyl, heterocyclo or substituted heterocyclo, cycloalkylalkyl or substituted cycloalkyalkyl, cycloalkenylalkyl or substituted cycloalkenylalkyl, heterocycloalkyl or substituted heterocycloalkyl, aryl or substituted aryl, arylalkyl or substituted arylalkyl, nitro, halo, CN, OR^1, amino, NHR^4, NR^2R^5, NOR^1, alkylthio or substituted alkylthio, $C{=}OSR^1$, $R^1OC{=}O$, $R^1C{=}O$, $R^1NHC{=}O$, $R^1R^{1'}NC{=}O$, SO_2OR^1, $S{=}OR^1$, SO_2R^1, $PO_3R^1R^{1'}$, or $SO_2NR^1R^{1'}$; and


R^9 and $R^{9'}$ are each independently H, alkyl or substituted alkyl, alkenyl or substituted alkenyl, cycloalkyl or substituted cycloalkyl, cycloalkenyl or substituted cycloalkenyl, heterocyclo or substituted heterocyclo, cycloalkylalkyl or substituted cycloalkylalkyl, cycloalkenylalkyl or substituted cycloalkenylalkyl, heterocycloalkyl or substituted heterocycloalkyl, aryl or

397

substituted aryl, arylalkyl or substituted arylalkyl, CN, OH, OR^1, $R^1C{=}O$, $R^1OC{=}O$, $R^1NHC{=}O$, SO_2R^1, SO_2OR^1, or $SO_2NR^1R^{1'}$.

6. A pharmaceutical composition of Claim 5 further comprising another anti-cancer agent.

7. A method of modulating the function of a nuclear hormone receptor which comprises administering to a mammalian species in need thereof an effective nuclear hormone receptor modulating amount of a compound of the following formula I:



(I)

wherein the symbols have the following meanings and are, for each occurrence, independently selected:

G is an aryl or heterocyclo group, where said group is mono- or polycyclic, and which is optionally substituted at one or more positions;

Z_1 is O, S, NH, or NR^6;

Z_2 is O, S, NH, or NR^6;

A_1 is CR^7 or N;

A_2 is CR^7 or N;

Y is J-J'-J" where J is $(CR^7R^{7'})n$ and n = 0-3, J' is a bond or O, S, S=O, SO_2, NH, NR^7, C=O, OC=O, $NR^1C{=}O$, $CR^7R^{7'}$, $C{=}CR^8R^{8'}$, $R^2P{=}O$, $R^2P{=}S$, $R^2OP{=}O$, $R^2NHP{=}O$, $OP{=}OOR^2$, $OP{=}ONHR^2$, $OP{=}OR^2$, OSO_2, $C{=}NR^7$, NHNH, $NHNR^6$, NR^6NH, N=N, cycloalkyl or substituted cycloalkyl, cycloalkenyl or

398

substituted cycloalkenyl, heterocyclo or substituted heterocyclo or aryl or substituted aryl, and J" is $(CR^7R^{7'})n$ and n = 0-3, where Y is not a bond;

W is $CR^7R^{7'}$—$CR^7R^{7'}$, CR^8=$CR^{8'}$, $CR^7R^{7'}$—C=O, NR^9—$CR^7R^{7'}$, N=CR^8, N=N, NR^9—$NR^{9'}$, S—$CR^7R^{7'}$, SO—$CR^7R^{7'}$, SO_2—$CR^7R^{7'}$, cycloalkyl or substituted cycloalkyl, cycloalkenyl or substituted cycloalkenyl, heterocyclo or substituted heterocyclo, or aryl or substituted aryl, wherein when W is not NR^9—$CR^7R^{7'}$, N=CR^8, N=N, NR^9—$NR^{9'}$, S—$CR^7R^{7'}$, SO—$CR^7R^{7'}$, SO_2—$CR^7R^{7'}$, or heterocyclo or substituted heterocyclo, then J' must be O, S, S=O, SO_2, NH, NR^7, OC=O, NR^1C=O, OP=OOR^2, OP=ONHR^2, OSO_2, NHNH, $NHNR^6$, NR^6NH, or N=N;

Q_1 is H, alkyl or substituted alkyl, alkenyl or substituted alkenyl, cycloalkyl or substituted cycloalkyl, cycloalkenyl or substituted cycloalkenyl, heterocycloalkyl or substituted heterocycloalkyl, arylalkyl or substituted arylalkyl, alkynyl or substituted alkynyl, aryl or substituted aryl, heterocyclo or substituted heterocyclo, halo, CN, R^1OC=O, R^4C=O, R^5R^6NC=O, $HOCR^7R^{7'}$, nitro, R^1OCH_2, R^1O, NH_2, C=OSR^1, SO_2R^1 or NR^4R^5;

Q_2 is H, alkyl or substituted alkyl, alkenyl or substituted alkenyl, cycloalkyl or substituted cycloalkyl, cycloalkenyl or substituted cycloalkenyl, heterocycloalkyl or substituted heterocycloalkyl, arylalkyl or substituted arylalkyl, alkynyl or substituted alkynyl, aryl or substituted aryl, heterocyclo or substituted heterocyclo, halo, CN, R^1OC=O, R^4C=O, R^5R^6NC=O, $HOCR^7R^{7'}$, nitro, R^1OCH_2, R^1O, NH_2, C=OSR^1, SO_2R^1 or NR^4R^5;

L is a bond, $(CR^7R^{7'})n$, NH, NR^5, $NH(CR^7R^{7'})n$ or $NR^5(CR^7R^{7'})n$, where n = 0-3;

R^1 and $R^{1'}$ are each independently H, alkyl or substituted alkyl, cycloalkyl or substituted cycloalkyl, cycloalkenyl or substituted cycloalkenyl, heterocyclo or substituted heterocyclo, cycloalkylalkyl or substituted cycloalkyalkyl, cycloalkenylalkyl or substituted cycloalkenylalkyl, heterocycloalkyl or substituted heterocycloalkyl, aryl or substituted aryl, arylalkyl or substituted arylalkyl;

399

R^2 is alkyl or substituted alkyl, cycloalkyl or substituted cycloalkyl, cycloalkenyl or substituted cycloalkenyl, heterocyclo or substituted heterocyclo, cycloalkylalkyl or substituted cycloalkylalkyl, cycloalkenylalkyl or substituted cycloalkenylalkyl, heterocycloalkyl or substituted heterocycloalkyl, aryl or substituted aryl, arylalkyl or substituted arylalkyl;

R^3 and $R^{3'}$ are each independently H, alkyl or substituted alkyl, cycloalkyl or substituted cycloalkyl, cycloalkenyl or substituted cycloalkenyl, heterocyclo or substituted heterocyclo, cycloalkylalkyl or substituted cycloalkylalkyl, cycloalkenylalkyl or substituted cycloalkenylalkyl, heterocycloalkyl or substituted heterocycloalkyl, aryl or substituted aryl, arylalkyl or substituted arylalkyl, halo, CN, hydroxylamine, hydroxamide, alkoxy or substituted alkoxy, amino, NR^1R^2, thiol, alkylthio or substituted alkylthio;

R^4 is H, alkyl or substituted alkyl, cycloalkyl or substituted cycloalkyl, cycloalkenyl or substituted cycloalkenyl, heterocyclo or substituted heterocyclo, cycloalkylalkyl or substituted cycloalkylalkyl, cycloalkenylalkyl or substituted cycloalkenylalkyl, heterocycloalkyl or substituted heterocycloalkyl, aryl or substituted aryl, arylalkyl or substituted arylalkyl, $R^1C{=}O$, $R^1NHC{=}O$, SO_2OR^1, or $SO_2NR^1R^{1'}$;

R^5 is alkyl or substituted alkyl, cycloalkyl or substituted cycloalkyl, cycloalkenyl or substituted cycloalkenyl, heterocyclo or substituted heterocyclo, cycloalkylalkyl or substituted cycloalkylalkyl, cycloalkenylalkyl or substituted cycloalkenylalkyl, heterocycloalkyl or substituted heterocycloalkyl, aryl or substituted aryl, arylalkyl or substituted arylalkyl, $R^1C{=}O$, $R^1NHC{=}O$, SO_2R^1, SO_2OR^1, or $SO_2NR^1R^{1'}$;

R^6 is alkyl or substituted alkyl, cycloalkyl or substituted cycloalkyl, cycloalkenyl or substituted cycloalkenyl, heterocyclo or substituted heterocyclo, cycloalkylalkyl or substituted cycloalkylalkyl, cycloalkenylalkyl or substituted cycloalkenylalkyl, heterocycloalkyl or substituted heterocycloalkyl, aryl or substituted aryl, arylalkyl or substituted arylalkyl, CN, OH, OR^1, $R^1C{=}O$, $R^1NHC{=}O$, SO_2R^1, SO_2OR^1, or $SO_2NR^1R^{1'}$;

400

R^7 and $R^{7'}$ are each independently H, alkyl or substituted alkyl, alkenyl or substituted alkenyl, cycloalkyl or substituted cycloalkyl, cycloalkenyl or substituted cycloalkenyl, heterocyclo or substituted heterocyclo, cycloalkylalkyl or substituted cycloalkylalkyl, cycloalkenylalkyl or substituted cycloalkenylalkyl, heterocycloalkyl or substituted heterocycloalkyl, aryl or substituted aryl, arylalkyl or substituted arylalkyl, halo, CN, OR^1, nitro, hydroxylamine, hydroxylamide, amino, NHR^4, NR^2R^5, NOR^1, thiol, alkylthio or substituted alkylthio, $R^1C{=}O$, $R^1OC{=}O$, $R^1NHC{=}O$, SO_2R^1, SOR^1, $PO_3R^1R^{1'}$, $R^1R^{1'}NC{=}O$, $C{=}OSR^1$, SO_2R^1, SO_2OR^1, or $SO_2NR^1R^{1'}$, or, wherein A_1 or A_2 contains a group R^7 and W contains a group R^7, said R^7 groups of A_1 or A_2 and W together form a heterocyclic ring;

R^8 and $R^{8'}$ are each independently H, alkyl or substituted alkyl, alkenyl or substituted alkenyl, cycloalkyl or substituted cycloalkyl, cycloalkenyl or substituted cycloalkenyl, heterocyclo or substituted heterocyclo, cycloalkylalkyl or substituted cycloalkyalkyl, cycloalkenylalkyl or substituted cycloalkenylalkyl, heterocycloalkyl or substituted heterocycloalkyl, aryl or substituted aryl, arylalkyl or substituted arylalkyl, nitro, halo, CN, OR^1, amino, NHR^4, NR^2R^5, NOR^1, alkylthio or substituted alkylthio, $C{=}OSR^1$, $R^1OC{=}O$, $R^1C{=}O$, $R^1NHC{=}O$, $R^1R^{1'}NC{=}O$, SO_2OR^1, $S{=}OR^1$, SO_2R^1, $PO_3R^1R^{1'}$, or $SO_2NR^1R^{1'}$; and

R^9 and $R^{9'}$ are each independently H, alkyl or substituted alkyl, alkenyl or substituted alkenyl, cycloalkyl or substituted cycloalkyl, cycloalkenyl or substituted cycloalkenyl, heterocyclo or substituted heterocyclo, cycloalkylalkyl or substituted cycloalkylalkyl, cycloalkenylalkyl or substituted cycloalkenylalkyl, heterocycloalkyl or substituted heterocycloalkyl, aryl or substituted aryl, arylalkyl or substituted arylalkyl, CN, OH, OR^1, $R^1C{=}O$, $R^1OC{=}O$, $R^1NHC{=}O$, SO_2R^1, SO_2OR^1, or $SO_2NR^1R^{1'}$.

8. The method of Claim 7 wherein said nuclear hormone receptor is a steroid binding nuclear hormone receptor.

401

9. The method of Claim 7 wherein said nuclear hormone receptor is the androgen receptor.

10. The method of Claim 7 wherein said nuclear hormone receptor is the estrogen receptor.


11. The method of Claim 7 wherein said nuclear hormone receptor is the progesterone receptor.

12. The method of Claim 7 wherein said nuclear hormone receptor is the glucocorticoid receptor.

13. The method of Claim 7 wherein said nuclear hormone receptor is the mineralocorticoid receptor.

14. The method of Claim 7 wherein said nuclear hormone receptor is the aldosterone receptor.

15. A method for treating a condition or disorder comprising administering to a mammalian species in need thereof a therapeutically effective amount of a compound of the following formula:



(I)

4102

wherein the symbols have the following meanings and are, for each occurrence, independently selected:

G is an aryl or heterocyclo group, where said group is mono- or polycyclic, and which is optionally substituted at one or more positions;

Z_1 is O, S, NH, or NR^6;

Z_2 is O, S, NH, or NR^6;

A_1 is CR^7 or N;

A_2 is CR^7 or N;

Y is J-J'-J" where J is $(CR^7R^{7'})n$ and n = 0-3, J' is a bond or O, S, S=O, SO_2, NH, NR^7, C=O, OC=O, $NR^1C=O$, $CR^7R^{7'}$, $C=CR^8R^{8'}$, $R^2P=O$, $R^2P=S$, $R^2OP=O$, $R^2NHP=O$, $OP=OOR^2$, $OP=ONHR^2$, $OP=OR^2$, OSO_2, $C=NR^7$, NHNH, $NHNR^6$, NR^6NH, N=N, cycloalkyl or substituted cycloalkyl, cycloalkenyl or substituted cycloalkenyl, heterocyclo or substituted heterocyclo or aryl or substituted aryl, and J" is $(CR^7R^{7'})n$ and n = 0-3, where Y is not a bond;

W is $CR^7R^{7'}—CR^7R^{7'}$, $CR^8=CR^{8'}$, $CR^7R^{7'}—C=O$, $NR^9—CR^7R^{7'}$, $N=CR^8$, N=N, $NR^9—NR^{9'}$, $S—CR^7R^{7'}$, $SO—CR^7R^{7'}$, $SO_2—CR^7R^{7'}$, cycloalkyl or substituted cycloalkyl, cycloalkenyl or substituted cycloalkenyl, heterocyclo or substituted heterocyclo, or aryl or substituted aryl, wherein when W is not $NR^9—CR^7R^{7'}$, $N=CR^8$, N=N, $NR^9—NR^{9'}$, $S—CR^7R^{7'}$, $SO—CR^7R^{7'}$, $SO_2—CR^7R^{7'}$, or heterocyclo or substituted heterocyclo, then J' must be O, S, S=O, SO_2, NH, NR^7, OC=O, $NR^1C=O$, $OP=OOR^2$, $OP=ONHR^2$, OSO_2, NHNH, $NHNR^6$, NR^6NH, or N=N;

Q_1 is H, alkyl or substituted alkyl, alkenyl or substituted alkenyl, cycloalkyl or substituted cycloalkyl, cycloalkenyl or substituted cycloalkenyl, heterocycloalkyl or substituted heterocycloalkyl, arylalkyl or substituted arylalkyl, alkynyl or substituted alkynyl, aryl or substituted aryl, heterocyclo or substituted heterocyclo, halo, CN, $R^1OC=O$, $R^4C=O$, $R^5R^6NC=O$, $HOCR^7R^{7'}$, nitro, R^1OCH_2, R^1O, NH_2, $C=OSR^1$, SO_2R^1 or NR^4R^5;

Q_2 is H, alkyl or substituted alkyl, alkenyl or substituted alkenyl, cycloalkyl or substituted cycloalkyl, cycloalkenyl or substituted cycloalkenyl,

403

heterocycloalkyl or substituted heterocycloalkyl, arylalkyl or substituted arylalkyl, alkynyl or substituted alkynyl, aryl or substituted aryl, heterocyclo or substituted heterocyclo, halo, CN, $R^1OC=O$, $R^4C=O$, $R^5R^6NC=O$, $HOCR^7R^{7'}$, nitro, R^1OCH_2, R^1O, NH_2, $C=OSR^1$, SO_2R^1 or NR^4R^5;

L is a bond, $(CR^7R^{7'})n$, NH, NR^5, $NH(CR^7R^{7'})n$ or $NR^5(CR^7R^{7'})n$, where n = 0-3;

R^1 and $R^{1'}$ are each independently H, alkyl or substituted alkyl, cycloalkyl or substituted cycloalkyl, cycloalkenyl or substituted cycloalkenyl, heterocyclo or substituted heterocyclo, cycloalkylalkyl or substituted cycloalkyalkyl, cycloalkenylalkyl or substituted cycloalkenylalkyl, heterocycloalkyl or substituted heterocycloalkyl, aryl or substituted aryl, arylalkyl or substituted arylalkyl;

R^2 is alkyl or substituted alkyl, cycloalkyl or substituted cycloalkyl, cycloalkenyl or substituted cycloalkenyl, heterocyclo or substituted heterocyclo, cycloalkylalkyl or substituted cycloalkylalkyl, cycloalkenylalkyl or substituted cycloalkenylalkyl, heterocycloalkyl or substituted heterocycloalkyl, aryl or substituted aryl, arylalkyl or substituted arylalkyl;

R^3 and $R^{3'}$ are each independently H, alkyl or substituted alkyl, cycloalkyl or substituted cycloalkyl, cycloalkenyl or substituted cycloalkenyl, heterocyclo or substituted heterocyclo, cycloalkylalkyl or substituted cycloalkylalkyl, cycloalkenylalkyl or substituted cycloalkenylalkyl, heterocycloalkyl or substituted heterocycloalkyl, aryl or substituted aryl, arylalkyl or substituted arylalkyl, halo, CN, hydroxylamine, hydroxamide, alkoxy or substituted alkoxy, amino, NR^1R^2, thiol, alkylthio or substituted alkylthio;

R^4 is H, alkyl or substituted alkyl, cycloalkyl or substituted cycloalkyl, cycloalkenyl or substituted cycloalkenyl, heterocyclo or substituted heterocyclo, cycloalkylalkyl or substituted cycloalkylalkyl, cycloalkenylalkyl or substituted cycloalkenylalkyl, heterocycloalkyl or substituted heterocycloalkyl, aryl or substituted aryl, arylalkyl or substituted arylalkyl, $R^1C=O$, $R^1NHC=O$, SO_2OR^1, or $SO_2NR^1R^{1'}$;

R^5 is alkyl or substituted alkyl, cycloalkyl or substituted cycloalkyl, cycloalkenyl or substituted cycloalkenyl, heterocyclo or substituted heterocyclo,

404

cycloalkylalkyl or substituted cycloalkylalkyl, cycloalkenylalkyl or substituted cycloalkenylalkyl, heterocycloalkyl or substituted heterocycloalkyl, aryl or substituted aryl, arylalkyl or substituted arylalkyl, $R^1C=O$, $R^1NHC=O$, SO_2R^1, SO_2OR^1, or $SO_2NR^1R^{1'}$;

R^6 is alkyl or substituted alkyl, cycloalkyl or substituted cycloalkyl, cycloalkenyl or substituted cycloalkenyl, heterocyclo or substituted heterocyclo, cycloalkylalkyl or substituted cycloalkylalkyl, cycloalkenylalkyl or substituted cycloalkenylalkyl, heterocycloalkyl or substituted heterocycloalkyl, aryl or substituted aryl, arylalkyl or substituted arylalkyl, CN, OH, OR^1, $R^1C=O$, $R^1NHC=O$, SO_2R^1, SO_2OR^1, or $SO_2NR^1R^{1'}$;

R^7 and $R^{7'}$ are each independently H, alkyl or substituted alkyl, alkenyl or substituted alkenyl, cycloalkyl or substituted cycloalkyl, cycloalkenyl or substituted cycloalkenyl, heterocyclo or substituted heterocyclo, cycloalkylalkyl or substituted cycloalkylalkyl, cycloalkenylalkyl or substituted cycloalkenylalkyl, heterocycloalkyl or substituted heterocycloalkyl, aryl or substituted aryl, arylalkyl or substituted arylalkyl, halo, CN, OR^1, nitro, hydroxylamine, hydroxylamide, amino, NHR^4, NR^2R^5, NOR^1, thiol, alkylthio or substituted alkylthio, $R^1C=O$, $R^1OC=O$, $R^1NHC=O$, SO_2R^1, SOR^1, $PO_3R^1R^{1'}$, $R^1R^{1'}NC=O$, $C=OSR^1$, SO_2R^1, SO_2OR^1, or $SO_2NR^1R^{1'}$, or, wherein A_1 or A_2 contains a group R^7 and W contains a group R^7, said R^7 groups of A_1 or A_2 and W together form a heterocyclic ring;

R^8 and $R^{8'}$ are each independently H, alkyl or substituted alkyl, alkenyl or substituted alkenyl, cycloalkyl or substituted cycloalkyl, cycloalkenyl or substituted cycloalkenyl, heterocyclo or substituted heterocyclo, cycloalkylalkyl or substituted cycloalkyalkyl, cycloalkenylalkyl or substituted cycloalkenylalkyl, heterocycloalkyl or substituted heterocycloalkyl, aryl or substituted aryl, arylalkyl or substituted arylalkyl, nitro, halo, CN, OR^1, amino, NHR^4, NR^2R^5, NOR^1, alkylthio or substituted alkylthio, $C=OSR^1$, $R^1OC=O$, $R^1C=O$, $R^1NHC=O$, $R^1R^{1'}NC=O$, SO_2OR^1, $S=OR^1$, SO_2R^1, $PO_3R^1R^{1'}$, or $SO_2NR^1R^{1'}$; and


405

R^9 and $R^{9'}$ are each independently H, alkyl or substituted alkyl, alkenyl or substituted alkenyl, cycloalkyl or substituted cycloalkyl, cycloalkenyl or substituted cycloalkenyl, heterocyclo or substituted heterocyclo, cycloalkylalkyl or substituted cycloalkylalkyl, cycloalkenylalkyl or substituted cycloalkenylalkyl, heterocycloalkyl or substituted heterocycloalkyl, aryl or substituted aryl, arylalkyl or substituted arylalkyl, CN, OH, OR^1, $R^1C{=}O$, $R^1OC{=}O$, $R^1NHC{=}O$, SO_2R^1, SO_2OR^1, or $SO_2NR^1R^{1'}$;

wherein said condition or disorder is selected from the group consisting of proliferate diseases, cancers, benign prostate hypertrophia, adenomas and neoplasies of the prostate, benign or malignant tumor cells containing the androgen receptor, heart disease, angiogenic conditions or disorders, hirsutism, acne, hyperpilosity, inflammation, immune modulation, seborrhea, endometriosis, polycystic ovary syndrome, androgenic alopecia, hypogonadism, osteoporosis, suppressing spermatogenisis, libido, cachexia, anorexia, inhibition of muscular atrophy in ambulatory patients, androgen supplementation for age related decreased testosterone levels in men, cancers expressing the estrogen receptor, prostate cancer, breast cancer, endometrial cancer, hot flushes, vaginal dryness, menopause, amennoreahea, dysmennoreahea, contraception, pregnancy termination, cancers containing the progesterone receptor, endometriosis, cachexia, menopause, cyclesynchrony, meniginoma, fibroids, labor induction, autoimmune diseases, Alzheimer's disease, psychotic disorders, drug dependence, non-insulin dependent Diabetes Mellitus, dopamine receptor mediated disorders, congestive heart failure, disregulation of cholesterol homeostasis, and attenuating the metabolism of a pharmaceutical agent.

16. A method for preparation of a compound of the following formula XVI, or salt thereof:

406



XVI

where

G is an aryl or heterocyclo group, where said group is mono- or polycyclic, and which is optionally substituted at one or more positions;

Z_1 is O, S, NH, or NR^6;

Z_2 is O, S, NH, or NR^6;

A_1 is CR^7 or N;

A_2 is CR^7 or N;

Y' is J-J'-J" where J is $(CR^7R^{7'})n$ and n = 0-3, J' is O, S, S=O, SO_2, NH, NR^7, OP=OOR^2, OC=O, NR^1C=O, OP=ONHR^2, OSO_2, NHNH, $NHNR^6$, NR^6NH, or N=N, and J" is $(CR^7R^{7'})n$ and n = 0-3;

Q_1 is H, alkyl or substituted alkyl, alkenyl or substituted alkenyl, cycloalkyl or substituted cycloalkyl, cycloalkenyl or substituted cycloalkenyl, heterocycloalkyl or substituted heterocycloalkyl, arylalkyl or substituted arylalkyl, alkynyl or substituted alkynyl, aryl or substituted aryl, heterocyclo or substituted heterocyclo, halo, CN, R^1OC=O, R^4C=O, R^5R^6NC=O, $HOCR^7R^{7'}$, nitro, R^1OCH_2, R^1O, NH_2, C=OSR^1, SO_2R^1 or NR^4R^5;

Q_2 is H, alkyl or substituted alkyl, alkenyl or substituted alkenyl, cycloalkyl or substituted cycloalkyl, cycloalkenyl or substituted cycloalkenyl, heterocycloalkyl or substituted heterocycloalkyl, arylalkyl or substituted arylalkyl, alkynyl or substituted alkynyl, aryl or substituted aryl, heterocyclo or substituted heterocyclo, halo, CN, R^1OC=O, R^4C=O, R^5R^6NC=O, $HOCR^7R^{7'}$, nitro, R^1OCH_2, R^1O, NH_2, C=OSR^1, SO_2R^1 or NR^4R^5;

L is a bond, $(CR^7R^{7'})n$, NH, NR^5 or $NR^5(CR^7R^{7'})n$, where n = 0-3;

R^1 and $R^{1'}$ are each independently H, alkyl or substituted alkyl, cycloalkyl or substituted cycloalkyl, cycloalkenyl or substituted cycloalkenyl, heterocyclo or substituted heterocyclo, cycloalkylalkyl or substituted cycloalkyalkyl,

cycloalkenylalkyl or substituted cycloalkenylalkyl, heterocycloalkyl or substituted heterocycloalkyl, aryl or substituted aryl, arylalkyl or substituted arylalkyl;

R^2 is alkyl or substituted alkyl, cycloalkyl or substituted cycloalkyl, cycloalkenyl or substituted cycloalkenyl, heterocyclo or substituted heterocyclo, cycloalkylalkyl or substituted cycloalkylalkyl, cycloalkenylalkyl or substituted cycloalkenylalkyl, heterocycloalkyl or substituted heterocycloalkyl, aryl or substituted aryl, arylalkyl or substituted arylalkyl;

R^4 is H, alkyl or substituted alkyl, cycloalkyl or substituted cycloalkyl, cycloalkenyl or substituted cycloalkenyl, heterocyclo or substituted heterocyclo, cycloalkylalkyl or substituted cycloalkylalkyl, cycloalkenylalkyl or substituted cycloalkenylalkyl, heterocycloalkyl or substituted heterocycloalkyl, aryl or substituted aryl, arylalkyl or substituted arylalkyl, $R^1C{=}O$, $R^1NHC{=}O$, SO_2OR^1, or $SO_2NR^1R^{1'}$;

R^5 is alkyl or substituted alkyl, cycloalkyl or substituted cycloalkyl, cycloalkenyl or substituted cycloalkenyl, heterocyclo or substituted heterocyclo, cycloalkylalkyl or substituted cycloalkylalkyl, cycloalkenylalkyl or substituted cycloalkenylalkyl, heterocycloalkyl or substituted heterocycloalkyl, aryl or substituted aryl, arylalkyl or substituted arylalkyl, $R^1C{=}O$, $R^1NHC{=}O$, SO_2R^1, SO_2OR^1, or $SO_2NR^1R^{1'}$;


R^6 is alkyl or substituted alkyl, cycloalkyl or substituted cycloalkyl, cycloalkenyl or substituted cycloalkenyl, heterocyclo or substituted heterocyclo, cycloalkylalkyl or substituted cycloalkylalkyl, cycloalkenylalkyl or substituted cycloalkenylalkyl, heterocycloalkyl or substituted heterocycloalkyl, aryl or substituted aryl, arylalkyl or substituted arylalkyl, CN, OH, OR^1, $R^1C{=}O$, $R^1NHC{=}O$, SO_2R^1, SO_2OR^1, or $SO_2NR^1R^{1'}$; and

R^7 and $R^{7'}$ are each independently H, alkyl or substituted alkyl, alkenyl or substituted alkenyl, cycloalkyl or substituted cycloalkyl, cycloalkenyl or substituted cycloalkenyl, heterocyclo or substituted heterocyclo, cycloalkylalkyl or substituted cycloalkylalkyl, cycloalkenylalkyl or substituted cycloalkenylalkyl, heterocycloalkyl or substituted heterocycloalkyl, aryl or

408

substituted aryl, arylalkyl or substituted arylalkyl, halo, CN, OR^1, nitro, hydroxylamine, hydroxylamide, amino, NHR^4, NR^2R^5, NOR^1, thiol, alkylthio or substituted alkylthio, $R^1C{=}O$, $R^1OC{=}O$, $R^1NHC{=}O$, SO_2R^1, SOR^1, $PO_3R^1R^{1'}$, $R^1R^{1'}NC{=}O$, $C{=}OSR^1$, SO_2R^1, SO_2OR^1, or $SO_2NR^1R^{1'}$;


comprising the steps of contacting a compound of the following formula XV, or salt thereof:



XV

where the symbols are as defined above;
with an enzyme or microorganism capable of catalyzing the hydroxylation of said compound XV to said compound XVI, and effecting said hydroxylation.

17. A method for preparation of a compound of the following formula XVIII, or salt thereof:



XVIII

where

G is an aryl or heterocyclo group, where said group is mono- or polycyclic, and which is optionally substituted at one or more positions;

Z_1 is O, S, NH, or NR^6;

Z_2 is O, S, NH, or NR^6;

A_1 is CR^7 or N;

A_2 is CR^7 or N;

Y' is J-J'-J" where J is $(CR^7R^{7'})n$ and n = 0-3, J' is O, S, S=O, SO_2, NH, NR^7, $OP{=}OOR^2$, $OC{=}O$, $NR^1C{=}O$, $OP{=}ONHR^2$, OSO_2, NHNH, $NHNR^6$, NR^6NH, or N=N, and J" is $(CR^7R^{7'})n$ and n = 0-3;

409

Q_1 is H, alkyl or substituted alkyl, alkenyl or substituted alkenyl, cycloalkyl or substituted cycloalkyl, cycloalkenyl or substituted cycloalkenyl, heterocycloalkyl or substituted heterocycloalkyl, arylalkyl or substituted arylalkyl, alkynyl or substituted alkynyl, aryl or substituted aryl, heterocyclo or substituted heterocyclo, halo, CN, $R^1OC=O$, $R^4C=O$, $R^5R^6NC=O$, $HOCR^7R^{7'}$, nitro, R^1OCH_2, R^1O, NH_2, $C=OSR^1$, SO_2R^1 or NR^4R^5;

Q_2 is H, alkyl or substituted alkyl, alkenyl or substituted alkenyl, cycloalkyl or substituted cycloalkyl, cycloalkenyl or substituted cycloalkenyl, heterocycloalkyl or substituted heterocycloalkyl, arylalkyl or substituted arylalkyl, alkynyl or substituted alkynyl, aryl or substituted aryl, heterocyclo or substituted heterocyclo, halo, CN, $R^1OC=O$, $R^4C=O$, $R^5R^6NC=O$, $HOCR^7R^{7'}$, nitro, R^1OCH_2, R^1O, NH_2, $C=OSR^1$, SO_2R^1 or NR^4R^5;

L is a bond, $(CR^7R^{7'})n$, NH, NR^5 or $NR^5(CR^7R^{7'})n$, where n = 0-3;

R^1 and $R^{1'}$ are each independently H, alkyl or substituted alkyl, cycloalkyl or substituted cycloalkyl, cycloalkenyl or substituted cycloalkenyl, heterocyclo or substituted heterocyclo, cycloalkylalkyl or substituted cycloalkyalkyl, cycloalkenylalkyl or substituted cycloalkenylalkyl, heterocycloalkyl or substituted heterocycloalkyl, aryl or substituted aryl, arylalkyl or substituted arylalkyl;

R^2 is alkyl or substituted alkyl, cycloalkyl or substituted cycloalkyl, cycloalkenyl or substituted cycloalkenyl, heterocyclo or substituted heterocyclo, cycloalkylalkyl or substituted cycloalkylalkyl, cycloalkenylalkyl or substituted cycloalkenylalkyl, heterocycloalkyl or substituted heterocycloalkyl, aryl or substituted aryl, arylalkyl or substituted arylalkyl;

R^4 is H, alkyl or substituted alkyl, cycloalkyl or substituted cycloalkyl, cycloalkenyl or substituted cycloalkenyl, heterocyclo or substituted heterocyclo, cycloalkylalkyl or substituted cycloalkylalkyl, cycloalkenylalkyl or substituted cycloalkenylalkyl, heterocycloalkyl or substituted heterocycloalkyl, aryl or substituted aryl, arylalkyl or substituted arylalkyl, $R^1C=O$, $R^1NHC=O$, SO_2OR^1, or $SO_2NR^1R^{1'}$;


410

R^5 is alkyl or substituted alkyl, cycloalkyl or substituted cycloalkyl, cycloalkenyl or substituted cycloalkenyl, heterocyclo or substituted heterocyclo, cycloalkylalkyl or substituted cycloalkylalkyl, cycloalkenylalkyl or substituted cycloalkenylalkyl, heterocycloalkyl or substituted heterocycloalkyl, aryl or substituted aryl, arylalkyl or substituted arylalkyl, $R^1C{=}O$, $R^1NHC{=}O$, SO_2R^1, SO_2OR^1, or $SO_2NR^1R^{1'}$;

R^6 is alkyl or substituted alkyl, cycloalkyl or substituted cycloalkyl, cycloalkenyl or substituted cycloalkenyl, heterocyclo or substituted heterocyclo, cycloalkylalkyl or substituted cycloalkylalkyl, cycloalkenylalkyl or substituted cycloalkenylalkyl, heterocycloalkyl or substituted heterocycloalkyl, aryl or substituted aryl, arylalkyl or substituted arylalkyl, CN, OH, OR^1, $R^1C{=}O$, $R^1NHC{=}O$, SO_2R^1, SO_2OR^1, or $SO_2NR^1R^{1'}$; and

R^7 and $R^{7'}$ are each independently H, alkyl or substituted alkyl, alkenyl or substituted alkenyl, cycloalkyl or substituted cycloalkyl, cycloalkenyl or substituted cycloalkenyl, heterocyclo or substituted heterocyclo, cycloalkylalkyl or substituted cycloalkylalkyl, cycloalkenylalkyl or substituted cycloalkenylalkyl, heterocycloalkyl or substituted heterocycloalkyl, aryl or substituted aryl, arylalkyl or substituted arylalkyl, halo, CN, OR^1, nitro, hydroxylamine, hydroxylamide, amino, NHR^4, NR^2R^5, NOR^1, thiol, alkylthio or substituted alkylthio, $R^1C{=}O$, $R^1OC{=}O$, $R^1NHC{=}O$, SO_2R^1, SOR^1, $PO_3R^1R^{1'}$, $R^1R^{1'}NC{=}O$, $C{=}OSR^1$, SO_2R^1, SO_2OR^1, or $SO_2NR^1R^{1'}$;

comprising the steps of contacting a compound of the following formula XVII, or salt thereof:




XVII

where the symbols are as defined above;

with an enzyme or microorganism capable of catalyzing the opening of the epoxide ring of compound XVII to form the diol of said compound XVIII, and effecting said ring opening and diol formation.

18. A compound of the following formula Ib:



Ib

where G, Z_1, Z_2, Q_1 and Q_2 are as defined in claim 1;

Y' is J-J'-J" where J is $(CR^7R^{7'})n$ and n = 0-3, J' is a bond or O, S, S=O, SO_2, NH, NR^7, $CR^7R^{7'}$, $R^2P=O$, $R^2P=S$, $R^2OP=O$, $R^2NHP=O$, $OP=OOR^2$, $OP=ONHR^2$, OSO_2, NHNH, $NHNR^6$, NR^6NH, N=N, cycloalkyl or substituted cycloalkyl, cycloalkenyl or substituted cycloalkenyl, or heterocyclo or substituted heterocyclo, and J" is $(CR^7R^{7'})n$ and n = 0-3, where Y is not a bond; and

W' is $CR^7R^{7'}$—$CR^7R^{7'}$, $CR^7R^{7'}$—C=O, NR^9—$CR^7R^{7'}$, N=CR^8, N=N, NR^9—$NR^{9'}$, cycloalkyl or substituted cycloalkyl, cycloalkenyl or substituted cycloalkenyl, heterocyclo or substituted heterocyclo, or aryl or substituted aryl, wherein, when W' is not NR^9—$CR^7R^{7'}$, N=CR^8, N=N, NR^9—$NR^{9'}$, or heterocyclo or substituted heterocyclo, then J' must be O, S, S=O, SO_2, NH, NR^7, $OP=OOR^2$, $OP=ONHR^2$, OSO_2, NHNH, $NHNR^6$, NR^6NH, or N=N; or alternatively,

Y' is $CR^7R^{7'}$-C=O and W' is NR^9-$CR^7R^{7'}$;

L is a bond; and

A_1 and A_2 are as defined above with the proviso that, when Y' = O and W' = -CH_2-CH_2-, then at least one of A_1 or A_2 is not CH;

with the further provisos (2), (3), (6), (7) and (8) of claim 1.

412

Fused Heterocyclic Succinimide Compounds and Analogs Thereof, Modulators of Nuclear Hormone Receptor Function

Abstract of the Disclosure

Fused cyclic compounds, methods of using such compounds in the treatment of nuclear hormone receptor-associated conditions such as cancer and immune disorders, and pharmaceutical compositions containing such compounds.

PATENT COOPERATION TREATY

413

From the
INTERNATIONAL PRELIMINARY EXAMINING AUTHORITY

RECEIVED
BMS PATENT LAW

To:
SUZANNE E. BABAJKO
BRISTOL-MYERS SQUIBB CO.
P.O. BOX 4000
PRINCETON, NJ 08543-4000

JAN 16 2003

Docketed Item
Due Date
Attorney SCB

NOTIFICATION OF TRANSMITTAL OF INTERNATIONAL PRELIMINARY EXAMINATION REPORT

(PCT Rule 71.1)

Date of Mailing (day/month/year)	14 JAN 2003

Applicant's or agent's file reference	IMPORTANT NOTIFICATION

International application No.	International filing date (day/month/year)	Priority date (day/month/year)
PCT/US01/19655	20 June 2001 (20.06.2001)	19 September 2000 (19.09.2000)

Applicant

BRISTOL-MYERS SQUIBB COMPANY

1. The applicant is hereby notified that this International Preliminary Examining Authority transmits herewith the international preliminary examination report and its annexes, if any, established on the international application.

2. A copy of the report and its annexes, if any, is being transmitted to the International Bureau for communication to all the elected Offices.

3. Where required by any of the elected Offices, the International Bureau will prepare an English translation of the report (but not of any annexes) and will transmit such translation to those Offices.

4. **REMINDER**

The applicant must enter the national phase before each elected Office by performing certain acts (filing translations and paying national fees) within 30 months from the priority date (or later in some Offices)(Article 39(1))(see also the reminder sent by the International Bureau with Form PCT/IB/301).

Where a translation of the international application must be furnished to an elected Office, that translation must contain a translation of any annexes to the international preliminary examination report. It is the applicant's responsibility to prepare and furnish such translation directly to each elected Office concerned.

For further details on the applicable time limits and requirements of the elected Offices, see Volume II of the PCT Applicant's Guide.

Name and mailing address of the IPEA/US	Authorized officer
Commissioner of Patents and Trademarks Box PCT Washington, D.C. 20231	Golam M Shameem
Facsimile No. (703)305-3230	Telephone No. (703) 308-1235

Form PCT/IPEA/416 (July 1992)

PATENT COOPERATION TREATY

414

PCT

INTERNATIONAL PRELIMINARY EXAMINATION REPORT

(PCT Article 36 and Rule 70)

Applicant's or agent's file reference LD0192	FOR FURTHER ACTION	See Notification of Transmittal of International Preliminary Examination Report (Form PCT/IPEA/416)
International application No. PCT/US01/19655	International filing date *(day/month/year)* 20 June 2001 (20.06.2001)	Priority date *(day/month/year)* 19 September 2000 (19.09.2000)
International Patent Classification (IPC) or national classification and IPC IPC(7): C07D 209/56; A61K 31/40 and US Cl.: 514/411; 548/435		
Applicant BRISTOL-MYERS SQUIBB COMPANY		

1. This international preliminary examination report has been prepared by this International Preliminary Examining Authority and is transmitted to the applicant according to Article 36.

2. This REPORT consists of a total of 9 sheets, including this cover sheet.

   ☐ This report is also accompanied by ANNEXES, i.e., sheets of the description, claims and/or drawings which have been amended and are the basis for this report and/or sheets containing rectifications made before this Authority (see Rule 70.16 and Section 607 of the Administrative Instructions under the PCT).

   These annexes consist of a total of 2 sheets.

3. This report contains indications relating to the following items:

   - I ☒ Basis of the report
   - II ☐ Priority
   - III ☐ Non-establishment of report with regard to novelty, inventive step and industrial applicability
   - IV ☐ Lack of unity of invention
   - V ☒ Reasoned statement under Article 35(2) with regard to novelty, inventive step or industrial applicability; citations and explanations supporting such statement
   - VI ☐ Certain documents cited
   - VII ☐ Certain defects in the international application
   - VIII ☐ Certain observations on the international application

Date of submission of the demand	Date of completion of this report
03 April 2002 (03.04.2002)	18 December 2002 (18.12.2002)
Name and mailing address of the IPEA/US Commissioner of Patents and Trademarks Box PCT Washington, D.C. 20231 Facsimile No. (703)305-3230	Authorized officer Golam M Shameem Telephone No. (703) 308-1235

Form PCT/IPEA/409 (cover sheet)(July 1998)

415

INTERNATIONAL PRELIMINARY EXAMINATION REPORT

International application No.
PCT/US01/19655

I. Basis of the report

1. With regard to the elements of the international application:*

☒ the international application as originally filed.

☒ the description:
pages 1-342 as originally filed
pages NONE, filed with the demand
pages NONE, filed with the letter of _____.

☒ the claims:
pages 343-405, as originally filed
pages NONE, as amended (together with any statement) under Article 19
pages NONE, filed with the demand
pages NONE, filed with the letter of _____.

☒ the drawings:
pages NONE, as originally filed
pages NONE, filed with the demand
pages NONE, filed with the letter of _____.

☐ the sequence listing part of the description:
pages NONE, as originally filed
pages NONE, filed with the demand
pages NONE, filed with the letter of _____.

2. With regard to the language, all the elements marked above were available or furnished to this Authority in the language in which the international application was filed, unless otherwise indicated under this item.
These elements were available or furnished to this Authority in the following language _____ which is:

☐ the language of a translation furnished for the purposes of international search (under Rule23.1(b)).

☐ the language of publication of the international application (under Rule 48.3(b)).

☐ the language of the translation furnished for the purposes of international preliminary examination(under Rules 55.2 and/or 55.3).

3. With regard to any nucleotide and/or amino acid sequence disclosed in the international application, the international preliminary examination was carried out on the basis of the sequence listing:

☐ contained in the international application in printed form.

☐ filed together with the international application in computer readable form.

☐ furnished subsequently to this Authority in written form.

☐ furnished subsequently to this Authority in computer readable form.

☐ The statement that the subsequently furnished written sequence listing does not go beyond the disclosure in the international application as filed has been furnished.

☐ The statement that the information recorded in computer readable form is identical to the written sequence listing has been furnished.

4. ☒ The amendments have resulted in the cancellation of:

☒ the description, pages None

☒ the claims, Nos. None

☒ the drawings, sheets/fig None

5. ☐ This report has been established as if (some of) the amendments had not been made, since they have been considered to go beyond the disclosure as filed, as indicated in the Supplemental Box (Rule 70.2(c)).**

** Replacement sheets which have been furnished to the receiving Office in response to an invitation under Article 14 are referred to in this report as "originally filed" and are not annexed to this report since they do not contain amendments (Rules 70.16 and 70.17).*

*** Any replacement sheet containing such amendments must be referred to under item 1 and annexed to this report.*

INTERNATIONAL PRELIMINARY EXAMINATION REPORT

International application No.
PCT/US01/19655

V. Reasoned statement under Rule 66.2(a)(ii) with regard to novelty, inventive step or industrial applicability; citations and explanations supporting such statement

1. STATEMENT

Novelty (N)	Claims 1-18	YES
	Claims NONE	NO
Inventive Step (IS)	Claims 1-18	YES
	Claims NONE	NO
Industrial Applicability (IA)	Claims 1-18	YES
	Claims NONE	NO

2. CITATIONS AND EXPLANATIONS

The invention relates to fused cyclic compounds that are useful in the treatment of nuclear hormon receptor-asociated conditions such as cancer, immune disorders, and to pharmaceutical compositions containing such compounds. Considering the prior art cited (WO 01/19831) in the International search report claims 1-18 of this invention are novel. The closest prior art of record is Andersen et al (WO 01/19831). Claims 1-18 meet the criteria set out in PCT rticle 33(20-(4). because the prior art do not teach or fairly suggest the fused cyclic compounds described in this application.

NEW CITATIONS

PATENT COOPERATION TREATY

417

From the INTERNATIONAL SEARCHING AUTHORITY

RECEIVED
BMS PATENT LAW
FEB 26 2002

PCT

NOTIFICATION OF TRANSMITTAL OF THE INTERNATIONAL SEARCH REPORT OR THE DECLARATION

(PCT Rule 44.1)

To:
BRISTOL-MYERS SQUIBB
Attn. Babajko, Suzanne
P.O. Box 4000
Lawrenceville-Princeton Rd.
PRINCETON, NJ 08543-4000
UNITED STATES OF AMERICA

SB

Docketed Item US-IOS-L00192 5/22/02
Due Date
Attorney US-IOS-L00192a - 5/22/02

	Date of mailing (day/month/year) 22/02/2002
Applicant's or agent's file reference LD0192	FOR FURTHER ACTION See paragraphs 1 and 4 below
International application No. PCT/US 01/19655	International filing date (day/month/year) 20/06/2001
Applicant BRISTOL-MYERS SQUIBB COMPANY	

1. [X] The applicant is hereby notified that the International Search Report has been established and is transmitted herewith.

   Filing of amendments and statement under Article 19:
   The applicant is entitled, if he so wishes, to amend the claims of the International Application (see Rule 46):

   When? The time limit for filing such amendments is normally 2 months from the date of transmittal of the International Search Report; however, for more details, see the notes on the accompanying sheet.

   Where? Directly to the International Bureau of WIPO
   34, chemin des Colombettes
   1211 Geneva 20, Switzerland
   Fascimile No.: (41-22) 740.14.35

   For more detailed instructions, see the notes on the accompanying sheet.

2. [ ] The applicant is hereby notified that no International Search Report will be established and that the declaration under Article 17(2)(a) to that effect is transmitted herewith.

3. [ ] With regard to the protest against payment of (an) additional fee(s) under Rule 40.2, the applicant is notified that:

   [ ] the protest together with the decision thereon has been transmitted to the International Bureau together with the applicant's request to forward the texts of both the protest and the decision thereon to the designated Offices.

   [ ] no decision has been made yet on the protest; the applicant will be notified as soon as a decision is made.

4. **Further action(s):** The applicant is reminded of the following:

   Shortly after 18 months from the priority date, the international application will be published by the International Bureau. If the applicant wishes to avoid or postpone publication, a notice of withdrawal of the international application, or of the priority claim, must reach the International Bureau as provided in Rules 90*bis*.1 and 90*bis*.3, respectively, before the completion of the technical preparations for international publication.

   Within 19 months from the priority date, a demand for international preliminary examination must be filed if the applicant wishes to postpone the entry into the national phase until 30 months from the priority date (in some Offices even later).

   Within 20 months from the priority date, the applicant must perform the prescribed acts for entry into the national phase before all designated Offices which have not been elected in the demand or in a later election within 19 months from the priority date or could not be elected because they are not bound by Chapter II.

Name and mailing address of the International Searching Authority	Authorized officer
European Patent Office, P.B. 5818 Patentlaan 2 NL-2280 HV Rijswijk Tel. (+31-70) 340-2040, Tx. 31 651 epo nl, Fax: (+31-70) 340-3016	Véronique Baillou

Form PCT/ISA/220 (July 1998)

NOTES TO FORM PCT/ISA/220

418

These Notes are intended to give the basic instructions concerning the filing of amendments under Article 19. The Notes are based on the requirements of the Patent Cooperation Treaty, the Regulations and the Administrative Instructions under that Treaty. In case of discrepancy between these Notes and those requirements, the latter are applicable. For more detailed information, see also the PCT Applicant's Guide, a publication of WIPO.

In these Notes, "Article", "Rule", and "Section" refer to the provisions of the PCT, the PCT Regulations and the PCT Administrative Instructions respectively.

INSTRUCTIONS CONCERNING AMENDMENTS UNDER ARTICLE 19

The applicant has, after having received the international search report, one opportunity to amend the claims of the international application. It should however be emphasized that, since all parts of the international application (claims, description and drawings) may be amended during the international preliminary examination procedure, there is usually no need to file amendments of the claims under Article 19 except where, e.g. the applicant wants the latter to be published for the purposes of provisional protection or has another reason for amending the claims before international publication. Furthermore, it should be emphasized that provisional protection is available in some States only.

What parts of the international application may be amended?

Under Article 19, only the claims may be amended.

During the international phase, the claims may also be amended (or further amended) under Article 34 before the International Preliminary Examining Authority. The description and drawings may only be amended under Article 34 before the International Examining Authority.

Upon entry into the national phase, all parts of the international application may be amended under Article 28 or, where applicable, Article 41.

When? Within 2 months from the date of transmittal of the international search report or 16 months from the priority date, whichever time limit expires later. It should be noted, however, that the amendments will be considered as having been received on time if they are received by the International Bureau after the expiration of the applicable time limit but before the completion of the technical preparations for international publication (Rule 46.1).

Where not to file the amendments?

The amendments may only be filed with the International Bureau and not with the receiving Office or the International Searching Authority (Rule 46.2).

Where a demand for international preliminary examination has been/is filed, see below.

How? Either by cancelling one or more entire claims, by adding one or more new claims or by amending the text of one or more of the claims as filed.

A replacement sheet must be submitted for each sheet of the claims which, on account of an amendment or amendments, differs from the sheet originally filed.

All the claims appearing on a replacement sheet must be numbered in Arabic numerals. Where a claim is cancelled, no renumbering of the other claims is required. In all cases where claims are renumbered, they must be renumbered consecutively (Administrative Instructions, Section 205(b)).

The amendments must be made in the language in which the international application is to be published.

What documents must/may accompany the amendments?

Letter (Section 205(b)):

The amendments must be submitted with a letter.

The letter will not be published with the international application and the amended claims. It should not be confused with the "Statement under Article 19(1)" (see below, under "Statement under Article 19(1)").

The letter must be in English or French, at the choice of the applicant. However, if the language of the international application is English, the letter must be in English; if the language of the international application is French, the letter must be in French.

BNSDOCID: <WSISA220NOBNP4_1_>

419

The letter must indicate the differences between the claims as filed and the claims as amended. It must, in particular, indicate, in connection with each claim appearing in the international application (it being understood that identical indications concerning several claims may be grouped), whether

(i) the claim is unchanged;

(ii) the claim is cancelled;

(iii) the claim is new;

(iv) the claim replaces one or more claims as filed;

(v) the claim is the result of the division of a claim as filed.

The following examples illustrate the manner in which amendments must be explained in the accompanying letter:

1. [Where originally there were 48 claims and after amendment of some claims there are 51]:
"Claims 1 to 29, 31, 32, 34, 35, 37 to 48 replaced by amended claims bearing the same numbers; claims 30, 33 and 36 unchanged; new claims 49 to 51 added."

2. [Where originally there were 15 claims and after amendment of all claims there are 11]:
"Claims 1 to 15 replaced by amended claims 1 to 11."

3. [Where originally there were 14 claims and the amendments consist in cancelling some claims and in adding new claims]:
"Claims 1 to 6 and 14 unchanged; claims 7 to 13 cancelled; new claims 15, 16 and 17 added." or
"Claims 7 to 13 cancelled; new claims 15, 16 and 17 added; all other claims unchanged."

4. [Where various kinds of amendments are made]:
"Claims 1-10 unchanged; claims 11 to 13, 18 and 19 cancelled; claims 14, 15 and 16 replaced by amended claim 14; claim 17 subdivided into amended claims 15, 16 and 17; new claims 20 and 21 added."

"Statement under article 19(1)" (Rule 46.4)

The amendments may be accompanied by a statement explaining the amendments and indicating any impact that such amendments might have on the description and the drawings (which cannot be amended under Article 19(1)).

The statement will be published with the international application and the amended claims.

It must be in the language in which the international application is to be published.

It must be brief, not exceeding 500 words if in English or if translated into English.

It should not be confused with and does not replace the letter indicating the differences between the claims as filed and as amended. It must be filed on a separate sheet and must be identified as such by a heading, preferably by using the words "Statement under Article 19(1)."

It may not contain any disparaging comments on the international search report or the relevance of citations contained in that report. Reference to citations, relevant to a given claim, contained in the international search report may be made only in connection with an amendment of that claim.

Consequence if a demand for international preliminary examination has already been filed

If, at the time of filing any amendments under Article 19, a demand for international preliminary examination has already been submitted, the applicant must preferably, at the same time of filing the amendments with the International Bureau, also file a copy of such amendments with the International Preliminary Examining Authority (see Rule 62.2(a), first sentence).

Consequence with regard to translation of the international application for entry into the national phase

The applicant's attention is drawn to the fact that, where upon entry into the national phase, a translation of the claims as amended under Article 19 may have to be furnished to the designated/elected Offices, instead of, or in addition to, the translation of the claims as filed.

For further details on the requirements of each designated/elected Office, see Volume II of the PCT Applicant's Guide.

PATENT COOPERATION TREATY

PCT

420

INTERNATIONAL SEARCH REPORT

(PCT Article 18 and Rules 43 and 44)

Applicant's or agent's file reference	FOR FURTHER ACTION	see Notification of Transmittal of International Search Report (Form PCT/ISA/220) as well as, where applicable, item 5 below.
LD0192		
International application No.	International filing date *(day/month/year)*	(Earliest) Priority Date *(day/month/year)*
PCT/US 01/ 19655	20/06/2001	19/09/2000
Applicant		
BRISTOL-MYERS SQUIBB COMPANY		

This International Search Report has been prepared by this International Searching Authority and is transmitted to the applicant according to Article 18. A copy is being transmitted to the International Bureau.

This International Search Report consists of a total of 6 sheets.

[X] It is also accompanied by a copy of each prior art document cited in this report.

1. **Basis of the report**

   a. With regard to the language, the international search was carried out on the basis of the international application in the language in which it was filed, unless otherwise indicated under this item.

   [ ] the international search was carried out on the basis of a translation of the international application furnished to this Authority (Rule 23.1(b)).

   b. With regard to any nucleotide and/or amino acid sequence disclosed in the international application, the international search was carried out on the basis of the sequence listing :

   [ ] contained in the international application in written form.

   [ ] filed together with the international application in computer readable form.

   [ ] furnished subsequently to this Authority in written form.

   [ ] furnished subsequently to this Authority in computer readable form.

   [ ] the statement that the subsequently furnished written sequence listing does not go beyond the disclosure in the international application as filed has been furnished.

   [ ] the statement that the information recorded in computer readable form is identical to the written sequence listing has been furnished

2. [X] Certain claims were found unsearchable (See Box I).

3. [ ] Unity of invention is lacking (see Box II).

4. With regard to the title,

   [X] the text is approved as submitted by the applicant.

   [ ] the text has been established by this Authority to read as follows:

5. With regard to the abstract,

   [X] the text is approved as submitted by the applicant.

   [ ] the text has been established, according to Rule 38.2(b), by this Authority as it appears in Box III. The applicant may, within one month from the date of mailing of this international search report, submit comments to this Authority.

6. The figure of the drawings to be published with the abstract is Figure No. _____

   [ ] as suggested by the applicant.

   [ ] because the applicant failed to suggest a figure.

   [ ] because this figure better characterizes the invention.

   [X] None of the figures.

INTERNATIONAL SEARCH REPORT

International Application No
PCT/US 01/19655

A. CLASSIFICATION OF SUBJECT MATTER
IPC 7 C07D491/08 C07D495/08 C07D471/08 A61K31/40 A61K31/439 A61P35/00

According to International Patent Classification (IPC) or to both national classification and IPC

B. FIELDS SEARCHED

Minimum documentation searched (classification system followed by classification symbols)
IPC 7 C07D

Documentation searched other than minimum documentation to the extent that such documents are included in the fields searched

Electronic data base consulted during the international search (name of data base and, where practical, search terms used)
EPO-Internal, CHEM ABS Data

C. DOCUMENTS CONSIDERED TO BE RELEVANT

Category *	Citation of document, with indication, where appropriate, of the relevant passages	Relevant to claim No.
E	WO 02 00617 A (GOTTARDIS MARCO M ;SQUIBB BRISTOL MYERS CO (US); SACK JOHN S (US);) 3 January 2002 (2002-01-03) * see p. 334 -83, examples * the whole document	1-18
P,X	WO 01 19831 A (NOVO NORDISK AS ;ONTOGEN CORP (US)) 22 March 2001 (2001-03-22) * see p.100, ex. 42 * the whole document	1-18

-/--

[X] Further documents are listed in the continuation of box C.

[X] Patent family members are listed in annex.

* Special categories of cited documents :

"A" document defining the general state of the art which is not considered to be of particular relevance

"E" earlier document but published on or after the international filing date

"L" document which may throw doubts on priority claim(s) or which is cited to establish the publication date of another citation or other special reason (as specified)

"O" document referring to an oral disclosure, use, exhibition or other means

"P" document published prior to the international filing date but later than the priority date claimed

"T" later document published after the international filing date or priority date and not in conflict with the application but cited to understand the principle or theory underlying the invention

"X" document of particular relevance; the claimed invention cannot be considered novel or cannot be considered to involve an inventive step when the document is taken alone

"Y" document of particular relevance; the claimed invention cannot be considered to involve an inventive step when the document is combined with one or more other such documents, such combination being obvious to a person skilled in the art.

"&" document member of the same patent family

Date of the actual completion of the international search	Date of mailing of the international search report
30 January 2002	22/02/2002

Name and mailing address of the ISA	Authorized officer
European Patent Office, P.B. 5818 Patentlaan 2 NL - 2280 HV Rijswijk Tel. (+31-70) 340-2040, Tx. 31 651 epo nl, Fax: (+31-70) 340-3016	Stellmach, J

Form PCT/ISA/210 (second sheet) (July 1992)

C.(Continuation) DOCUMENTS CONSIDERED TO BE RELEVANT

Category *	Citation of document, with indication, where appropriate, of the relevant passages	Relevant to claim No.
Y	XU,B.: "Pharmacology of some natural products of China" TRENDS IN PHARMACOLOGICAL SCIENCE, vol. 2, October 1981 (1981-10), pages 271-2272, XP002188686 AMSTERDAM * see p.272, fig .5 * the whole document	1-18
Y	WALTER,W.G.: "Antitumor Imide Derivatives of 7-Oxabicyclo'2.2.1!heptane-2,3-dimethyl-2,3-dicarboxylic Acid " J.PHARM.SCI., vol. 78, no. 1, January 1989 (1989-01), pages 66-67, XP002188687 * see p.66, formula 2-4 * the whole document	1-18
Y	EVANS R M: "THE STERIOD AND THYRIOD HORMONE RECEPTOR SUPERFAMILY" SCIENCE, AMERICAN ASSOCIATION FOR THE ADVANCEMENT OF SCIENCE, US, vol. 240, no. 4854, 13 May 1988 (1988-05-13), pages 889-895, XP000574469 ISSN: 0036-8075 cited in the application * see page 889, abstract * the whole document	1-18
Y	DENISON,M.S. ET AL.: "Xenobiotic-inducible Transcription of Cytochrome P450 Genes" J.BIOL.CHEM., vol. 270, no. 31, 4 August 1995 (1995-08-04), pages 18175-18178, XP002188273 ROCKVILLE PIKE * see p.18177,right col. * the whole document	1-18
Y	WALLER,C.W. ET AL.: "Three-Dimensional Quantitative Structure-Activity Relationships for androgen Receptro Ligands" TOXICOL.APPL.PHARMACOL., vol. 137, no. 2, April 1996 (1996-04), pages 219-227, XP002188688 NEW YORK * see p.221, Procymidone * the whole document	1-18

-/—

C.(Continuation) DOCUMENTS CONSIDERED TO BE RELEVANT

Category *	Citation of document, with indication, where appropriate, of the relevant passages	Relevant to claim No.
Y	WO 99 27365 A (TULARIK INC) 3 June 1999 (1999-06-03) * see page 3, line 5-18 * the whole document	1-18
Y	WO 98 49555 A (SALK INST FOR BIOLOGICAL STUDI) 5 November 1998 (1998-11-05) * see p.1, line 2 - 23, p.4, line 17 - 28 * the whole document	1-18
A	EP 0 678 507 A (SQUIBB BRISTOL MYERS CO) 25 October 1995 (1995-10-25) * see ex. 2 * the whole document	1-18
A	WO 96 19458 A (LIGAND PHARM INC) 27 June 1996 (1996-06-27) cited in the application the whole document	1-18
A	WO 97 49709 A (EDWARDS JAMES P ;HIGUCHI ROBERT (US); JONES TODD (US); LIGAND PHAR) 31 December 1997 (1997-12-31) cited in the application the whole document	1-18

FURTHER INFORMATION CONTINUED FROM PCT/ISA/ 210

Continuation of Box I.2

Present claims 1-3 and 18 relate to an extremely large number of possible compounds. In fact, the claims contain so many options, variables, possible permutations and provisos at the end of claim 1 that a lack of clarity (and/or conciseness) within the meaning of Article 6 PCT arises to such an extent as to render a meaningful search of the claims impossible. Consequently, the search has been carried out for those parts of the application which do appear to be clear and concise), namely the families of compounds disclosed on page 56 as espeeially preferred subgenus..

Morevover, present claims 1- 3 and 18 relate to an extremely large number of possible families of compounds. Support within the meaning of Article 6 PCT and/or disclosure within the meaning of Article 5 PCT is to be found, however, for only a very small proportion of the compounds claimed. In the present case, the claims so lack support, and the application so lacks disclosure, that a meaningful search over the whole of the claimed scope is impossible. Consequently, the search has been carried out for those parts of the claims which appear to be supported and disclosed, namely those parts relating to the families of compounds disclosed on page 56 as especially preferred subgenus.

****

The applicant's attention is drawn to the fact that claims, or parts of claims, relating to inventions in respect of which no international search report has been established need not be the subject of an international preliminary examination (Rule 66.1(e) PCT). The applicant is advised that the EPO policy when acting as an International Preliminary Examining Authority is normally not to carry out a preliminary examination on matter which has not been searched. This is the case irrespective of whether or not the claims are amended following receipt of the search report or during any Chapter II procedure.

INTERNATIONAL SEARCH REPORT

International application No.
PCT/US 01/19655

Box I Observations where certain claims were found unsearchable (Continuation of item 1 of first sheet)

This International Search Report has not been established in respect of certain claims under Article 17(2)(a) for the following reasons: 425

1. [X] Claims Nos.:
because they relate to subject matter not required to be searched by this Authority, namely:

Although claims 7-15 are directed to a method of treatment of the human/animal body, the search has been carried out and based on the alleged effects of the compound/composition.

2. [X] Claims Nos.: -
because they relate to parts of the International Application that do not comply with the prescribed requirements to such an extent that no meaningful International Search can be carried out, specifically:

see FURTHER INFORMATION sheet PCT/ISA/210

3. [ ] Claims Nos.:
because they are dependent claims and are not drafted in accordance with the second and third sentences of Rule 6.4(a).

Box II Observations where unity of invention is lacking (Continuation of item 2 of first sheet)

This International Searching Authority found multiple inventions in this international application, as follows:

1. [ ] As all required additional search fees were timely paid by the applicant, this International Search Report covers all searchable claims.

2. [ ] As all searchable claims could be searched without effort justifying an additional fee, this Authority did not invite payment of any additional fee.

3. [ ] As only some of the required additional search fees were timely paid by the applicant, this International Search Report covers only those claims for which fees were paid, specifically claims Nos.:

4. [ ] No required additional search fees were timely paid by the applicant. Consequently, this International Search Report is restricted to the invention first mentioned in the claims; it is covered by claims Nos.:

Remark on Protest

[ ] The additional search fees were accompanied by the applicant's protest.

[ ] No protest accompanied the payment of additional search fees.

I RNATIONAL SEARCH REPORT

Information on patent family members

International Application No PCT/US 01/19655

Patent document cited in search report		Publication date	Patent family member(s)		Publication date
WO 0200617	A	03-01-2002	WO	0200716 A2	03-01-2002
			WO	0200653 A2	03-01-2002
			WO	0200617 A2	03-01-2002
WO 0119831	A	22-03-2001	AU	6985300 A	17-04-2001
			WO	0119831 A1	22-03-2001
WO 9927365	A	03-06-1999	AU	734875 B2	21-06-2001
			AU	1598999 A	15-06-1999
			EP	1032834 A1	06-09-2000
			JP	2001524672 T	04-12-2001
			WO	9927365 A1	03-06-1999
WO 9849555	A	05-11-1998	AU	6945898 A	24-11-1998
			EP	0979407 A1	16-02-2000
			WO	9849555 A1	05-11-1998
EP 0678507	A	25-10-1995	US	5539126 A	23-07-1996
			AU	1656195 A	02-11-1995
			CA	2146038 A1	21-10-1995
			EP	0678507 A1	25-10-1995
			JP	7300457 A	14-11-1995
WO 9619458	A	27-06-1996	US	5688810 A	18-11-1997
			US	5688808 A	18-11-1997
			US	5693647 A	02-12-1997
			US	5696127 A	09-12-1997
			US	5693646 A	02-12-1997
			US	5696130 A	09-12-1997
			US	5696133 A	09-12-1997
			AU	717251 B2	23-03-2000
			AU	4597796 A	10-07-1996
			BR	9510486 A	02-06-1998
			CA	2208347 A1	27-06-1996
			CN	1175247 A	04-03-1998
			CZ	9701761 A3	16-09-1998
			EP	1043325 A1	11-10-2000
			EP	1043326 A1	11-10-2000
			EP	1041071 A1	04-10-2000
			EP	1041066 A1	04-10-2000
			EP	1043315 A1	11-10-2000
			EP	0800519 A1	15-10-1997
			HU	78117 A2	29-11-1999
			JP	10510840 T	20-10-1998
			NO	972591 A	14-08-1997
			NO	20003550 A	14-08-1997
			NO	20003551 A	14-08-1997
			NO	20003552 A	14-08-1997
			WO	9619458 A2	27-06-1996
			US	6093821 A	25-07-2000
			US	5994544 A	30-11-1999
			US	6121450 A	19-09-2000
WO 9749709	A	31-12-1997	AT	209207 T	15-12-2001
			AU	728178 B2	04-01-2001
			AU	3508497 A	14-01-1998
			BR	9710988 A	15-01-2002
			CA	2259031 A1	31-12-1997

The demand must be filed directly with the competent International Preliminary Examining Authority or, if two or more Authorities are competent, with the one chosen by the applicant. The full name or two-letter code of that Authority may be indicated by the applicant on the line below:

IPEA/ US

PCT

CHAPTER II

427

DEMAND

under Article 31 of the Patent Cooperation Treaty:
The undersigned requests that the international application specified below be the subject of international preliminary examination according to the Patent Cooperation Treaty and hereby elects all eligible States (except where otherwise indicated).

For International Preliminary Examining Authority use only	
Identification of IPEA	Date of receipt of DEMAND

Box No. I IDENTIFICATION OF THE INTERNATIONAL APPLICATION		Applicant's or agent's file reference: LD0192
International application No.: PCT/US01/19655	International filing date *(day/month/year)*: (20.06.01) 20.JUNE.2001	(Earliest) Priority date *(day/month/year)*: (19.09.00) 19.September.00

Title of invention:
FUSED HETEROCYCLIC SUCCINIMIDE COMPOUNDS AND ANALOGS THEREOF, MODULATORS OF NUCLEAR HORMONE RECEPTOR FUNCTION

Box No. II APPLICANT(S)

Name and address: *(Family name followed by given name; for a legal entity, full official designation. The address must include postal code and name of country.)*	Telephone No. / Facsimile No. / Teleprinter No. / Applicant's registration No. with the Office
Bristol-Myers Squibb Company P.O. Box 4000 Princeton, NJ 08543-4000 United States of America	609-252-4009 609-252-4526

State *(that is, country)* of nationality:	State *(that is, country)* of residence:
United States of America	United States of America

Name and address: *(Family name followed by given name; for a legal entity, full official designation. The address must include postal code and name of country.)*
SALVATI, Mark E.
9 Tracey Drive
Lawrenceville, NJ 08648
UNITED STATES OF AMERICA

State *(that is, country)* of nationality:	State *(that is, country)* of residence:
US	US

Name and address: *(Family name followed by given name; for a legal entity, full official designation. The address must include postal code and name of country.)*
BALOG, James Aaron
2 Sassafras Court
Scotch Plains, NJ 07076
UNITED STATES OF AMERICA

State *(that is, country)* of nationality:	State *(that is, country)* of residence:
US	US

☒ Further applicants are indicated on a continuation sheet.

International application No.
PCT/US01/19655

Continuation of Box No. II APPLICANT(S)

If none of the following sub-boxes is used, this sheet should not be included in the demand.

428

Name and address: *(Family name followed by given name; for a legal entity, full official designation. The address must include postal code and name of country.)*
PICKERING, Dacia A.
507 Drexel Avenue
Lawrenceville, NJ 08648
UNITED STATES OF AMERICA

State *(that is, country)* of nationality:	State *(that is, country)* of residence:
British Virgin Islands	US

Name and address: *(Family name followed by given name; for a legal entity, full official designation. The address must include postal code and name of country.)*
GIESE, Soren
1113 Polo Run Drive
Yardley, PA 19067
UNITED STATES OF AMERICA

State *(that is, country)* of nationality:	State *(that is, country)* of residence:
Germany	US

Name and address: *(Family name followed by given name; for a legal entity, full official designation. The address must include postal code and name of country.)*
FURA, Aberra
15 Cresthill Road
Lawrenceville, NJ 08648

State *(that is, country)* of nationality:	State *(that is, country)* of residence:
ETHIOPIA	US

Name and address: *(Family name followed by given name; for a legal entity, full official designation. The address must include postal code and name of country.)*
LI, Wenying
6221 Town Place
Middletown, CT 06457
UNITED STATES OF AMERICA

State *(that is, country)* of nationality:	State *(that is, country)* of residence:
P.R. CHINA	US

☒ Further applicants are indicated on another continuation sheet.

International application No.
PCT/US01/19655

Continuation of Box No. II APPLICANT(S)

If none of the following sub-boxes is used, this sheet should not be included in the demand.

Name and address: *(Family name followed by given name; for a legal entity, full official designation. The address must include postal code and name of country.)*

PATEL, Ramesh N.
572 Cabot Hill Road
Bridgewater, NJ 08807
UNITED STATES OF AMERICA

State *(that is, country)* of nationality:	State *(that is, country)* of residence:
US	US

Name and address: *(Family name followed by given name; for a legal entity, full official designation. The address must include postal code and name of country.)*

HANSON, Ronald L.
54 Whitewood Drive
Morris Plains, NJ 07950
UNITED STATES OF AMERICA

State *(that is, country)* of nationality:	State *(that is, country)* of residence:
US	US

Name and address: *(Family name followed by given name; for a legal entity, full official designation. The address must include postal code and name of country.)*

State *(that is, country)* of nationality:	State *(that is, country)* of residence:

Name and address: *(Family name followed by given name; for a legal entity, full official designation. The address must include postal code and name of country.)*

State *(that is, country)* of nationality:	State *(that is, country)* of residence:

☐ Further applicants are indicated on another continuation sheet.

430

Sheet No. 4

International application No.
PCT/US01/19655

Box No. III AGENT OR COMMON REPRESENTATIVE; OR ADDRESS FOR CORRESPONDENCE

The following person is ☒ agent ☐ common representative

and ☒ has been appointed earlier and represents the applicant(s) also for international preliminary examination.

☐ is hereby appointed and any earlier appointment of (an) agent(s)/common representative is hereby revoked.

☐ is hereby appointed, specifically for the procedure before the International Preliminary Examining Authority, in addition to the agent(s)/common representative appointed earlier.

Name and address: *(Family name followed by given name; for a legal entity, full official designation. The address must include postal code and name of country.)*

BABAJKO, Suzanne E.
Bristol-Myers Squibb Company
P.O. Box 4000
Princeton, NJ 08543-4000
United States of America

Telephone No.
609-252-4009

Facsimile No.
609-252-4526

Teleprinter No.

Agent's registration No. with the Office
32,880

☐ Address for correspondence: Mark this check-box where no agent or common representative is/has been appointed and the space above is used instead to indicate a special address to which correspondence should be sent.

Box No. IV BASIS FOR INTERNATIONAL PRELIMINARY EXAMINATION

Statement concerning amendments:*

1. The applicant wishes the international preliminary examination to start on the basis of:

☒ the international application as originally filed

the description ☒ as originally filed
☐ as amended under Article 34

the claims ☒ as originally filed
☐ as amended under Article 19 (together with any accompanying statement)
☐ as amended under Article 34

the drawings ☒ as originally filed
☐ as amended under Article 34

2. ☐ The applicant wishes any amendment to the claims under Article 19 to be considered as reversed.

3. ☐ The applicant wishes the start of the international preliminary examination to be postponed until the expiration of 20 months from the priority date unless the International Preliminary Examining Authority receives a copy of any amendments made under Article 19 or a notice from the applicant that he does not wish to make such amendments (Rule 69.1(d)). *(This check-box may be marked only where the time limit under Article 19 has not yet expired.)*

* Where no check-box is marked, international preliminary examination will start on the basis of the international application as originally filed or, where a copy of amendments to the claims under Article 19 and/or amendments of the international application under Article 34 are received by the International Preliminary Examining Authority before it has begun to draw up a written opinion or the international preliminary examination report, as so amended.

Language for the purposes of international preliminary examination: English

☒ which is the language in which the international application was filed.

☐ which is the language of a translation furnished for the purposes of international search.

☐ which is the language of publication of the international application.

☐ which is the language of the translation (to be) furnished for the purposes of international preliminary examination.

Box No. V ELECTION OF STATES

The applicant hereby elects all eligible States *(that is, all States which have been designated and which are bound by Chapter II of the PCT)*

excluding the following States which the applicant wishes not to elect:

431

Sheet No. .5.

International application No.
PCT/US01/19655

Box No. VI CHECK LIST

The demand is accompanied by the following elements, in the language referred to in Box No. IV, for the purposes of international preliminary examination:			For International Preliminary Examining Authority use only: received	not received
1. translation of international application	:	0 sheets	☐	☐
2. amendments under Article 34	:	0 sheets	☐	☐
3. copy (or, where required, translation) of amendments under Article 19	:	0 sheets	☐	☐
4. copy (or, where required, translation) of statement under Article 19	:	0 sheets	☐	☐
5. letter	:	0 sheets	☐	☐
6. other *(specify)*	:	0 sheets	☐	☐

The demand is also accompanied by the item(s) marked below:

1. ☒ fee calculation sheet
2. ☐ original separate power of attorney
3. ☐ original general power of attorney
4. ☐ copy of general power of attorney; reference number, if any:
5. ☐ statement explaining lack of signature
6. ☐ sequence listing in computer readable form
7. ☐ other *(Certification for POA)*:

Box No. VII SIGNATURE OF APPLICANT, AGENT OR COMMON REPRESENTATIVE

Next to each signature, indicate the name of the person signing and the capacity in which the person signs (if such capacity is not obvious from reading the demand).

Suzanne E. Babajko, Agent Date: April 3, 2002

Suzanne E. Babajko

For International Preliminary Examining Authority use only

1. Date of actual receipt of DEMAND:
2. Adjusted date of receipt of demand due to CORRECTIONS under Rule 80.1(b):
3. ☐ The date of receipt of the demand is AFTER the expiration of 19 months from the priority date and item 4 or 5, below, does not apply. ☐ The applicant has been informed accordingly.
4. ☐ The date of receipt of the demand is WITHIN the period of 19 months from the priority date as extended by virtue of Rule 80.5.
5. ☐ Although the date of receipt of the demand is after the expiration of 19 months from the priority date, the delay in arrival is EXCUSED pursuant to Rule 82.

For International Bureau use only

Demand received from IPEA on:

NOTES TO THE DEMAND FORM (PCT/IPEA/401)

432

These Notes are intended to facilitate the filling in of the demand form and to give some information concerning international preliminary examination under Chapter II of the Patent Cooperation Treaty (PCT). For more detailed information, see the *PCT Applicant's Guide*, a WIPO publication, which is available, together with other PCT related documents, at WIPO's Website, www.wipo.int/pct/en/index.html. The Notes are based on the requirements of the PCT, the Regulations and the Administrative Instructions under the PCT. In case of any discrepancy between these Notes and those requirements, the latter are applicable.

In the demand form and these Notes, "Article", "Rule" and "Section" refer to the provisions of the PCT, the PCT Regulations and the Administrative Instructions, respectively.

Please use a typewriter; check-boxes may be marked by hand with dark ink (Rules 11.9(a) and (b) and 11.14).

The demand form and these Notes may be downloaded from WIPO's Website at the address given above.

IMPORTANT GENERAL INFORMATION

Who May File a Demand? (Article 31(2)(a) and Rule 54): A demand (for international preliminary examination) may only be filed by an applicant who is a national or resident of a PCT Contracting State which is bound by Chapter II of the PCT; furthermore, the international application must have been filed with a receiving Office of, or acting for, a State bound by Chapter II. Where there are two or more applicants (for the same or different elected States) at least one of them must qualify.

Where Must the Demand Be Filed? (Article 31(6)(a)): The demand must be filed with a competent International Preliminary Examining Authority (IPEA). The receiving Office with which the international application was filed will, upon request, give information about the competent IPEA (or see the *PCT Applicant's Guide*, Volume I/B, Annex C). If several IPEAs are competent, the applicant has the choice and the demand must be filed with (and the fees must be paid to) the IPEA chosen by the applicant. The IPEA chosen by the applicant may be identified, preferably by an indication of the name or two-letter code of the IPEA, at the top of the first sheet of the demand in the space provided for that purpose.

When Must the Demand Be Filed? (Article 39(1)): The demand must be filed before the expiration of *19 months from the priority date* in order to extend the time limit for entering the national phase of the PCT procedure from 20 to 30 months from the priority date. *Warning*: if the demand is filed later, the national phase will not be delayed in respect of the elected States and the applicant must enter the national phase before the expiration of the time limit applicable under Article 22 (which is usually 20 months from the priority date).

In Which Language Must the Demand Be Filed? (Rule 55.1): The demand must be filed in the language in which international preliminary examination will be carried out (see Notes to Box No. IV).

What is the Language of Correspondence? (Rules 66.9 and 92.2 and Section 104): Any letter from the applicant to the IPEA must be in the same language as the international application to which it relates. However, where the international preliminary examination will be carried out on the basis of a translation (see Notes to Box No. IV), any letter from the applicant to the IPEA must be in the language of the translation. The IPEA may authorize the use of other languages for letters which do not contain or relate to amendments of the international application. Any letter from the applicant to the International Bureau must be in English or French, at the choice of the applicant. However, if the language of the international application is English, the letter must be in English; if the language of the international application is French, the letter must be in French.

Which Fees Must Be Paid and When? (Rules 57 and 58): Two fees are due in respect of the international preliminary examination: the preliminary examination fee and the handling fee. Both fees must be paid to the IPEA within one month from the date on which the demand is submitted. The Fee Calculation Sheet should be used for that purpose. For details concerning the payment of the fees, see the Notes to that Sheet.

BOX No. I

Applicant's or Agent's File Reference: A file reference may be indicated, if desired. It should not exceed 12 characters. Characters in excess of 12 may be disregarded (Section 109).

Identification of the International Application (Rule 53.6): The international application number must be indicated in Box No. I. Where the demand is filed at a time when the international application number has not yet been notified by the receiving Office, the name of that Office must be indicated instead of the international application number.

International Filing Date and (Earliest) Priority Date (Section 110): Dates must be indicated by the Arabic number of the day, the name of the month and the Arabic number of the year—in that order; after, below or above such indication, the date should be repeated in parentheses, using two-digit Arabic numerals for each of the number of the day, the number of the month and the last two digits of the year, in that order, and separated by periods, slants or hyphens, for example, "20 March 2001 (20.03.01)", "20 March 2001 (20/03/01)" or "20 March 2001 (20-03-01)". Where the international application claims the priority of several earlier applications, the filing date of the earliest application whose priority is claimed must be indicated as the priority date.

Title of the Invention: If a new title has been established by the International Searching Authority, that title must be indicated in Box No. I.

BOX No. II

Applicant(s) (Rule 53.4): All the applicants for the elected States must be indicated in the demand; an applicant named in the request (Form PCT/RO/101) for a State which is not elected need not be named in the demand. It should be noted that the persons named as "inventor only" in the request need not be named in the demand.

Make in Box No. II of the demand the required indications as appearing in Boxes Nos. II and III of the request. The Notes to the request apply *mutatis mutandis*. If there are two or more applicants for the States elected in the demand, give the required indications for each of them; if there are more than

433

three applicants, make the required indications on the "Continuation Sheet".

If different applicants are indicated in the request for different designated States, indicate in Box No. II of the demand only the applicants for the States elected in Box No. V (no indication of the States for which a person is applicant need be made, because those indications have been made in the request).

Applicant's registration number with the Office (Rule 53.4): Where the applicant is registered with the national or regional Office that is acting as International Preliminary Examining Authority, the demand may indicate the number or other indication under which the applicant is so registered.

BOX No. III

Agent or Common Representative (Rules 53.5, 90.1 and 90.2): Mark the applicable check-boxes to indicate *first* whether the person named in this Box is agent or common representative, *then* whether that person *has been appointed earlier* (i.e., during the procedure under Chapter I), or *is appointed in the demand* and any earlier appointment of another person is revoked, or *is appointed specifically for the procedure before the IPEA* (without revocation of any earlier appointment), in addition to the person(s) appointed earlier.

Where an additional person is appointed specifically for the procedure before the IPEA, all notifications issued by the IPEA will be addressed only to that additional person.

A separate power of attorney must be filed with the IPEA, the International Bureau or the receiving Office, if the person appointed at the time the demand is filed (i.e., was not appointed earlier) signs the demand on behalf of the applicant (Rule 90.4).

Agent's registration number with the Office (Rule 53.5): Where the agent is registered with the national or regional Office that is acting as International Preliminary Examining Authority, the demand may indicate the number or other indication under which the agent is so registered.

Address for Correspondence (Rule 4.4(d) and Section 108): Where an agent is appointed, any correspondence intended for the applicant will be sent to the address indicated for that agent (or for the first-mentioned agent, if more than one is appointed). Where one of two or more applicants is appointed as common representative, the address indicated for that applicant in Box No. III will be used.

Where no agent or common representative is appointed, any correspondence will be sent to the address, indicated in Box No. II, of the applicant (if only one person is named as applicant) or of the applicant who is considered to be common representative (if there are two or more persons named as applicants). However, if the applicant wishes correspondence to be sent to a different address in such a case, that address may be indicated in Box No. III instead of the designation of an agent or common representative. In this case, and only in this case, the last check-box of Box No. III must be marked (that is, the last check-box must not be marked if either of the check-boxes "agent" or "common representative" in Box No. III has been marked).

BOX No. IV

Statement Concerning Amendments (Rules 53.2(a)(v), 53.9, 62, 66.1 and 69.1): The international preliminary examination will start on the basis of the international application as filed or, if amendments have been filed, as amended. Mark the appropriate check-box(es) to enable the IPEA to determine when and on what basis it can start international preliminary examination.

Mark the corresponding check-box(es) under No. 1 where the international preliminary examination should start on the basis of the international application as originally filed or where amendments are to be taken into account, as the case may be. Where amendments are to be taken into account, the applicant must submit *with the demand* a copy of amendments to the claims under Article 19 (Rule 53.9(a)(i)) and/or the amendments of the international application under Article 34 (Rule 53.9(c)), as the case may be. If a check-box is marked but the demand is not accompanied by the documents referred to, the start of international preliminary examination will be delayed until the IPEA receives them.

Mark check-box No. 2 if amendments of the claims under Article 19 have been filed with the International Bureau during the Chapter I procedure, but the applicant does not want these amendments to be taken into account for the purpose of international preliminary examination when the latter starts (Rule 53.9(a)(ii)).

Mark check-box No. 3 where the time limit for filing amendments of the claims under Article 19 has not expired at the time the demand is filed and the applicant wants to keep the option for the filing of such amendments open; the IPEA is thus requested to postpone the start of international preliminary examination (Rules 53.9(b) and 69.1(d)). It should be noted that the examination will start in any event after the expiration of 20 months from the priority date even where the time limit for filing amendments has not yet expired or no amendments have been received by the IPEA.

If no check-box is marked, refer to the footnote at the bottom of the Box.

Language for the Purposes of International Preliminary Examination (Rule 55.2): Where neither the language in which the international application is filed nor the language in which the international application is published is accepted by the IPEA that is to carry out the international preliminary examination, the applicant must furnish with the demand a translation of the international application into a language which is both a language accepted by that Authority and a language of publication.

Where such translation has already been furnished to the International Searching Authority for the purposes of carrying out international search and the IPEA is part of the same Office or intergovernmental organization as the International Searching Authority, the applicant need not furnish another translation. In such a case the international preliminary examination is carried out on the basis of the translation furnished for the purposes of international search.

The language for the purposes of international preliminary examination should be indicated in Box No. IV, on the dotted line, and the corresponding check-box should be marked.

Language of Amendments (Rules 55.3 and 66.9): Amendments and letters relating thereto must be in the same language as that in which the international preliminary examination is carried out, as explained in the preceding paragraphs.

434

Time Limit for Furnishing Translation of the International Application (Rule 55.2): Any required translation of the international application should be furnished (by the applicant) together with the demand. If it is not so furnished, the IPEA will invite the applicant to furnish it within a time limit which shall not be less than one month from the date of the invitation. That time limit may be extended by the IPEA.

BOX No. V

Election of States (Rule 53.7): Only States which are bound by Chapter II of the PCT *and* which have been designated in the international application (that is, States whose designations have been made under Rule 4.9(a), confirmed under Rule 4.9(c) or considered as having been made under Rule 32.2(a)(i)) can be elected. They are the "eligible States".

For the convenience and protection of applicants, Box No. V contains a statement to the effect that all eligible States are elected. It is only where the applicant does not wish to elect certain eligible States that the name(s) or two-letter code(s) of those States must be indicated after the words "wishes not to elect:".

The indication in the demand of the kind of protection or treatment desired for any elected State is not required since it follows the indication made when designating that State in the international application.

BOX No. VI

Check List: It is recommended that this Box be filled in carefully in order for the IPEA to determine as soon as possible whether it is in possession of the documents on the basis of which the applicant wishes international preliminary examination to start.

Where the international application contains disclosure of one or more nucleotide and/or amino acid sequences, and a copy of the sequence listing in computer readable form complying with the standard provided for in the Administrative Instructions is required by the IPEA, the applicant may furnish the listing in computer readable form to the IPEA with the demand. If this is the case, check-box No. 5 must be marked.

BOX No. VII

Signature (Rules 53.8, 90.3(a) and 90.4(a)): The demand must be signed by the applicant or by his agent; if there are two or more applicants, the common representative may sign the demand. If the demand is not signed by (all) the persons who are applicants for the elected States (a person who is applicant only for a State which is not elected need not sign the demand), a power of attorney signed by that (all those) applicant(s) must be filed with the IPEA, with the International Bureau or with the receiving Office unless the agent has previously been appointed.

CHAPTER II

435

PCT

FEE CALCULATION SHEET

Annex to the Demand

International application No. PCT/US01/19655	For International Preliminary Examining Authority use only
Applicant's or agent's file reference LD0192	Date stamp of the IPEA

Applicant

Bristol-Myers Squibb Company

CALCULATION OF PRESCRIBED FEES

1. Preliminary examination fee	750.00	P	
2. Handling fee *(Applicants from certain States are entitled to a reduction of 75% of the handling fee. Where the applicant is (or all applicants are) so entitled, the amount to be entered at H is 25% of the handling fee.)*	146.00	H	
3. Total of prescribed fees Add the amounts entered at P and H and enter total in the TOTAL box	896.00 TOTAL		

MODE OF PAYMENT

- [X] *authorization to charge deposit account with the IPEA (see below)*
- [ ] cash
- [ ] cheque
- [ ] revenue stamps
- [ ] postal money order
- [ ] coupons
- [ ] bank draft
- [ ] other *(specify):*

AUTHORIZATION TO CHARGE (OR CREDIT) DEPOSIT ACCOUNT
(This mode of payment may not be available at all IPEAs)

IPEA/ US

- [X] Authorization to charge the total fees indicated above.
- [X] *(This check-box may be marked only if the conditions for deposit accounts of the IPEA so permit)* Authorization to charge any deficiency or credit any overpayment in the total fees indicated above.

Deposit Account No.: 19-3880

Date: April 3, 2002

Name: Suzanne E. Babalko

Signature: Suzanne E. Babalko

PCT

REQUEST

The undersigned requests that the present international application be processed according to the Patent Cooperation Treaty.

For receiving Office use only

International Application No. 436

International Filing Date

Name of receiving Office and "PCT International Application"

Applicant's or agent's file reference *(if desired) (12 characters maximum)* LD0192

Box No. I TITLE OF INVENTION

FUSED HETEROCYCLIC SUCCINIMIDE COMPOUNDS AND ANALOGS THEREOF, MODULATORS OF NUCLEAR HORMONE RECEPTOR FUNCTION

Box No. II APPLICANT

Name and address: *(Family name followed by given name; for a legal entity, full official designation. The address must include postal code and name of country. The country of the address indicated in this Box is the applicant's State (that is, country) of residence if no State of residence is indicated below.)*

BRISTOL-MYERS SQUIBB COMPANY
P.O. Box 4000 ; Lawrenceville-Princeton Rd.
Princeton, NJ 08543-4000, USA

☐ This person is also inventor.

Telephone No. (609)252-4009

Facsimile No. (609)252-4526

Teleprinter No.

State *(that is, country)* of nationality: US

State *(that is, country)* of residence: US

This person is applicant for the purposes of: ☐ all designated States ☒ all designated States except the United States of America ☐ the United States of America only ☐ the States indicated in the Supplemental Box

Box No. III FURTHER APPLICANT(S) AND/OR (FURTHER) INVENTOR(S)

Name and address: *(Family name followed by given name; for a legal entity, full official designation. The address must include postal code and name of country. The country of the address indicated in this Box is the applicant's State (that is, country) of residence if no State of residence is indicated below.)*

SALVATI, Mark E.
9 Tracey Drive
Lawrenceville, NJ 08648
UNITED STATES OF AMERICA

This person is:

☐ applicant only

☒ applicant and inventor

☐ inventor only *(If this check-box is marked, do not fill in below.)*

State *(that is, country)* of nationality: US

State *(that is, country)* of residence: US

This person is applicant for the purposes of: ☐ all designated States ☐ all designated States except the United States of America ☒ the United States of America only ☐ the States indicated in the Supplemental Box

☒ Further applicants and/or (further) inventors are indicated on a continuation sheet.

Box No. IV AGENT OR COMMON REPRESENTATIVE; OR ADDRESS FOR CORRESPONDENCE

The person identified below is hereby/has been appointed to act on behalf of the applicant(s) before the competent International Authorities as: ☒ agent ☐ common representative

Name and address: *(Family name followed by given name; for a legal entity, full official designation. The address must include postal code and name of country.)*

ALGIERI, Aldo A.; BABAJKO, Suzanne E.; BABCOCK, Timothy J.;D'AMICO, Stephen C; DAVIS, Stephen B.; DUBOFF, Samuel J.; HERMENAU, Ronald S.; KILCOYNE, John M.; KLEIN, Christopher A.; LANGE, Keith R.; LOPEZ, Gabriel; MAKUJINA, Shah R.; MATHIAS, Maria J.; MORSE, David M.; O'BRIEN, Maureen P.; PATEL, Rena; PEIST, Kenneth W; PROVOOST, Jonathan N.; RODNEY, Burton; RYAN, Richard P.; SHER, Audrey F.; SWITZER, Joan E.; WILK-ORESCAN, Rosemarie R. (continued on suppl. sheet)

Telephone No. (609)252-4009

Facsimile No. (609)252-4526

Teleprinter No.

☐ **Address for correspondence:** *Mark this check-box where no agent or common representative is/has been appointed and the space above is used instead to indicate a special address to which correspondence should be sent.*

437

Continuation of Box No. III FURTHER APPLICANTS AND/OR (FURTHER) INVENTOR(S)

If none of the following sub-boxes is used, this sheet is not to be included in the request.

Name and address: *(Family name followed by given name; for a legal entity, full official designation. The address must include postal code and name of country. The country of the address indicated in this Box is the applicant's State (that is, country) of residence if no State of residence is indicated below.)*
BALOG, James Aaron
2 Sassafras Court, Scotch Plains, NJ 07076
UNITED STATES OF AMERICA

This person is:
☐ applicant only
☒ applicant and inventor
☐ inventor only *(If this check-box is marked, do not fill in below.)*

State *(that is, country)* of nationality: US

State *(that is, country)* of residence: US

This person is applicant for the purposes of: ☐ all designated States ☐ all designated States except the United States of America ☒ the United States of America only ☐ the States indicated in the Supplemental Box

Name and address: *(Family name followed by given name; for a legal entity, full official designation. The address must include postal code and name of country. The country of the address indicated in this Box is the applicant's State (that is, country) of residence if no State of residence is indicated below.)*
PICKERING, Decia A.
507 Drexel Avenue, Lawrenceville, NJ 08648-3844
UNITED STATES OF AMERICA

This person is:
☐ applicant only
☒ applicant and inventor
☐ inventor only *(If this check-box is marked, do not fill in below.)*

State *(that is, country)* of nationality: British Virgin Islands

State *(that is, country)* of residence: US

This person is applicant for the purposes of: ☐ all designated States ☐ all designated States except the United States of America ☒ the United States of America only ☐ the States indicated in the Supplemental Box

Name and address: *(Family name followed by given name; for a legal entity, full official designation. The address must include postal code and name of country. The country of the address indicated in this Box is the applicant's State (that is, country) of residence if no State of residence is indicated below.)*
GIESE, Sören
1113 Polo Run Drive, Yardley, PA 19067
UNITED STATES OF AMERICA

This person is:
☐ applicant only
☒ applicant and inventor
☐ inventor only *(If this check-box is marked, do not fill in below.)*

State *(that is, country)* of nationality: Germany

State *(that is, country)* of residence: US

This person is applicant for the purposes of: ☐ all designated States ☐ all designated States except the United States of America ☒ the United States of America only ☐ the States indicated in the Supplemental Box

Name and address: *(Family name followed by given name; for a legal entity, full official designation. The address must include postal code and name of country. The country of the address indicated in this Box is the applicant's State (that is, country) of residence if no State of residence is indicated below.)*
FURA, Aberra
15 Crosthill Road, Lawrenceville, NJ 08648
UNITED STATES OF AMERICA

This person is:
☐ applicant only
☒ applicant and inventor
☐ inventor only *(If this check-box is marked, do not fill in below.)*

State *(that is, country)* of nationality: Qatar

State *(that is, country)* of residence: US

This person is applicant for the purposes of: ☐ all designated States ☐ all designated States except the United States of America ☒ the United States of America only ☐ the States indicated in the Supplemental Box

☒ Further applicants and/or (further) inventors are indicated on another continuation sheet.

438

Continuation of Box No. III FURTHER APPLICANTS AND/OR (FURTHER) INVENTOR(S)

If none of the following sub-boxes is used, this sheet is not to be included in the request.

Name and address: *(Family name followed by given name; for a legal entity, full official designation. The address must include postal code and name of country. The country of the address indicated in this Box is the applicant's State (that is, country) of residence if no State of residence is indicated below.)*

LI, Wenying
6221 Town Place Middletown, CT 06457
UNITED STATES OF AMERICA

This person is:

- ☐ applicant only
- ☒ applicant and inventor
- ☐ inventor only *(If this check-box is marked, do not fill in below.)*

State *(that is, country)* of nationality: P.R. CHINA

State *(that is, country)* of residence: US

This person is applicant for the purposes of: ☐ all designated States ☐ all designated States except the United States of America ☒ the United States of America only ☐ the States indicated in the Supplemental Box

Name and address: *(Family name followed by given name; for a legal entity, full official designation. The address must include postal code and name of country. The country of the address indicated in this Box is the applicant's State (that is, country) of residence if no State of residence is indicated below.)*

PATEL, Ramesh N.
572 Cabott Hill Rd.
Bridgewater, NJ 08807
UNITED STATES OF AMERICA

This person is:

- ☐ applicant only
- ☒ applicant and inventor
- ☐ inventor only *(If this check-box is marked, do not fill in below.)*

State *(that is, country)* of nationality: US

State *(that is, country)* of residence: US

This person is applicant for the purposes of: ☐ all designated States ☐ all designated States except the United States of America ☒ the United States of America only ☐ the States indicated in the Supplemental Box

Name and address: *(Family name followed by given name; for a legal entity, full official designation. The address must include postal code and name of country. The country of the address indicated in this Box is the applicant's State (that is, country) of residence if no State of residence is indicated below.)*

HANSON, Ronald L.
54 Whitewood Drive
Morris Plains, NJ 07950
UNITED STATES OF AMERICA

This person is:

- ☐ applicant only
- ☒ applicant and inventor
- ☐ inventor only *(If this check-box is marked, do not fill in below.)*

State *(that is, country)* of nationality: US

State *(that is, country)* of residence: US

This person is applicant for the purposes of: ☐ all designated States ☐ all designated States except the United States of America ☒ the United States of America only ☐ the States indicated in the Supplemental Box

Name and address: *(Family name followed by given name; for a legal entity, full official designation. The address must include postal code and name of country. The country of the address indicated in this Box is the applicant's State (that is, country) of residence if no State of residence is indicated below.)*

This person is:

- ☐ applicant only
- ☐ applicant and inventor
- ☐ inventor only *(If this check-box is marked, do not fill in below.)*

State *(that is, country)* of nationality:

State *(that is, country)* of residence:

This person is applicant for the purposes of: ☐ all designated States ☐ all designated States except the United States of America ☐ the United States of America only ☐ the States indicated in the Supplemental Box

☐ Further applicants and/or (further) inventors are indicated on another continuation sheet.

439

Box No. VI PRIORITY CLAIM ☐ Further priority claims are listed in the Supplemental Box.

Filing date of earlier application (day/month/year)	Number of earlier application	Where earlier application is: national application: country	regional application:* regional Office	international application: receiving Office
item (1) 19 Sept. 2000 (19.09.00)	60/233,519	US		
item (2) 18 April 2001 (18.04.01)	60/284,730	US		
item (3) 18 April 2001 (18.04.01)	60/284,438	US		

☒ The receiving Office is requested to prepare and transmit to the International Bureau a certified copy of the earlier application(s) *(only if the earlier application was filed with the Office which for the purposes of the present international application is the receiving Office)* identified above as item(s): (1), (2) & (3)

* *Where the earlier application is an ARIPO application, it is mandatory to indicate in the Supplemental Box at least one country party to the Paris Convention for the Protection of Industrial Property for which that earlier application was filed (Rule 4.10(b)(ii)). See Supplemental Box.*

Box No. VII INTERNATIONAL SEARCHING AUTHORITY

Choice of International Searching Authority (ISA) *(if two or more International Searching Authorities are competent to carry out the international search, indicate the Authority chosen; the two-letter code may be used):*

ISA/ EP

Request to use results of earlier search; reference to that search *(if an earlier search has been carried out by or requested from the International Searching Authority):*

Date *(day/month/year)* Number Country (or regional Office)

Box No. VIII CHECK LIST: LANGUAGE OF FILING

This international application contains the following number of sheets:

request	: 5
description (excluding sequence listing part)	: 343
claims	: 61
abstract	: 1
drawings	:
sequence listing part of description	:
Total number of sheets	: 410

This international application is accompanied by the item(s) marked below:

1. ☒ fee calculation sheet
2. ☒ separate signed power of attorney
3. ☐ copy of general power of attorney; reference number, if any:
4. ☐ statement explaining lack of signature
5. ☐ priority document(s) identified in Box No. VI as item(s):
6. ☐ translation of international application into (language):
7. ☐ separate indications concerning deposited microorganism or other biological material
8. ☐ nucleotide and/or amino acid sequence listing in computer readable form
9. ☒ other *(specify)*: Transmittal letter

Figure of the drawings which should accompany the abstract:

Language of filing of the international application:

Box No. IX SIGNATURE OF APPLICANT OR AGENT

Next to each signature, indicate the name of the person signing and the capacity in which the person signs (if such capacity is not obvious from reading the request).

Suzanne E. Babajko

Suzanne E. Babajko

For receiving Office use only

1. Date of actual receipt of the purported international application:
2. Drawings: ☐ received: ☐ not received:
3. Corrected date of actual receipt due to later but timely received papers or drawings completing the purported international application:
4. Date of timely receipt of the required corrections under PCT Article 11(2):
5. International Searching Authority (if two or more are competent): ISA/
6. ☐ Transmittal of search copy delayed until search fee is paid.

For International Bureau use only

Date of receipt of the record copy by the International Bureau:

440

Box No.V DESIGNATION OF STATES *Mark the applicable check-boxes below; at least one must be marked.*

The following designations are hereby made under Rule 4.9(a):

Regional Patent

☒ AP **ARIPO Patent:** GH Ghana, GM Gambia, KE Kenya, LS Lesotho, MW Malawi, MZ Mozambique, SD Sudan, SL Sierra Leone, SZ Swaziland, TZ United Republic of Tanzania, UG Uganda, ZW Zimbabwe, and any other State which is a Contracting State of the Harare Protocol and of the PCT

☒ EA **Eurasian Patent:** AM Armenia, AZ Azerbaijan, BY Belarus, KG Kyrgyzstan, KZ Kazakhstan, MD Republic of Moldova, RU Russian Federation, TJ Tajikistan, TM Turkmenistan, and any other State which is a Contracting State of the Eurasian Patent Convention and of the PCT

☒ EP **European Patent:** AT Austria, BE Belgium, CH & LI Switzerland and Liechtenstein, CY Cyprus, DE Germany, DK Denmark, ES Spain, FI Finland, FR France, GB United Kingdom, GR Greece, IE Ireland, IT Italy, LU Luxembourg, MC Monaco, NL Netherlands, PT Portugal, SE Sweden, TR Turkey, and any other State which is a Contracting State of the European Patent Convention and of the PCT

☒ OA **OAPI Patent:** BF Burkina Faso, BJ Benin, CF Central African Republic, CG Congo, CI Côte d'Ivoire, CM Cameroon, GA Gabon, GN Guinea, GW Guinea-Bissau, ML Mali, MR Mauritania, NE Niger, SN Senegal, TD Chad, TG Togo, and any other State which is a member State of OAPI and a Contracting State of the PCT *(if other kind of protection or treatment desired, specify on dotted line)* .....

National Patent *(if other kind of protection or treatment desired, specify on dotted line):*

☒ AE United Arab Emirates
☒ AG Antigua and Barbuda
☒ AL Albania
☒ AM Armenia
☒ AT Austria
☒ AU Australia
☒ AZ Azerbaijan
☒ BA Bosnia and Herzegovina
☒ BB Barbados
☒ BG Bulgaria
☒ BR Brazil
☒ BY Belarus
☒ BZ Belize
☒ CA Canada
☒ CH & LI Switzerland and Liechtenstein
☒ CN China
☒ CO Colombia
☒ CR Costa Rica
☒ CU Cuba
☒ CZ Czech Republic
☒ DE Germany
☒ DK Denmark
☒ DM Dominica
☒ DZ Algeria
☒ EE Estonia
☒ ES Spain
☒ FI Finland
☒ GB United Kingdom
☒ GD Grenada
☒ GE Georgia
☒ GH Ghana
☒ GM Gambia
☒ HR Croatia
☒ HU Hungary
☒ ID Indonesia
☒ IL Israel
☒ IN India
☒ IS Iceland
☒ JP Japan
☒ KE Kenya
☒ KG Kyrgyzstan
☒ KP Democratic People's Republic of Korea
☒ KR Republic of Korea
☒ KZ Kazakhstan
☒ LC Saint Lucia
☒ LK Sri Lanka
☒ LR Liberia
☒ LS Lesotho
☒ LT Lithuania
☒ LU Luxembourg
☒ LV Latvia
☒ MA Morocco
☒ MD Republic of Moldova
☒ MG Madagascar
☒ MK The former Yugoslav Republic of Macedonia
☒ MN Mongolia
☒ MW Malawi
☒ MX Mexico
☒ MZ Mozambique
☒ NO Norway
☒ NZ New Zealand
☒ PL Poland
☒ PT Portugal
☒ RO Romania
☒ RU Russian Federation
☒ SD Sudan
☒ SE Sweden
☒ SG Singapore
☒ SI Slovenia
☒ SK Slovakia
☒ SL Sierra Leone
☒ TJ Tajikistan
☒ TM Turkmenistan
☒ TR Turkey
☒ TT Trinidad and Tobago
☒ TZ United Republic of Tanzania
☒ UA Ukraine
☒ UG Uganda
☒ US United States of America
☒ UZ Uzbekistan
☒ VN Viet Nam
☒ YU Yugoslavia
☒ ZA South Africa
☒ ZW Zimbabwe

Check-boxes below reserved for designating States which have become party to the PCT after issuance of this sheet:

☒ ECUADOR ..... ☐ ..... ☐ .....
☐ ..... ☐ ..... ☐ .....

Precautionary Designation Statement: In addition to the designations made above, the applicant also makes under Rule 4.9(b) all other designations which would be permitted under the PCT except any designation(s) indicated in the Supplemental Box as being excluded from the scope of this statement. The applicant declares that those additional designations are subject to confirmation and that any designation which is not confirmed before the expiration of 15 months from the priority date is to be regarded as withdrawn by the applicant at the expiration of that time limit. *(Confirmation (including fee) must reach the receiving Office within the 15-month time limit.)*

441

Supplemental Box *If the Supplemental Box is not used, this sheet need not be included in the request.*

1. If, in any of the Boxes, the space is insufficient to furnish all the information: in such case, write "Continuation of Box No. ..." [indicate the number of the Box] and furnish the information in the same manner as required according to the captions of the Box in which the space was insufficient, in particular:

(i) if more than two persons are involved as applicants and/or inventors and no "continuation sheet" is available: in such case, write "Continuation of Box No. III" and indicate for each additional person the same type of information as required in Box No. III. The country of the address indicated in this Box is the applicant's State (that is, country) of residence if no State of residence is indicated below;

(ii) if, in Box No. II or in any of the sub-boxes of Box No. III, the indication "the States Indicated in the Supplemental Box" is checked: in such case, write "Continuation of Box No. II" or "Continuation of Box No. III" or "Continuation of Boxes No. II and No. III" (as the case may be), indicate the name of the applicant(s) involved and, next to (each) such name, the State(s) (and/or, where applicable, ARIPO, Eurasian, European or OAPI patent) for the purposes of which the named person is applicant;

(iii) if, in Box No. II or in any of the sub-boxes of Box No. III, the inventor or the inventor/applicant is not inventor for the purposes of all designated States or for the purposes of the United States of America: in such case, write "Continuation of Box No. II" or "Continuation of Box No. III" or "Continuation of Boxes No. II and No. III" (as the case may be), indicate the name of the inventor(s) and, next to (each) such name, the State(s) (and/or, where applicable, ARIPO, Eurasian, European or OAPI patent) for the purposes of which the named person is inventor;

(iv) if, in addition to the agent(s) indicated in Box IV, there are further agents: in such case, write "Continuation of Box No. IV" and indicate for each further agent the same type of information as required in Box No. IV;

(v) if, in Box No. V, the name of any State (or OAPI) is accompanied by the indication "patent of addition," or "certificate of addition," or if, in Box No. V, the name of the United States of America is accompanied by an indication "continuation" or "continuation-in-part": in such case, write "Continuation of Box No. V" and the name of each State involved (or OAPI), and after the name of each such State (or OAPI), the number of the parent title or parent application and the date of grant of the parent title or filing of the parent application;

(vi) if, in Box No. VI, there are more than three earlier applications whose priority is claimed: in such case, write "Continuation of Box No. VI" and indicate for each additional earlier application the same type of information as required in Box No. VI;

(vii) if, in Box No. VI, the earlier application is an ARIPO application: in such case, write "Continuation of Box No. VI", specify the number of the item corresponding to that earlier application and indicate at least one country party to the Paris Convention for the Protection of Industrial Property or one Member of the World Trade Organization for which that earlier application was filed.

2. If, with regard to the precautionary designation statement contained in Box No. V, the applicant wishes to exclude any State(s) from the scope of that statement: in such case, write "Designation(s) excluded from precautionary designation statement" and indicate the name or two-letter code of each State so excluded.

3. If the applicant claims, in respect of any designated Office, the benefits of provisions of the national law concerning non-prejudicial disclosures or exceptions to lack of novelty: in such case, write "Statement concerning non-prejudical disclosures or exceptions to lack of novelty" and furnish that statement below.

Continued from box IV:

BRISTOL-MYERS SQUIBB CO.
P.O. BOX 4000, Lawrenceville-Princeton Rd.
PRINCETON, NEW JERSEY 08543
UNITED STATES OF AMERICA

Continued from box II:

60/284,730	18 April 2001	18.04.01
60/284,438	18 April 2001	18.04.01

This sheet is not part of ar[illegible]as not count as a sheet of the international applic[illegible].

442

PCT

FEE CALCULATION SHEET
Annex to the Request

For receiving Office use only

International application No.

Date stamp of the receiving Office

Applicant's or agent's file reference: LD0192

Applicant
BRISTOL-MYERS SQUIBB CO.

CALCULATION OF PRESCRIBED FEES

1. TRANSMITTAL FEE ..... 240.00 T

2. SEARCH FEE ..... 848.00 S
International search to be carried out by ISA/EP
(If two or more International Searching Authorities are competent in relation to the international application, indicate the name of the Authority which is chosen to carry out the international search.)

3. INTERNATIONAL FEE

Basic Fee
The international application contains 410 sheets.
first 30 sheets 382.00 b1
380 (remaining sheets) x 9.00 (additional amount) = 3,420.00 b2
Add amounts entered at b1 and b2 and enter total at B .. 3,802.00 B

Designation Fees
The international application contains 80 designations.
6 (number of designation fees payable *(maximum 8)*) x 82.00 (amount of designation fee) = 492.00 D

Add amounts entered at B and D and enter total at I ..... 4,294.00 I
(Applicants from certain States are entitled to a reduction of 75% of the international fee. Where the applicant is (or all applicants are) so entitled, the total to be entered at I is 25% of the sum of the amounts entered at B and D.)

4. FEE FOR PRIORITY DOCUMENT *(if applicable)* ..... 415.00 P

5. TOTAL FEES PAYABLE .....
Add amounts entered at T, S, I and P, and enter total in the TOTAL box: 5,425.00 TOTAL

☐ The designation fees are not paid at this time.

MODE OF PAYMENT

☒ authorization to charge deposit account (see below)
☐ bank draft
☐ coupons
☐ cheque
☐ cash
☐ other *(specify)*:
☐ postal money order
☐ revenue stamps

DEPOSIT ACCOUNT AUTHORIZATION *(this mode of payment may not be available at all receiving Offices)*

The RO/ US ☒ is hereby authorized to charge the total fees indicated above to my deposit account.

☒ *(this check-box may be marked only if the conditions for deposit accounts of the receiving Office so permit)* is hereby authorized to charge any deficiency or credit any overpayment in the total fees indicated above to my deposit account.

☒ is hereby authorized to charge the fee for preparation and transmittal of the priority document to the International Bureau of WIPO to my deposit account.

19-3880	20.06.01	Suzanne E. Babajko
Deposit Account No.	Date *(day/month/year)*	Signature Suzanne E. Babajko